


Industrial Waste Treatment Handbook

Industrial Waste Treatment Handbook

Frank Woodard, Ph.D., P.E.,
President



Boston Oxford Auckland Johannesburg Melbourne New Delhi

Copyright © 2001 by Butterworth-Heinemann

 A member of the Reed Elsevier group

All rights reserved.

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, without the prior written permission of the publisher.

Recognizing the importance of preserving what has been written, Butterworth-Heinemann prints its books on acid-free paper whenever possible.



Butterworth-Heinemann supports the efforts of American Forests and the Global ReLeaf program in its campaign for the betterment of trees, forests, and our environment.

Library of Congress Cataloging-in-Publication Data

Woodard, Frank, 1939

Industrial waste treatment handbook/Frank Woodard

p. cm.

Includes bibliographical references and indexes.

ISBN 0-7506-7317-6

1. Factory and trade waste—Management—Handbooks, manuals, etc. 2. Sewage—Purification—Handbooks, manuals, etc. 3. Industries—Environmental

TD897.W67 2000]

628.4—dc21

00-044448

British Library Cataloguing-in-Publication Data

A catalogue record for this book is available from the British Library.

The publisher offers special discounts on bulk orders of this book.

For information, please contact:

Manager of Special Sales

Butterworth-Heinemann

225 Wildwood Avenue

Woburn, MA 01801-2041

Tel: 781-904-2500

Fax: 781-904-2620

For information on all Butterworth-Heinemann publications available, contact our World Wide Web home page at:

<http://www.bh.com>

10 9 8 7 6 5 4 3 2 1

Printed in the United States of America

Dedication

To Dr. James C. Buzzell, whose fascinating anecdotes lured me into this profession; Dr. Otis J. Sproul, by whose example I became accustomed to and enjoyed hard work and a scholarly approach to life; Dr. James E. Etzel, by whose example I developed an insatiable desire to figure out better ways to achieve treatment of industrial wastes; and my (almost) lifelong best friend, Jean McNeary Woodard, who deserves much of the credit for the existence of this book.

1 Management of Industrial Wastes: Solids, Liquids, and Gases	1
1.1 Management of Industrial Wastewater	1
1.2 O&M Costs	10
1.3 Management of Solid Wastes from Industries	18
1.4 Management of Discharges to the Air	20
1.5 Bibliography	28
2 Fundamentals	29
2.1 Introduction	29
2.2 Characteristics of Industrial Wastewater	29
2.3 The Polar Properties of Water	30
2.4 Electrical and Thermodynamic Stability	33
2.5 Chemical Structure and Polarity of Water	36
2.6 Hydrogen Bonding	37
2.7 Polar Solvents versus Nonpolar Solvents True Solutions.....	38
2.8 Emulsification	40
2.9 Colloidal Suspensions	43
2.10 Mixtures Made Stable by Chelating Agents	44
2.11 Summary	44
2.12 Examples	45
2.13 Bibliography	48
3 Laws and Regulations	49
3.1 Introduction	49
3.2 History of Permitting and Reporting	49
3.3 Requirements	49
3.4 Water Pollution Control Laws.....	50
3.5 Groundwater Pollution Control Laws	52
3.6 Air Pollution Control Laws.....	55
3.7 Bibliography	60
4 Wastes from Industries	61
4.1 Chemical Descaling	61
4.2 Degreasing	62
4.3 Rinsing	64
4.4 Electroplating of Tin	65
4.5 The Copper Forming Industry	74
4.6 Prepared Frozen Foods	77
4.7 Wastes From De-inking	86
4.8 Die Casting: Aluminum, Zinc, and Magnesium	93
4.9 Anodizing and Alodizing.....	99
4.10 Production and Processing of Coke	103
4.11 The Wine-Making Industry	107
4.12 The Synthetic Rubber Industry	110
4.13 The Soft Drink Bottling Industry	119
4.14 Production and Processing of Beef, Pork, and Other Sources of Red Meat	124
4.15 Rendering of By-Products from the Processing of Meat, Poultry, and Fish	130
4.16 The Manufacture of Lead Acid Batteries.....	138
4.17 Bibliography	144
5 Industrial Stormwater Management	149
5.1 General	149
5.2 Federal Stormwater Regulations	149
5.3 Prevention of Groundwater Contamination	151
5.4 Stormwater Segregation, Collection, Retention, and Treatment.....	152
5.5 Design Storm	152
5.6 System Failure Protection.....	153
5.7 Stormwater Retention	153
5.8 Stormwater Treatment	153
5.9 Stormwater as a Source of Process Water Makeup	154
5.10 Bibliography	165

6 Wastes Characterization: The Wastes Characterization Study, Wastes Audit, and the Environmental Audit	166
6.1 Wastes Characterization Study	166
6.2 Wastes Audit	169
6.3 Environmental Audit	172
6.4 Characteristics of Industrial Wastewater	179
6.5 Characteristics of Discharges to the Air	192
6.6 Sample Analysis	198
6.7 Ambient Air Sampling	198
6.8 Characteristics of Solid Waste Streams from Industries	201
6.9 Bibliography	205
7 Pollution Prevention	208
Findings and Policy	208
7.1 General Approach	209
7.2 Source Reduction	212
7.3 The Waste Audit	215
7.4 Benefits of Pollution Prevention	216
7.5 Bibliography	216
8 Methods for Treating Wastewaters from Industry	219
8.1 General	219
8.2 Principle and Nonprinciple Treatment Mechanisms	220
8.3 Waste Equalization	223
8.4 pH Control	227
8.5 Chemical Methods of Wastewater Treatment	230
8.6 Biological Methods of Wastewater Treatment	255
8.7 Development of Design Equations for Biological Treatment of Industrial Wastes	256
8.8 Physical Methods of Wastewater Treatment	322
8.9 Bibliography	394
9 Treatment and Disposal of Solid Wastes from Industry	397
9.1 Characterization of Solid Wastes	398
9.2 The Solid Waste Landfill	400
9.3 Solid Waste Incineration	409
9.4 The Process of Composting Industrial Wastes	421
9.5 Solidification and Stabilization of Industrial Solid Wastes	427
9.6 Bibliography	433
10 Methods for Treating Air Discharges from Industry	437
10.1 Reduction at the Source	437
10.2 Containment	437
10.3 Treatment	438
10.4 Bibliography	456
Index	461

Preface

This book has been developed with the intention of providing an updated primary reference for environmental managers working in industry, environmental engineering consultants, graduate students in environmental engineering, and government agency employees concerned with wastes from industries. It presents an explanation of the fundamental mechanisms by which pollutants become dissolved or suspended in water or air, then builds on this knowledge to explain how different treatment processes work, how they can be optimized, and how one would go about efficiently selecting candidate treatment processes.

Examples from the recent work history of Woodard & Curran, as well as other environmental engineering and science consultants, are presented to illustrate both the approach used in solving various environmental quality problems and the step-by-step design of facilities to implement the solutions. Where permission was granted, the industry involved in each of these examples is identified by name. Otherwise, no name was given to the industry, and the industry has been identified only as to type

of industry and size. In all cases, the actual numbers and all pertinent information have been reproduced as they occurred, with the intent of providing accurate illustrations of how environmental quality problems have been solved by one of the leading consultants in the field of industrial wastes management.

This book is intended to fulfill the need for an updated source of information on the characteristics of wastes from numerous types of industries, how the different types of wastes are most efficiently treated, the mechanisms involved in treatment, and the design process itself. In many cases, “tricks” that enable lower cost treatment are presented. These “tricks” have been developed through many years of experience and have not been generally available except by word of mouth.

The chapter on laws and regulations is presented as a summary as of the date stated in the chapter itself and/or the addendum that is issued periodically by the publisher. For information on the most recent addendum, please call the publisher or Woodard & Curran’s office in Portland, Maine, at (207) 774-2112.

Acknowledgments

This work was produced over a period of more than five years; during that time, a very large number of individuals, corporations, and various business organizations contributed significant material. I have tried to cite each contributor, and I apologize mightily if I have missed one or more. Thus, I extend heartfelt gratitude and acknowledgement to:

Adam H. Steinman; Aeration Technologies, Inc.; R. Gary Gilbert; Albert M. Presgraves; Andy Miller; Claire P. Betze; Connie Bogard; Connie Gipson; Dennis Merrill; Dr. Steven E. Woodard; Geoffrey D. Pellechia; George Abide; George W. Bloom; Henri J. Vincent; Dr. Hugh J. Campbell; J. Alastair Lough; Janet

Robinson; Dr. James E. Etzel; James D. Ekedahl; Karen L. Townsend; Katahdin Analytical Services; Keith A. Weisenberger; Kurt R. Marston; Michael Harlos; Michael J. Curato; Patricia A. Proux-Lough; Paul Bishop; Randy E. Tome; Eric P. King; Raymond G. Pepin; Robert W. Severance; Steven N. Whipple; Steven Smock; Susan G. Stevens; Terry Rinehart; and Thora Knakkegaard, all of whom contributed text or verbal information from which I freely drew, either word-for-word or by way of paraphrase. I extend special thanks to Adam Steinman, Esq., who provided text and verbal information regarding laws, regulations and environmental audits.

1 Management of Industrial Wastes: Solids, Liquids, and Gases

The approach used to develop systems to treat and dispose of industrial wastes is distinctly different from the approach used for municipal wastes. There is a lot of similarity in the characteristics of wastes from one municipality, or one region, to another. Because of this, the best approach to designing a treatment system for municipal wastes is to analyze the performance characteristics of many existing municipal systems and deduce an optimal set of design parameters for the system under consideration. Emphasis is placed on the analysis of other systems, rather than on the waste stream under consideration. In the case of industrial waste, however, few industrial plants have a high degree of similarity between products produced and wastes generated. Therefore, emphasis is placed on analysis of the wastes under consideration, rather than on what is taking place at other industrial locations. This is not to say that there is little value in analyzing the performance of treatment systems at other, more or less similar, industrial locations. Quite the opposite is true. It is simply a matter of emphasis.

Wastes from industries are customarily classified as liquid wastes, solid wastes, or air pollutants, and often the three are managed by different people or departments. The three separate categories are regulated by separate and distinct bodies of laws and regulations, and historically, public and governmental emphasis has moved from one category to another from one time period to another. The fact is, however, that the three categories of wastes are closely interrelated, both as they impact on the environment and as they are generated and managed by individual industrial facilities. Solid wastes disposed of in the ground can influence the quality of groundwater and

surface waters by way of leachate entering the groundwater and traveling with it through the ground, then entering a surface water body with groundwater recharge. Volatile organics in that recharge water can contaminate the air. Air pollutants can fall out to become surface water or groundwater pollutants, and water pollutants can infiltrate into the ground or volatilize into the air.

Waste treatment processes can also transfer substances from one of the three waste categories to one or both of the others. Air pollutants can be removed from an air discharge by means of a water solution scrubber. The waste scrubber solution must then be managed to enable it to be discarded within compliance with applicable water regulations. Airborne particulates can be removed from an air discharge using a bag house, thus creating a solid waste to be managed. On still a third level, waste treatment or disposal systems themselves can directly impact on the quality of air, water, or ground. Activated sludge aeration tanks are very effective in causing volatilization of substances from wastewater. Failed landfills can be potent polluters of both groundwater and surface water.

The total spectrum of industrial wastes, then, must be managed as substances resulting from a system of interrelated activities. Materials balances must be tracked, and overall cost effectiveness must be kept in focus.

Management of Industrial Wastewater

With respect to industrial wastewater, Figure 1-1 illustrates the approach for developing a well-operating, cost-effective treatment system. The first step is to gain familiarity with the manufacturing processes themselves. This




Figure 1-1 Approach for developing an industrial wastewater treatment system.

usually starts with a tour of the facility, and then progresses through a review of the literature and interviews with knowledgeable people. The objective is to gain an understanding of how wastewater is produced, for two reasons. The first is to enable an informed and therefore effective wastes reduction, or minimization (pollution prevention) program; the second is to enable proper choice of candidate treatment technologies.

Analysis of Manufacturing Processes

One of the first steps in the analysis of manufacturing processes is to develop a block diagram that shows how each manufacturing process contributes wastewater to the treatment facility, as is illustrated in Figure 1-2. In Figure 1-2, a block represents each step in the manufacturing process. The supply of water to each point of use is represented on the left side of the block diagram. Wastewater that flows away from each point of wastewater generation is shown on the right side.

Figure 1-2 is representative of the processes involved in producing finished woven fabric from an intermediate product of the textile industry. The “raw material” for this process is first subjected to a process called “desizing,” during which the substances used to size the woven greige goods, or raw fabric, are removed. The process uses sulfuric acid; therefore, the liquid waste from this process would be expected to have a low pH as well as contain whatever substances were used as sizing. For instance, if starch were the substance used to size the fabric, the liquid waste from the desizing process would be expected to exhibit a high biochemical oxygen demand (BOD).

As the knowledge became available, from the industry’s records, if possible, or from measurements taken as part of a wastewater characterization study, the flow rates, total quantities for a typical processing day, upper and lower limits, and characteristics such as BOD, chemical oxygen demand (COD), total suspended solids (TSS), total dissolved solids (TDS), and specific chemicals would be indicated on the block diagram. Each individual process

undergone during the industrial process would be developed and shown on the block diagram, as illustrated in Figure 1-2.

Wastes Minimization and Wastes Characterization Study

After becoming sufficiently familiar with the manufacturing processes as they relate to

wastewater generation, the design team should institute a wastes minimization program (actually part of a pollution prevention program) as described in Chapter 7. Then, after the wastes reduction program has become fully implemented, a wastewater characterization study should be carried out, as described in Chapter 6.




Figure 1-2 Typical woven fabric finishing process flow diagram. (From the EPA Development Document for the Textile Mills Industry.)

The ultimate purpose of the wastewater characterization study is to provide the design team with accurate and complete information on which to base the design of the treatment system. Both quantitative and qualitative data are needed to properly size the facility and to select the most appropriate treatment technologies.

Often, enough new information about materials usage, water use efficiency, and wastes generation is learned during the wastewater characterization study to warrant a second level of wastes minimization effort. This second part of the wastes minimization program should be fully implemented, and its effectiveness should be verified by more sampling and analyses, which amounts to an extension of the wastewater characterization study.

A cautionary note is appropriate here concerning maintenance of the wastes minimization program. If, after implementation of the wastes minimization program, operation of the manufacturing facilities and/or housekeeping practices loses attention and becomes lax so that wastewater increases in volume, strength, or both, the treatment facility will be underdesigned and will be overloaded at the start. It is extremely important that realistic goals be set and maintained for the wastes minimization program, and that the design team, as well as the industry's management team, are fully aware of the consequences of overloading the treatment system.

Treatment Objectives

After the volume, strength, and substance characteristics of the wastewater have been established, the treatment objectives must be determined. These objectives depend on where the wastewater is to be sent after treatment. If the treated wastewater is discharged to another treatment facility, such as a regional facility or a municipal treatment system, pretreatment requirements must be complied with. As a minimum, the Federal Pretreatment Guidelines issued by the Environmental Protection Agency (EPA) and published in the *Federal Register* must be complied with. Some

municipal or regional treatment facilities have pretreatment standards that are more stringent than those required by the EPA.

If the treated effluent is discharged to an open body of water, then a National Pollutant Discharge Elimination System (NPDES) permit, plus a permit issued by the appropriate state agency, must be complied with. In all cases, Categorical Standards issued by the Federal EPA apply, and it is necessary to work closely with one or more government agencies while developing the treatment objectives.

Selection of Candidate Technologies

Once the wastewater characteristics and the treatment objectives are known, candidate technologies for treatment can be selected. Rationale for selection is discussed in detail in Chapter 8. The selection should be based on one or more of the following:

- Successful application to a similar wastewater
- Knowledge of chemistry, biochemistry, and microbiology
- Knowledge of what technologies are available, as well as knowledge of their respective capabilities and limitations

Then, bench scale investigations should be conducted to determine technical as well as financial feasibility.

Bench Scale Investigations

Bench scale investigations quickly and efficiently determine the technical feasibility and a rough approximation of the financial feasibility of a given technology. Bench scale studies range from rough experiments in which substances are mixed in a beaker and results are observed almost immediately, to rather sophisticated continuous flow studies in which a refrigerated reservoir contains representative industrial wastewater, which is pumped through a series of miniature treatment devices that are models of the full-size equipment. Typical bench scale equipment

includes the six-place stirrer shown in Figure 1-3(a), small columns for ion exchange resins, activated carbon, or sand, shown in Figure 1-3(b), “block aerators,” shown in Figures 1-3(c) and (d), for performing microbiological treatability studies, and any number of custom-designed devices for testing the technical feasibility of given treatment technologies.

Because of scale-up problems, it is seldom advisable to proceed directly from the results of bench scale investigations to design of the full-scale wastewater treatment system. Only in cases for which extensive experience exists with both the type of wastewater being treated and the technology and types of equipment to be used can this approach be justified. Otherwise, pilot scale investigations should be

conducted for each technology that appears to be a legitimate candidate for reliable, cost-effective treatment.

In the absence of pilot scale investigations, the design team is obliged to be conservative in estimating design criteria for the treatment system. The likely result is that the cost for the facility will be greater than the total cost for the pilot scale investigations plus the treatment facility that would have been designed using the information that would have been developed from the pilot scale investigations. Said another way, the objective of pilot scale investigations is to develop the data necessary to determine the minimum size and least costly system of equipment to enable the design of a treatment system that will reliably meet its intended purpose.




Figure 1-3(a) Photograph of a six-place stirrer. (Courtesy of ©Phipps & Bird, Inc., 2000.)




Figure 1-3(b) Illustration of a column set-up to evaluate treatment methods that use granular media. (From Wachinski and Etzel, *Environmental Ion Exchange: Principles and Design*, 1997. Reprinted by permission of CRC/Lewis Publishers.)




Figure 1-3(c) Diagrammatic sketch of a block aerator set-up for performing treatability studies in the laboratory.

Pilot Scale Investigations

A pilot scale investigation is a study of the performance of a given treatment technology using the actual wastewater to be treated, usually on site, and using a representative model of the equipment that would be used in the full-scale treatment system. The term “representative model” refers to the capability of the

pilot treatment system to closely duplicate the performance of the full-scale system. In some cases, accurate scale models of the full-scale system are used. In other cases, the pilot equipment bears no physical resemblance to the full-scale system. Fifty-five gallon drums have been successfully used for pilot scale investigations.



Figure 1-3(d) Photograph of a block aerator set-up for performing treatability studies in the laboratory. (Courtesy of AWARE Environmental, Inc.)

It is not unusual for equipment manufacturers to have pilot scale treatment systems that can be transported to the industrial site on a flatbed truck trailer. A rental fee is usually charged, and there is sometimes an option to include an operator in the rental fee. It is important, however, to keep all options open. Operation of a pilot scale treatment system that is rented from one equipment manufacturer might produce results that indicate that another type of equipment (using or not using the same technology) would be the wiser choice.

Figure 1-4 presents a photograph of a pilot scale wastewater treatment system.

One of the difficulties in operating a pilot scale treatment system is the susceptibility of the system to upset caused by slug doses, wide swings in temperature, plugging of the relatively small diameter pipes, and lack of familiarity on the part of the operator.

When operating a pilot scale treatment system for a sufficiently long period, it is critically important to:

1. Evaluate its performance on all combinations of wastes that are reasonably expected to occur during the foreseeable life of the prototype system.
2. Provide sufficient opportunity to evaluate all reasonable combinations of operation parameters. When operation parameters are changed—for instance the volumetric loading of an air scrubber, the chemical feed rate of a sludge press, or the recycle ratio for a reverse osmosis system—the system must operate for a long enough time to achieve steady state before data to be used for evaluation are taken. Of course, it will be necessary to obtain data during the period just after operation parameters are changed, to determine when steady state has been reached.

During the pilot plant operation period, observations should be made to determine whether performance predicted from the results of the bench scale investigations is being confirmed. If performance is significantly different from what was predicted, it may be prudent to

stop the pilot scale investigation work and try to determine the cause.

Preliminary Designs

The results of the pilot scale investigations show which technologies are capable of meeting the treatment objectives, but do not enable an accurate estimation of capital and operating costs. A meaningful cost-effectiveness analysis can take place only after preliminary designs of those technologies that produced satisfactory effluent quality in the pilot scale investigations have been completed. A preliminary design, then, is a design of an entire wastewater treatment facility, carried out in sufficient detail to enable accurate estimation of the costs for constructing and operating a wastewater treatment facility. It must be complete to the extent that the sizes and descriptions of all of the pumps, pipes, valves, tanks, concrete work, buildings, site work, control systems, and labor requirements are established. The difference between a preliminary design and a final design is principally in the completeness of detail in the drawings and in the specifications. It is almost as though the team that produces the preliminary design could use it to directly construct the plant. The extra detail that goes into the final design is principally used to communicate all of the intentions of the design team to people not involved in the design.

Economic Comparisons

The choice of treatment technology and a complete treatment system between two or more systems proven to be reliably capable of meeting the treatment objectives should be based on a thorough analysis of all costs over the expected life of the system.

Example: Pretreatment for a Microcrystalline Cellulose Manufacturing Plant

By Henri Vincent

The following sections illustrate an economic comparison of five alternatives for treating wastewater from an industrial plant producing



Figure 1-4 Photograph of a pilot scale wastewater treatment system. (Courtesy of Paques ADI, Inc.)

microcrystalline cellulose from wood pulp. This plant discharged about 41,000 gallons per day (GPD) of wastewater to the local municipal sewer system (publicly owned treatment works [POTW]). The municipality that owned the POTW charged the industry a fee for treatment, and the charge was proportional to the strength, in terms of the BOD, TSS, fats, oils, and greases (FOG), and total daily flow (Q).

In order to reduce the treatment charges from the POTW, the plant had the option of constructing and operating its own wastewater treatment system; however, because there was not an alternative place to discharge the treated wastewater other than the municipal sewer system, there would continue to be a charge from the POTW, but it would be reduced in proportion to the degree of treatment accomplished by the industry. Because the industry's treated wastewater would be further treated by the POTW, the industry's treatment system is referred to as a "pretreatment system," regardless of the degree of treatment accomplished.

Sequencing Batch Reactors

The use of sequencing batch reactors is one alternative for pretreating the plant's wastewaters. Table 1-1 presents capital costs associated with this.

Rotating Biological Contactors

Table 1-2 presents a summary of the capital costs associated with this option. Also included in Table 1-2 is the number of each unit required, along with its size and installed cost.

Fluidized Bed Anaerobic Reactors

Table 1-3 presents a summary of the capital costs associated with this option. Also included in Table 1-3 is the number of each unit required, along with its size and installed cost.

Expanded Bed Anaerobic Reactors

Because the expanded bed is not commercially available, capital costs were estimated

using the major system components from the fluidized bed anaerobic reactor (see Table 1-3) and deleting the following items that are not required for the expanded bed system:

- Two 40-ft Secondary Clarifiers
- Two 20 GPM Sludge Pumps
- One 40-ft³ Filter Press
- Two 60 GPM Filter Feed Pumps
- Two 80 GPM Sludge Transfer Pumps
- One 10 BP Sludge Tank Mixer
- One 5 HP Sludge Tank Mixer
- One 100 CFM Compressor

Also, a smaller building was designed for this option.

As a result of these deletions, the estimated capital cost for the expanded bed anaerobic reactor system is \$1,600,000.

O&M Costs

Operational and maintenance costs presented for each treatment alternative include the following elements:

- Chemicals
- Power
- Labor
- Sludge disposal, if applicable
- Sewer use charges
- Maintenance

The bases for estimating the annual operating cost for each of the previous elements were (1) the quantity of chemicals required for average design value; (2) power costs for running pumps, motors, blowers, etc.; (3) labor required to operate the facility; (4) sludge disposal costs, assuming sludge would be disposed of at a local landfill; (5) the cost for sewer use charges based on present rates; and (6) maintenance costs at a fixed percentage of total capital costs. The estimated sewer use charges for each treatment alternative are given in Table 1-4.

Table 1-1 Capital Cost Opinion; Sequencing Batch Reactors — Alternative #1

<i>Equipment</i>	<i>No. Units</i>	<i>Size</i>	<i>Installed Cost (\$)</i>
SBR Feed Pumps	3	220 GPM	20,000
Blowers	5	1,500 ACFM	120,000
Aeration Equipment	2	6,000 ACFM	77,000
Floating Mixer	2	15 HP	66,000
Floating Decanter	2	1,200 GPM	44,000
Decant Pump	2	1,200 GPM	26,000
Waste Sludge Pumps	2	450 GPM	13,000
Sludge Press	1	100 ft ³	186,000
Filter Feed Pumps	2	60 GPM	8,000
Thickener	1	100 GPM	100,000
Thickener Feed Pumps	2	50 GPM	8,000
Air Compressor	1	100 CFM	44,000
Ammonia Feed System	1	360 PPD	22,000
Phosphoric Acid Feed System	1	15 GPD	6,000
Potassium Chloride Feed System	1	50 PPD	11,000
Sludge Tank Mixer	1	15 HP	13,000
Filter Feed Tank Mixer	1	5 HP	7,000
Total Installed Equipment Cost			770,000
Site Work @ 5%			38,000
Electrical & Instrumentation @ 10%			77,000
Process Pipes & Valves @ 10%			77,000
30' × 60' Building @ \$65/ft ²			117,000
2-SBR Tanks (390,000 gal)			300,000 ¹
Sludge Holding Tank (160,000 gal)			95,000
Equalization Tank (50,000 gal)			58,000
Subtotal:			1,532,000
OH & P @ 22%			337,000
Subtotal:			1,869,000
Engineering @ 12%			224,000
Subtotal:			2,093,000
Contingency @ 25%			523,000
Estimated Construction Cost:			2,616,000
Say:			2,600,000

¹ Total for Both Tanks

Table 1-2 Capital Cost Opinion; Rotating Biological Contactors — Alternative #2

<i>Equipment</i>	<i>No. Units</i>	<i>Size</i>	<i>Installed Cost (\$)</i>
RBC Feed Pumps	3	220 GPM	20,000
Clarifiers	2	40' Diameter	195,000
Sludge Pumps	2	100 GPM	11,000
Sludge Press	1	100 ft ³	186,000
Filter Feed Pumps	2	60 GPM	8,000
Thickener	1	100 GPM	100,000
Thickener Feed Pumps	2	50 GPM	8,000
Air Compressor	1	100 CFM	44,000
Ammonia Feed System	1	360 PPD	22,000
Phosphoric Acid Feed System	1	15 GPD	5,500
Potassium Chloride Feed System	1	60 PPD	11,000
Sludge Tank Mixer	1	15 HP	13,000
Filter Feed Tank Mixer	1	5 HP	7,000
Blowers	5	500 CFM	63,000
Aeration System	1	2,000 CFM	44,000
Total Installed Equipment Cost:			737,000
Site Work @ 5%			37,000
Electrical & Instrumentation @ 10%			74,000
Process Pipes & Valves @ 10%			74,000
30' × 60' Building @ \$65/ft ²			117,000
Sludge Holding Tank (160,000 gal)			95,000
RBC Tanks (Concrete)			50,000
Subtotal:			1,184,000
22% OH & P			260,000
RBC Shafts & Enclosures			1,444,000
Subtotal:			2,806,000
12% Engineering			337,000
Subtotal:			3,143,000
25% Contingency			786,000
Estimated Construction Cost:			3,929,000
Say:			3,900,000

Table 1-3 Capital Cost Opinion; Fluidized Bed Anaerobic Reactors — Alternative #3

<i>Equipment</i>	<i>No. Units</i>	<i>Size</i>	<i>Installed Cost (\$)</i>
Reactor Feed Pumps	3	220 GPM	20,000
Secondary Clarifiers	2	40' Diameter	195,000
Sludge Pumps	2	20 GPM	3,300
Filter Press	1	40 ft ³	108,000
Filter Feed Pumps	2	60 GPM	8,000
Sludge Transfer Pumps	2	80 GPM	8,000
Sludge Tank Mixer	1	10 HP	1,000
Filter Feed Tank Mixer	1	5 HP	7,000
Compressor	1	100 CFM	44,000
Gas Recovery Blower		40 CFM	18,700
Total Installed Equipment Cost:			413,000
Site Work @ 5%			21,000
Electrical & Instrumentation @ 10%			42,000
Process Pipes & Valves @ 10%			42,000
30' × 30' Building @ \$65/ft ²			58,000
Sludge Holding Tank (30,000 gal)			35,000
Subtotal:			611,000
OH & P @ 22%			134,000
Subtotal:			745,000
Upflow Fluidized Bed Reactor System			1,000,000
Subtotal:			1,745,000
Engineering @ 12%			209,000
Subtotal:			1,954,000
Contingency @ 25%			488,000
Estimated Construction Cost:			2,442,000
Say:			2,450,000

Sequencing Batch Reactors

An illustration of yearly O&M costs associated with the use of sequencing batch reactors for wastewater pretreatment is presented in Table 1-5.

Rotating Biological Contactors

Table 1-6 presents a summary of the capital costs associated with this treatment alternative. Also included in Table 1-6 is the estimated quantity and unit cost for each O&M element.

Table 1-4 Estimated Sewer Use Charges

<i>Scenario</i>	<i>*Yearly Cost (\$)</i>
No Treatment	928,000
SBR Alternative	325,000
RBC Alternative	325,000
Fluidized Bed Alternative	384,000
Expanded Bed Alternative	335,000

*Based on flow, TSS, and BOD5 charges currently incurred.

Table 1-5 Yearly O&M Cost Summary; Sequencing Batch Reactors — Alternative #1

<i>Item</i>	<i>Unit</i>	<i>Quantity</i>	<i>Unit Cost (\$)</i>	<i>*Yearly Cost (\$)</i>
Chemicals				
Ammonia (Anhydrous)	Ton	66	135	8,910
Phosphoric Acid (85%)	lb	83,000	0.22	18,260
Potassium Chloride (99%)	lb	41,000	0.67	27,470
Sludge Conditioning	lb	9,000	1.00	9,000
Polymer				
Power	kw-hr	3,000,000	0.054	162,000
Labor	man-hr	4,380	38	166,440
Sludge disposal ¹	Ton	3,600	70	252,000
Sewer Use Charges ²	—	—	—	325,000
Maintenance ³	—	—	—	52,000
Total:				1,021,000
Say:				1,000,000

*Total rounded to nearest \$50,000.

¹ Sludge assumed to be nonhazardous; includes transportation.

² Per Table 1-4.

³ Assumed to be 2% of total capital cost.

Fluidized Bed Anaerobic Reactors

Table 1-7 presents a summary of the capital costs associated with this treatment alternative. Included in Table 1-7 is the estimated quantity and unit cost for each O&M element. Additional information on gas recovery is also included to show potential offsetting of O&M costs.

Expanded Bed Anaerobic Reactors

Because the expanded bed is not commercially available, O&M costs were estimated with the

O&M elements from the fluidized bed anaerobic reactor (see Table 1-7) and adjusted for the following:

- Labor. Because no sludge dewatering is required, labor requirements can be decreased by 75%.
- Sludge Disposal. None required because cellulose can be recycled.

Based on the above, the total O&M cost without gas recovery is \$400,000, and with gas recovery is \$300,000.

Table 1-6 Yearly Operating Cost Summary; Rotating Biological Contactors — Alternative #2

<i>Item</i>	<i>Unit</i>	<i>Quantity</i>	<i>Unit Cost (\$)</i>	<i>*Yearly Cost (\$)</i>
Chemicals				
Ammonia (Anhydrous)	Ton	66	135	8,910
Phosphoric Acid (85%)	lb.	83,000	0.22	18,260
Potassium Chloride (99%)	lb.	41,000	0.67	24,470
Sludge Conditioning	lb.	9,000	1.00	9,000
Polymer	kw-hr	890,000	0.054	48,060
Power				
Labor	man-hr	4,380	38	166,440
Sludge disposal ¹	Ton	3,600	70	252,000
Sewer Use Charges ²	—	—	—	325,000
Maintenance ³	—	—	—	78,000
Total:				930,140
Say:				950,000

*Total rounded to nearest \$50,000.

¹ Sludge assumed to be nonhazardous; includes transportation.

² Per Table 1-4.

³ Assumed to be 2% of total capital cost.

Annualized Costs

Annualized costs are a convenient method for making economic comparisons among treatment alternatives. To obtain annualized costs, the capital cost for the alternative in question is amortized over the life of the system, which for the purposes of this example is assumed to be 20 years. The cost of money is assumed to be 10%.

The five alternative treatment systems evaluated in the previous sections include (1) a sequencing batch reactor (SBR), (2) a rotating biological contactor (RBC), (3) a fluidized bed anaerobic reactor, (4) an expanded bed anaerobic reactor, and (5) the option of no pretreatment, which would result in paying the POTW for accomplishing all of the treatment. The four treatment system types are described in Chapter 8.

The estimated costs for the major items of equipment presented in this example, referred to as “cost opinions,” and also presented in Table 1-8, were obtained by soliciting price quotations from vendors. Ancillary equipment costs were obtained from cost estimating guides such as Richardson’s, as well as experience with similar projects. Elements of capital cost such as equipment installation, electrical, process piping, and instrumentation were estimated as a fixed percentage of the purchase price of major items of equipment. Costs for the building, including plumbing and heating, ventilation, and air conditioning (HVAC) were estimated as a cost per square foot of the building. At this level of cost opinion, it is appropriate to use a contingency of 25%, and to expect a level of accuracy of plus or minus 30% for the total estimated cost.

Table 1-7 Yearly Operating Cost Summary; Fluidized Bed Anaerobic Reactor — Alternative #3

<i>Item</i>	<i>Unit</i>	<i>Quantity</i>	<i>Unit Cost (\$)</i>	<i>*Yearly Cost (\$)</i>
Chemicals				
Ammonia (Anhydrous)	Ton	5	135	675
Phosphoric Acid (85%)	lb.	7,000	0.22	1,500
Potassium Chloride (99%)	lb.	3,000	0.67	2,000
Sludge Conditioning				
Polymer	lb.	6,000	1.00	6,000
Power	kw-hr	262,000	0.054	14,150
Labor	man-hr	4,380	38	166,440
Sludge disposal ¹	Ton	1,642	70	114,940
Sewer Use Charges ²	—	—	—	384,000
Maintenance ³	—	—	—	49,000
Total:				738,705
Say:				700,000
Gas Recovery	MCF:	19,000	3.50	(56,000)
Total with Gas Recovery:				640,000
Say:				650,000

* Total rounded to nearest \$50,000.

¹ Sludge assumed to be nonhazardous; includes transportation.² Per Table 1-4.³ Assumed to be 2% of total capital cost.**Table 1-8** Annualized Costs

<i>Total Capital Alternative</i>	<i>Annual Capital Cost (\$)</i>	<i>Cost (\$)</i> ¹	<i>Total Annual O&M Cost (\$)</i> ²	<i>Cost (\$)</i>
#1 SBRs	2,600,000	300,000	1,000,000	1,300,000
#2 RBCs	3,900,000	450,000	950,000	1,400,000
#3 Fluidized Bed	2,450,000	300,000	700,000	1,000,000
			(650,000)	(950,000)
#4 Expanded Bed	1,600,000	200,000	400,000	600,000
			(300,000)	(500,000)
#5 Day Surcharge	—	900,000		900,000

¹ Assumes 20-yr. life, 10% cost of money.² Assumes no increase in future O&M costs. Numbers in parentheses reflect energy recovery.

Final Design

The final design process is both a formality during which standardized documents including plans and specifications are produced, and a procedure during which all of the subtle details of the facility that is to be constructed are worked out. The standardized documents have a dual purpose; the first is to provide a common basis for several contractors to prepare competitive bids for constructing the facility. The second is to provide complete instructions for building the facility, so that what gets built is exactly what the design team intended.

Competitive Bids for Construction

The purpose of going through the competitive bidding process is to ensure that the facility developed by the design team is built at the lowest achievable cost. In addition, the contractors invited to participate in the bidding process should be carefully selected on the basis of competence, experience, workmanship, and reliability. In the end, the best construction job for the lowest possible price will not have a chance of being realized if the best contractor is not on the list of those invited to submit bids.

The foundation of the bidding process is the set of documents known as the “plans and specifications.” The first duty of the plans and specifications is to provide all information in sufficiently complete detail that each of the contractors preparing bids submits cost proposals for exactly the same, or truly equivalent, items. It is essential that each contractor’s bid proposal be capable of being compared on an “apples to apples” basis. That is, regardless of which contractor builds the facility, it would be essentially identical in all respects relating to performance, reliability, O&M requirements, and useful life. The key to obtaining this result is accuracy and completeness, down to the finest details, of the plans and specifications.

As it has developed in the United States, the bidding process follows the block diagram shown in Figure 1-5. Figure 1-5 illustrates that the first of six phases is to develop a list of potential bidders, as discussed previously. This

list is developed based on past experience, references, and discussion with contractors regarding their capabilities. Other means for developing the list can involve advertising for potential bidders in local and regional newspapers, trade journals, or publications issued by trade associations. In the second phase, a formal request for bids is issued, along with plans, specifications, a bid form, and a timetable for bidding and construction.

The third phase, the pre-bid conference, is key to the overall success of the project. This phase involves assembling all potential contractors and other interested parties, such




Figure 1-5 Illustration of the bidding process.

as potential subcontractors, vendors, and suppliers, for a meeting, preferably at the project site. This site visit normally includes a guided and annotated tour, a presentation of the engineer's/owner's concept of the project, and a question-and-answer period. This meeting can result in identification of areas of the design that require additional information or change. If this is the case, the additional information and/or changes are then addressed to all parties by issuance of formal addenda to the plans and specifications.

The final three phases—receipt and opening of bids, bid evaluation, and award of contract—are highly interrelated. Upon receipt, the bids are reviewed to determine accuracy, completeness, and the lowest responsible bidder. If all bids are higher than was expected, the industry's management and engineers have the opportunity to explore alternatives for redesign of the project. Finally, the project is awarded to the contractor submitting the lowest responsible bid. Construction or implementation can now begin.

Management of Solid Wastes from Industries

By Janet Robinson

Industrial wastes that are discharged to neither air nor water are classified as solid, industrial, or hazardous waste. At the federal level, these wastes are regulated primarily by the Resource Conservation and Recovery Act (RCRA), which contains specific design and management standards for both hazardous wastes (Subtitle C of the Act) and municipal solid wastes (Subtitle D).

Solid Waste

Solid waste (i.e., trash) includes such routine wastes as office trash, un reusable packaging, lunchroom wastes, and manufacturing or processing wastes that are not otherwise classified as "hazardous" under RCRA. These wastes are normally deposited in trash cans and dumpsters and collected by a local trash hauler for disposal

in a municipal landfill or treatment at a municipal incinerator. Although RCRA contains design and other standards for municipal waste management facilities, these facilities are normally governed primarily by state and local regulation.

General solid waste management has come under increasing scrutiny in recent years because of a recognition of the relatively high proportion of hazardous household compounds that solid waste contains. As a result, technical design standards for solid waste landfills are now approaching those for industrial and hazardous waste landfills. In addition, a reduction in the amount of available landfill space nationwide has caused a steady increase in tipping fees (the fees charged for using municipal landfills) and has prompted energetic recycling efforts by many industries and communities.

Industrial or Special Wastes

Industrial or special wastes are nonhazardous manufacturing wastes that are barred from municipal waste treatment or disposal facilities, but do not meet the regulatory definition of "hazardous waste." Examples of these wastes include tannery leather scraps, feathers and other wastes from poultry processing, nonhazardous sludge, and asbestos. These materials are normally disposed of in an industrial landfill, which is generally more strictly regulated, more highly designed, and more closely monitored than municipal landfills. Prior waste testing and approval are necessary before an industry can ship waste to the site.

Industrial wastes are normally regulated on the state and local levels, and most facilities are licensed to accept only certain kinds of waste. Special state approval is often necessary for unusual waste streams.

Hazardous Waste

Hazardous waste is a type of waste that meets specific characteristics of toxicity, ignitability, reactivity, or corrosivity, or is specifically listed as a hazardous waste in RCRA regulations. Examples of wastes that are said to exhibit a hazardous "characteristic" are sludges

containing heavy metals that can be solubilized by certain weak acids (toxic), waste gasoline (ignitable), elemental alkali metals such as sodium or potassium (reactive), and acid wastes (corrosive). “Listed hazardous wastes” include waste commercial products, wastes from specific industrial processes, and wastes (e.g., spent solvents) from nonspecific sources.

Hazardous waste management is arguably among the most complex and comprehensive arenas of environmental regulation. As described in Chapter 3, the RCRA program contains detailed requirements for storing, handling, transporting, treating, and disposing of hazardous wastes, and mandates a “cradle-to-grave” waste tracking system to ensure that wastes are transported and disposed of only by properly licensed firms. Although hazardous waste regulations originated at the federal level, most states are authorized by the EPA to administer their own programs and often promulgate standards that are more strict than the federal standards.

Hazardous waste generators are required by the land disposal restrictions (LDRs), also referred to as “land ban” restrictions, to determine the concentrations of certain constituents in their hazardous wastes. Depending on the constituents present and their concentrations, specific treatment standards, expressed as specified technologies, may be required before the wastes can be land disposed. Residues resulting from treatment of the waste are subject to the same requirements and restrictions.

The distinctions between each of the waste categories (municipal, industrial, and hazardous) as described are not always clear, and the onus is on the individual industry, or appropriate facility, to make the correct determination. Some states, for instance, consider waste oils to be hazardous waste, even though federal law does not. Cans of dried paint are generally regarded as a normal solid waste that can go in a dumpster; however, cans of wet paint, especially those that contain lead or chromate, are usually designated as hazardous. Tannery wastes with trivalent chrome usually can go to an industrial landfill, but some states consider these materials to be hazardous. And, at the

present time, mixtures of listed hazardous wastes and nonhazardous wastes (e.g., rinsewaters containing spent plating solution, a listed hazardous waste) are hazardous in many cases. The so-called mixture rule illustrates the importance of keeping waste streams separate to minimize the volume of hazardous waste for disposal.

In addition to these wastes, most industries produce by-products, scraps, or spent materials that can be reused, reclaimed, or recycled for use on or off site. Depending on their characteristics, these materials may be regulated as hazardous wastes even during the recycling process, or they may become wastes if the demand for them decreases to the point where reprocessing becomes unprofitable. A good working knowledge of the solid waste management laws, or the advice of a reputable consultant or attorney, is imperative to avoid violations of waste RCRA regulations.

Waste management and disposal often represent significant and constantly increasing costs for industry. In order to minimize these costs and reduce the likelihood of enforcement actions by regulators, environmental managers must ensure that a sound program is in place and that all personnel, from laborers to top managers, are vigilant in carrying it out. The following guidelines are often helpful:

- Know the facility waste streams. Like industrial wastewaters, these are seldom the same for different plants. As a first step, facilities must know how much of each type of solid waste they are producing.
- Keep wastes segregated. Heavy fines, as well as criminal sentences, are the penalties for improper waste disposal. Facilities must ensure that hazardous wastes are not put in the trash dumpster, that listed hazardous wastes are not mixed with other nonhazardous materials, and generally that wastes are handled as they’re supposed to be.
- Choose waste disposal firms carefully. Because facilities can be held responsible for clean-up costs of the waste facilities they use, waste transporters and facilities should be chosen carefully.

- Institute a pollution prevention program that includes a vigorous wastes minimization effort. Where possible, reduce the quantity or toxicity of materials used in production.
- Keep areas clean. Frequent spills or releases not only present safety hazards, but also will increase the amount of facility decontamination necessary at closure.
- Keep good records. Industrywide, a great deal of money is wasted on testing and disposing of unknown materials or in investigating areas with insufficient historical data. Good recordkeeping is essential to keep both current and future waste management costs to a minimum.

Excellent texts that discuss in detail the many aspects of solid, industrial, and hazardous waste management are available; these references are listed in the bibliography at the end of this chapter and can be consulted for specific information.

Management of Discharges to the Air

The discharge, or release, of substances to the air, no matter how slight, is regarded as air pollution. Such discharges can be classified in one of only two categories, within compliance or not within compliance. A federal permit as well as a state license or permit must cover all discharges over a certain quantity per unit time. Local ordinances or regulations may also apply.

Discharges to the air can be direct, by means of a stack, or by way of leaks from a building's windows, doors, or other openings. The latter are referred to as "fugitive emissions." Volatilization of organic compounds, such as solvents and gasoline from storage containers, transfer equipment, or even points of use, are important sources of air discharges. Another source of discharge to the air of volatile organics is aerated wastewater treatment systems.

Management of discharges to the air is almost always interrelated with management of discharges to the water and/or the ground because air pollution control devices usually remove substances from the air discharge (usually a stack) and transfer them to a liquid

solution or suspension, as with a scrubber, or to a collector of solids, as with a bag house. Therefore, a total system approach to environmental pollution control is preferred, and this approach should include a pollution prevention program with vigorous waste minimization.

There are three phases to the air pollution cycle: (1) the release, or discharge, at the source; (2) the dispersal of pollutants in the atmosphere; and (3) the reception of pollutants by humans, animals, or inanimate objects. Management of the first phase is a matter of engineering, control, and operation of equipment. The second phase can be influenced by stack height, but meteorology dictates the path of travel of released pollutants. Because the motions of the atmosphere can be highly variable in all dimensions, management of the third phase, which is the ultimate objective of air pollution control, requires knowledge of meteorology and the influence of topography.

Chapter 3 presents a detailed synopsis of laws and regulations that pertain to protection of the nation's air resources. Because these laws are constantly being revised and replaced by new legislation, an updated supplement to this book is published every five years.

Analysis of Manufacturing Process

Successful and cost-effective air pollution control has its foundation in complete awareness of all of the individual sources, fugitive as well as point sources. The process of cataloguing each and every individual air discharge within an industrial manufacturing or other facility is most efficiently done by developing detailed diagrams of the facility as a whole. Depending on the size and complexity of the facility, it may also be advantageous to develop separate diagrams for point sources and sources of fugitive emissions. Next, a separate block diagram for each air discharge source should be developed. The purpose of each block diagram is to illustrate how each manufacturing process and wastewater or solid wastes treatment or handling process contributes unwanted substances to the air. Figures 1-6 through 1-8 are examples of these diagrams.




Figure 1-6 Block diagram of a cement manufacturing plant.




Figure 1-7 Flowsheet for the manufacture of Portland Cement. (Taken from the EPA Development Document PB-238 610, 1974.)




Figure 1-8 Kiln dust collection and handling.

Figures 1-6 through 1-8 are block diagrams that pertain to a facility that manufactures cement from limestone. Figure 1-6 is a diagram of the facility as a whole, showing the cement manufacturing process as well as the physical plant, including the buildings, parking lots, and storage facilities.

Cement, manufactured for use in making concrete, is produced by grinding limestone, cement rock, oyster shell marl, or chalk, all principally calcium carbonate, and mixing it with ground sand, clay, shale, iron ore, and blast furnace slag, as necessary, to obtain the desired ingredients in proper proportions. This mixture is dried in a kiln and then ground again while mixing with gypsum. The final product is then stored, bagged, and shipped. Each of the individual production operations generates, or is otherwise associated with, dust or "particulates" and is a potential source of air pollutant emissions exceeding permit limits.

Figures 1-6 and 1-7 illustrate that raw materials are received and stockpiled at the plant, and are potential sources of particulate emissions because of the fine particles of dust that are generated during the mining, transportation, loading, and unloading processes. Their susceptibility to being blown around if they are out in the open is also a factor. In order to control emissions from these sources, it is necessary to conduct all loading, unloading, grinding, and handling operations within enclosures that are reasonably air-tight, to prevent fugitive emissions, and are also ventilated, for the health and safety of employees. Ventilation requires a fresh air intake and a discharge. The discharge requires a treatment process. Candidate treatment processes for this application include bag houses, wet scrubbers, and electrostatic precipitators, possibly in combination with one or more inertial separators. Each of these treatment technologies is discussed in Chapter 10.

A very important aspect of air pollution control is to obtain and then maintain a high degree of integrity of the buildings and other enclosures that have as at least one of their purposes that of containment of potential air pollutants. Doors and windows and vents must be kept

shut. The building or enclosure must be kept in good repair to avoid leaks. In many cases, it is necessary to maintain a negative pressure (pressure inside building below atmospheric pressure outside building) in order to prevent the escape of gasses or particulates. Maintaining the integrity of the building or enclosure becomes very important in this case to minimize costs for maintaining the negative pressure gradient.

As further illustrated in Figure 1-6, the next series of processing operations constitutes the cement manufacturing process itself, and starts with crushing, then proceeds through mixing, grinding, blending, and drying in a kiln. Each of these processes generates major amounts of particulates, which must be contained, transported, and collected by use of one or more treatment technologies, as explained in Chapter 10. In some cases, it may be most advantageous from points of view of reliability or cost effectiveness, or both, to use one treatment system for all point sources. In other cases, it might prove best to treat one or more of the sources individually.

Continuing through the remaining processes illustrated in Figures 1-6 and 1-7, the finished product (cement) must be cooled, subjected to finish grinding, cooled again, stored, then bagged and sent off to sales distribution locations. Again, each of these operations is a potential source of airborne pollutants, in the form of particulate matter, and it is necessary to contain, transport, and collect the particulates using hoods, fans, ductwork, and one or more treatment technologies as explained in Chapter 10.

The next step in the process of identifying each and every source of air pollutant discharge from the cement manufacturing plant being used as an example is to develop a block diagram for each individual activity that is a major emission source. Figure 1-8 illustrates this step. Figure 1-8 is a block diagram of the process referred to as the "kiln," which dries the unfinished cement using heat. This diagram pertains to only the manufacturing process and does not include sources of emissions from the physical plant, most of which are sources of fugitive emissions.

Figure 1-8 shows that the inputs to the kiln include partially manufactured (wet) cement and hot air. The outputs include dry partially manufactured cement and exhaust air, laden with cement dust, or particulates. The diagram then shows that there are four candidate technologies to treat the exhaust gas to remove the particulates before discharge to the ambient air. The four candidate technologies are:

- Electrostatic precipitator
- Cyclone
- Bag house
- Wet scrubber

Each of these technologies is worthy of further investigation, including their technical feasibility and cost effectiveness. Also, each of these technologies results in a residual, which must be handled and disposed of properly.

For instance, the bag house technology produces a residual that can be described as a dry, fine dust that is essentially “raw” cement. This material can be stored in a “dust bin” (the dust bin must be managed as a potential air pollution source), and from there can be:

- Returned to the kiln in an attempt to increase the yield of the manufacturing process
- Buried
- Hauled (as a by-product) to another point of use
- Mixed with water to form a slurry

The first of the aforementioned options is only a partial solution, at best, because there must be some “blow down,” if only to maintain quality specifications for the finished product. The second option, “burial,” is a final solution, but it must be accomplished within the parameters of good solid waste disposal practice, and the third option, “water slurry,” is only an interim treatment step. Forming a water slurry transforms the air pollution potential problem into a water pollution potential problem (“cross-media” effect). The slurry can be transported to another location without risk of air pollution, but it must then be dewatered by sedimentation before final disposal within the

bounds of acceptable solid waste and wastewater disposal practices.

The foregoing example illustrates how an entire manufacturing facility must be analyzed and diagrammed to define each and every source of discharge of pollutants to the air as an early step in a technically feasible and cost-effective air pollution control program. The next steps are presented as follows.

Wastes Minimization and Characterization Study

After all potential sources of air pollutants have been identified, the objectives of the industry’s pollution prevention program should be addressed. As explained in Chapter 7, wastes minimization is only one aspect of a pollution prevention program, but it is a critical one. Each source should first be analyzed to determine if it could be eliminated. Next, materials substitution should be considered to determine if there are opportunities to use nonobjectionable substances in place of currently used objectionable ones. Then, it should be determined whether a change in present operations, for instance, improved preventive maintenance or improved equipment, can significantly reduce pollutant generation. Finally, it should be determined whether improvements in accident and spill prevention as well as improved emergency response are warranted.

After a prudent wastes minimization program has been carried out, a period should be allocated to determine if the changes made appear to be permanent. This phase of the overall air pollution control program is important because, if the determination of air pollutant flow rates and concentrations is made on the basis of improved maintenance and operational procedures, and if the facility regresses to the way things were done previously, the handling and treatment equipment designed on the basis of the improved procedures will be overloaded and will fail.

Once all air pollution flows and loads have become stabilized, each of the sources should be subjected to a characterization program to determine flow rates and target pollutant

concentrations (flows and loads) for the purpose of developing design criteria for handling and treatment facilities. Examples of handling facilities are hoods, fans, and ductwork. Examples of treatment equipment are electrostatic precipitators and fabric filters (bag houses, for instance). The characterization study is essentially the process of developing estimates of emission rates based on historical records of either the facility under consideration or those of a similar facility. For instance, materials balances showing amounts of raw materials purchased and products sold can be used to estimate loss rates.

Treatment Objectives

Treatment objectives are needed to complete the development of design criteria for handling and treatment equipment. The air discharge permit, either in hand or anticipated, is one of the principal factors used in this development. Another principal factor is the strategy to be used regarding allowances, i.e., whether or not to buy allowances from another source or to reduce emissions below permit limits and attempt to recover costs by selling allowances. This strategy and its legal basis are discussed in Chapter 3. Only after all treatment objectives have been developed can candidate treatment technologies be determined; however, it may be beneficial to employ an iterative process, whereby more than one set of treatment objectives and their appropriate candidate technologies are compared as competing alternatives in a financial analysis to determine the most cost-effective system.

Selection of Candidate Technologies

After the characteristics of air discharges, in terms of flows and loads, have been determined (based on stabilized processes after changes were made for wastes minimization), and treatment objectives have been agreed upon, candidate technologies for removal of pollutants can be selected. The principles discussed in Chapters 2 and 8 are used as the bases for this selection. The selection should be based on one or more of the following:

- Successful application in a similar set of conditions
- Knowledge of chemistry
- Knowledge of options available, as well as knowledge of capabilities and limitations of those alternative treatment technologies

The next step is to conduct bench scale investigations to determine technical and financial feasibility.

Bench Scale Investigations

Unless there is unequivocal proof that a given technology will be successful in a given application, a rigorous program of bench scale followed by pilot scale investigations must be carried out. Such a program is necessary for standard treatment technologies as well as innovative technologies. The cost for this type of program will be recovered quickly, as a result of the equipment being appropriately sized and operated. Under-designed equipment will simply be unsuccessful. Over-designed equipment will cost far more to purchase, install, and operate.

The results of a carefully executed bench scale pollutant removal investigation provide the design engineer with reliable data on which to determine the technical feasibility of a given pollutant removal technology, as well as a preliminary estimate of the costs for purchase, construction and installation, and operation and maintenance. Without such data, the design engineer is forced to use very conservative assumptions and design criteria. The result, barring outrageous serendipity, will be unnecessarily high costs for treatment throughout the life of the treatment process.

Pilot Scale Investigations

Bench scale investigations are only the first step in a necessary procedure for determining the most cost-effective treatment technology. Inherent scale-up problems make it inadvisable, to say the least; imprudent, to be conservative; and negligent, to be truthful, to design a full-scale treatment system based only

on data from bench scale work. The next step after bench scale investigations is the pilot scale work. A pilot plant is simply a small version of the anticipated full-scale treatment system.

A good pilot plant should have the capability to vary operational parameters. It is not sufficient to merely confirm that successful treatment, in terms of compliance with discharge limitations, can be achieved using the same operating parameters as was determined by the bench scale investigations. Again, it would be outrageous serendipity if the results of the bench scale investigations truly identified the most cost-effective, as well as reliable, full-scale treatment system design and operating parameters.

The pilot scale investigation should be carried out at the industrial site, using a portion of the actual gas stream to be treated. A pilot scale treatment unit, for instance a wet scrubber, or an electrostatic precipitator, can, in many cases, be rented from a manufacturer and transported to the site on a flatbed truck.

The pilot plant should be operated continuously, over a representative period, so as to include as many of the waste stream variations that are expected to be experienced by the full-scale unit as is reasonably possible. One difficulty in carrying out a pilot scale study is that smaller units are more susceptible to upset, fouling, plugging, or other damage from slug doses caused by spills or malfunctions in processing equipment. Also, unfamiliarity on the part of the pilot plant, either with the gas stream being treated, the processing system from which the stream is generated, or the pilot plant itself, can result in the need for prolonged investigations.

Similar to wastewater treatment pilot plant investigations, it is critically important to operate a pilot scale treatment system for a sufficiently long period to:

- Include as many combinations of wastes that are reasonably expected to occur during the foreseeable life of the prototype system, as is reasonably possible.

- Evaluate as many combinations of operation parameters as is reasonably possible. When operation parameters are changed, for instance the volumetric loading of an air scrubber, the chemical feed rate of a pH neutralization system, or the effective pore size of a bag house type fabric filter, the system must operate for a long enough time to achieve steady state before data to be used for evaluation are taken. Of course, it will be necessary to obtain data during the period just after operation parameters are changed, to determine when steady state has been reached.

Observations should be made to determine whether performance of the pilot plant using a particular set of parameters is in the range of what was predicted from the results of the bench scale investigations. If the difference in performance is significant, it may be prudent to stop the pilot scale investigation work and try to determine the cause.

Preliminary Designs

The results of the pilot scale investigations show which technologies are capable of meeting the treatment objectives, but do not enable an accurate estimation of capital and operating costs. A meaningful cost-effectiveness analysis can take place only after preliminary designs of those technologies that produced satisfactory effluent quality in the pilot scale investigations have been completed. A preliminary design, then, is a design of an entire waste treatment facility, carried out in sufficient detail to enable accurate estimation of the costs for constructing and operating a waste treatment facility. It must be complete to the extent that the sizes and descriptions of all of the pumps, pipes, valves, tanks, concrete work, buildings, site work, control systems, and labor requirements are established. The difference between a preliminary design and a final design is principally in the completeness of detail in the drawings and specifications. It is almost as though the team that produces the preliminary design could use it to directly construct the plant. The extra detail that goes into the final design is

principally used to communicate all of the intentions of the design team to people not involved in the design.

Economic Comparisons

The choice of treatment technology and complete treatment system between two or more systems proven to be reliably capable of meeting the treatment objectives should be based on a thorough analysis of all costs over the expected life of the system.

Bibliography

- American Society of Civil Engineers, *Manual of Practice: Quality in the Construction Project—A Guide for Owners, Designers, and Contractors*, New York, 1988.
- CELDS: United States Army Corps of Engineers, Construction Engineering Research.
- Chanlett, E.T., *Environmental Protection*, 2nd ed., McGraw-Hill, New York, 1979.
- Dunne, T., and L.D. Leopold, *Water in Environmental Planning*, Freeman, San Francisco, 1978.
- Pruett, J.M., "Using Statistical Analysis for Engineering Decisions," *Plant Engineering*, May 13, 1976, pp. 155–157.
- U.S. Environmental Protection Agency, *Design Criteria for Mechanical, Electric, and Fluid System and Component Reliability*, EPA-430-99-74-001, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitations and Guidelines and New Source Performance Standards for the Cement Manufacturing Point Source Category*, EPA/PB-238 610, January 1974.
- U.S. Environmental Protection Agency, *ISO 14000 Resource Directory*, National Risk Management Research Laboratory, EPA/625/R-97/003, Cincinnati, Ohio, 1997.
- Vesilind, P.A., *Environmental Pollution and Control*, 10th ed., Ann Arbor Science Publishers, Ann Arbor, Michigan, 1982.
- Wachinski, A.M., and J.E. Etzel, *Environmental Ion Exchange*, Lewis Publishers, New York, 1997.
- Willis, J.T., (ed.), *Environmental TQM*, 2nd ed., McGraw-Hill, New York, 1994.

2 Fundamentals

Introduction

Although the laws and regulations that require industrial wastewater treatment are constantly changing, the fundamental principles on which treatment technologies are based do not change. This chapter presents a summarized version of the basic chemistry and physics that treatment technologies are based on, with the objective of showing that a command of these principles can enable quick, efficient identification of very effective treatment technologies for almost any given type of wastewater.

The fundamental idea upon which the approach suggested in this chapter is based can be stated as follows: If the mechanisms by which individual pollutants become incorporated into a waste stream can be identified, analyzed, and described, the most efficient methodology of removal, or treatment, will be obvious.

As an example of the usefulness of this approach to quickly develop an effective, efficient treatment scheme, the leachate from a landfill was to be pretreated, then discharged to a municipal wastewater treatment facility (publicly owned treatment works [POTW]). Because the waste sludge from the POTW was to be disposed of by land application, a restrictive limitation was placed on heavy metals in the pretreated leachate. Analysis of the leachate showed that the content of iron was relatively high. Other metals such as cadmium (probably from discarded batteries), zinc, copper, nickel, and lead were also present in excess of the concentrations allowed by the pretreatment permit, but substantially lower than iron.

Knowledge of the following enabled quick conceptualization of a treatment scheme:

- All metals are sparingly soluble in water.
- Iron in the divalent state is highly soluble in water, whereas iron in the trivalent state is not.

- Iron can be converted from the divalent state to the trivalent state by passing air through the aqueous solution containing the dissolved iron. (The oxygen in the air oxidizes the ferrous (divalent) ion to ferric (trivalent) ion.)
- Because substances such as cadmium, zinc, and lead are so sparingly soluble, they tend to adsorb to the surface of almost any solid particle in an aqueous environment.

In this scheme, the leachate would be conveyed to a simple, open concrete tank where air was bubbled through it. In this tank, insoluble iron oxide was formed from soluble ferrous compounds, the precipitated iron oxide particles would coagulate and flocculate because of the gentle mixing action of the air bubbles, and dissolved species of other metals would adsorb to the iron oxide particles. Next, the aerated leachate was allowed to settle, effectively removing all of the heavy metals to within the limits of the pretreatment permit.

The following sections of this chapter have been developed to explain the fundamental chemical and physical principles by which pollutants become dissolved, suspended, or otherwise incorporated into wastewater. At the end of this chapter, several simple examples, similar to that involving the leachate, are given to further illustrate the usefulness of the technique whereby fundamental concepts of chemistry and physics can be applied to efficiently deduce optimal treatment schemes.

Characteristics of Industrial Wastewater

Industrial wastewater is the aqueous discard that results from the use of water in an industrial manufacturing process or the cleaning activities that take place along with that process.

Industrial wastewater is the result of substances other than water having been dissolved or suspended in water. The objective of industrial wastewater treatment is to remove those dissolved or suspended substances. The best approach to working out an effective and efficient method of industrial wastewater treatment is to examine those properties of water and of the dissolved or suspended substances that enabled or caused the dissolution or suspension, then to deduce plausible chemical or physical actions that would reverse those processes. Familiarity with the polar characteristics of water is fundamental to being able to make such deductions.

The Polar Properties of Water

Water molecules are polar. This polarity arises from the spatial arrangement of protons and electrons in the individual hydrogen and oxygen atoms that make up each water molecule. Considering hydrogen first, it is the smallest of the elements. Hydrogen consists of one proton within a small, extremely dense nucleus and one electron contained within an orbital that is more or less spherical and surrounds the nucleus. An orbital is a region in space where, according to the theory of quantum mechanics, an electron is most likely to be found. Figure 2-1 is a two-dimensional portrayal of the three-dimensional hydrogen atom, but is sufficient to show that, at any given instant, the negatively charged electron is able to counteract the positively charged nucleus within only a small region of the space that the atom occupies.




Figure 2-1 Diagram of a hydrogen atom.

Figure 2-1 illustrates that, if a charge detector could be placed near the hydrogen atom, at any given instant, it would detect a negative charge in the region near the electron and a positive charge everywhere else. The positive charge would register strongest in the region opposite in space to the region occupied by the electron. At any given instant then, a hydrogen atom is a polar object, having a negatively charged region and a positively charged region. In this sense, at any given instant, a hydrogen atom exhibits properties of a tiny magnet; however, the electron is in continual motion, and at any given instant can be found anywhere within the approximately spherical orbital surrounding the nucleus. The net effect of an isolated hydrogen atom is to appear electrically neutral and not polar.

Before proceeding to an examination of the structure and electrically charged characteristics of oxygen, and then water, it is useful to examine the construction of the six elements that lie between hydrogen and oxygen in size, and to consider, in a step-by-step way, how each successive proton and its associated electron influence the characteristics of each element. Several "rules" govern where electrons are to be found within an atom or a molecule. The first has to do with energy level. As atoms increase in size, the additional protons always reside in the nucleus, but the additional electrons reside in successively larger orbitals that, in turn, exist within successively larger concentric shells. The electrons within orbitals that are closer to the nucleus are of lower energy level than those in larger orbitals. One of the strict rules of electron location is that no electron can occupy an orbital of higher energy level until all orbitals of lower energy are "full." A second rule is that only two electrons can occupy any atomic orbital, and these electrons must have opposite spins. These electrons of opposite spin are called "electron pairs." Electrons of like spin tend to get as far away from each other as possible. This rule is the "Pauli exclusion principle" and is the most important of all the influences that determine the properties and shapes of molecules.

Figures 2-2(a) and (b) show two ways to depict a spherical electron orbital. Figure 2-2(a) presents the orbital as a spherical cloud surrounding the nucleus. Figure 2-2(b) is simply a convenient, two-dimensional representation of the orbital. Figure 2-3 shows the shapes of the two orbitals of lowest energy level, which are the two smallest orbitals as well.

Figure 2-3(a) shows that the smallest and, therefore, lowest energy level orbital is designated the “1s” orbital and is approximately spherical. The center of the 1s orbital coincides with the center of the atom’s nucleus. Figure 2-3(b) shows that the next larger orbital is called the “2s” orbital and is also approximately spherical, with its center coinciding with the center of the nucleus. Next in size (and energy level) are three orbitals of equal energy level that have two approximately spherical lobes each, and can thus be described as having

shapes similar to dumbbells (as in weightlifting). These orbitals, named “2p orbitals,” are shown in Figures 2-4(a), (b), and (c). Figure 2-4(a), (b), and (c) show that the three two-lobed orbitals are arranged so as to be as far away from one another as possible, and are thus arranged such that the center of each lobe lies on one of three axes that are perpendicular to one another.

The center of the atomic nucleus coincides with the origin of the three axes. The axes are referred to as the x, y, and z-axes, and the three orbitals are called the $2p_x$, $2p_y$, and $2p_z$ orbitals.

The electron orbitals exist within electron shells. The electron shells are concentric and are numbered 1, 2, 3, 4, etc., and the smaller shells, closer to the nucleus, must become full before electrons will be found in orbitals in higher, or larger, shells. Shell 1 is full with one (1s) orbital. The total number of electrons in shell 1, when it is full, then, is two. Shell 2 is




Figure 2-2(a) Spherical electron orbital as a spherical cloud surrounding the nucleus.



Figure 2-2(b) Two-dimensional representation of the electron orbital.




Figure 2-3(a) 1s orbital.




Figure 2-3(b) 1s and 2s orbital.

full when it contains four (one 2s and three 2p) orbitals. Thus, a full shell 2 contains eight electrons. Figure 2-5 shows an atom with the five orbitals of lowest energy level. The 1s orbital

resides within shell 1, and the 2s, $2p_x$, $2p_y$, and $2p_z$ orbitals reside within shell 2. The center of the nucleus coincides with the origin of the three axes.




Figure 2-4(a) $2p_x$ orbital.





Figure 2-4(b) $2p_y$ orbital.






Figure 2-4(c) $2p_z$ orbital.






Figure 2-5 Arrangement of electron orbitals within shells 1 and 2.

Electrical and Thermodynamic Stability

Chemical elements are electrically stable when the number of electrons equals the number of protons. They are thermodynamically stable when their outermost, or largest, electron shell is full. An element that has more or less electrons than protons, as would result from the ionic bonding process, carries an electric charge. If electrons are in excess, the charge is negative and the element is said to be an anion. If protons are in excess, the charge is positive and the element is said to be a cation. Both cations and anions are electrically active and are therefore said to be electrically unstable. Cations and anions are attracted to each other because of opposite electric charges, and thus form chemical compounds.

Because of a strong tendency to attain thermodynamic stability, atoms tend to either lose electrons until the next smaller shell (being full) becomes the outermost shell, or gain electrons until the original outermost shell becomes full. Electrons in shells that are not full are called “valence electrons” and are active in chemical bonding. Electrons in full shells are essentially unreactive. The only role these electrons play in chemical bonding is that of insulating the valence electrons from the attraction of the positively charged nucleus. This will be demonstrated in the discussion on electronegativity.

The elements at the far right of the periodic table have full outermost shells in their natural state. The number of electrons equals the number of protons. Being both electrically stable and thermodynamically stable, these elements are unreactive. They are known as the “noble elements.”

The element that is next larger in size to hydrogen is helium. Helium has two protons in its nucleus and two electrons in the single (1s) orbital that resides within shell 1. Helium is thus both electrically stable (two protons and two electrons) and thermodynamically stable (full outer shell) and is one of the noble elements. Helium also has two neutrons within its nucleus, which add mass to the atom but do not affect the reactivity of the atom.

The element next in size larger than helium is lithium. Lithium consists of three protons in the nucleus and three electrons. Two of the electrons reside within the 1s orbital within shell 1, and the third electron resides within the 2s orbital within shell 2. Lithium is an extremely reactive element because of its tendency to give up its third electron, thus leaving it with a full outer shell (the 1s shell) and with a positive charge. When the lithium atom gives up one electron, it is said to be a monovalent cation.

Each of the next successively larger elements—beryllium, boron, carbon, nitrogen, and oxygen—have, respectively, one additional proton and one additional electron. While the protons are all in the nucleus, the electrons are in, successively, the 1s orbital within shell 1, and the 2s, then the 2p orbitals within shell 2. Beryllium has two electrons in shell 2, both residing within the 2s orbital. Although this outermost electron orbital is full, the outermost shell, shell 2, is not. Shell 2 is full when it contains eight electrons. Beryllium, therefore, strongly tends to lose two electrons, thus becoming a divalent cation. Boron, the next larger element, must either lose three electrons or gain five to attain a full outer shell. Its tendency is to lose three rather than gain five. It therefore tends to become a cation, but less strongly so than lithium or beryllium.

Carbon, the next larger element, has six protons and six electrons. Carbon must therefore lose four electrons or gain four to attain a full outer electron shell. In fact, carbon has almost no tendency to do either, but tends to attain a full outer shell by way of a process called electron sharing. Using the electron-sharing mechanism, carbon can enter into what is known as the covalent bonding process, as illustrated in Figure 2-6.

Figure 2-6 depicts the formation of methane, CH_4 , the result of the covalent bonding of four hydrogen atoms with a single carbon atom. Figure 2-7 shows a carbon atom with each of the four valence electrons arranged in space so that they are as far away from one another as they can be and still occupy the same electron shell. Some rearranging of orbitals is required to make this configuration possible. Because carbon has a total of six electrons, it would be expected, on the basis of the foregoing discussion, that two would reside as a pair within the 1s orbital, another pair would reside in the 2s orbital, and one unpaired electron would reside in each of two 2p orbitals; however, this arrangement would allow only two covalent bonds, yielding CH_2 if those bonds were with hydrogen atoms. This configuration would result in carbon having six electrons in its outer shell, whereas eight are required for a full

outer shell. What actually happens, because of the very strong tendency for carbon to attain a full outer shell of eight electrons, is that the 2s orbital and the three 2p orbitals form four hybrid orbitals of equal energy level having one unpaired electron in each. These four hybrid orbitals are called sp^3 orbitals and are shaped as shown in Figure 2-7. As shown in Figure 2-7, an sp^3 orbital has two lobes of unequal size. The nucleus of the atom resides between the two lobes. Figure 2-8 shows that the four hybrid sp^3 orbitals of a carbon atom are arranged to be as far from one another as possible. The carbon atom thus attains a shape such that, if straight lines are drawn to connect the outer limits of each lobe, a tetrahedron will be drawn. Thus, carbon atoms are said to exist in the shape of a regular (all sides equal in size) tetrahedron, with one valence electron available to form a covalent bond at each corner of the tetrahedron, and with the center of the nucleus coinciding with the center of mass of the tetrahedron. Figure 2-9 shows a two-dimensional representation of Figure 2-6. Figure 2-10 depicts four hydrogen atoms, each needing one additional electron to fill its outer shell, combining with each of the four valence electrons of the carbon atom to form the methane molecule. The bonds between the hydrogen atoms and the carbon atom that




Figure 2-6 Formation of a molecule of methane.

together makeup the methane molecule are covalent bonds. Each of the four electron pairs is shared, and the molecule exists as a cohesive unit. This is in contrast to compounds of lithium, for example. In water solution, lithium gives up its one valence

electron to another atom—chlorine, for instance—and exists as the discrete lithium ion, Li^+ , not physically attached to another ion. Thus, the principal difference between covalent bonds and ionic bonds has been illustrated.



Figure 2-7 Configuration of a hybrid sp^3 orbital.




Figure 2-8 The four sp^3 orbitals of an atom of carbon.




Figure 2-9 Two-dimensional representation of a carbon atom showing the four valence electrons.

Chemical Structure and Polarity of Water

Moving on to an examination of the characteristics of oxygen, and then water, it is seen that oxygen has eight protons in its nucleus and eight electrons arranged such that two reside in the 1s orbital within shell 1, two are within the 2s orbital within shell 2, and four are within the 2p orbitals in shell 2 such that one 2p is full with a pair and the other two 2p orbitals have

one unpaired electron each. Two additional electrons are needed to fill shell 2. One way this can be accomplished is for the oxygen atom to form covalent bonds with each of two hydrogen atoms. Figure 2-11 shows how a water molecule is created by the formation of two covalent bonds.

Figure 2-11 shows the spatial arrangement of the six valence electrons of oxygen. Four of the six electrons are arranged into two pairs,




Figure 2-10 A carbon atom forms covalent bonds with each of four hydrogen atoms to produce a molecule of methane.




Figure 2-11 An oxygen atom forms covalent bonds with each of two hydrogen atoms to produce a molecule of water.

and two are arranged so that each can participate in a covalent bond, and thus be included in an electron pair. When the covalent bonds have been formed, the resulting four electron pairs arrange themselves to be as far away from one another as possible, resulting in another tetrahedral structure of four sp^3 orbitals similar to that of the carbon molecule. The mutual repulsion caused by like charges (negative) associated with each of the electron pairs causes them to form the tetrahedral structure and thus be as far away from one another as possible and still occupy the same electron shell.

There is a difference between the methane molecule's tetrahedral structure and that for the water molecule, for the following reason: In the case of methane, there are equivalent hydrogen atom-carbon valence electron structures at each of the four corners. In the case of water, two of the corners of the tetrahedral structure contain the hydrogen-oxygen valence electron pair and two contain simply an electron pair. There is equal repulsion between the electron pairs in the case of methane; therefore, a regular tetrahedron structure results. The structure of the methane molecule is almost perfectly symmetrical. In the case of water, however, equal repulsion does not exist between the structures at the corners of the tetrahedral molecule, and a distorted tetrahedral structure results.

Figure 2-12 shows a slightly different two-dimensional representation of a water molecule. Figure 2-12 shows that, in the region of each of the two hydrogen atoms that are involved in the makeup of each water molecule, the electron pair that makes up the covalent bond spends most of the time in the space between the oxygen atom and the hydrogen's nucleus. The result is that the positive charge of each hydrogen nucleus is exposed. Figure 2-12 further shows that the two electron pairs that occupy the corners of the distorted tetrahedral structure of the water molecule other than the two occupied by hydrogen atoms display a negative charge. Therefore, each water molecule is seen to have regions of positive charge and regions of negative charge. Each water molecule thus exhibits characteristics of a tiny

magnet, having a negative "pole" and a positive "pole," and is said to be a polar molecule. Methane, on the other hand, as described previously, has a tetrahedral structure where all four corners are identical. Methane is therefore said to be nonpolar.

The consequence of the polar versus nonpolar nature of molecules is well illustrated by the remarkable difference in physical state between water and methane. Water has a molecular weight of 18, and is liquid at room temperature. Methane has a molecular weight of 14, very close to that of water, but is a gas at room temperature. The reason that such a low-molecular-weight substance as water is liquid at room temperature is illustrated in Figure 2-13. Figure 2-13 shows that water molecules, acting like tiny magnets, attract each other, whereas methane molecules, having no polar properties, have no attraction for one another. The result in the case of water is that the space between molecules is relatively small, compared to the larger space between methane molecules at room temperature.

Hydrogen Bonding

The attraction between the positive areas on the hydrogen atoms of each water molecule and the negatively charged areas that result from the two unbonded electron pairs on the oxygen atom of each water molecule is referred to as "hydrogen bonding." Hydrogen bonding not




Figure 2-12 Relative position of electron pairs on a water molecule.




Figure 2-13 Strong attractive forces between molecules of water as compared to weak attractive forces between molecules of methane.

only accounts for water existing as a liquid at room temperature, but it also accounts for the capability of water to solvate, or dissolve, many substances; thus, its nickname, “the universal solvent.”

Polar Solvents versus Nonpolar Solvents — True Solutions

A solvent is a medium into which other substances can dissolve. When dissolved, these substances, in accordance with the second law of thermodynamics (explained following, but basically states that, “In nature, everything tends to become randomly distributed.” It takes a force of some kind, which requires energy, to counteract this tendency), become distributed uniformly throughout the volume of the solvent. As illustrated in Figure 2-14, substances that ionize into cations and anions are soluble in polar solvents such as water. Substances that do not ionize, such as oil, are poorly soluble (everything is soluble to some degree, in water)

in polar solvents, but are highly, and in many cases infinitely, soluble in nonpolar solvents. Substances that are polar in nature and therefore soluble in water are said to be “hydrophilic.” Nonpolar substances are only sparingly soluble in water and are said to be “hydrophobic.”

The mechanism of solubility of sodium chloride in water can be used to illustrate how hydrophilic substances become dissolved in water. Sodium chloride is made up of sodium ions, each of which has a single electron in its outer shell, and chloride ions, each of which needs one electron to fill its outer shell. Sodium chloride exists as a crystalline solid in its pure form, and in water, it ionizes to sodium ions and chloride ions (cations and anions, respectively). The positively charged sodium ions are attracted to the negatively charged sites on water molecules, and the negatively charged chloride ions are attracted to the positively charged sites on water molecules (hydrogen bonding).




Figure 2-14 Shows why sodium chloride is soluble in water.

The mechanism involved in the dissolution of sodium chloride in water is hydrogen bonding, and the second law of thermodynamics accounts for the driving force. The second law of thermodynamics states that, in nature, all systems tend toward a state in which free energy is minimized. The free energy of a system is given by the following expression:

$$G = H - TS \quad (2-1)$$

Where G is the free energy (often referred to as the Gibbs free energy) and is that portion of the heat content, or enthalpy, H , that is available to do work, isothermally; T is the absolute temperature; and S is entropy. Entropy can be described as “degree of disorganization,” that is, the more highly organized a system is, the lower its entropy. Consider a glass of water into which a teaspoon of sodium chloride (table salt) is placed. Because it has a density greater than that of water, the crystals of sodium chloride will sink to the bottom of the glass and sit there for awhile. After a period, however, the salt crystals will “disappear,” having gone into solution. Explanation of this phenomenon provides a convenient way to explain both the second law of thermodynamics and the Gibbs free energy equation.

When the salt is on the bottom of the glass, the system is highly organized. The salt is in one place and the water is in another, although they are both in the same container. The enthalpy, H , includes all of the bond energies within the system, which includes all of the ionic bonds within the sodium chloride crystals

and all of the bonds within the water molecules and the hydrogen bonds between water molecules. Over a period, water molecules surround each individual sodium ion and each individual chloride ion, until they are all dissolved and evenly dispersed throughout the volume of water in the glass. When this process is complete, entropy is maximized (disorganization of the system is complete; everything in the glass is randomly distributed), and the sum of all the chemical bond energies within the system is greater than it was before dissolution took place. That is, the sum of all the bond energies of the bonds caused by electrical attraction between water molecules and chloride ions (hydrogen bonds), plus the bonds of electrical attraction between water molecules and sodium ions, plus the bonds within the water molecules themselves, is greater than the sum of all the bond energies within the system when the salt was on the bottom of the glass.

Thus, it is seen that water dissolves substances that are capable of ionizing or otherwise exhibiting an electric charge, either positive or negative, and the resulting mixture of water and dispersed ions is referred to as a “true solution.” Most, if not all, substances whose molecules have been formed by the ionic bonding process are soluble in water and are referred to as hydrophilic. Substances such as light mineral oil, which is made up of molecules formed by the covalent bonding process, are hydrophobic, and form true solutions in nonpolar solvents. These hydrophobic substances can be induced to go into a state that is

equivalent in many ways to a water solution, by a process known as emulsification. An emulsion is equivalent to a solution in that it consists of a stable mixture that will not separate under quiescent conditions. A sample taken from anywhere within the volume of the mixture is representative of the mixture as a whole, and as the mixture flows from one place to another, it does not change in character. At least two processes can produce such a mixture; both can be referred to as emulsification.

Emulsification

Pure hexane is a liquid that is sparingly soluble in water. It is composed of a six-carbon chain having hydrogen atoms bonded by covalent bonds at all bonding sites other than those involved in the six-carbon chain. Figure 2-15 depicts a hexane molecule.

Hexane has a molecular weight of about 86 and exists as a liquid at room temperature. Very small electrical attractive forces exist between molecules, resulting from the fact that, at the site of any given hydrogen atom bonded by covalent bonds to a carbon atom, when both of the electrons involved in the bond are located between the hydrogen and the carbon, the nucleus of the hydrogen atom presents a positively charged site on the molecule. Figure 2-16 depicts this state.




Figure 2-15 A single molecule of hexane.



Figure 2-16 Carbon-hydrogen covalent bond exhibiting positive charge.

In fact, the two electrons involved in each hydrogen-carbon bond are in continuous orbital motion around the hydrogen nucleus, so the time during which the positively charged nucleus is exposed is very brief, it is intermittent, and the strength of the charge is relatively weak. In exactly the same fashion, when one or both of the electrons involved in any given hydrogen-carbon bond are on the side of the hydrogen nucleus that is away from the carbon atom, a negative charge is presented to the surrounding environment. At any given instant, then, there is a probability that there will be one or more positively charged sites on each hexane molecule and one or more negatively charged sites, and there will be an electrical, or magnetic-type attraction between hexane molecules. These charged sites are much weaker than those involved in the hydrogen bonding that is characteristic of water, however; therefore, hexane is sparingly soluble in water.

Hexane can be emulsified in water, however, and the result is, for practical purposes, equivalent to true solution as far as industrial waste is concerned. There are at least two ways to accomplish emulsion. One way is to use an emulsifying agent, such as a detergent. The second way is to mix hexane and water together vigorously. The mechanisms of these two methods for forming an emulsion are explained as follows.

Forming an Emulsion with an Emulsifying Agent

Figure 2-17 presents a representation of a typical detergent.

The detergent molecule shown in Figure 2-17 consists of two active components, a group that will ionize in water, in this case the sulfonate group ($-SO_3^-$), and a group that is nonpolar in nature and is therefore attracted to, and soluble in, organic material such as fats, oils, and greases. Figure 2-18 depicts the process by which detergent molecules form a link between water and substances that are only sparingly soluble in water (note—dirt usually adheres to a thin film of oil on skin, clothing, etc.).

The organic, nonpolar portion of the detergent molecule clings to the oily particle. The particle of "dirt" also clings to the oily particle. The forces involved include the strong hydrophobic nature of the dirt, the oil, and the nonpolar portion of the detergent molecule. There are attractive forces between the nonpolar portion of the detergent molecule and the oily particle as well as between certain portions of the "dirt" particle and the oily particle. The strong hydrophobic nature of the oil and dirt particles results in the medium of water molecules forcefully excluding these substances from the bulk solution. The free energy of the system is reduced when hydrogen bonds between water molecules are formed, whereas no such bonds

form between molecules of water and molecules that make up the dirt or oil particles.

In summary, the organic portion of the detergent sticks to the oil or dirt; the ionized inorganic portion dissolves in water; and, the detergent thus forms a link between the two.

The second law of thermodynamics is thus seen to be the driving force in the process of cleaning with water and a detergent. Ordinary soap, of course, cleans in exactly the same way as synthetic detergents. The principal differences between soaps and detergents are that the hydrophobic, organic (nonpolar) portion of soaps is usually a more simple organic compound than that of a typical detergent, and the hydrophilic (ionizable) portion of a typical detergent is characteristically the salt of a




Figure 2-17 A molecule of alkylbenzenesulfonate.



Figure 2-18 Detergent molecule forming a link between water and oily particle with attached “dirt.”

strong acid (sodium sulfonate, for instance), whereas it is usually the salt of a weak acid (sodium carbonate, for instance) in the case of soaps.

Figure 2-19 shows how oil and other nonpolar substances can be held in a solution-like suspension, referred to as an emulsion, by an emulsifying agent such as a synthetic detergent.

Forming an Emulsion by Vigorous Mixing

Figure 2-20 shows an emulsion of a light oil in water. By vigorous mixing, as in a kitchen blender, the oil has been separated into very fine droplets. There is an electric charge on the surface of each oil droplet. This charge can be

either positive or negative, depending on the type of oil and whatever ions or other substances exist in the water that adhere to the surface of the oil droplets, but is almost always negative.

The fact that the charge is of the same type on all droplets causes mutual repulsion between the droplets. This mutual repulsion is the source of stability of the emulsion. At least two forces tend to destabilize the emulsion, and cause the oil and the water to separate into distinct phases. Gravity is one force. If the oil is less dense than water, gravity tends to cause the water to sink below all of the oil, resulting in the oil forming a




Figure 2-19 Emulsion by use of an emulsifying agent.




Figure 2-20 Emulsion by vigorous mixing.

separate layer on top of the water. Gentle mixing tends to cause the droplets of oil to collide, whereupon the droplets would coalesce until finally the oil would form a completely separate phase over or under the water, depending on its density. If the mutually repulsive forces caused by similar surface charges on the droplets are sufficiently strong, then the destabilizing forces will not prevail, and the emulsion will remain stable.

Colloidal Suspensions

A third type of industrial wastewater mixture, in addition to true solutions (pollutants dissolved in water) and emulsions (pollutants suspended in water by emulsification) is the colloidal suspension. In all three types of wastewater mixture, the pollutants are held in the water medium by electrical forces. The forces are those of attraction in the case of true solutions and are those of repulsion in the case of both emulsions and colloidal suspensions. In fact, colloidal suspensions are essentially identical to emulsions formed by vigorous mixing, described in the previous section, in that the source of stability for the mixture, mutual repulsion by like electric charges, results from dissociated bonds (i.e., the resulting sites of attraction and/or cohesion). Figure 2-21 illustrates the source of stability of colloidal suspensions of clay. Figure 2-21 illustrates the physical structure of clay as an indefinitely

extended sheet of crystalline hydrous aluminum silicate. Many of the chemical bonds within the crystal lattice structure are covalent. This arrangement of silicon, aluminum, oxygen, and hydrogen atoms results in a relatively strong negative charge on each flat surface of the “indefinitely extended sheet.” This charge attracts cations, such as magnesium, aluminum, ferrous and ferric, potassium, etc., and these cations attract individual sheets together to make up an indefinitely extended three-dimensional structural mass of clay.

When the clay is pulverized into very small (colloidal-sized) particles, the pulverizing process amounts to the dissociation of countless bonds, whereby each dissociated bond results in a site having a negative charge. Each of these sites contributes to an electric charge surrounding the surface of each particle, and if the particles are mixed into water, the particles repel each other. After the mixing has taken place, three important forces act on the suspension: (1) gravity acts to cause the particles to settle to the bottom of whatever contains the suspension; (2) Brownian and other forces, referred to as “thermal agitation,” keep the particles in ceaseless motion, tending to make them collide (These collisions, if successful, would result in coalescence, reversing the dispersal process.); and (3) repulsive forces caused by like electric charges on the surface of each particle tend to prevent collisions, and even settling caused by the force of gravity. If the surface charges are




Figure 2-21 Source of the negative charge that is present on the surface of particles of clay.

strong enough to overcome the force of gravity as well as the forces of thermal agitation, then the particles will be successfully held away from each other, and the colloidal suspension will be stable.

The principal difference, therefore, between an emulsion and a colloidal suspension as they relate to industrial wastes, is that the suspended substance, or “pollutant,” in an emulsion is a liquid under ambient conditions, whereas the pollutant in the case of a colloidal suspension is a solid. Substances in addition to clays that form colloidal suspensions include those substances that do not readily dissolve into ions in water, and are therefore “insoluble” (meaning only sparingly soluble, or very poorly soluble), but can be pulverized into very small particles having a surface charge. Almost any substance that exists as a solid at room temperature, but will not dissolve to any great extent in water, can be made to form a colloidal suspension.

Mixtures Made Stable by Chelating Agents

Most metal ions are soluble in water within certain pH ranges and are quite insoluble outside the appropriate pH range. Even within the optimum pH ranges for solubility, however, most metals are soluble to only a limited extent. Certain chemical agents, called “chelating agents,” are able to “hold” metal ions in “solution” over broad ranges of pH, inside as well as outside the optimum pH ranges for solubility, at concentrations far in excess of their solubility limits. These agents, whose name derives from the Greek word “chele,” which means “claw,” have physical structures that accommodate, or “fit,” the metal cations, like an object in the grip of a claw, and thus “seize,” or “sequester,” them to prevent them from forming insoluble salts or hydroxides with anions or to enter into ion exchange reactions. Chelating agents can be inorganic, for instance, polyphosphates (the active ingredient in Calgon), or they can be organic, for instance, EDTA (ethylenediaminetetraacetic acid). Typically, a chelating agent consists of “ligand” atoms, for instance, oxygen, nitrogen, or sulfur,

which have available two electrons to form a “coordinate” bond with the metal ion. The ligand portion of the chelating agent bonds the cation, and the “claw” structure protects the cation from other chemical influences.

Summary

Wastewater can be described as a mixture of undesirable substances, or “pollutants,” in water. If the mixture is stable, the pollutants will not settle out of the water under quiescent conditions under the influence of gravity; and one or more treatment processes, other than plain sedimentation, must be used to render the water suitable to be returned to the environment. The key to determining an efficient, effective treatment process lies in the ability to recognize what forces are responsible for the stability of the mixture (unless biological treatment is to be used). This chapter has described five general types of mixtures: (1) true solutions, where the stability arises from hydrogen bonding between water molecules and the electrical charge associated with each ion; (2) emulsions caused by emulsifying agents, where stability is provided by an agent, such as a detergent, that links small droplets of a liquid substance to water by having one portion of the agent dissolved in the water and another dissolved in the droplets of suspended liquid pollutant; (3) emulsions in which the stability of a mixture of small droplets of a liquid pollutant in water arises from the repulsion caused by like electric charges on the surface of each droplet; (4) colloidal suspensions in which small particles of a nonsoluble solid are held away from each other by the repulsive forces of like electric charges on the surface of each solid particle; and (5) solutions in which ions that would not normally be soluble in water under the prevailing conditions are held in solution by so-called chelating agents.

In each of the five cases, the most efficient way to develop an effective treatment scheme is to directly address the force that is responsible for the stability of the wastewater mixture. Chapters 6 and 8 present the details of this suggested approach.

Examples

The following descriptive examples are intended to show how a working knowledge of the foregoing fundamental concepts can be used to quickly deduce the proper technologies for efficiently treating different types of industrial wastewater.

Poultry Processing Wastewater

The processing of poultry involves receiving live birds and preparing them for sale in food stores. As shown in Figure 2-22, a typical poultry processing operation includes at least six operations in which water is used, contaminated, then discharged, plus washdown for plant clean-up. Several of the operations involve water having direct contact with the birds as they are being processed (defeathered, washed, eviscerated, washed again, chilled, then cut up if desired), leading one to expect that any and all of the component materials of chicken flesh and blood will be found in the wastewater. These component substances would be expected to include blood cells, fats and oils, protein materials, and suspended solids of various makeup, including “dirt.”

Most of the materials in the wastewater would be expected to be organic in nature, and therefore biodegradable. For this reason, a biological treatment process, aerobic or anaerobic, would appear to be a good choice for treatment. Laboratory analyses of the combined wastewater from a typical poultry processing plant, however, as shown in Table 2-1, reveal that the oil and grease content is relatively high. Also, it is reasonable to expect that much of the biochemical oxygen demand (BOD) would result from the presence of blood. Poultry fat is known to be relatively soft, and therefore more soluble, especially in hot water, than other animal fats, and would likely exist in “solution” as a colloidal suspension, or emulsion. The pertinent indication here is that the oil and grease component of poultry processing wastewater would be relatively slowly degraded by a biological treatment process. On the other hand, a combined physical-chemical treatment process should work well, because surface chemistry holds the fats, oils, and greases (FOG) in suspension. A gravity separation process should work well once the suspension is destabilized by taking advantage of surface chemistry phenomena.

Table 2-1 Characteristics of Raw Wastewater Poultry Processing*

<i>Sampling Point</i>	<i>Flow (MGD)</i>	<i>BOD (lb/day)</i>	<i>SS (lb/day)</i>	<i>Grease (lb/day)</i>
Main drain	0.052	430	460	40
New York room (excluding feather flush)				
Main drain	0.448	1,680	1,140	850
Processing room				
Evisceration	0.30	910	930	520
Carriage water				
Chiller overflow	0.05	240	150	90
Chiller dump	0.09	440	270	115
Scalder overflow	0.027	200	210	5
Scalder dump	0.015	110	80	2
Washdown (night)	0.36	240	810	750
Total for plant	0.860	2,850	2,410	1,640

*Data based on a 34-day average; production averaged 72,000 broilers/day.

A second major component of poultry processing wastewater is blood. This is obvious from Figure 2-22, which shows that two of the major steps in the processing of poultry are killing followed by bleeding, and that these processes undergo cleaning by washing with water each day. Because blood contains red blood cells, which can be described as large particles that will not truly dissolve in water but will disperse uniformly throughout a volume of water in which it is placed, the conclusion is that blood must form a stable suspension in water. The stabilizing force in the

suspension of blood is most likely electric surface charge; therefore, chemical coagulation would quickly come to mind as an efficient method for its removal.

The previous considerations, taken together with the knowledge that (1) poultry fat has a specific gravity less than 1.0, and (2) red blood cells have a specific gravity very close to that of water, indicate that chemical coagulation followed by dissolved air flotation (DAF) should be a very promising candidate technology for treatment of poultry processing wastewater.




Figure 2-22 Schematic of a poultry processing system.

Wastewater from Metal Galvanizing

Wastewater from a metal galvanizing process would be expected to contain dissolved zinc. A quick check of the properties of various compounds would reveal that zinc hydroxide, zinc sulfide, and zinc phosphate are all very poorly soluble in water within certain ranges of pH. Therefore, treatment of the wastewater using caustic, a sulfide compound, or a soluble compound of phosphate would probably all be viable candidates for treatment of the wastewater; however, zinc phosphate is seen to be the least soluble in the acid pH range and, therefore, would likely produce a sludge that would be more stable than either the hydroxide or the sulfide. For this reason, treatment of wastewater from a galvanizing process would seem to be best treated by the addition of a soluble compound of phosphorus (phosphoric acid, for instance, or super phosphate fertilizer). A further check would reveal that the phosphate compounds of all metals likely to be present in wastewater from a galvanizing process (iron, lead, nickel, tin) are all very poorly soluble in water of low pH as well as in the neutral pH range, further indicating treatment with phosphorus as a likely optimal treatment approach.

Removal of Heavy Metals from an Industrial Wastewater Containing Dissolved Iron

Many industrial wastewaters contain iron as well as other heavy metals, all of which must be removed to one degree or another. It is often possible to take advantage of two characteristics of metal ions, the first being specific to iron, and the second being common to many metal ions.

Iron is soluble in water in its plus two valence state (ferrous form) but is insoluble in its plus three valence state (ferric form). Moreover, the ferrous form can readily be oxidized to the ferric form by contact with atmospheric oxygen (air). Therefore, it is easy to remove iron from wastewater by simply bubbling air through it, which accomplishes the conversion of the dissolved ferrous ions to insoluble ferric ions, then providing a slow mix time of 5 or 10 minutes to allow flocculation of the ferric oxide particles, then

passing the mixture through a gravity separation device such as a tube or plate settler.

It is a characteristic of nearly all heavy metal ions that they are only weakly soluble in water and tend to adsorb onto the surface of small particulates in suspension whenever they are available. Iron flocs, precipitated by bubbling air through wastewater containing dissolved ferrous ions, present just such a surface.

On the basis of the previous two characteristics of metal ions, an extremely simple and inexpensive system, consisting of an aeration step, a flocculation step, and a sedimentation step, can be used to remove the ions of many metal species to concentrations of between 2 and 6 mg/l, which is often a very worthwhile pretreatment prior to ion exchange or another more expensive process, which can then be used to polish the wastewater to very low concentrations suitable for discharge. The inexpensive pretreatment process can greatly prolong the life of the more expensive process, resulting in a less expensive total cost.

Wastewater from a Parts Cleaning Process

Wastewater from a parts cleaning process within an automobile gear manufacturing facility was shown to contain a high concentration of oil, but the oil could not be removed in a standard API separator (plain sedimentation device). It was determined that treatment of this waste stream at the source was desirable because the FOG load contributed by this process to the total waste stream from the manufacturing facility was so great as to be a cause for failure of the main wastewater treatment facility. Investigation of the parts washing process revealed the presence of a detergent of the sulfonate type, giving rise to the thought that addition of calcium chloride, an inexpensive substance, would result in the formation of insoluble calcium sulfonate at the water-soluble sulfonate site on the detergent molecule. This caused the oil emulsion, which was stabilized by the detergent, to "break," allowing the droplets of oil to coalesce, then rise to the surface in the API separator, enabling easy removal.

Bibliography

Seinfeld, J.H., Air Pollution: *Physical and Chemical Fundamentals*, McGraw-Hill, New York, 1975.

Streitwieser, A., Jr., and C.H. Heathcock, *Introduction to Organic Chemistry*, Macmillan, New York, 1985.

3 Laws and Regulations

Introduction

The plethora of laws, rules, regulations, ordinances, and restrictions that regulate the discharge of industrial liquid, solid, and airborne wastes presents a truly formidable challenge to anyone attempting to become knowledgeable in the area of environmental regulation. These legal entities are published in hundreds of documents, and new laws are written and passed every year by dozens of local, county, state, and federal governments and agencies.

History of Permitting and Reporting Requirements

Most states have had regulations forbidding the “pollution” of surface water and groundwater since well before the 1950s. For instance, the Pennsylvania State Legislature passed the *Clean Streams Act* in 1937, which created the Sanitary Water Board and empowered it to administer the law, as interpreted by the Board and implemented by a “bureau.” The *Clean Streams Act* expressly prohibited the discharge of industrial wastes to “waters of the Commonwealth,” which included groundwater, as well as surface water. “Industrial waste” was broadly defined as any liquid, gaseous, or solid substance, not sewage, resulting from any manufacturing or industry. As one of its first items of business, the Board issued a number of rules, including a requirement that all facilities for industrial waste treatment must apply for and be granted a permit before commencing construction. The Pennsylvania Department of Health served as administrative and enforcement agent for the Sanitary Water Board.

Other states had similar laws that essentially made it illegal for an industry to discharge wastes in such a way as to cause the receiving water to be unhealthful or unusable. The State

of Maine promulgated a set of laws in 1941 that created its Sanitary Water Board and made it illegal to pollute waters used for recreation, among other restrictions. Maine’s law, in fact, was similar to Pennsylvania’s law, regarding intended protection of the waters of the state. As further examples, The State of Illinois enacted a body of legislation in 1929 that “establish[ed] a sanitary water board to control, prevent and abate pollution of the streams, lakes, ponds and other surface and underground waters in the state.” South Carolina enacted a statute in 1925 that made it “unlawful for any person, firm or corporation to throw, run, drain or deposit any dye-stuffs, coal tar, sawdust, poison or other deleterious substance or substances in any of the waters, either fresh or salt, which are frequented by game fish, within the territorial jurisdiction of this State, in quantities sufficient to injure, stupefy, or kill any fish or shellfish, or destructive to their spawn, which may inhabit said waters.”

In fact, almost all the states had laws similar to those of these four states prior to 1950; however, because of limited resources on the part of each of the states’ environmental regulatory agencies, and because these limited resources were focused, for the most part, on wastes from municipalities, little (but nonetheless some) enforcement against industries took place.

Involvement of the federal government in prosecuting industries for pollution has a remarkably limited history prior to the 1970s. Prior to 1948, when Congress passed the *Federal Water Pollution Control Act* (FWPCA), the only legislation under which a discharger of pollutants could be prosecuted was the *Refuse Act of 1899* (Section 13 of the *Rivers and Harbors Act*). The FWPCA was amended in 1956, including the *Water Quality Act of 1965*, the *Clean Water Restoration Act of 1966*, and the *Water Quality Improvement Act of 1970*. Here, again, however, despite the reality of

federal laws, actual prosecution of industries for polluting was very limited before the 1970s.

Development of the intense regulatory climate that industrialists must operate within during the 2000s began with passage of the 1972 amendments to the *Clean Water Act*, Public Law 92-500 (PL 92-500), which replaced the entire language of the original 1956 act, including all amendments. This comprehensive legal milestone had the broad objective of returning all bodies of water in the United States to a condition where they could safely and enjoyably be fished in and swum in, within a few years of passage of the law itself. Many rivers, streams, and lakes at that time were virtually open sewers, and it was rare that any significant water body within the bounds of civilized development was not polluted, simply because of the lack of enforcement of existing laws, both state and federal, which resulted from a basic lack of resources on the part of enforcement agencies.

As an example of the prevailing attitude toward clean water during the 1940s, a footbridge was built across a major river so workers could walk from a town to a large integrated pulp and paper mill in the Northeast. A garbage chute was built into the side of the footbridge as a convenience to these workers so they could carry bags of household trash and garbage on their way to work and simply drop them into the river.

There is, however, a tendency to over-extrapolate the apparent indifference toward pollution of the environment that prevailed prior to the 1970s. Synthetic organic chemicals having a high degree of toxicity were not widely available and not widely recognized as a threat to environmental quality before the 1960s. The prevailing thought was that all garbage and other household wastes were biodegradable, and would ultimately “disappear,” and eventually be incorporated into the environment “from whence it came.” The Superfund sites and other problems of gross environmental degradation of the 1980s and 1990s, for the most part, involved synthetic chemicals such as PCBs, pesticides, herbicides, and chlorinated hydrocarbons.

In addition to the unacceptable state of the nation’s waterways, a significant portion of the nation’s groundwater became contaminated by unregulated deposition of solid as well as liquid wastes in open, unlined dumps. Much of this material was toxic. Beginning in the 1980s, several lawsuits were brought against industries whose waste disposal practices resulted in contamination of groundwater supplies that served entire cities.

Inadequately controlled release of air pollutants has degraded the quality of air in the United States to the point where significant numbers of people with respiratory illnesses have been pushed to the point of death and many thousands of others have suffered health impairment. Visibility has become substantially reduced in many regions of the country. It has even reached the point where nations have threatened legal action against other nations because of massive quantities of air pollutants that have crossed international boundaries. As with the quality of the nation’s water resources, a low point was reached during the 1970s and 1980s, and because of the installation and operation of control technologies, the overall quality of air in most regions of the United States has improved. There are still many regions that have unsatisfactory air quality, however, and the business of air quality protection is a robust one.

Water Pollution Control Laws

The foundation of all federal, state, and local water pollution control laws and regulations continues to be PL 92-500, the 1972 amendments to the *Clean Water Act*. Before passage of this watershed legislation, water pollution control laws were based on an approach that focused on water quality standards and effluent limitations tailored to those standards. The degree of treatment required of a given industrial discharger depended on the assimilative capacity of the receiving water body. The foundation of this approach was that the “solution to pollution is dilution,” and the amount of dilution available was the basis of the degree of

treatment required. One doctoral thesis, written during the late 1960s, used dissolved oxygen monitors in a river to control a valve to regulate the rate of discharge from an industrial facility. The flow of treated industrial wastewater to the river was from a reservoir into which the effluent from the treatment plant flowed. Treated wastewater would build up in volume in the reservoir when the allowable discharge to the river was low, and the reservoir would empty into the river during periods when the allowable discharge rate (as indicated by a relatively high concentration of dissolved oxygen in the river) was high.

The approach used in developing modern environmental protection laws was to require equal treatment by all dischargers, regardless of the assimilative capacity of the receiving water. The assimilative capacity of the receiving water took on a different role, which was that of an indicator of minimum degree of treatment required as opposed to its former role as an indicator of maximum degree of treatment required. The modern use of mathematical water quality models determines if the “categorical standard” requirement for waste treatment will ensure that the water body never violates legislated quality standards. If the model indicates a potential violation, then additional treatment is typically required.

PL 92-500 has been amended several times since 1972 and is a comprehensive law that is difficult to summarize in a few pages. Some of the more important requirements are identified in the following statements:

- All dischargers must have a permit under the National Pollutant Discharge Elimination System (NPDES). The permits have three major parts: (1) effluent limitations, (2) compliance schedules, and (3) monitoring and reporting requirements.
- All dischargers are required to treat wastewater to a specified degree, as a minimum. If there are hazardous wastes involved, additional requirements must be complied with.
- Each industry has been classified under the Standard Industrial Classification (SIC). One of the principal purposes of the SIC is to maintain uniformity of requirements among industries of the same type to prevent a competitive disadvantage on the part of any individual industrial plant.
- Within each SIC category, a study, leading to production of a guidance document called a “development document,” has been carried out. Each development document identifies typical characteristics of wastewater from that industry, discusses methods for minimizing waste production, and defines achievable as well as acceptable levels of wastewater treatment.
- Penalties for noncompliance are set forth.
- Industries that discharge to publicly owned treatment works (POTWs) are regulated by the so-called *Pretreatment Regulations*. The *Pretreatment Regulations* are published in part 403 of PL-92-500.
- Receiving waters for which the provisions of PL 92-500 are applicable include all rivers, streams, brooks, creeks, lakes, ponds, bogs, swamps, territorial seas within the 3-mile limit, as well as wetlands, drainage ditches, and intermittent streams. In short, if a receiving body of water has a free surface that is open to the atmosphere, it is wise to assume that the provisions of PL 92-500 apply.
- Discharge of toxic substances is regulated under separate provisions from discharge of conventional substances.
- In 1983, an amendment was enacted that required each state to adopt an anti-degradation policy, known as “anti-backsliding,” and to identify methods of implementing it.
- Nonpoint sources of pollution, including stormwater runoff from industrial sites, are regulated.
- Combined sewer overflows are regulated.
- Development and implementation of area-wide waste treatment management plans are authorized.
- Water quality standards and implementation plans for achieving those standards for each water body are required.

- If the desired quality in the receiving water (water quality standard) cannot be achieved by the so-called categorical effluent limitations for a given discharger, then additional treatment is required.
- New sources are held to more restrictive discharge limitations than sources that were in existence at the time of passage of the law.
- Before an NPDES permit can be granted, the industry must obtain a discharge permit from the appropriate state.

Each state has its own body of water pollution control laws. Any of the individual states' laws and/or regulations can be more restrictive than the comparable federal law or regulation; however, it would be meaningless if a state were to promulgate a law or regulation having less restrictive requirements than the federal law.

The provisions of the federal *Clean Water Act* as amended are such that any given state can be authorized to administer the federal law. In fact, most states do. In these cases, application for discharge permits under federal law (NPDES permit) and state law are done concurrently.

Groundwater Pollution Control Laws

By Adam Steinman

Whereas PL 92-500 is primarily addressed to the protection of the quality of waterways, other laws have been promulgated that have protection of the ground, the groundwater, and the air as primary objectives. The primary federal law that is addressed to the protection of both the groundwater and the ground itself is the *Resource Conservation and Recovery Act (RCRA)*, (PL 94-580), passed by the U.S. Congress in 1976, which places restrictions on disposal of substances on or in the ground. It thereby restricts activities that would lead to pollution of the ground, directly, and the groundwater, via the formation of leachate and subsequent percolation down through the soil to the groundwater. *RCRA* also protects the groundwater by prohibiting deposition of wastes directly therein.

RCRA, as amended, also defines the term, "hazardous waste," and identifies substances to which this term is to be applied. These definitions are discussed in Chapter 6 of this text. Disposal of all solid wastes, as well as containerized liquids, can be done only as allowed in the provisions of *RCRA*.

RCRA completely replaced the *Solid Waste Disposal Act of 1965*, and supplemented the *Resource Recovery Act of 1970*. *RCRA* was amended extensively in 1980 and again in 1984, by the *Hazardous and Solid Waste Amendments (HSWA)*.

The principle objectives of *RCRA* are to:

- Promote the protection of human health and the environment from potential adverse effects of improper solid and hazardous waste management.
- Conserve material and energy resources through waste recycling and recovery.
- Reduce or eliminate the generation of hazardous waste as expeditiously as possible.

RCRA authorizes the EPA to regulate the generation, management, treatment, storage, transportation, and disposal of hazardous wastes, solid wastes, and underground storage tanks. This authorization is put forth in the form of nine subtitles, three of which contain the specific laws and regulations that industrial facilities must operate in compliance with. *Subtitles C* and *D* contain the programs for hazardous wastes and nonhazardous wastes, respectively. *Subtitle I* contains the program for underground storage tanks.

Subtitle C authorizes the EPA to:

- Promulgate standards governing hazardous waste generation and management.
- Promulgate standards for permitting hazardous waste treatment, storage, and disposal facilities (TSDs).
- Inspect hazardous waste management facilities.
- Enforce *RCRA* standards.
- Authorize states to manage the *RCRA Subtitle C* program, in whole or in part, within

their respective borders, subject to EPA oversight.

Through *RCRA*, as amended, then, each state is both required and authorized to set up and administer regulations that govern the generation, use, and ultimate fate of all substances that fall within the definition of “hazardous.”

The 1986 amendment to *RCRA*, *HSWA*, mentioned previously, adds requirements for handling and disposal of present wastes and regulates the clean-up of problems resulting from past disposal of solid (including hazardous) wastes.

The *Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA)* and the *1986 Superfund Amendments and Reauthorization Act (SARA)* are bodies of legislation in addition to *RCRA* and *HSWA*, upon which solid (including hazardous) wastes are regulated. *CERCLA* and *SARA* provide for and regulate the clean-up and restoration of abandoned hazardous waste disposal sites.

Among the more prominent provisions of *RCRA* is the requirement to document the location and movement of all hazardous materials. Known as “cradle-to-grave” documentation, this section of *RCRA* requires that a manifest, or written record, accompany all hazardous materials from creation to disposal. An example manifest is shown in Chapter 6. *RCRA*’s core regulations establish the “cradle-to-grave” program through the following major sets of rules:

- Identification and listing of regulated hazardous wastes (*Part 261*)
- Standards for generators of hazardous wastes (*Part 262*)
- Standards for transporters of hazardous wastes (*Part 263*)
- Standards for owners/operators of hazardous waste TSD facilities (*Parts 264, 265, and 267*)
- Standards for the management of specific hazardous wastes and specific types of hazardous waste management facilities (*Part 266*)

- Land disposal restrictions (*Part 268*)
- Requirements for the issuance of permits to hazardous waste facilities (*Part 270*)
- Standards and procedures for authorizing state hazardous waste programs to be operated in lieu of the federal program (*Part 271*)

The EPA may authorize a state to administer and enforce its hazardous waste program *in lieu* of the federal *Subtitle C* program (pursuant to *section 3006* of *RCRA*). For a state to receive authorization for its program, its rules must:

- Be consistent with and no less stringent than the federal program.
- Provide adequate enforcement to ensure compliance with *Subtitle C* requirements.

In practical terms, state programs must follow the same general approach and be at least as stringent as federal hazardous waste rules. State law must include penalties that are at least equal to federal penalties (although the penalties don’t have to be identical); and state enforcement activities must be equivalent to those performed by the EPA. Because state rules can be more stringent than federal rules, and each state’s rules are somewhat different, large corporations having manufacturing plants or other facilities in more than one state must make accommodation for the differences.

States have generally received authorization incrementally, consistent with the gradual implementation of the federal *RCRA* program. This is because of the unavoidable lag between federal promulgation of *Subtitle C* standards and adoption of similar standards by the states. Consequently, a state may be authorized to administer and enforce its programs regulating certain types of waste management units and practices within the state, but it may not be authorized for other types of units. Typically, states are more likely to be authorized to enforce rules adopted pursuant to *RCRA* than rules adopted pursuant to *HSWA*. As a result, some facilities in a state may be subject to state enforcement, whereas others are subject to federal enforcement through EPA regional offices.

Some facilities may be subject to joint federal/state enforcement.

Some federal rules do not apply in a state with an authorized program until the state adopts those federal rules. Federal rules that are adopted under *HSWA* apply as a matter of federal law when they are promulgated, even if a state's rules have not incorporated them; however, only the EPA may enforce these rules.

In general, when a facility is subject to joint federal/state authority, compliance inspections may be conducted by the EPA, the state, or both.

Any industrial establishment that generates hazardous wastes and intends to dispose of some or all of them on the land is subject to certain requirements referred to, collectively, as "land disposal restrictions" (LDRs). All generators are required to determine the concentrations of certain constituents in their wastes. Depending on the constituents present and their concentrations, generators may be required to treat their wastes, or the residues from treatment of these wastes, using certain specified technologies. This requirement, referred to as the "Universal Treatment Standards," is contained in *40 C.F.R. §268.42*. In order to determine which treatment standard is applicable, the generator must determine whether a listed waste exhibits any characteristic (*40 C.F.R. §262.11[c]*) and, if it does, the listed waste treatment standard specifically addresses the characteristic. For example, F005 wastes are listed for both toxicity and ignitability. For treatment standard purposes under *40 C.F.R. Part 268*, the waste must be considered as F005/D001 because the F005 treatment standard does not specifically address ignitability.

If a waste is restricted, the generator must certify, on a land disposal restriction notification form that accompanies the hazardous waste manifest, whether it:

- Meets applicable treatment standards or exceeds applicable prohibition levels at the "point of generation"
- Can be land disposed without further treatment

- Is subject to a "national capacity variance" or a "case-by-case extension"

A generator of hazardous waste may not rely on transporters or TSD facilities to make determinations regarding land disposal restrictions on the wastes it generates. The regulations are clear that the responsibility for these determinations rests solely with the generators themselves. Although this does not appear to be a widely known or appreciated reality, it is very important. If a transporter or TSD facility neglects to make a determination, or makes an incorrect determination, the generator is subject to enforcement for violating LDR rules. If a facility treats hazardous waste to meet applicable treatment standards, then it must develop and make available a written waste analysis plan. The plan must describe how the procedures it uses comply with the LDRs (*40 C.F.R. §268.7 [a][4]*).

The LDRs prohibit dilution from being used in any way to comply with any of the requirements or restrictions. The LDR dilution prohibition is that:

- (a) No one shall in any way dilute a restricted waste, or residual from treatment of a restricted waste, as a substitute for adequate treatment to achieve compliance with *Subpart D*, to circumvent effective dates, or to circumvent a statutory prohibition under *RCRA §3004*.
- (b) Dilution of wastes that are hazardous only because they exhibit a characteristic in a treatment system that subsequently discharges pursuant to a permit issued under §402 of the *Clean Water Act (CWA)* or pretreatment of waste discharged under §307 of the *CWA*; or dilution of D003 reactive cyanide waste is permissible unless a specific treatment method is specified as the treatment standard at *40 C.F.R. §268.42*.

For instance, if a waste is hazardous only because it is an acid and therefore exhibits the characteristic of corrosivity, and if that waste stream is subsequently treated in a simple pH neutralization system, then further treated in a treatment system that discharges under a *CWA*

permit, mixing that waste with other waste streams does not constitute prohibited dilution under LDR regulations. Furthermore, the residuals from that treatment system do not, for reasons of only the acid waste stream, have to be managed under LDR regulations; however, if that same acid waste stream also contains cadmium, in concentrations that exceed applicable prohibition levels, it does fall under 40 C.F.R. §268.3 and cannot be diluted in any way to achieve compliance with *Subpart D*. One of the specific exceptions to the dilution prohibition, however, is that it is permissible to combine waste streams for centralized treatment if appropriate treatment of the waste is occurring. Therefore, if the centralized wastewater treatment plant has one or more processes that are specifically designed and operated to remove cadmium (as well as other heavy metals), then combining the waste streams is not considered inappropriate or prohibited under LDRs.

Air Pollution Control Laws

General

This section presents, first, a brief history of the development of air pollution control laws and regulations, as well as a synopsis of the provisions of each of the major laws. Then, a synopsis of the laws and regulations that were in effect as of the year 2000, including a description of the major requirements of the *Clean Air Act* (CAA) that are pertinent to the management of discharges to the air from industrial facilities, as affected by those regulations, is presented.

Before 1963, the only federal law under which an industrial facility could be penalized, or otherwise required under law to control (manage) discharges to the air, was under either general nuisance statutes or public health statutes. General nuisance laws had their roots in the 600-year-old rule of common law—“*sic utere tuo, ut alienum non laedas*.” (Use your own property in such a manner as not to injure that of another.) (Black’s Law Dictionary, 1551 [4th ed., 1951].)

Federal involvement in air pollution control had humble beginnings in 1955, with passage of the *Air Pollution Control Act of 1955*, Public Law 84-159. This act was very narrow in scope, and because of the reluctance of Congress to encroach on states’ rights, considered prevention and control of air pollution to be primarily the responsibility of state and local governments. In 1955, the federal government considered itself a resource, as opposed to an enforcer, and this perception was reflected in the provisions of the *Air Pollution Control Act*, which were as follows:

- The Public Health Service was mandated to initiate research on the effects of air pollution.
- There were provisions for:
 - technical assistance to the states
 - training of individuals in the area of air pollution
 - research on air pollution control

Although modest in its impact at the time, the 1955 law served as a wake-up call to states that air pollution was to be taken seriously, and that enforceable laws regulating emission of pollutants would be forthcoming.

The 1955 law was amended in 1960 to the extent that it directed the surgeon general to conduct research into the health effects of automobile exhaust. A report was submitted in 1962, and as a result, the 1955 law was further amended to require the surgeon general to conduct still more research. The result of the further research was the *Clean Air Act of 1963*, Public Law 88-206, which has been amended several times, the most dramatic (in fact, earth-shaking) change being the 1970 amendments and the present, prevailing law, the 1990 amendments.

The *Clean Air Act of 1963* provided for:

- A stepped-up research and training program
- A matching grants program whereby states and local agencies would receive federal assistance in promulgating air pollution regulation
- The development of air quality criteria

- Federal authority to require abatement of interstate flow of air pollutants

The 1963 *Clean Air Act* designated six pollutants as “criteria pollutants,” thought to be the most important substances affecting the public’s health and welfare. These criteria pollutants, still regarded as such in the year 2000, were as follows:

- Sulfur dioxide
- Nitrogen oxides
- Carbon monoxide
- Lead
- Ozone
- Particulate matter

The 1990 amendments made additional sweeping changes, especially with regard to industrial sources. *Title V* established a new permitting system that had the effect of permanently changing the way environmental managers in industry must do their job. Among the major provisions of *Title V* are monitoring and reporting requirements that are greatly expanded compared to previous requirements. Now, all “regulated pollutants” must be catalogued, approved treatment equipment must be installed, and the equipment must be operated in compliance with standards written into the permit. It is also required that compliance monitoring and reporting be carried out. This requirement for monitoring and reporting has been compared to a (hypothetical) requirement that individual citizens attach strip chart recorders to their private automobiles, and then report each speed limit exceedance.

In addition to the new permitting, monitoring, and reporting requirements, the number of designated hazardous air pollutants (“air toxics”) (*Title III*) was increased from 7 to 189, and then subsequently (in 1999) reduced by one to 188. Also, significant changes were made regarding nonattainment areas, emissions from automobiles (*Title II*), and acid rain provisions (*Title IV*), all of which are pertinent to the job of the industrial environmental manager.

Air Pollution Control Law, as of the Year 2000

Most industrial establishments are regulated by the *Clean Air Act (CAA)* as amended in 1990, and as administered by the state, or the local Air Quality Management Agency, in which the industry operates. Some industrial establishments may be regulated by one or more state or agency requirements that are more restrictive than the CAA. The federal government, through the EPA, issues regulations that must be followed by the administering authorities, and oversees that administration.

As prescribed by the CAA as amended, the EPA is charged with setting National Ambient Air Quality Standards (NAAQSs), a process that began in the 1970s and undergoes revision periodically. Each state has developed a State Implementation Plan (SIP) to attain those standards.

The CAA is organized into 11 titles, five of which are of direct concern to the industrial environmental manager. Those five are:

- *Title I*, Attainment and Maintenance of National Ambient Air Quality Standards (NAAQSs).
- *Title III*, Air Toxics Control
- *Title IV*, Acid Rain Control
- *Title V*, Permits and Reporting
- *Title VII*, Enforcement

The following sections present a synopsis of the provisions of each of these five titles that are of most concern to the industrial environmental manager.

Title V

The requirements that pertain to applying for, obtaining, and operating within compliance of air discharge permits is a major concern of the industrial environmental manager. The permit system under the CAA has been modeled after the NPDES system, with the exception that each state, or Air Quality Management Agency, where applicable, administers the system. (In the case of NPDES permits, some “designated” states administer the program.)

The permits can be enforced by either the states or the EPA. The cost of administration is recovered through a fee system, through which each permittee pays not less than \$25 per ton of regulated pollutant (excluding carbon monoxide). This fee can be adjusted each year, based on the consumer price index.

Application

Each state has developed standard forms for applying for air discharge permits. The forms differ somewhat from state to state, but, in accordance with *Title IV*, certain “key elements” must be included. One key element is identification and description of each and every emission point. Also required is a complete list of regulated substances to be discharged, compliance and monitoring plans, an assessment of past compliance, alternative operating scenarios, and identification and description, including location, of any and all air pollution control equipment. Determination of whether or not the source is “major” is one of the most important requirements of the application.

Regulated Air Pollutants

The substances that are regulated under the CAA include the six criteria pollutants that were originally regulated under the *Clean Air Act of 1963* (sulfur dioxide, nitrogen oxides, carbon monoxide, lead, ozone, and particulate matter), volatile organic compounds (VOCs), and those substances already regulated under new source performance standards (NSPSs), which include hydrogen sulfide, reduced sulfur compounds, total reduced sulfur, sulfuric acid mist, dioxin/furan, fluorides, and hydrogen chloride. In addition, 188 hazardous air pollutants (HAPs) are regulated on a “technologically achievable” basis, as are substances that deplete the ozone and those chemicals that are subject to the accidental release provisions.

Ozone Protection Requirements

Certain requirements under the CAA relate to prevention of leaks and servicing of stationary and mobile air conditioning units, which must

be included in the permit. These requirements are contained in *sections 608 and 609*.

National Emission Standards for Hazardous Air Pollutants (NESHAPs)

NESHAPs are addressed directly in *Title III* and are very important regarding completion of the permit application. In the case of major sources, the NESHAPs become “maximum achievable control technology” (MACT). In the case of small or area sources, they become “generally available control technology” (GACT). These control technologies are intended to reduce emissions of each of the 188 designated HAPs, if the state to which the application for permit is to be submitted has issued a MACT or GACT standard.

Monitoring and Reporting

Operating permits, issued under *Title V*, contain the monitoring procedures and test methods to be used for each substance regulated under the permit. Reporting is normally required at six-month intervals. Certain industrial facilities are subject to “compliance assurance monitoring” (CAM), which involves additional requirements. These facilities, generally, are those major sources that rely on pollution control equipment to comply with the terms of the permit, as opposed to restricting operations or other strategy.

New Source Performance Standards (NSPSs)

NSPSs have been issued for several types of industrial establishments. (A new source is one that commences construction or reconstruction after a standard that applies to that source has been proposed.) In general, NSPSs reflect “cutting-edge” control technology for major sources. In some cases, monitoring and reporting requirements are more comprehensive. For instance, regarding VOC emissions, requirements for recording include the quantities of solvents used in manufacturing processes and calculations of solvent usage versus the quantity emitted to the air.

In summary, each source that is subject to the operating permit program is required to prepare and submit an application for a permit. The application must describe each and every source of air pollutants, as well as pertinent air pollution control requirements and standards. Whenever a facility is in a noncompliance situation, compliance plans and remedial measures must be developed and submitted. Actual emissions must be monitored, and monitoring reports must be submitted periodically. At least once a year, each source must certify its status of compliance.

Whenever the operating status of a source changes, applications for permit modifications must be submitted. Also, permit renewals must be submitted at least every 5 years. The sources that are subject to the operating permit program include the following:

- Major sources, as defined by the CAA, or (more restrictively) by the applicable state or local Air Quality Control Agency
- “Affected sources,” which includes any stationary source that contains one or more units subject to an acid rain emission limitation, or reduction (*Title IV*)
- Any source, including area sources, which is subject to NSPSs
- Any source, including area sources, that is subject to standards, limitations, or other restrictions of the NESHAPs

Title III

The requirements of *Title III*, control of hazardous air pollutants, include limiting the release of 188 substances referred to as “air toxics.” The approach that Congress adopted in writing and promulgating the requirements of *Title III* was to mandate the publishing by the EPA of emission standards for each of the 188 hazardous substances based on what could reasonably be expected to be achievable by the best technology available. It was intended that the EPA would issue the national standards for significant sources for 40 of the source categories by November 15, 1992, another 25% of source categories by November 15, 1994, another 25%

by November 15, 1997, and the remaining by November 15, 2000. Compliance with these national standards was to be complete within no more than 6 years of issuance of the standards. (Facilities are allowed to delay compliance for up to 6 years if they reduce emissions before standards are issued.)

MACT

Under *Title III*, MACT can include process changes, materials substitutions, enclosures and other containment strategies, as well as active treatment for pollutant removal.

Record Keeping

Industrial facilities permitted under *Title V* and subject to the requirements of *Title III* must keep records of processing and monitoring for at least 5 years, and retain them on site for at least 2 years.

Title I

Whether or not an industrial facility is located in a nonattainment area, and the classification of that area, has a significant influence on the financial burden that facility must bear to maintain compliance with requirements of the CAA. For instance, if an industrial plant is located in a nonattainment area classified as “moderate,” it will be allowed to emit no more than 100 tons per year of VOCs. If the same plant is located in a nonattainment area classified as “extreme,” it is limited to no more than 10 tons per year of VOC emissions. The basic structure for designations on nonattainment areas resides in *Title I*.

Simply put, an area is designated as “nonattainment” if the ambient air is not of a specified quality. Nonattainment, then, refers to a deficiency in quality regarding one or more specific substances. If an area is designated as nonattainment in particulate matter, then that situation may be of little consequence to an industry having no significant particulate matter emissions. The opposite is equally important. An industry having significant particulate emissions would be well advised not to locate in this area.

Title IV

Strategies that are being pursued for the purpose of acid rain control are based on the realization that the mobility of the acidic compounds in the atmosphere that result from emissions of sulfur and nitrogen oxides makes it impossible to control on a local basis. The essence of these strategies is to achieve reduction of SO₂ emissions by use of a market-based approach, and NO_x emissions through emission limits. For instance, sources that generate heat and/or power by burning coal are allocated certain “allowances” regarding SO₂ emissions. The allowances that have been given out were done so with the goal of reducing yearly emissions, nationwide, of SO₂ by 10 million pounds from 1980 levels. What is unique about the acid rain reduction approach is that the allowances can be bartered. If a given source emits less than the allowance, it can sell the excess, or “bank” it for future use.

A given source has the options of selecting low-sulfur fuel, making use of emission treatment technologies, or buying allowances from another source to meet its own allowance. A given source can also sell excess allowance that it has obtained by selecting low-sulfur fuel, for instance, to reduce the net cost of the selected option.

NO_x emission limits are levied on the basis of type of burner, with the nationwide goal of reducing NO_x emissions by 2 million tons from 1980 levels. The strategy is to achieve attainment of acid rain control goals through the emission limits, then to institute an allocation bartering system similar to that in use for SO₂ emissions to achieve regional ozone level issues if necessary.

Title VII

The best strategy for environmental managers to follow regarding enforcement is to use all reasonable means to avoid enforcement actions. Enforcement actions can be initiated by the federal government, the state government, local agencies, citizen groups, or individual citizens.

The foundation of avoiding enforcement actions is in implementing corporate policy toward compliance. “Fighting city hall” is exceedingly expensive and has a poor track record. Experience bears out that getting actively involved in the permit process, developing a good working relationship with regulators, fostering a sound policy among employees of careful handling and use of potential environmental pollutants, substituting nonpolluting substances when possible, and prudently maintaining and operating pollution control equipment are far preferable to dealing with enforcement actions.

Industrial establishments, referred to as “sources,” are categorized as a “major source” if their air emissions exceed certain specified amounts. The specified amounts are different, depending on whether or not the source is located in a nonattainment area, and if that nonattainment area has been designated as marginal, moderate, serious, severe, or extreme, or if the source is located in a designated Ozone Transport Region. In any case, a source is categorized as major if it emits, or has the potential to emit, 100 tons per day (tpd) or more of any air pollutant or 10 tpd of any one, or 25 tpd of a combination, of the 188 designated HAPs (air toxics). Major sources have significantly more requirements regarding applying for and operating under a CAA permit than do nonmajor sources. If a source is subject to NSPSs, is subject to national emissions standards for HAPs, or is an “affected source” subject to the acid rain program under *Title IV*, it also has significantly greater requirements.

For some industries, “fugitive emissions” are to be included in the emission totals. “Fugitive emissions” are those that issue from open windows and doors, cracks in buildings or ductwork, or, in general, via any outlet other than a stack, vent, or other device specifically designed and built to discharge substances to the air.

It is possible for an industrial establishment that has potential emissions that exceed major source thresholds to avoid major source classification, and thus become a “synthetic minor source” by agreeing to limit emissions to below

the designated maximums (even though they have the potential). Some states have actively encouraged such agreements in order to reduce the considerable cost of administration.

Bibliography

- Army Corps/EPA, *Section 404(b) (1) Guidelines Mitigation MOA* (February 7, 1990); EPA/Army Corps, Memorandum to the Field: Appropriate Level of Analysis Required for Evaluating Compliance with the Section 404(b) (1) Guidelines Alternatives Requirements (August 23, 1993).
- Clean Water Act*, 33 U.S.C. 1251 et seq. (1948–1987).
- Clean Water Act*, 404, 33 U.S.C. 1344.
- Coastal Zone Management Act*, 16 U.S.C. 1451 et seq. (1972–1986).
- Comprehensive Environmental Response, Compensation and Liability Act*, 42 U.S.C. 9601 et seq. (1980–1987).
- Council on Environmental Quality, Implementation of Procedural Provisions of NEPA, Final Regulations, 43FR, No. 230, November 19, 1978.
- Endangered Species Act*, 16 U.S.C. 1531–1542 et seq. (1973–1984).
- Federal Guidelines—State and Local Pretreatment Programs*, U.S. Environmental Protection Agency, Office of Water Program Operations, EPA-43019-76-017c, Washington, D.C., January 1977.
- Federal Insecticide, Fungicide, and Rodenticide Act*, 7 U.S.C. 136 et seq. (1972–1991).
- Fish and Wildlife Coordination Act*, 16 U.S.C. 661 et seq. (1958–1965).
- National Academy of Sciences, National Academy of Engineering, *Water Quality—1972*, U.S. Government Printing Office, Washington, D.C., 1974.
- National Environmental Policy Act*, 42 U.S.C. 4321 et seq. (1970–1975).
- National Historic Preservation Act*, 16 U.S.C. 470–470 et seq. (1966–1992).
- National Technical Advisory Committee, *Water Quality Criteria*, Federal Water Pollution Control Administration, Washington, D.C., 1968.
- Pollution Prevention Act*, PL 101-508, Title VI, subtitle F, Sections 6601–6610 et seq. (1990).
- Quality Criteria for Water*, U.S. Environmental Protection Agency, Washington, D.C., 1976.
- Resource Conservation and Recovery Act*, 42 U.S.C. 6901 et seq. (1976–1992).
- Safe Drinking Water Act*, 42 U.S.C. 300f et seq. (1974–1996).
- Superfund Amendments and Reauthorization Act*, 42 U.S.C. 11001 et seq. (1986).
- Toxic Substances Control Act*, 15 U.S.C. 2601 et seq. (1976–1988).
- U.S. Environmental Protection Agency, *Legislation, Programs and Organization*, January 1979.
- U.S. Environmental Protection Agency, “National Discharge Elimination System,” Code of Federal Regulations, Title 40, Part 122, U.S. Government Printing Office, Washington, D.C., 1983–1995.
- U.S. Environmental Protection Agency, “National Emission Standards for Hazardous Air Pollutants,” Code of Federal Regulations, Title 40, Part 61, U.S. Government Printing Office, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, “National Primary and Secondary Ambient Air Quality Standards,” Code of Federal Regulations, Title 40, Part 50, U.S. Government Printing Office, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, “Pretreatment Standards,” Code of Federal Regulations, Title 40, Part 403, U.S. Government Printing Office, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, “Secondary Treatment Regulation,” Code of Federal Regulations, Title 40, Part 133, U.S. Government Printing Office, Washington, D.C., 1985.
- U.S. Environmental Protection Agency, “Standards of Performance for New Stationary Sources,” Code of Federal Regulations, Title 40, Part 60, U.S. Government Printing Office, Washington, D.C., 1997.
- Wild and Scenic Rivers Act*, 16 U.S.C. 1271 et seq. (1968–1987).

4 Wastes from Industries

Wastes from industries include solid wastes, air pollutants, and wastewaters. These separate categories of wastes are regulated by separate and distinct bodies of laws and regulations; i.e., solid wastes are regulated by *RCRA*, *CERCLA*, *SARA*, *HSWA*, and other federal laws and regulations as well as certain state laws and regulations; air pollutants are regulated by the *Clean Air Act* (as well as other federal and certain state laws and regulations); and wastewater discharges are regulated by the *Clean Water Act*, as amended (as well as other federal and certain state laws and regulations). However, the three categories of wastes are closely interrelated, both as they impact the environment and as they are generated and managed by individual industrial facilities. As examples, certain solid wastes handling, treatment, and disposal facilities are themselves generators of both air discharges and wastewaters. Bag houses used for air pollution control generate solid wastes, air scrubbers and other air pollution control devices generate both liquid and solid wastes streams, and wastewater treatment systems generate sludges as solid wastes and release volatile organics and aerosols as air pollutants.

The total spectrum of industrial wastes, then, must be managed as a system of interrelated activities and substances. Materials balances must be tracked, and overall cost-effectiveness must be kept in focus. Moreover, as discussed more fully in Chapter 7, the principles of pollution prevention must be implemented to the most complete extent practicable. All wastes must be viewed as potential resources. In some cases, wastes can be used as raw materials for additional products, either on site or at other industrial facilities. In other cases, wastes can be used as treatment media for other wastes. In all cases, the generation of wastes must be minimized by employment of scrupulous house-keeping, aggressive preventive maintenance,

substitution of nonhazardous substances for hazardous substances, and prudent replacement of old, inefficient process technology with technology that results in generation of less pollutants.

The objective of this chapter is to present fourteen industries as representative of many more industries regarding types of manufacturing processes; generation of solid wastes, air discharges, and wastewaters; strategies for pollution prevention; and wastes handling, treatment, and disposal technologies. A general description of manufacturing processes is discussed in order to show the “roots” of each significant solid, airborne, and waterborne pollutant. Then, techniques for wastes minimization as part of an overall pollution prevention program are discussed. Finally, methods for “end-of-pipe” treatment are presented and discussed.

Discussion of the thirteen representative industries is preceded by a discussion of three processes that are common to many different industries: chemical descaling (pickling), vapor degreasing, and rinsing. Vapor degreasing is used by nearly all industries that place a coating on metal as part of the manufacturing process. It is very common for these industries to require extensive cleaning of the metal surfaces before the coating is applied, and vapor degreasing is often included in the cleaning process. In addition, the process of rinsing is used by many industries to remove residual substances from one manufacturing process in preparation for another.

Chemical Descaling

Many manufacturing processes that involve metal parts include a step for removing the products of corrosion from those metal parts. A common method for doing this is to immerse the parts in a bath of aqueous solution of acid

or molten alkali. If acid is used, it is often sulfuric because of its relatively low cost. If a caustic bath is used, it is usually sodium hydroxide. This process is known as “pickling” and is usually followed by a rinse to remove residual acid or caustic. Other chemical descaling agents include aqueous solutions of nitric and hydrofluoric acids, molten salt baths, and various proprietary formulations.

When sulfuric acid is used to descale ferrous metals, some of the iron dissolves in the acid solution and exists there as FeSO_4 . As the quantity of dissolved FeSO_4 builds up over time, the solution loses its effectiveness and must be renewed, by either batch replacement or continuous makeup and overflow. The spent solution must be treated before disposal. Similar acid salts result from the use of acids other than sulfuric to descale metals other than ferrous.

As with all other immersion processes, the pickling solution that fails to drip back into the pickling bath after the piece is removed (dragout) must be dealt with. The quantity of dragout can be minimized by use of air squeegees, longer drip times, or both.

Treatment of spent pickling solutions involves neutralization and precipitation of dissolved metals. The metals precipitate as a consequence of the neutralization; however, the precipitation process must be well managed in order to prevent loss to the effluent due to non-completion of the precipitation and/or solids removal process. If the precipitation/solids removal process does not take place before discharge, it will take place after discharge, potentially causing problems of toxicity or, as a minimum, discharge permit excursions.

Degreasing

Industries that are engaged in the working, forming, plating, or welding of metals almost always apply, and then remove, one or more oily or greasy substances to the metal surfaces during the manufacturing process. For instance, virtually all industries that apply a coating to metal in the course of their manufacturing activities operate one or more processes that

remove greasy substances that were applied to prevent corrosion. A commonly used process is washing in hot caustic solution, with or without detergents. In addition, some facilities make use of a device known as the vapor degreaser. Simple immersion tanks, otherwise known as “dip tanks,” are also common.

Vapor degreasers consist of the following elements:

- A heated tank to contain and volatilize the liquid degreaser substance
- An open chamber to contain the vapors above the heated tank
- A system to condense the vapors
- A system of hangers or baskets, typically mounted on a moving conveyor overhead, to hold the objects to be degreased (the work)

American Society for Testing Materials (ASTM) *publication No. D 3698-99*, titled “*Standard Practice for Solvent Vapor Degreasing Operations*,” defines “solvent vapor degreasing operations” as “the process by which materials are immersed in vapors of boiling liquids for the purpose of cleaning or altering their surfaces, and are subsequently removed from the vapors, drained, and dried in a solvent vapor degreaser.” This publication defines a “solvent vapor degreaser” as “a solvent and corrosion-resistant tank with a heated solvent reservoir or sump at the bottom, a condensing means near the top, and freeboard above the condensing means, in which sufficient heat is introduced to boil the solvent and generate hot solvent vapor. Because the hot vapor is heavier than air, it displaces the air and fills the tank up to the condensing zone. The hot vapor condenses on the cooled condensing means, thus maintaining a fixed vapor level and creating a thermal balance.”

Figure 4-1 shows a photograph of a typical vapor degreaser. The system, or “means,” to cool the space above the heated tank typically consists of coils containing cold water or a refrigerant. As the objects to be degreased move through the open chamber, vapors of the degreasing substance condense on the (relatively cold) objects. The condensed degreasing



Figure 4-1 Photograph of a typical vapor degreaser. (Courtesy of Greco.)

liquid dissolves grease on the surfaces of the objects. As the degreasing liquid drips off the objects, it drops into a system of troughs that carry it to a reservoir, from which it then flows back into the tank. Anything that it dissolved or suspended from the surfaces of the objects is carried into the reservoir (and then, in the case of a portion of this material, into the tank with the condensed solvent).

Because only the vapors from the heated tank contact the objects to be degreased, foreign material from previously cleaned objects is not brought into contact with the objects being cleaned. As dirt and dissolved grease accumulate in the heated tank, they must be maintained below a desired concentration by adding fresh degreaser. Some systems use a batch process where the tank is dumped periodically and refilled with fresh degreaser; others use a continuous overflow from the tank and continuous makeup with fresh degreasing substance.

Water also condenses from the ambient air in the (relatively cool) space above the heated degreasing tank. Some of this condensation takes place as the humid shop air contacts the (relatively cold) metal objects entering the vapor degreaser. Some condensation simply occurs in the open space of the upper portion of the degreasing chamber. This condensed water gradually accumulates in the tank, along with

accumulating oil, grease, and dirt. As this water accumulates, it begins to interfere with the effectiveness of the solvent. Water must, therefore, be maintained below a certain concentration, in order to achieve satisfactory operation.

Other sources of water contamination include:

- Water brought in on the surfaces of the work
- Water remaining in the degreaser after cleaning
- Leaks in the water coils or the steam coils

There are two methods by which this water is removed from the vapor degreasers. The first is by use of a separator that simply provides a quiescent volume within which water that is not dissolved in the solvent separates from it under the influence of gravity. The second is by use of a still that makes use of the large difference between the boiling temperatures of the water and the solvent. When the separated water and solvent exit the gravity separator, there is water dissolved in the solvent phase (as a contaminant) and there is solvent dissolved in the water phase (also as a contaminant). Stills can then be used to remove the water contamination from the solvent, and to remove the solvent contamination from the water.

Many vapor degreaser systems include what is known as an “auxiliary still” to remove water contamination from the solvent before returning the (reclaimed) solvent to the heated tank.

Desirable characteristics of the degreasing substance include high solubilities of the greasy materials used to preserve metals, a high degree of volatility, and chemical stability. Substances used as degreasers have included methylene chloride, methyl chloroform, perchloroethylene, 1,1,1 trichloroethane, trichloroethylene, perchloroethane, n-propyl bromide, and trichlorotrifluoroethane.

Periodically, the vapor degreaser must be emptied, the sludge cleaned out, and the spent degreaser disposed of. Disposal of spent degreasing liquids is best done by fractional distillation to recover relatively pure degreasing substance for reuse. The still bottoms

should be incinerated or placed in a secure landfill. Spent degreaser liquid should never be landfilled directly because of toxic properties and the virtual impossibility of containing it "forever." The sludge that is cleaned from the degreaser must also be disposed of by means similar to those used for the spent solvent.

Residual degreasing substance that fails to drip back into the degreaser before the degreased object leaves the process (dragout) is a toxic contaminant that must be dealt with. It can be minimized by use of air squeegees and/or longer drip times.

Certain vapor degreasing facilities are subject to air discharge restrictions of the *National Emission Standards for Halogenated Solvent Cleaning* (Halogenated Solvent Cleaner NESHAP). These restrictions are contained in *40 CFR Part 63, Subpart T*. The user must determine the applicability of these regulations.


Rinsing

Rinsing processes are common in many industries. Typically, parts and pieces undergoing manufacturing processes are rinsed in a water bath after each process that involves emersion in an aqueous solution. For instance, a typical electroplating process involves emersion of the object being plated (the work), typically a

metal, in an aqueous solution (plating bath) of a salt of the plating material, usually a different metal. In order to dissolve the metal salt being plated, the plating bath must be highly acidic. It will, therefore, be highly corrosive. For this reason, the plating bath is normally followed immediately by two or three rinse tanks in succession.

After completing the process in the plating bath, the work is emersed in the first water bath, where most of the residuals from the plating bath are removed. Because these residuals simply dissolve in the rinse water, they are present on the surface of the rinsed work in proportion to their concentration in the rinse water. Therefore, it is necessary to rinse the work in a cleaner bath after the first rinse, and so on, until the work is sufficiently clean. Each time an object is removed from an emersion tank, it brings a certain amount of the bath solution (dragout) with it. Dragout contaminates the next emersion solution or rinsewater bath. Use of air squeegees and/or longer drip times can minimize dragout. Figure 4-2 shows a typical rinsing sequence for an electroplating process.

It is common to have three rinse tanks in series and advisable to have them set up such that fresh makeup water is added to the final rinse tank, ensuring a concentration of "impurities" sufficiently low that the rinsed



Mass Balance for Counter-Current Rinse System

Figure 4-2 Rinsing sequence for a typical electroplating process. (From Bishop, © 2000. Reprinted by permission of McGraw-Hill, Inc.)

work is as clean as required. The final rinse tank should overflow into the preceding rinse tank, and so on, and the overflow from the first rinse tank should be used as makeup water for fresh plating bath solution. This set-up is referred to as “counter-current rinsing” and has largely replaced the older practice of forward flow rinsing, where fresh rinsewater was added to the first rinse tank, which overflowed into the second rinse tank, and so on. Because the concentration of contaminants in the final rinse tank (even when there is only one tank) governs the required flow rate of the clean makeup water, it follows, then, that the concentration of contaminants will always be lower, for any given flow rate of makeup water, in the second (or final) tank if the clean makeup water is added to the final tank rather than the first tank.

In the forward flow set-up, lightly contaminated rinsewater from only the final rinse tank had to be treated before discharge within permit compliance, and spent plating bath solution, heavily contaminated, had to be treated by a separate system. With counter-current rinsing, where the overflow from the first rinse tank is used as makeup water for fresh plating solution, only the spent plating solution has to be treated.

Treatment of spent plating solution or spent rinsewater involves removal of all those substances used in the plating bath plus dissolved ions from the object being plated (the work). The same is true for treatment of spent plating solution, which is typically much lower in volume, and, consequently, more concentrated. Technologies for treatment of these wastewaters before reuse or discharge are presented in Chapter 8.

Electroplating of Tin

Tin has been used for centuries as both a primary metal with which to make tools, utensils, and other useful objects, and as a cover or “plate” over other metals such as iron, to protect them from the elements. The tinning of iron, by hammering it onto the surface of the iron, appeared around the fourteenth century in

Bohemia. The largest simple use for tin in modern times has been as a coating for steel to make tin plate, which is used in the manufacture of the “tin can.” Over half the tin used in the United States is for this purpose. Other uses for tin include dairy and other food handling equipment, washing machine parts, radio and electronic components, as a coating on refrigerator evaporators, as a coating on copper wire, as a component of piston rings, and for bearing surfaces. Tin is of great importance to the electronics industry, which uses coatings of tin and tin-rich (greater than 50% tin) tin-lead alloys (solder plate). Tin’s resistance to corrosion and chemical etchants, as well as ease of soldering, are highly desirable.

The favorable characteristics of tin as a plating material or coating are the following:

- Nontoxic properties
- Resistance to corrosion
- Ease of soldering
- Ductility—easy to work with

Tin and its inorganic compounds and alloys are essentially nontoxic. This characteristic is extremely important to the food industry, the prepared foods industry, the dairy industry, and environmental engineers or scientists. Considering that the elements that are closest to tin on the periodic chart exhibit considerable toxicity, the nontoxic nature of tin is somewhat surprising. Those elements include arsenic, lead, cadmium, antimony, and thallium. The only hazardous characteristics exhibited by inorganic tin substances are a result of properties other than toxicity; for instance, stannous chloride is acidic, and the various stannates are strongly alkaline. Although there are many organic compounds of tin, none is present in metal finishing operations.

Production Processes

Electroplating is by far the most widely encountered manufacturing process for tin. The basic tin electroplating process is illustrated diagrammatically in Figure 4-3. The object to be plated, called the work, is immersed in an




Figure 4-3 Schematic diagram of the tin-plating process.

electrolyte (solution of metal salts). The plating metal (tin) is also immersed in the electrolyte or bath. Using DC current, the work is made the cathode, and the plating metal (tin, in this case) is made the anode. The electric current causes ions of tin to be dissolved into the bath, then to be deposited (plated out) on the surface of the work. The quality, thickness, and other characteristics of the resulting tin plate depend on the current amperage, which is a function of the electrical conductivity of the electrolyte and the applied voltage. Also affecting the quality and thickness of the tin plate product are plating time and the quality of preparation of the work.

Preplating

The surface of the work must be very clean, as well as activated, before plating. Consequently, as is illustrated in Figure 4-3, the first five steps in a typical tin-plating operation are for the purpose of thoroughly cleaning and activating the surface of the work. The actual mechanics of the operation of each of these five steps differs somewhat, depending on the characteristics of the work. As well, two or more of the steps may be combined for certain types of work. Of interest to the environmental engineer

or scientist is that rinsing with water, using one or more rinse tanks or sprays, follows each of the preplating steps.

Preclean

The first step in preparing the work for tin plating is to remove all gross amounts of oil, grease, and dirt. Depending on the work and its condition on arrival at the plating shop, pre-cleaning can include wiping, air spraying, brushing, vapor degreasing, emulsifiable solvent, solvent spray, hot alkaline spray, invert emulsion cleaners, or other processes in order to decrease, to the extent practicable, the load on the following cleaning processes. Various solvents are used for precleaning, including mineral spirits, kerosene, and chlorinated hydrocarbons such as perchloroethylene. Extreme measures are required in handling these solvents and disposing of the residuals because of their toxic nature. When vapor degreasing is used, the vapors as well as the liquids must be contained. An advantage to the volatile solvents is that they can be reclaimed on site or by use of a commercial reclaiming service, and the concentrated residuals from the reclaiming process can be destroyed or encapsulated for safe landfill disposal.

Clean

The second step, or clean step, removes all residuals from the preclean step as well as removes substances that were resistant to removal by vapor degreasing, solvent emulsion, or other processes used in the preclean step. Typically, the clean step makes use of alkaline solutions to remove soils that have been softened but not completely removed by the precleaning step. Cleaning solutions can be made up using various alkali soaps, detergents, chelating agents, complexing agents, and various surfactants. Cleaning processes include manual brushing, mechanical brushing, soaking, spraying, or high-pressure spraying. Heat is often used. For instance, one process involves immersing the work in a detergent solution, and heating to a rolling boil, followed by soaking for a period. Mechanical agitation, ultrasonic energy, and high-pressure under-surface spraying are options for use in lifting the soil off the surface of the work. Another option, alkaline electrolytic cleaning, results in the production of bubbles of hydrogen and oxygen gas, which provide a scrubbing action. After rinsing, the precleaned and cleaned work should be completely free of any type of soil other than chemical derivatives of the work itself, such as oxides (rust) and scale.

Pickling

Pickling is an acid or alkaline (usually acid) dip process that is common to many metal-cleaning operations. Pickling dissolves, by use of strong acids, corrosion products (rust, in the case of ferrous metals) or scale. Pickling processes vary from an acid dip to anodic treatment in a dry, alkaline salt. Sulfuric acid is widely used because of its relatively low cost; other acids include hydrochloric, phosphoric, and nitric.

Desmutting

When the work is made from steel, a carbide film must be removed after pickling. This carbide film is referred to as smut and must be removed before plating. Several processes are available for this purpose, including anodic

treatment in a dry, alkaline salt. If this type of treatment is used as the pickling step, desmutting occurs simultaneously.

Acid Dip

The final step in cleaning the work is an acid dip in relatively dilute sulfuric or hydrochloric (or other) acid to remove residual alkali, remove any remaining oxides, and micro-etch the surface. The micro-etching is referred to as activation because of its effect of enhancing adhesion of the plating metal.

Plating Baths

Plating baths for tin are either acid or alkaline. There are advantages and disadvantages to each type, and the choice depends on the specific requirements of a given application. Acid baths are made from stannous sulfate or stannous fluoborate. When these substances are used, the process can take place at room temperature, the current density can be relatively low, and deposition of tin onto the work takes place from the stannous, or bivalent (+2), state. Acid bath plating has the disadvantages of requiring so-called addition agents, and there is less throwing power. Throwing power refers to the uniformity of deposition of the plating metal over the entire surface of the work. Another characteristic of acid bath plating is the brightness of the tin plate. This represents no advantage when the tin plate is on the inside of a food can, but in other situations it might represent enough of an advantage to favor the acid bath process over the alkaline bath process.

Alkaline bath plating uses sodium or potassium stannate as the base material. A wide range of concentrations can be used as a means of regulating the rate of plating, and the formulation is relatively simple. No additional agents are needed. Also, alkaline tin plating baths have excellent throwing power. Another advantage is that insoluble anodes can be used, which means that all of the plated tin has its origin in the stannate ions. Hot stannate baths are also known for their ability to tolerate imperfect cleaning of the work. Disadvantages

of alkaline bath plating compared to acid bath plating include the fact that the tin is plated from the stannic, or trivalent (+3), state, which requires higher current density. Another disadvantage is the requirement for the bath to be heated. The hot bath is not suitable for plating delicate work, such as printed circuit boards.

Du Pont has developed an alternative bath specifically for the purpose of electroplating steel strips on a continuous throughput basis. Stannous chloride is used to provide the tin and fluoride salts with conductivity. This bath is known as the halogen electrolyte bath. Table 4-1 lists components of typical plating baths, including acid, alkaline, and halogen baths.

Rinse

The sequential steps of the tin-plating process must each be followed by a thorough and complete rinse before beginning the next sequential step. For instance, if the work is not rinsed completely after the acid dip and before an alkaline plating bath, the alkalinity of the plating bath will be too quickly neutralized. As another example, if the cleaning solution is not completely rinsed from the work, the detergents and contaminants from the washwater will contaminate the following bath or baths. Some rinse steps involve only one tank. The work is dipped in the bath, then extracted from it. As the work is dipped in, any dragout from the previous process contaminates the rinse bath. When the work is extracted, it drags out a certain quantity of the rinsewater with it, along with whatever contaminants are in the rinsewater. Therefore, to keep the concentration of these contaminants low, fresh water must be continually added to the rinse tank. Consequently, an amount of flow leaves the rinse tank that is equal to the inflow minus the dragout. This outflow water constitutes a waste stream unless a use can be found for it.

One way to reduce the quantity of outflow is to use two rinse tanks in series, rather than a single tank. With two rinse tanks in series, the first tank can be allowed to build up in

Table 4-1 Components of Typical Plating Baths

<i>Plating Bath Composition</i>	
<i>Alkaline Stannate Baths</i>	
<i>Bath</i>	<i>Makeup (g/L)</i>
Potassium stannate	100
Free potassium hydroxide	15
Potassium stannate	210
Free potassium hydroxide	22
<i>Alkaline Stannate Baths</i>	
<i>Bath</i>	<i>Makeup (g/L)</i>
Potassium stannate	420
Free potassium hydroxide	22
Sodium stannate	100
Free sodium hydroxide	10
<i>Acid Baths</i>	
<i>Stannous Sulfate Bath</i>	
Stannous sulfate	72
Free sulfuric acid	50
Pheno-/cresolsulfonic acid	40
Gelatin	2
<i>Acid Baths</i>	
<i>Stannous Sulfate Bath</i>	
Beta-naphthol	1
<i>Stannous Fluoborate Bath</i>	
Stannous fluoborate	200
Fluoboric acid	150
Gelatin	6
Beta-naphthol	1
<i>Halogen Bath</i>	
Stannous chloride	63
Sodium fluoride	25
Potassium bifluoride	50
Sodium chloride	45
Addition agents	2
[Lowenheim, 1978]	

concentration of contaminants to considerable strength, and the work can still be rinsed completely with much less makeup (and effluent) flow than with a single rinse tank. In fact, only if the first rinse tank builds up to a concentration equal to that in the preceding process tank will the rate of inflow of clean makeup water need to equal that of the single rinse tank.

There is a choice to be made regarding the arrangement of inflow and outflow of clean

makeup and contaminated rinsewaters when two or more rinse tanks are arranged in series. On the one hand, the clean makeup water can flow into the first tank following the process tank, as shown in Figure 4-4. As illustrated in Figure 4-4, rinsewater outflow, or wastewater, flows out from the second rinse tank. This arrangement is called “forward flow” makeup water. The second, and by far better, choice is to employ “counter-current” makeup water flow. In this arrangement, clean makeup




Figure 4-4 Alternative arrangements for rinsing.

water is added to the second of the two tanks in series (or final tank, if more than two tanks in series are used). Because the concentration of contaminants in the final rinse tank (even when there is only one tank) governs the required flow rate of the clean makeup water, it follows, then, axiomatically, that the concentration of contaminants will always be lower, for any given flow rate of makeup water, in the second (or final) tank if the clean makeup water is added to the final tank rather than the first tank.

Where rinsing is the final step, it is necessary to dry the plated product completely before packing for shipping to prevent staining, corrosion, or other discoloration.

Sources and Characteristics of Wastes

Solid Wastes

Solid wastes from the tin-plating industry include sludges from baths and from air and wastewater treatment facilities. Also included are unrecyclable trash from packaging and shipping, and construction debris from general repair, rebuilding, expansion, and remodeling that takes place over time. Sludges from baths include the preclean, clean, pickle, and de-smut baths and other devices, as well as the plating baths. The cleaning baths contain products of corrosion and scaling as well as oils, greases, and general dirt. The still bottoms from the stills used to regenerate volatile organic solvents used for cleaning oils and greases from the work that is being prepared for plating are solid wastes that must be managed as hazardous wastes.

Airborne Wastes

Air pollutants that must be managed include fumes from degreasing, etching, and plating operations, plus the air discharges from boilers. Wet scrubbers are the standard devices used to control fumes. The wet scrubbers convert air pollutants to water pollutants with the attendant production of a certain quantity of solid wastes in the form of sludges.

Waterborne Wastes

There are three primary sources of wastewater from tin-plating facilities: (1) rinsewaters, (2) cleaning and conditioning solutions, and (3) plating solutions. Rinsewaters are normally produced on a continuous basis because of continuous freshwater makeup and consequent effluent overflow. Periodically, rinse baths are dumped in order to clean the tanks.

Cleaning and conditioning solutions and plating solutions are normally discharged on a batch basis, as a result of the periodic need to dump spent cleaning and plating baths.

Spent Rinse Waters

As discussed previously and illustrated in Figures 4-2 and 4-3, a rinse step normally follows each cleaning, preparing, and plating step. These rinsing processes can be dip tanks, sprays, or both. Also, dip tanks can be single tanks or multiple tanks in series. Multiple (two or more) tanks can be operated as forward flow or counter-current flow, regarding the makeup of clean water and discharge of contaminated rinsewater. As explained previously, for purposes of wastes minimization, counter-current flow is highly preferred, to the extent that there is essentially no justification for forward flow.

Contaminated discharges from rinsing processes are basically dilute solutions of the cleaning, conditioning, or plating processes that precede the rinsing process, along with small amounts of other contaminants. For this reason, the most advantageous method for “disposing” of “spent” rinsewaters is to use them to the extent possible, as the source of water for making up new batches of the preceding cleaning, conditioning, or plating solution. The excess rinsewaters must then be treated before discharge, but their quantity will be minimized.

Spent Cleaning and Conditioning Solutions

Cleaning and conditioning (conditioning is normally considered part of cleaning) are the first processes used by the tin-plating industry, as illustrated in Figure 4-1. Because the

purpose of cleaning is to remove oils, grease, dirt, products of corrosion and scaling, and to condition, or activate the surface of the work to bond well with the tin, the spent cleaning and conditioning solutions contain all of the oils, greases, dirt, and products of corrosion and scaling, as well as the spent and unspent detergents, solvents, acids, alkalis, and other substances used for cleaning and conditioning. Because many cleaning solutions are proprietary, it often takes some intensive research to determine the individual components in the waste cleaning solutions.

Although not usually present in significant amounts, some spent cleaning and conditioning solutions contain chromium and cyanide. Chromium results from dissolution from carbon steel during strong acid treatment. The chromium content of carbon steel ranges from 0.5% to 1%. Cyanide, in the form of ferrocyanide, is sometimes used in tin plating to scavenge other heavy metals from the surface of the work. Also, sodium cyanide is sometimes used as a cyanide dip or as an integral part of one of the cleaning steps to help preserve work that will not be plated immediately.

Spent Plating Solutions

There is great variability in tin-plating operations; therefore, it is not feasible to set forth a typical or average wastewater. As an example of one industry's wastewater, Tables 4-2 and 4-3 are presented to illustrate the wastewater characteristics from two continuous strip electroplating facilities.

Spent plating baths, although considered hazardous in the as-is state because of

Table 4-2 Waste Characteristics, Continuous Strip Tin-plating

<i>Parameter</i>	<i>Value (g/L)</i>
pH	3.3
Chloride	2.6
Total iron	0.04
Tin (II)	1.3
Tin (IV)	0.5
Fluoride	2.1
[Ellis and Whitton, 1978]	

Table 4-3 Additional Waste Characteristics, Continuous Strip Tin-plating

<i>Parameter</i>	<i>Tin lines</i>			<i>Average</i>
	<i>4</i>	<i>5</i>	<i>6</i>	—
pH	6.4	4.6	3.9	4.6
Chloride	39.1	207.0	45.5	97.2
Sulfate	104.6	152.00	250.7	169.1
Suspended solids	80.2	129.1	146.0	118.4
Total iron	4.4	21.6	29.0	18.3
Total chromium	20.2	15.5	2.1	12.6
Hexavalent chromium	10.4	0.34	0.0	3.6
Cyanide	0.74	1.06	1.04	0.95
Tin	48.9	122.9	12.4	61.4
Fluoride	27.0	30.5	8.6	22.0
(all values except pH in mg/L)				
[Azad, 1976]				

corrosivity or possibly other characteristics, are not normally considered toxic. This makes tin-plating waste somewhat unique as a metal-plating waste, simply because, as discussed earlier, tin is not a toxic substance.

Wastes Minimization

As is the case with other metal electroplating industries, the key to minimizing the cost for eventual waste treatment and disposal is wastes minimization, within an overall pollution prevention program, as illustrated by the following:

- Whenever possible, nontoxic substances should be used for degreasing and cleaning.
- If toxic substances, for instance, chlorinated volatile organics, must be used for degreasing or other cleaning processes, containment, recycle, and reuse must be practiced to the maximum extent possible.
- Biodegradable detergents should be used.
- Drips must be contained and returned to the source.
- Aggressive maintenance must be practiced to eliminate the occurrence of leaks or other accidents that could lead to noncontainment of chemicals and other substances.
- Reconstitution of cleaning baths, acid baths, alkali baths, and plating baths should be done on an as-needed basis according to the work performed, rather than on a regular timing or other schedule.
- Dry methods of clean-up, including brooms, shovels, and dry vacuuming, should be used to the maximum extent.
- Rinsing should be counter-current, with respect to freshwater makeup and spent rinsewater overflow.
- Maximum (feasible) time should be provided for dipped work to drip back into the tank from which that work has been extracted. To this end, speed of withdrawal should be minimized. Also, shaking techniques are options to consider.
- Air squeegees should be used to the maximum extent to increase dripping into source

tanks and prevent dragout and consequent contamination of the next sequential bath or other process.

- Temperature and viscosity of bath should be included in those variables that can be adjusted to minimize dragout.
- Purchasing should be guided by aggressive selection of raw materials in order to obtain the cleanest possible materials.
- Purchasing should be guided to demand that packaging of materials delivered to the plant be recyclable, or otherwise of low solid waste nature.
- There should be a constant and consistent program to substitute less-polluting and nonpolluting substances for those that require expensive treatment and disposal.
- There should be a constant and consistent program for replacing cleaning, conditioning, plating, and rinsing processes with technologies that inherently generate less wastes, having even less objectionable characteristics.
- In concert with the previous point, there should be a constant and consistent program for replacing process controls, including sensors, microprocessors, and hardware, with the objective of decreasing waste and maximizing retention, containment, recycle, and reuse of all substances.
- Technologies for recovering and regenerating chemicals, as well as separating and removing contaminants, should be aggressively employed. The general objective should be to treat wastes as close as possible to the source (individual manufacturing process) and to reuse as much material as possible. Reverse osmosis or ultrafiltration to effect removal of oils from alkaline cleaning solutions are examples. Centrifugation has also been used for this purpose. Activated carbon can be used to remove organic impurities.

Both filtration and centrifugation produce concentrated impurities that offer the possibility of recovery. If recovery of substances is not feasible, the concentrated impurities are in a

form more easily disposed of. Evaporation has also been used with success. If the total aqueous wastes, or, alternatively, a side stream, can be reduced in volume by counter-current rinsing, use of spent rinsewaters as makeup for wash and/or plating baths, the cost energy to evaporate may be less than other treatment and disposal. The relatively pure water condensed from the vapor can be used as rinsewater makeup.

Recovery of metals from spent plating baths and concentrated rinsing baths by electrolytic techniques has been very well developed. Metals that have been deposited on the cathode are relatively easy to recover. These metals can then be reused in the plating bath. Even though complete recovery is not feasible, the process is very effective in reducing overall costs by reducing costs for the plating chemicals and for waste treatment and disposal. Evaporation, ion exchange, and reverse osmosis are additional methods that can be used to enhance recovery by concentrating the metals before electrolytic recovery. As a final example, ferrocyanide has been used as a chelating agent in tin-plating to effect selective scavenging of other metals in solution.

Wastewater Treatment

When wastes minimization has been implemented to the maximum extent, those contaminants that remain must be treated and disposed of. In fact, several wastes minimization methods discussed previously can be construed to constitute waste treatment; however, other techniques can be employed that are truly end-of-pipe treatment.

Although some waste streams can be combined and managed as one, regarding waste treatment processes, it is usually advisable to treat certain waste streams separately.

Treatment of tin-plating wastes usually involves removal of oils and greases from the preplating operations, and recovery of tin, and possibly other metals, from the plating bath and rinse wastes. The removal of oils and greases can be done by reverse osmosis, ultrafiltration, chemical coagulation followed by

dissolved or dispersed air flotation, in combination with simple skimming.

As discussed in Chapter 8, recovery of tin and other metals is most often accomplished by alkaline, sulfide, phosphate, or carbonate precipitation. If the wastewaters contain fluoride, then use of lime as the precipitating agent will effect removal of fluorides concurrently. If the effluent contains hexavalent chromium, then addition of (slightly soluble) ferrous sulfide will effect sulfide precipitation of tin and other metals, and at the same time reduce the hexavalent chrome to trivalent chrome (far less toxic). If the pH is maintained between 8.0 and 9.0 during this process, then the trivalent chrome will be precipitated as the hydroxide. Thus, tin, other metals, and hexavalent chrome can be removed simultaneously, by addition of ferrous sulfide, pH adjustment, slow mixing, sedimentation, and filtration. These methods, combined, produce an effluent having metals (tin plus other metals, including trivalent chromium) between 2 and 5 mg/L. Ion exchange can then be employed to reduce the concentrations of these substances to, essentially, nondetect levels, as discussed in Chapter 8. The product water can then be returned to the process for use as either plating bath makeup water or rinse makeup water.

Insoluble starch xanthate has been used successfully as a precipitant for tin and other metals over pH levels from 3.0 to 11.0, with optimal effectiveness above 7.0. This process is effective over a wide range of metals concentration levels.

When metals, including tin, are removed by a reaction to produce an insoluble compound (precipitation) (for instance, stannous sulfide), the precipitation stage is normally followed by gravity sedimentation, often by use of tube or plate settlers. Because simple precipitation often results in small particles of precipitate that do not settle well, a coagulation step must be added. Coagulation (see Chapter 8) involves the addition of a metal salt or an organic polymer, followed by a very short (15 to 30 seconds) rapid mix, then followed by a period of 15 to 30 minutes of slow mixing before the gravity settling process. These processes

combine to produce a large, relatively heavy floc that settles much faster and more completely than the original small, precipitated particles. Three distinct processes are involved: (1) precipitation, brought about by addition of the chemical (sodium hydroxide, for instance) that reacts with the target metal ions to produce an insoluble compound (metal hydroxide); (2) coagulation, brought about by addition of the coagulant (metal salt or organic polymer); and (3) flocculation, brought about by the slow mixing process. The result is an effluent that has 5–15 mg/L of metal ions. Filtration can reduce the concentration to 2–5 mg/L. If it is desired to produce an effluent reliability lower than 5 mg/L of metals, then ion exchange must be employed.

The Copper Forming Industry

Copper forming includes rolling, drawing, extruding, and/or forging copper and copper alloys. The products of copper forming vary from wires to brewery kettles.

The raw materials for the copper-forming industry are copper bars, square cross-section wire bars, rectangular cakes or slabs, sheets, strips and cylindrical billets, all, of which are cast in copper refineries. Other metals are often mixed with copper at the refinery in order to improve corrosion resistance, electrical conductivity, and other properties of the end product of copper forming.

The products made by the copper-forming industry can be divided into six categories: plates, sheets, strips, wires, rods, and tubes. Bars and wires make up about 65% of the total, whereas sheets, strips, and plates account for about 20%. The remaining 15% is made up of tubes and pipes. Plates are usually greater than one-quarter inch thick and are used for the manufacture of processing vessels, heat exchangers, and printing equipment. Sheets are thin plates, and strips are basically sheets having one long dimension. Sheets and strips are both used for roof flashing, gutters, radio parts, and washers. Rods and wires have circular cross-sections and are used for springs, electrical conductors, fasteners, and cables. Tubes

and pipes are used for hydraulic lines, or by the plumbing and heating industry.

The Copper Forming Process

Five different processes, plus variations within those five processes, are used to form copper.

Hot Rolling

Hot rolling is carried out at temperatures above the recrystallization temperature of the metal. The recrystallization temperature is that temperature at which the crystal lattice structure of the metal becomes reoriented. Consequently, the metal becomes more workable and ductile.

Cold Rolling

Like hot rolling, cold rolling involves passing the metal between a series of rollers, some of which are opposite others, in order to make this cross-section of the metal piece become even smaller. Because cold rolling is done at temperatures below the recrystallization temperature, the product is less ductile.

Extension

Extension involves forcing molten copper or copper alloy through an orifice or die at temperatures of 1,200–2,000°F.

Forging

Forging involves intermittent application of pressure, as with hammering, to force the metal into a desired shape.

Annealing

Annealing involves heating the copper or copper alloy, often by the combustion of natural gas, to reduce stresses introduced into the metal by forging or cold rolling. Electroneal units work by passing electrical current through the formed wire. In some cases, a quenching step follows the heating step with the consequent production of wastewater. Figure 4-5 presents a flow diagram of a typical copper-forming process.




Figure 4-5 Process flow diagram.

Additional processes, which may take place at a copper-forming plant, include the following.

Pickling

Pickling, or treatment by immersion in an acid bath, is sometimes done to remove corrosion products before or after the copper-forming process.

Alkaline Cleaning

Alkaline cleaning is similar to pickling, except that the bath contains some or all of the following: caustic, sodium, polyphosphate, silicates, sodium carbonates, resin-type soap, organic emulsifiers, wetting agents, and chelating agents.

Solution Heat Treatment

Also called quenching, solution heat treatment involves cooling the copper products after forming by immersion in a continuous flow bath, or by spraying. Water is normally used. An exception is the quenching of products formed by extension, in which case an oil and water solution is normally used.

Rolling and Drawing Process

Lubricants and coolants are used in the rolling process as well as the drawing process to

prevent excessive wear on the rollers and to facilitate the drawing process. Normally, dilute solutions of soluble or emulsified oil or, sometimes, water alone are used. These solutions perform the functions of cooling and lubrication. They are normally sprayed on the rolls in the cases of the hot and cold rolling processes, and are sprayed on the rod or wire as it enters the die, or the die may be immersed in the oil/water mixture, which is cooled externally, in the drawing process. These solutions are often treated (by filtration, for instance) and reused, but there is always a blow-down that requires management as a waste stream, as well as periodic dumps that are replaced by fresh mixtures.

Solution Heat Treating and Annealing Quenches

There are both continuous and periodic discharges of wastewater streams from two different types of heat treatment quenches used for cooling the copper product after it exits the forming machine and from the quenches following the annealing process. These wastewater streams are generally similar to one another in characteristics but normally have varying substance concentrations. These waste streams are usually continuous flow, as well as occasional batch dump, as described earlier for the rolling and drawing process lubricants and coolants.

Alkaline Cleaning Rinse and Baths

Alkaline cleaning, which normally precedes the annealing process, removes lubricants, tarnish, and dirt. Therefore, all of these substances, including the substances added into the alkaline cleaning baths, are present in the waste streams from those processes. The alkaline cleaning bath may contain some or all of caustic, sodium polyphosphate, silicates, sodium carbonates, soaps, aquatic emulsifiers, wetting agents, and chelating agents.

Pickling Baths, Rinses, and Fume Scrubbers

Pickling is basically a cleaning process. Acid solutions are used to remove oxides from the surface of the metal. In addition, other substances that are on the surface of the metal will be removed, in whole or in part, and will, therefore, be present in the waste stream. In particular, metal sulfates accumulate in pickling baths when sulfuric acid is used as the pickling agent, as is generally the case. For instance, copper sulfate forms when copper is pickled, as follows:



Equation 4-1 shows that as the pickling process proceeds, the acid is gradually depleted and copper sulfate builds up. For this reason, makeup acid must be added, either continuously or periodically.

When the metal parts are taken out of the pickling bath and placed in a rinse tank, drag-out transfers a certain amount of the pickling solution to the rinse tank; therefore, the treated rinsewaters have the same substances as the pickling bath, except that they are far more dilute, and these treated rinsewaters should be used as makeup water for fresh pickling solution in order to reduce overall wastewater discharge.

Wastes Generation

Lubrication, cooling, and blow-down from wet scrubbers are the most important sources of

wastes that require management in the copper-forming industry.

Solid Wastes

Solid waste streams include ordinary trash from shipping and packaging, sludges from copper-forming processes, and sludges from scrubbers and wastewater treatment.

Airborne Wastes

Air pollutants include fumes from furnaces, pickling processes, and other cleaning operations.

Waterborne Wastes, Wastes Minimization, and Wastewater Treatment

The primary pollutants from the copper-forming process are listed in Table 4-4.

Oil and Grease

Glycerides of fatty acids consisting of 16 to 18 carbon atoms are commonly used as lubricants throughout the copper-forming process. The oil molecules are charged such that the water molecules reject them. Because of the specific gravity of the oils, they rise to the surface and can be removed mechanically; however, because water-soluble oils or emulsified oils are used, precipitation techniques must be used to separate them from the water.

Toxic Organics and Metals

Toxic organics, such as chlorinated solvents used to clean oils and greases from the surfaces of raw materials, intermediates, and products, should be replaced by nontoxic solvents, such as detergents, and thus be eliminated from the waste stream. Metals, however, cannot be eliminated. Metals can be removed from the waste stream by alkaline, sulfide, phosphate, or carbonate precipitation, followed by filtration and ion exchange, as discussed in Chapter 8. In many instances, metals can be recovered from sludges and ion exchange resins, and every opportunity to do so should be thoroughly investigated.

Table 4-4 Sources of Copper-Forming Wastes

<i>Process</i>	<i>Waste Source</i>	<i>Pollutants/Parameters</i>
Hot Rolling	Lubricant	O&G, TM, TO, SS
Cold Rolling	Lubricant	O&G, TM, TO, SS
Drawing	Lubricant	O&G, TM, TO, SS
Solution Heat Tmt. (SHT)	Quench	O&G, TM, TO, SS
Extrusion Press SHT	Quench	O&G, TM, TO, SS
Alkaline Cleaning	Bath Dump	O&G, SS, high pH
Alkaline Cleaning	Rinse Water	O&G, SS, high pH
Annealing	Water	O&G, SS
Annealing	Oil	O&G, SS
Pickling	Bath	TM, low pH
Pickling	Rinse	TM, low pH
Pickling	Fume Scrubber	TM, low pH

O&G = Oil and Grease

TM = Toxic Metals

TO = Toxic Organics

SS = Suspended Solids

Suspended Solids

Particles of metals, metal oxides, and dirt are always present in metal-processing wastes because of abrasion, both intended and otherwise. Airborne particles are often scrubbed using wet scrubbers, converting these particles from air pollutants to water pollutants. It is usually a viable option to mix these wastes with wastewaters from the process itself, then to remove the combined suspended solids by chemical coagulation and filtration. Maximum recycle and reuse of treated wastewater should be a continuous objective.

Prepared Frozen Foods

Prepared frozen foods are foods that have been mixed with other ingredients, sometimes cooked or partially cooked, and packaged for easy consumer use. TV dinners are examples. Prepared frozen foods vary from frozen single items to complete meals arranged in segmented aluminum or plastic plates for convenient bake-and-consume or microwave-and-consume use.

There is evidence that prehistoric people froze foods for later consumption. The rapid increase in commercialization of frozen foods (as opposed to prepared frozen foods) began in the 1920s, when Clarence Birdseye developed the process of quickly freezing foods in a way that preserved taste and texture. Apparently, as freezing takes place, the smaller the ice crystals that result, the more closely the product resembles fresh product at the time of consumption. The rapid growth of prepared frozen foods began with the rapid increase in time spent viewing television, starting in the 1950s.

The American Frozen Food Institute (AFFI) has divided the specialty foods industry into ten categories, the following five of which are appropriately included under prepared frozen foods:

- Prepared dinners
- Frozen bakery products
- Italian specialties
- Chinese and Mexican foods
- Breaded frozen products

Prepared frozen foods can be characterized as having value (and pollution potential) added when compared to frozen fruits, vegetables, and unprocessed meat, fish, and poultry. In general, the substances added during the (factory) preparation of prepared frozen foods are a larger source of pollutants that must be managed than are the basic foods themselves.

Preparing frozen foods, like essentially all of the food-processing industry, is not associated with toxic wastes. Some of the wastes may exhibit one or more hazardous characteristics, for instance, corrosivity due to low pH or high pH, resulting from one or more cleaning activities. These characteristics can readily be corrected by simple treatment techniques such as neutralization, using one or more acid or caustic substances.

Food processing of all types, including the prepared frozen foods industries, is characterized by a start-up, operate, and plant clean-up sequence. It is essentially always true that plant clean-up activities produce the greatest quantities of wastes. Process start-up is a distant second and, for well-operated and maintained plants, the operation phase produces a small quantity of pollutants. This is in contrast to operations such as pulp mills, where the bulk of the pollutants are produced on a continuous basis.

The food-processing industry is here to stay. Furthermore, there is every indication that the prepared frozen foods industry will enjoy steady growth in the foreseeable future.

Because plant clean-up activities produce most of the wastes from prepared frozen foods production facilities, those activities that lead to starting and stopping processing lines warrant close scrutiny regarding wastes minimization. There is an inherent economy of scale regarding wastes generation. The ideal processing plant, from a wastes minimization standpoint, is a relatively large plant that processes at near maximum capacity for two or more shifts per day and undergoes plant clean-up only once per day. The most difficult processing plant in terms of wastes minimization

is a relatively small plant that changes products one or more times each shift and often operates under capacity. Each time there is a change of process on a given processing line, the line, and much of the rest of the plant, must be thoroughly washed down.

Wastes Generation

Solid Wastes

Considerable solid wastes are generated at prepared frozen food plants, including debris from fresh raw materials that make up the basic substance of the prepared food. Examples are as follows:

- Fish carcasses in the case of fish-processing plants
- Feather and inedible body parts in the case of poultry-processing plants
- Dirt, stems, leaves, etc., in the case of vegetable or fruit-processing plants

Some prepared frozen food plants initiate production with all raw materials processed to some degree at other locations. For instance, certain producers of frozen chicken potpies purchase chicken that has been processed to the degree that it is ready for cooking. In these cases, the solid wastes from processing the live chickens do not have to be dealt with; however, packaging and shipping materials such as boxes, wrappers, steel bands, etc., make up an important portion of the solid waste stream. Additional solid wastes include sludges from processing tanks, sludges from wastewater treatment processes, and the material that is collected during plant clean-up operations using dry methods such as brooms, air squeezes, and shovels.

Many of the solid wastes from prepared frozen foods as well as other food-processing facilities are putrescible; therefore, they are potential nuisance odor problems (thus, they represent a source of air pollution). The best management practice to prevent such an odor problem from developing is to maintain a

clean plant throughout the premises, and to dispose of the solid wastes before a problem develops.

Airborne Wastes

The only airborne waste from prepared frozen food processing plants should be those normally associated with the boilers. Nuisance odor problems are often a potential problem, but should never be allowed to develop.

Waterborne Wastes

Plant clean-up operations produce the largest percentage of waterborne wastes. The substances included in these wastes are characteristic of the products produced, as discussed in the following sections.

Prepared Dinners

More plants produce prepared dinners than any other category of prepared frozen foods. Frozen potpies represent a large portion of the total. Some of these plants process live chickens, turkeys, swine, or cattle; most purchase processed or partially processed poultry meat or beef. Characteristically, most of the wastewater is generated by plant clean-up operations, usually during a late night or early morning clean-up shift. Additional clean-up takes place at changes of shifts, changes of items being processed or products being prepared, and as a result of spills. Washing, rinsing, and blanching of vegetables represent other sources of wastewater, and frying, breading, and cooking represent other sources. Tables 4-5 and 4-6 present average values of wastewater characteristics obtained from several prepared frozen foods processing plants. These tables have been reproduced from a report on a study conducted by the AFFI during the 1980s. These results are not presented as average or even typical for the industry as a whole because such great variability exists from one plant to another regarding raw materials taken in, processes taking place, frequency of clean-up,

items produced, and plant maintenance procedures. Tables 4-5 and 4-6 are presented here simply to illustrate the wastewater characteristics observed at six individual prepared frozen food plants.

In general, it can be said that the wastewaters from prepared frozen dinner plants, as represented by the six plants that were the subjects of Tables 4-5 and 4-6, were relatively strong, were organic in nature, and had every indication of being biodegradable. For instance, Table 4-6 shows that, for the six plants included in this portion of the report, the concentration of biochemical oxygen demand (BOD₅) varied from a low of 620 mg/L (plant C) to a high of 4,000 mg/L (plant A), with the average concentration for all six plants equaling 1,900 mg/L. This compares to the BOD₅ for domestic wastewater of 250–350 mg/L.

Frozen Bakery Products

Compared to frozen dinners, frozen bakery products processing plants produce wastewaters that are higher in fats, oils, and grease (FOG), higher in carbohydrates, and lower in protein. The high FOG result from the use of butter, shortening, and cooking oils. The high carbohydrates result from the use of starch (flour) and sugar.

Again, there is a tendency for the bulk of the waste load to be generated by clean-up activities, and again, there is every indication that the substances in the wastewater would respond well to biological treatment.

Tables 4-7 and 4-8 are also reproduced from the AFFI study mentioned earlier. These data show that the wastewaters from the preparation of frozen bakery products, as represented by two plants studied by the AFFI during the early 1980s, can be characterized as strong. For instance, the concentration of BOD₅ in the wastewater from the two plants was about 2,100 mg/L for one of the plants, and 4,300 mg/L for the other plant, compared to about 250–350 mg/L for domestic wastewater.

Table 4-5 Prepared Dinners, Average Pollutants Contained in Wastewater Per Unit Production

<i>Plant code</i>	<i>Constituent (kg/kg finished product)*</i>							
	<i>COD**</i>	<i>BOD</i>	<i>SS</i>	<i>VSS</i>	<i>Total P</i>	<i>TKN</i>	<i>Grease and oil</i>	<i>Volume (L/kg)</i>
A	69	35	34	33	0.25	0.44	44	8,700
B	42	18	11	11	0.18	0.25	21	6,200
C	28	13	11	11	0.24	0.61	—	22,000
D	27	15	14	14	0.16	0.55	2.9	21,000
E	20	11	6.6	6.0	—	—	3.8	9,400
F	17	8.8	6.2	6.2	0.12	0.37	4.8	4,400
Average	34	17	14	14	0.19	0.44	15	12,000
Range	17–69	9–34	6–34	6–33	.12–.25	.25–.61	2.9–44	4,400–22,000

* kg = kilogram

kkg = thousand kilogram

** COD = Chemical Oxygen Demand

BOD = Biological Oxygen Demand

SS = Suspended Solids (Total)

VSS = Volatile Suspended Solids

Total P = Total phosphorus

TKN = Total Kjeldahl Nitrogen

L/kg = Liters per thousand kilograms

Table 4-6 Prepared Dinners, Average Wastewater Characteristics

<i>Plant code</i>	<i>Concentration (mg/L)</i>						
	<i>COD</i>	<i>BOD</i>	<i>SS</i>	<i>VSS</i>	<i>Total P</i>	<i>TKN</i>	<i>Grease and oil</i>
A	7,900	4,000	3,900	3,800	29	51	5,100
B	6,800	2,900	1,800	1,700	30	34	3,400
C	1,300	620	530	510	11	28	—
D	1,300	720	680	650	7.6	26	140
E	2,100	1,240	700	640	—	—	400
F	3,800	2,000	1,400	1,400	28	85	1,100
Average	3,900	1,900	1,500	1,500	21	45	2,000
Range	1,300–7,900	620–4,000	530–3,900	510–3,800	7.6–30	26–85	140–5,100

Italian Specialties

Prepared frozen foods included in the category of Italian specialties include frozen spaghetti, lasagna, ravioli, pizza, and sauces for

Italian foods. The raw materials for these products include tomatoes, cheese, and flour (starch). Meat and seasonings are included as well.

Tables 4-9 and 4-10 are reproductions of tables presented in the AFFI study mentioned earlier. The data included in Tables 4-9 and 4-10 indicate, among other things, the characteristic variability of wastewater from one processing plant to another. For instance, the BOD₅ reported for the wastewater from plant Q was 200 mg/L. The BOD₅ from plant R was 690 mg/L. These results compare to the BOD₅ from domestic wastewater of 250–350 mg/L. A wastewater treatment plant designed on the basis of the characteristics reported for

plant Q would appear to be severely overloaded if placed into operation at Plant R. This observation is contradicted by the results presented in Table 4-9. When expressed as units of BOD₅ per thousand units of product, plant Q discharged 5.2 mg/kg, but plant R discharged only 1.1 pounds. From these data it would appear that the wastewater treatment plant designed on the basis of data obtained at plant Q would be severely underloaded if placed into operation at Plant R.

Table 4-7 Frozen Bakery Products, Average Pollutants Contained in Wastewater Per Unit Production

<i>Plant code</i>	<i>Constituent (kg/kg finished product)</i>							
	<i>COD</i>	<i>BOD</i>	<i>SS</i>	<i>VSS</i>	<i>Total P</i>	<i>TKN</i>	<i>Grease and oil</i>	<i>Volume (l/kg)</i>
G	52	23	14	14	0.082	0.30	11	11,000
H	No production information provided							

Table 4-8 Frozen Bakery Products, Average Wastewater Characteristics

<i>Plant code</i>	<i>Concentration (mg/L)</i>						
	<i>COD</i>	<i>BOD</i>	<i>SS</i>	<i>VSS</i>	<i>Total P</i>	<i>TKN</i>	<i>Grease and oil</i>
G	4,600	2,100	1,300	1,200	7.8	27	940
H	9,300	4,300	3,100	3,000	5.7	45	690
Average	7,000	3,200	2,200	2,100	6.8	36	820

Table 4-9 Italian Specialties, Average Pollutants Contained in Wastewater Per Unit Production

<i>Plant code</i>	<i>Constituent (kg/kg product)</i>							
	<i>COD</i>	<i>BOD</i>	<i>SS</i>	<i>VSS</i>	<i>Total P</i>	<i>TKN</i>	<i>Grease and oil</i>	<i>Volume (l/kg)</i>
O	39	19	14	13	0.79	0.59	—	80,000
P	—	3.3	—	—	—	0.12	—	9,800
Q	8.8	5.2	3.4	3.1	0.052	0.15	4.7	26,000
R	2.6	1.1	0.65	0.59	0.011	0.061	—	1,800
Average	17	7.2	6.0	5.6	0.28	0.23		29,000

Table 4-10 Italian Specialties, Average Wastewater Characteristics

Plant code	Concentration (mg/L)						
	COD	BOD	SS	VSS	Total P	TKN	Grease and oil
O	500	240	180	150	10	7.6	—
P	—	340	—	—	—	11.8	—
Q	340	200	130	120	2.0	5.6	180
R	1,500	690	360	330	6.0	34	—
Average	780	370	220	200	6.0	15	

Chinese Foods and Mexican Foods

Prepared frozen Chinese and Mexican foods result in the production of waste characteristics that are somewhat stronger in terms of conventional pollutant (BOD, COD, TSS, O&G) than domestic wastes, and are expected to be biodegradable. Both types of plants use vegetables, some poultry, and some meats. Both use rice to a significant degree, and neither of the two use large amounts of oils or fats. It is common for producers of both prepared frozen Chinese foods and prepared frozen Mexican foods to receive, as raw materials, at least some fresh vegetables, and to preprocess them by cleaning and peeling. Tables 4-11 and 4-12 present the characteristics of wastewater from two different plants that produced frozen Chinese foods. Again, these tables are reproductions from the AFFI study discussed previously. No data were presented for prepared frozen Mexican foods in the AFFI study. In lieu of data on prepared frozen food production, the

AFFI presented data on Plant X, which produced canned Mexican foods. Because all of the processes are the same up to the point of either freezing or canning, and because neither the freezing nor canning processes should produce significant wastes—solid, airborne, or waterborne—it appears to be a good assumption to consider that wastes generated during the preparation of frozen Mexican foods should be similar in characteristics to wastes generated during the preparation of canned Mexican foods.

As shown in Tables 4-11 and 4-12, the BOD₅ of the two plants that prepared frozen Chinese foods was 370 to 450 mg/L, reasonably close to what would be expected for normal domestic wastes. The BOD₅ of the wastewater from the preparation of canned Mexican foods was about 900 mg/L (see Table 4-12), significantly higher than what would be expected in domestic wastes (250–350 mg/L).

Table 4-11 Frozen Chinese and Mexican Foods, Average Pollutants Contained in Wastewater Per Unit Production

Plant code	Constituent (kg/kg finished product)							
	COD	BOD	SS	VSS	Total P	TKN	Grease and oil	Volume (l/kg)
V	12	6.3	2.4	2.2	0.084	0.36	1.2	14,000
W	12	6.7	4.0	3.8	0.041	0.27	4.7	18,000
X	12	7.8	1.9	1.2	0.29	0.21	—	8,900
Average	12	6.9	2.8	2.4	0.14	0.28	3.0	14,000

Table 4-12 Frozen Chinese and Mexican Foods, Average Wastewater Characteristics

Plant code	Concentration (mg/L)						
	COD	BOD	SS	VSS	Total P	TKN	Grease and oil
V	830	450	170	160	6.0	26	85
W	670	370	220	210	2.3	15	260
X	1,300	900	210	140	34	22	—
Average	930	570	200	170	14	21	170

Breaded Frozen Products

Major products from the breaded frozen products category are breaded fish sticks, onion rings, mushrooms, and shellfish. Some plants purchase fresh raw material, such as fresh-picked onions and mushrooms. Some plants purchase raw material already processed and frozen, such as frozen processed fish or shellfish. These plants thaw the frozen raw material, process it further, then freeze it again. Tables 4-13 and 4-14 are, again, reproductions of tables presented in the report of the AFFI study mentioned earlier. The data shown in these tables

illustrate, again, that wastewater characteristics vary greatly from one plant to another, and that at least some of these plants can be expected to have relatively strong wastes. For instance, Table 4-14 shows that one of the prepared frozen food plants producing breaded products, Plant Z, was discharging wastewater characterized by a BOD₅ of 400 mg/L, slightly on the strong side compared to the strength of domestic wastewater. Another plant was discharging wastewater having a concentration of BOD₅ of 4,500 mg/L. This plant's wastewater was very strong compared to domestic wastewater.

Table 4-13 Breaded Frozen Products, Average Pollutants Contained in Wastewater Per Unit Production

Plant code	Constituent (kg/kg raw product)							
	COD	BOD	SS	VSS	Total P	TKN	Grease and oil	Volume (l/kg)
Y	40	15	23	23	0.12	0.33	1.2	3,300
Z	66	37	30	29	0.58	4.8	—	92,000
Average	53	26	26	26	0.35	2.6	—	48,000

Table 4-14 Breaded Frozen Products, Average Wastewater Characteristics

Plant code	Concentration (mg/L)						
	COD	BOD	SS	VSS	Total P	TKN	Grease and oil
Y	12,000	4,500	7,100	7,100	37	100	360
Z	720	400	330	320	6.3	52	—
Average	6,400	2,400	3,700	3,700	22	76	—

Wastes Minimization

Most of the wastes that require management in the form of containment, treatment, and disposal from industrial plants engaged in the production of prepared frozen foods have been shown to have their principal source in clean-up operations, spills, and leaks. The most important steps that can be taken to reduce to a minimum the quantity of wastes generated are the following:

- Pursue an aggressive, ongoing, daily program to prevent accidental spills. Spills are the most prevalent of the preventable occurrences that add to the quantity and strength of discharged wastes in food-processing plants of all types.
- Pursue an aggressive preventive maintenance program to eliminate the occurrence of leaks of water or wastewater from anywhere in the plant.
- Aggressively employ technologies for recovering lost raw material as well as separating and removing contaminants. The general objective should be to treat wastes as close as possible to the source (individual manufacturing process) and to reuse as much material as possible.
- Limit plant clean-up occurrences to as few as possible on any given day. Plan the processing of different products so as to change what is being produced on each line as few times per day as is feasible.
- During plant clean-up, use dry methods, such as brooms, air squeegees, and shovels, to remove as much of what needs to be cleaned up as possible. This material becomes solid waste, which can probably be treated and disposed of, or used as animal feed via a rendering facility, at much less cost than for wastewater treatment.
- Never have running water when wash stations are not in use. Water should be turned on by hand, knee, or foot-actuated valves, and should turn off automatically when the user is finished.
- Never leave water running in hoses that are not in use.

- Make sure the ingredients of all detergents are known and scrutinized to ensure compatibility with wastewater treatment processes.

The AFFI study found that the attitude of plant management was an extremely important factor regarding the quantity of wastes that ultimately required handling and treatment. One specialty food-processing plant employed continuous monitoring to keep track of the loss of valuable product. When waste quantity increased to 1% of the product produced, an investigation was initiated to determine and correct the cause.

Other factors that have been shown to influence the quantity of wastes generated at prepared frozen foods processing plants include plant size, number of shifts, relative amounts of ingredients preprocessed at other locations, the cost of water, the cost of waste disposal, the age of the plant, and the age of the individual processes and equipment. There definitely appears to be an economy of scale regarding waste generated (proportional to product loss). Larger plants have been shown to generate less waste material (equivalent to losing less product) than smaller plants.

Treatment and Disposal of Wastes

Two prominent characteristics of both solid and waterborne wastes from most processing plants engaged in the production of prepared frozen foods are that they are amenable to biological methods of treatment and that they tend to be relatively strong. For these reasons, candidate treatment technologies that would appear to hold promise are composting in the case of solid wastes and anaerobic or aerobic biological treatment for waterborne wastes.

Solid Wastes

A significant portion of the solid waste stream from prepared frozen foods plants consists of normal industrial plant trash, such as packaging and shipping material (associated with both incoming and outgoing material); construction debris from remodeling, plant

expansion, and regular maintenance; and equipment and appurtenances that are no longer usable. In fact, because packaging and shipping are such major activities for this industry, the quantity of waste packaging and shipping material, such as cardboard boxes, paper boxes, paper wrapping, and strapping material, are considerable. Because much of this material is recyclable, a large portion of the solid wastes disposal problem can be avoided.

Success in solving waste disposal problems by recycling is best enhanced by proper set-up of storage facilities, proper arrangements for transportation to a recycling facility, and an aggressive program for keeping recyclable materials cleaned up around the plant and placed in appropriate containers. Nonrecyclable wastes can usually be landfilled because hazardous materials are not normally included in wastes from food-processing plants of this type.

Other than packaging and shipping wastes, the principle solid waste stream from prepared frozen plants consists of trimmings, rejected raw material, and other portions of the organic (edible, for the most part) wastes from foods. Composting, therefore, presents itself as a potential disposal method that can accept all of this portion of the plant's solid waste stream and result in a useful product, namely, soil conditioner and fertilizer. Another possibility for disposal of organic solid wastes is by direct application on land, followed by tilling into the soil to avoid problems with odors and pests such as rodents and flies.

Waterborne Wastes

Three characteristics that strongly influence selection of candidate treatment technologies for wastewaters from prepared frozen foods industrial plants are as follows:

1. The wastes are amenable to biological treatment.
2. In the case of most plants, the liquid waste streams are relatively strong, in terms of concentration of BOD₅, TSS (largely organic solids), and, sometimes, oil and grease.

3. The wastewaters tend to come in slugs, such as the high quantity of flow during the occurrence of plant clean-up, and the emptying of processing facilities when a product line is changed.

The characteristic of being generated in slugs, as opposed to being generated at a steady rate, strongly indicates that flow equalization should be one of the first components in the wastewater treatment system. The flow equalization device should be preceded by bar racks, screens, or both to remove large objects and screenable materials that would settle to the bottom of the equalization device. A grease trap or other oil and grease removal device should also be placed upstream of the equalization device. As discussed in Chapter 8, if the equalization device is a variable-depth holding basin, it should be equipped with surface skimming equipment as well as bottom scraping and sludge removal. The high degree of putrescibility of food-processing wastes requires that there be no opportunity for solids that are either lighter than water or heavier than water to collect and remain for any length of time before being removed and processed.

The characteristics of amenability to biological treatment, along with relatively high strength, strongly suggest anaerobic biological treatment as a candidate treatment technology, especially one of the high-rate anaerobic technologies, such as the upflow anaerobic sludge blanket (UASB), a suspended growth system, or one of the fixed film systems, such as the fluidized reactor or the expanded bed reactor. These technologies are presented and discussed in Chapter 8. There are two major advantages of anaerobic treatment technologies, as opposed to aerobic systems. The first is a far lower requirement for electrical energy. The second is a much smaller quantity (20% to 30%) of biological solids generated that must be managed.

Notwithstanding the apparent advantages of anaerobic treatment technologies, the most prevalent methods of wastewater treatment that have been used in the past are aerobic

systems. Aerobic lagoons, extended aeration activated sludge, and land disposal have been used extensively. In many cases, wastewaters have been discharged untreated to municipal sewer systems, where they were treated by means of the publicly owned treatment works (POTW). The principle advantage of having wastewaters treated by means of a POTW is convenience. The principal disadvantage is cost. POTW treatment normally involves a substantial surcharge penalty for wastes having BOD and TSS concentrations significantly greater than normal domestic wastewater.

Although, in general, food-processing wastewaters are amenable to wastewater treatment by nearly all of the available aerobic and anaerobic treatment technologies, prepared foods sometimes involve the use of sugar, flour, starch, and other high carbon, low nitrogen, and/or phosphorus substances. Prepared frozen foods sometimes fall into that category. The report that resulted from the AFFI study referenced earlier contained a table summarizing, by way of averaging, the BOD₅/TKN/phosphorus ratios found for the five categories of prepared frozen food products, reproduced here as Table 4-15.

Figure 4-6 presents a schematic of a wastewater treatment facility that was in use when the AFFI study was conducted. As shown in Figure 4-6, this particular wastewater treatment system, which was said to have evolved over a considerable period, was complex, had many sources of solids, or "sludge," and was obviously a relatively expensive system to operate. It is almost certain that a single anaerobic system such as a UASB or AAFEB,

followed, possibly, by an aerobic polishing system, would be more reliable, efficient, and economical.

Wastes From De-inking

De-inking wastes are regulated under 40 CFR Part 430, Subpart Q, pertaining to the De-inking Division of the Secondary Fibers subcategory of the pulp, paper, and paper-board point source category. The Secondary Fibers subcategory includes all recycled paper. The De-inking Division includes those secondary fiber processes where ink is removed before production of white (recycled) paper. The objective of the de-inking process is to remove ink in order to brighten the pulp and to remove other noncellulosic substances such as pigments, fillers, and coatings. Therefore, wastes from de-inking processes contain all of these substances plus a portion of additional substances added in the de-inking process.

For purposes of federal regulation, the De-inking Division is divided into three subdivisions that correspond to differences in final product production requirements, as well as differences in wastewater characteristics. Those de-inking facilities that produce pulp for tissue paper generally have the highest pollutant load, in terms of daily flow, BOD₅, and TSS. Those that produce pulp for newsprint generally have the lowest pollutant loads, and those that produce fine papers such as office stationery, copier paper, and computer printout paper have pollutional loads that are less than those of the tissue paper mills and more than those of the newsprint mills.

Table 4-15 Carbon:Nitrogen:Phosphorus Ratios

<i>Category</i>	<i>BOD</i>	<i>TKN</i>	<i>Phosphorus</i>
Prepared Dinners	100	2.4	1.1
Frozen Bakery Products	100	1.1	0.2
Italian Specialties	100	4.0	1.6
Chinese and Mexican Foods	100	3.7	2.5
Breaded Frozen Products	100	3.2	0.9




Figure 4-6 Plant A—wastewater treatment facility.

The De-inking Process—Wastes Generation

Wastepapers to be reused as secondary fiber products must first be sorted and classified as to suitability for final product. Newer secondary fiber processing facilities are capable of handling a much wider range of recycled paper types and are equipped to separate out wire, bottles, and a wide variety of unwanted foreign objects. Older mills are not as well equipped. Once the “used” paper has been sorted, the following processes convert it to a pulp product that is ready for the paper mill. In some cases, the recycled pulp is mixed with virgin pulp. In many cases, it proceeds directly to the paper-making process by itself.

There are ten basic steps in the de-inking process, and they are as follows:

1. Pulping
2. Prewashing, heat, and chemical loop
3. Screening (coarse and fine)
4. Through-flow cleaning (or reverse cleaning)
5. Forward cleaning
6. Washing
7. Flotation
8. Dispersion
9. Bleaching
10. Water recirculation and makeup

Different de-inking facilities employ different numbers and different sequences of these ten steps depending on the requirements of the final product and the characteristics of the wastepaper. A brief description of each step is as follows.

Pulping

Waste paper is loaded into a pulper, where it is mixed with hot water, alkali (pH = 9 to 11), and various solvents, detergents, and dispersants. This mixture is “cooked,” which produces a “stock” of the resulting pulverized paper. The added chemicals dissolve and disperse adhesives, fillers, sizes, ink pigments, binders, and coatings, all of which eventually end up in one or another waste stream from the process. A built-in coarse screen allows smaller solids and liquids to continue on. Those solids that do not

pass the screen are either returned for another pass through the pulper or enter the waste stream.

Prewashing

Gross amounts of ink, clay, and other materials are removed by prewashing, which consists of fine screening, partial dewatering, dissolved or dispersed air flotation, and/or settling.

Screening

The prewashed stock is next subjected to both coarse and fine screening. The fine screens are sometimes operated under pressure.

Through-flow Cleaning

Also called “reverse cleaning,” this process is typified by a counter-current washing process. In one form, the stock flows down an inclined screen having several intermediate barriers. The stock is sprayed with water at each barrier, which washes substances such as ink particles through the screen. Clean water is applied at the lowest barrier and recycled. Progressively dirtier water is applied at progressively higher barriers. Because of the relatively large amount of water used, this process is a significant source of wastewater.

Forward Cleaning

Heavy contaminants that pass through the through-flow and fine-screening processes are the target pollutants for the forward cleaning process. This process operates in a multistage sequence similar to that of the through-flow process; however, the stock is much more dilute (less than 1% solids). Large amounts of water are used. This water is cleaner than that used for through-flow cleaning.

Washing

The washing process makes use of counter-current flow washing to remove ink from the stock that has not yet been successfully removed. Equipment includes tangential screens, gravity deckers, and dewatering screws.

Flotation

Those colloidal substances, including inks that are resistant to screening and washing processes, are the target substances for the flotation process. Flotation does not make use of added water but may use coagulation chemicals including organic polymers. In some instances, the flotation process is located ahead of the washing process. The high pH from the pulping process sometimes aids significantly in flotation.

Dispersion

Those quantities of inks that are not removed by screening, through-flow cleaning, forward cleaning, washing, and flotation are dispersed in order to make them undetectable in the finished paper.

Bleaching

Bleaching of the recycled pulp is highly specific to each individual mill. Bleaching can be done in the pulper, just after prewashing, or after flotation and dispersion. Bleaching chemicals can include chlorine, chlorine dioxide, peroxides, and/or hydrosulfites.

Water Recirculation and Makeup

The nine processes discussed previously are diagramed in Figure 4-7. One of many alternatives to the processing sequence shown in Figure 4-7 is presented in Figure 4-8. In the alternative process, some of the steps shown in Figure 4-8 have been eliminated or combined, leaving seven of the major processing steps in five processes.

Wastes Generation and Wastes Minimization

De-inking facilities produce significant solid wastes in the form of wastepaper sorting rejects, screening rejects, and sludges from flotation and sedimentation. Air pollutants are relatively few and are treated by use of wet scrubbers, which create more wastewater and solid waste (sludge).

De-inking facilities use very large quantities of water, which can be reduced by aggressive application of recycle. The different processes, sequence of processes, and chemicals used result in varying wastewater loads and characteristics from one de-inking plant to another.

The de-inking process illustrated in Figure 4-7 shows that the major source of wastewater is blow-down from the recycle of rinsewaters and process water makeup. To this blow-down water is added contaminated water from leaks and spills, which become incorporated in the second major source of wastewater, plant washdown water. The plant must be washed down periodically because of leaks and spills.

Consequently, aggressive maintenance to prevent leaks and careful management of spills and clean-up become among the most important waste management activities.

Contaminants in de-inking wastewater are those substances extracted from the waste paper, plus a portion of the detergents, dispersants, coagulants, and other chemicals added during the de-inking process. A listing of the major pollutants of concern includes adhesives, starches, clays, ink particles and carriers, sizing, fillers, detergents, dispersants, coagulants, lost fiber, solvents, and bleaching chemicals.

Toxic Pollutants

Pentachlorophenol (PCP) and trichlorophenol are among the most common toxic pollutants in de-inking wastewater. The source of these substances is the slimicides and biocides used to keep troublesome biological growths under control. This fact amounts to strong indication for biological treatment as a candidate treatment process for de-inking plant wastewaters.

Wastewater Characteristics

Table 4-16 presents average values of characteristics of wastewater from the de-inking industry, as published in the EPA's Development Document for the pulp, paper, and paperboard point source category.




Figure 4-7 Ten-step de-inking process flow diagram.




Figure 4-8 Seven-step de-inking modified process flow diagram.

Table 4-16 De-inking Wastewater—Average Values of Untreated Wastewater Characteristics by Subdivision

	<i>Flow</i>		<i>BOD₅</i>		<i>TSS</i>	
	<i>kL/kg</i>	<i>kgal/ton</i>	<i>kg/kg</i>	<i>lb/ton</i>	<i>kg/kg</i>	<i>lb/ton</i>
Fine Papers	88.1	21.1	37.3	74.6	174.1	348.1
Tissue	136.9	32.8	87.2	174.3	251.0	501.9
Newsprint	67.5	16.2	15.9	31.7	96.8	193.5
Toxic Pollutants—De-inked Pulp for Tissue Papers						
	2,4,6-Trichlorophenol, <i>ug/L</i>		Pentachlorophenol, <i>ug/L</i>		PCB-1242, <i>ug/L</i>	
	8.8		4.8		21.3	

All values obtained from Development Document for Effluent Limitations Guidelines and Standards for the Pulp, Paper and Paperboard Point Source Category, Tables V-14 and V-33.

Wastes Minimization

Minimization of wastes from the de-inking industry is best accomplished by the following:

- Substitution of nontoxic chemicals for toxic chemicals
- Aggressive pursuit of good housekeeping
- Preventive maintenance to eliminate leaks
- Equipment modifications to prevent spills
- Reuse of water to the maximum extent feasible
- Recovery of usable fiber
- A continuous program to reduce usage of water

Wastewater Treatment

After substitution of nontoxic materials for toxic materials, the most advantageous technology for treatment of wastewaters from the de-inking industry has often been determined to be aerobic or anaerobic biological treatment. When preceded by appropriate primary treatment, for instance, pH neutralization, screening, flow equalization, and primary clarification, biological secondary treatment has garnered a history of success. Because of low nutrient levels, it is necessary to add sources of nitrogen, phosphorus, and some trace nutrients. The following biological treatment technologies have been used.

Aerated Lagoons

Aerated lagoons have been used extensively for the treatment of wastewaters from many pulp and paper-related industries, including de-inking wastes. Two attractive features of aerobic lagoons for these and other industrial wastes are (1) the low-stressed nature of the system because of relatively low organic loading rates; and (2) the fact that a significant fraction of aeration is atmospheric, as opposed to mechanical, or by way of diffusers. The low organic loading rates result in the ability to absorb shock, or spike loads, and require relatively low intensity of operator attention. The atmospheric aeration results in lower costs for power. As is the case with all lagoons, aerated lagoons must be lined to protect the groundwater.

Oxidation Basins

Oxidation basins have been used in southern regions, where higher temperatures favor higher biological reaction rates and more intense sunlight provides more energy for oxygen generation by algae. These lagoons should be preceded by primary treatment, have excellent buffering capacity against shock loads, and have no mechanical requirements. These facilities must be lined to protect the groundwater.

Activated Sludge

Modifications of the activated sludge process that have been used with success to treat wastewaters from de-inking include complete mix, conventional, tapered aeration, step aeration, contact-stabilization, and pure oxygen. A two-stage activated sludge process having a detention time of 4 hours and having an integrated selector was discussed in the development document as being particularly effective for the treatment of wastewaters from de-inking.

Anaerobic Contact Filter

The anaerobic contact filter is essentially a nonaerated trickling filter. This technology has proved to be successful at several de-inking facilities. Detention times of up to 3 days have been used.

Die Casting: Aluminum, Zinc, and Magnesium

Die casting is one of the oldest methods used to shape metals. The metal or metal alloy is melted, then poured into a prepared mold and allowed to cool. The molded piece is then removed from the mold and processed further by one or more of a great variety of processes. The mold, depending on the process used, may be used again as is, may be rebuilt to varying degrees and used again, or may be completely destroyed during the process of removing the shaped piece. Molds are normally made of a metal or metal alloy that has a significantly higher melting point than the metal being molded. There are three principal elements to all die casting machines: (1) a casting machine to hold the die into which the molten metal to be cast is injected, (2) the mold itself that receives the molten metal and is capable of ejecting the solidified product, and (3) the casting metal or alloy. The process proceeds by first melting the metal and adding desired additives, if any. Then, a source of hydraulic energy impacts a high velocity to the molten metal, causing it to rapidly fill the die. The die must absorb the stresses of injection and dissipate the heat from the molten metal.

Two types of die casting machines are in common use; the first is an air-operated machine. Compressed air forces the molten metal (or metal alloy) into the die by exerting high pressure on the surface of the molten metal in a special ladle referred to as the goose. The second type of die casting machine has a cylinder and piston submerged in the molten metal to force the molten metal into the die.

There are three primary variations of the die casting process: (1) the hot chamber process, used for lower-melting metals such as zinc and magnesium, (2) the cold chamber process, used for higher-melting metals such as aluminum, and (3) the direct injection process. In the hot chamber process, the hydraulically actuated cylinder and piston are submerged in the molten metal. In the cold chamber process, the molten metal is fed to the cylinder and piston from a reservoir. In the direct injection process, nozzles directly inject molten metal into the dies. Large amounts of noncontact cooling water are normally associated with the die casting process. Also, lubricants, referred to as "die lubes," are used to prevent adherence of the casting to the die. Selection of the die lube is governed by, first, wastewater treatment and discharge permit considerations, and second, by its performance in providing the casting with a better finish, allowing the metal to flow into all cavities of the die, and handling characteristics. Die lubes that were used historically that contained complex phenolic compounds and even PCBs have been replaced with die lubes having a vegetable oil base.

Aluminum Die Casting

Figure 4-9 presents a schematic of a typical aluminum die casting process. Aluminum die castings are used in automobiles and many other products. The raw material for aluminum die castings is largely recycled aluminum cans and other articles. The first step in an aluminum die casting operation is to crush, shred, and sort the raw material. Then, the raw material is melted, by use of coreless and channel induction furnaces, crucible and open-hearth reverberatory furnaces fired by fuel oil, natural




Figure 4-9 Schematic of an aluminum die casting process. (From the EPA Development Document, 1980.)

gas, or electric resistance and electric radiation furnaces. Air flows from the furnaces to wet scrubbers. Furnace temperatures are in the range of 425–600°F.

Next, salts are added to remove oxides from the melt, then hydrogen, which causes voids in the product casting, is removed by addition of dry, chemically pure nitrogen, argon, or chlorine.

The next step is to lubricate the dye, which is normally done by automatic spray. Then, the molten metal is injected into the mold. Cold chamber processing is typically used for die casting aluminum. Processes referred to as gating and risering are sometimes used to minimize shrinkage and to produce directional solidification.

Quenching in a water bath is then used to rapidly cool the casting to room temperature. Oil, salt baths, and various organic solutions are alternative quenching solutions, but water is most often used. After quenching, the casting is sometimes “heat treated” by holding the casting at a temperature of 95 to 260°C. This process is sometimes referred to as aging. Finally, the casting is cleaned by use of alkaline and/or acid solutions.

Zinc Die Casting

Figure 4-10 presents a schematic diagram of a typical zinc die casting process. The first step is to crush the scrap metal and prepare it for melting. Then, the metal is melted at temperatures between 325 and 475°F. Next, the molten metal alloy, having a typical mixture of 1% copper, 3.9% aluminum, 0.06% magnesium, and the balance, zinc, is maintained at the desired temperature within 6 degrees in the holding furnace. After the die has been lubricated, the molten zinc alloy is injected into the mold. The hot chamber process is used. After solidifying, the casting is extracted, trimmed, then dropped into a quenching tank. Finishing may include texturing by acid etching or another process, electroplating, or polishing.

Magnesium Die Casting

Magnesium die casting follows approximately the same procedure as that shown for zinc die

casting in Figure 4-11. Magnesium alloy typically contains zinc plus aluminum, beryllium, nickel, and copper. Oxygen may be released from the molten alloy by use of a flux (magnesium chloride, potassium chloride, or sodium chloride) or by use of a fluxless process that uses air/sulfur-hexafluoride. The temperature of the molten alloy is held in the range of 475–525°F by use of a crucible furnace. Before it is injected into the die, the molten alloy is surface skimmed to remove oxides, and the die is lubricated very lightly (or, in some cases of magnesium die casting, not at all).

The molten alloy is injected using the hot chamber procedure. Relatively low pressure is used. After solidification, the casting is extracted, quenched, then finished by use of grinding.

Waste Streams and Waste Management

Waste streams from each of aluminum, zinc, and magnesium die casting processes have similar sources, and the waste substances are characteristic of the alloys used and the state of cleanliness of the raw material. The following is an itemization of sources of wastes, common to all three die casting processes, and comments about treatment.

Heating Furnace

Off-gasses are normally treated by wet scrubbers. Sludge from metal residuals develops in the bottom of the furnace and can be recovered.

Scrubbers

Wet scrubbers are used extensively at die cast facilities. Ammonia, cyanide, magnesium, phenols, sulfide, copper, iron, and zinc, as well as total suspended solids (TSS) and oil and grease, are waste substances that are common to the scrubber blow-down from all three types of facilities. In addition, aluminum and nickel are found in scrubber blow-down from aluminum die casting facilities. Copper is found in scrubber blow-down from magnesium and zinc die casting facilities. Treatment of scrubber blow-down after recycle is carried out to the




Figure 4-10 Schematic of a zinc die casting process. (From the EPA Development Document, 1980.)




Figure 4-11 Schematic of a magnesium die casting process. (From the EPA Development Document, 1980.)

maximum extent it can be by precipitation, coagulation, sedimentation, filtration, and ion exchange.

Quench

The molded product is allowed to cool just enough to solidify in the die. It is then ejected into a water bath, or "quench tank." The water bath is continually renewed, to prevent the buildup of impurities to levels that would adversely affect the casting, and to keep it cool. The overflow goes to wastewater treatment. The principal objective of water management in the die casting industry is to recycle as much of the treated wastewater as possible. A certain fraction must always be bled, or "blown down," from the system, and an equal amount of clean water replaced, or "made up," thus eliminating the possibility of complete recycle. The fraction that must be blown down is a function of the maximum concentration allowable in the quench tank of that substance that is least well removed in the wastewater treatment system. Blow-down from the quench tanks contains metal residuals, plus substances used to lubricate the dies. Biological treatment has been used successfully when the die lube was derived from vegetable oils. Metals have been a problem and have resulted in the necessity of disposing of the dewatered sludge as hazardous waste.

Die Casting

Surface cooling sprays and machine and floor washdown waters, together with leaks from hydraulic systems, leaks from noncontact cooling water piping, and in some cases, intermingling of all of the above with quench water produces a waste stream that must be managed. When all substances in this waste stream have been carefully selected to be biodegradable, including the hydraulic oils and the detergents used for machine, floor, and general plant clean-up, biological treatment has been used successfully.

Finishing

Waste characteristics differ among the three die casting processes. In the case of aluminum die

casting, trim pieces are knocked off mechanically as well as by hand. The solid waste stream that results is recycled back to the scrap aluminum crusher at the head of the process, and associated oils, greases, and dirt thus become a portion of the waste discussed earlier. In the case of magnesium and zinc die casting, trimming is done by grinding, which creates dust. The wastes (dust) from this grinding operation are captured by scrubbers. The scrubber blow-down then becomes the principle waste stream from the magnesium die casting finishing process. This waste stream can be treated by chemical precipitation, coagulation, sedimentation, and filtration. Recycle and reuse of the clarified effluent as quench water, cooling water, and/or plant washdown water can significantly reduce overall waste discharges from the plant. Because lead and zinc are listed as toxic pollutants, all steps in the waste treatment and recycle system must be carefully managed.

Additional Waste Management Considerations

Several substances that have normally been used in aluminum, magnesium, and zinc die casting operations are listed as hazardous. These substances include degreasing solvents, such as perchloroethane, perchloroethylene, and trichloroethane, and other chlorinated solvents as well as cyanide, copper, lead, zinc, and nickel. In some cases, phenolic compounds are present. The following discussion is arranged such that categories of pollutant substances are grouped, regardless of the individual sources, and treatment techniques are presented.

Solids

As discussed in Chapter 8 under Physical Treatment Methods, suspended TSS and settleable solids are normally removed from wastewater streams by sedimentation, followed by, or along with, chemical coagulation. Plate or tube settlers are often used. These processes can be followed by filtration. Dissolved solids such as dissolved metals can be removed by

alkaline precipitation, followed by sand or other filtration. Pressure filtration has been used with success. Other filtration processes that have been used before recycle and reuse or direct discharge include vacuum filtration and ultrafiltration. Resulting sludges and filter cakes must be disposed of as hazardous waste, unless they fall in a category that has been delisted.

Dissolved Organics

Dissolved organics in wastewaters from die casting processes can be successfully treated by biological processes, if care is taken to ensure that all products used in the manufacturing process contain only biodegradable organic substances.

Dissolved Inorganics

The principle dissolved inorganics in wastes from die casting processes include the metal being cast, plus those added as alloys, and their salts. Other inorganic substances include sodium, calcium, compounds of sulfur, nitrogen, and chloride, and those additional inorganics included in proprietary products. In general, alkaline, carbonate, sulfide, or phosphate precipitation followed by sedimentation and filtration are used to remove the metals. As discussed in Chapter 8, the solubility characteristics of the various metal hydroxides, carbonates, sulfides, and phosphates must be carefully considered when designing a metal removal process. In addition, the toxic or other hazardous characteristic of the treatment residuals is a major factor regarding treatment and disposal of these wastes.

Oil and Grease

The two principle methods for removing substances that are measured and reported as oil and grease are mechanical skimming for the nondissolved fraction and chemical coagulation (sometimes with just pH adjustment), often with dissolved air flotation, for the dissolved and/or suspended (including emulsified) fraction. Ultrafiltration or reverse osmosis can

be used as polishing steps, or, in some cases, as the only method for removal of oil and grease.

Destruction of Phenolics

Every effort should be made to exclude phenolic substances from die casting processing and cleaning materials, and thus from the wastewater. When unavoidably present, simple phenolic compounds can quite easily be removed by biological treatment. Some complex phenolics must be removed by activated carbon adsorption, which must be preceded by sand (or other) filtration.

Anodizing and Alodizing

Anodizing and alodizing are industrial processes that enhance the property that some metals have of forming a protective coating of the metal oxide on their surfaces. This layer of metal oxide is quite stable and protects the metal from further contact with oxygen, hydrogen ions, and other substances that would otherwise cause further corrosion.

Anodizing is an electrochemical process; alodizing is a strictly chemical process. Both processes act to produce a thicker, more even, and more predictable coating than would be formed naturally. In addition, the anodized or alodized metals have a strong affinity for paints and other organic coatings.

The processes by which anodizing or alodizing coatings form are complex. Basically, oxygen from the hydrolysis of water, in the case of anodizing, reacts with the metal itself to produce two results. One is the formation of pits on the surface of the metal; the other is the formation of metal oxide molecules and ions. The next step is an attachment of the metal oxide species to the newly formed surfaces of the pits. As this process progresses, the local areas on the metal surface where this process has taken place become nonreactive. Consequently, those local areas that have not yet been coated become somewhat more reactive, until the entire surface of the metal becomes coated.



In nature, this progressive process is seldom complete. There are almost always local areas

on the metal surface that are not completely coated and are thus exposed to additional corrosion. The controlled industrial processes have the objective of taking the progressive self-coating process to completion.

The thickness of the protective metal oxide coating can be increased by increasing the intensity of the electrochemical (in the case of anodizing) or chemical (in the case of alodizing) process and the time over which it is allowed to take place. Thus, there is control over the product in terms of money spent (energy, chemicals, and time).

Anodizing

When aluminum, for example, is placed in an electrolytic (good conductor of electric current) solution, and is made the anode, then oxygen from the electrolysis of water reacts with the aluminum at its surface as illustrated by the following simplified reactions:



As aluminum atoms are extracted from the surface of the metal, pits are formed. The surfaces of the pits are also particularly reactive, probably because of the availability of electrons for covalent bonding. The aluminum oxide that is in the process of forming also has available electrons; therefore, aluminum oxide bonds with the raw metal surface of the pits, forming a relatively stable complex.

The desired properties of the electrolyte are that it conducts electric current efficiently and is a good solvent for the metal species (aluminum ions, partially formed aluminum oxides) involved in the electrolysis process. It should not, however, be a solvent for the final coating product, which is the aluminum oxide–aluminum metal complex.

The electric current intensity, electrolyte characteristics, temperature, and process duration all influence the characteristics of the pitting and the thickness and integrity of the coating. Higher applied voltage increases the speed of oxidation, the size of the pits, and

the thickness of the coating. Longer duration increases coating thickness. Temperature and electrolyte characteristics influence the rate of dissolution of the metal surface. Electrolyte characteristics affect pore density. For instance, use of sulfuric acid results in more than twice the number of pores generated compared to use of chromic acid.

The size and density of the pores affect abrasion resistance as well as the capacity of the coating to absorb dyes for coloring and paints for desired surface characteristics. Generally, coatings having a higher density of smaller pores, which have a higher resistance to abrasion.

Alodizing

Alodizing produces a protective oxide coating on metal surfaces similar to that produced by electrolysis, but the process is purely chemical. Often, the metal to be coated is dipped in an acid solution containing chromate, phosphate, and fluoride ions. Alternatively, coatings can be applied by brushing or swabbing. The acid acts to dissolve metal from the surface, which then reacts with oxygen in the alodizing bath to form the metal oxide, which then reacts with the newly exposed metal surface to result in the protective metal oxide coating. The coating formed by alodizing is characteristically thinner and has less abrasion resistance than does the coating formed by anodizing. Alodizing is an economical alternative to anodizing if resistance to abrasion is not required.

Wastes Generation

The anodizing and alodizing processes have similar steps that produce wastes. The basic production steps are cleaning, rinsing, deoxidizing, rinsing, etching, anodizing or alodizing, rinsing, coloring, rinsing, and sealing. All steps produce wastes, as described in the following sections.

Cleaning

The cleaning of metal objects to be processed produces various wastes. If degreasing is required, an important waste that must be

managed is the waste solvent, as well as the substance removed. In general, the most appropriate way to manage the waste solvents is to regenerate for reuse, then dispose of the residuals. For instance, if a chlorinated solvent is used for degreasing, regeneration is accomplished by use of a still. The still bottoms are then treated and disposed of by one of the methods described in Chapter 8.

Rinsing

In general, rinsing after any of the five processing steps (cleaning, deoxidizing, etching, anodizing or alodizing, and coloring) identified previously, produces wastes that are simply dilute forms of the wastes produced directly by those processing steps. Often, rinsing wastes are best managed by operating the rinsing process in a counter-current mode, in which two or more rinsing baths are used for each of the processing steps. Clean makeup water is continually added to the final rinse tank, which overflows in the rinse tanks that precede it in the processing steps, and so on, if more than two rinse tanks are used, as discussed previously in this chapter. The overflow from the first rinse tank after each processing step, anodizing, for instance, is then used as make-up water for the process itself.

Deoxidizing and Etching

Deoxidizing and etching are both done with either caustic or acid solutions. Deoxidizing may use both, in series, if the metal to be anodized or alodized is badly oxidized. The purpose of deoxidizing is to remove oxides that have formed naturally, but in an undesirable manner. The purpose of etching is to expose a clean, fresh metal surface for the anodizing or alodizing process. Wastes contain spent acid or caustic solutions and ions of the metal being coated.

Anodizing or Alodizing

The spent acid baths from the anodizing or alodizing process constitute the major waste from the coating process. These solutions must

be maintained above a certain quality for the coating processes to be satisfactory. Buildup of metal salts (from the metal being coated) must be kept below a level where they interfere with the anodizing or alodizing process. Also, as the solution is weakened by drag-in from the previous rinse process, the active ingredients must be made up to maintain a required minimum concentration. In continuous flow anodizing or alodizing operations, continuous make-up of water and active ingredients can maintain successful operation for a period; however, as the acid or alkali bath solutions continually attack the metal being coated, eventually the bath must be dumped and the process restarted with new anodizing or alodizing solution. These dumps of spent solutions, which normally occur about once per month, represent a major waste stream.

Coloring

Coloring, if included in the process, produces wastes that are specific to the coloring process being used.

Tables 4-17 and 4-18 present typical wastewater sources with typical flows and characteristics from an aluminum anodizing operation, which includes acid polishing before the caustic etch. The process also includes a coloring process.

Wastes Minimization

As discussed previously, wastes from rinsing can be minimized, and sometimes eliminated, by use of counter-current rinsing and using the most concentrated rinse wastes as makeup water for baths that precede that particular rinse. Other waste-minimizing alternatives include use of air squeegees to minimize dragout and use of either static rinses or maintaining makeup water flow-through at as low a rate as possible. Strict adherence to the rule of turning water off when the rinse line is not in use is an absolute requirement. Regarding the processing baths, which may include cleaning baths, deoxidizing, caustic etching, acid etching, anodizing, alodizing, and


Table 4-17 Wastewater from an Actual Anodizing Plant. (Anodizing capacity of the plant: 2,500 tons aluminum per month)

<i>Description</i>	<i>Alkaline Wastewater</i>	<i>Acidic Wastewater</i>	<i>Rinsewater</i>
pH	Strong alkaline soln.	Strong acidic soln.	4–5
Liquid Temp. (°C)	15–60	15–60	15–25
NaOH (%)	5–7	—	—
H ₂ SO ₄ (%)	—	15	—
Al ³⁺ (%)	5.0–9.0	1.5–1.8	—
SS* (mg/l)	—	—	100–200
Flow Rate	56 cu m/day	60 cu m/day	250 cu m/hr

* Primarily insoluble Al(OH)₃**Table 4-18** Wastewater Sources

<i>Extrusion</i>	
Extrusion Press Cooling Tower Blow-down	Negligible
Extrusion Press Die Quench	1,300
Caustic Die Cleaner	1,300
<i>Fabrication</i>	
Negligible	
<i>Finishing</i>	
Tap Water Rinses	52,000
Tap Water Sprays	2,400
Chiller Cooling Water Rinse	10,000
De-Ionized Water Rinse	2,000
Demineralized Water Rinse	1,000
Rectifier Cooling Water Rinse	15,000
Periodic Tank Dumping	3,500
<i>Miscellaneous</i>	
Air Compressor Cooling Water	12,500
Regeneration of Water De-Ionizer	Negligible
Demineralizer and Soltener Units	
Boiler Water Blowdown	Negligible
Total	101,000

recovered using the Bayer reaction. This can be accomplished by operating the caustic soda etch tank (where applicable) so as to favor movement of the following chemical equilibrium to the right:




When operation is conducted in such a manner, it is said that the etching bath is operated in a metastable range; however, crystallization nuclei are needed for sodium aluminate to decompose to sodium hydroxide and aluminum hydroxide. A process patented by Alcoa introduces the waste etch solution to a reactor that contains 300–500 g/L aluminum hydroxide. Precipitated aluminum hydroxide is separated from the sodium hydroxide solution by filtration, and the sodium hydroxide solution is returned to the caustic etch process. The aluminum hydroxide can be marketed as a waste treatment chemical.

coloring, all solutions should be rebuilt and/or maintained at working strength according to need based on work done, rather than by a regular time table.

In some cases, usable, and even marketable, products have been prepared from spent acid etch solutions. When aluminum is the metal being coated, sodium hydroxide can be

Another method that combines waste treatment (of the caustic etch wastes) with wastes minimization is to precipitate and recover calcium aluminate from spent caustic etching solutions. High calcium lime is added to the spent etch solution, which contains aluminum ions at high pH. The recovered calcium aluminate can be sold or given to a cement

manufacturer, to be used as an additive. Spent caustic etch solutions have been processed as shown by the following chemical reaction:



The product, nephelin hydrate, can be marketed as a toilet cleaning product.

Regarding spent acid etch solutions, a strong base ion exchange resin can be used to separate the acid from its salts.

Technologies for recovering and regenerating chemicals, as well as separating and removing contaminants, should be aggressively employed. The general objective should be to treat wastes as close as possible to the source (individual manufacturing process) and to reuse as much material as possible. Reverse osmosis, or ultrafiltration to effect removal of oils from alkaline cleaning solutions are examples. Centrifugation has also been used for this purpose. Activated carbon can be used to remove organic impurities.

Waste Treatment and Disposal

Treatment and disposal of wastes, including solid wastes and liquid wastes, are best accomplished by recovering substances for reuse, wherever feasible, then treating remaining waste solutions and solids using procedures presented in Chapter 8 so as to produce as few residuals for disposal as possible. For instance, spent acid and caustic solutions can be combined to produce water and nonhazardous salts such as sodium sulfate. Precipitated metal salts can be treated and conditioned so as to enable disposal as ordinary nonhazardous waste.

Production and Processing of Coke

Coke is a dark gray, porous solid that is produced when pulverized soft coal is heated in an oxygen-deprived atmosphere. It contains 87% to 89% carbon and burns with intense heat and very little smoke. Coke is used as fuel in blast furnaces for the manufacture of iron and steel.

The Coking Process

The process of producing coke involves heating coal to about 2000°F. Many of the organic substances that make up coal volatilize at that temperature, leaving the coke behind. The volatilized gas is then subjected to sequentially lower temperature condensing chambers (as shown in Figure 4-12), which capture tar (a mixture of many relatively heavy organic compounds), oils, light oils, then low-molecular-weight gases. The separated coke is then used as fuel or as a component of steel. Often, some of the coke is used as fuel in the same coke ovens where it was produced. Production of coke is one of the major processes in an integrated steel mill.

As illustrated in Figure 4-12, the first compounds (highest condensing temperature) to be recovered are tars. Some coke plants recover several high-molecular-weight materials from several separate high-temperature condensers. Others simply use only one high-temperature condenser, which collects all of the high-molecular-weight compounds together as the tar. The next successively lower temperature condensers collect oils, then light oils, and finally, low-molecular-weight (methane, ethane, propane, etc.) gases.

The heating of the coal is done in narrow, rectangular, silica brick ovens. The ovens stand in groups of 10 to 100 or more, called batteries. After about 18 hours of “cooking,” the remaining substance, “coke,” which amounts to 1,300 to 1,550 pounds for each ton of coal heated, is pushed into a quenching car that transports the coke to quenching towers. Here, the coke is sprayed with water to lower the temperature. About 35% of this water evaporates and leaves the system as steam, or water vapor. The remaining water drains to a settling basin, where the coke fines are removed.

The vaporized organics produced in the ovens are withdrawn during cooking by exhausters, then sprayed with water in the first of several condensers. The sprayed water saturates and cools the gas, causing condensation of the tar. The mixture of “flushing liquid,” or “flushing liquor,” and tar flow to a separator where the water is decanted. The remaining gas




Figure 4-12 The coking process for producing coke and by-products. (From the EPA Development Document, 1973.)

flows on through a tar extractor, which is an electrostatic precipitator that removes most of the remaining tar.

Ammonia can also be recovered from the flushing liquid, using either of two methods: the semi-direct and the indirect processes. In the semi-direct process, ammonia is recovered by use of an ammonia absorber or saturator after the tar extractor. The gas is brought into contact with 5% to 10% sulfuric acid solution, causing ammonium sulfate to precipitate. The crystals of ammonium sulfate are dried and sold. In the indirect process, some of the ammonia dissolves into the flushing liquor. More ammonia is scrubbed from the gas with water and mixed with the flushing liquor. The flushing liquor is then distilled and dephenolized, and the recovered ammonia is marketed.

The phenol that is removed from the ammonia liquor is recovered as sodium phenolate. Light oil is recovered as the gas passes through a scrubber that uses an absorbent known as straw oil. The straw oil absorbs 2% to 3% of its weight of light oil. The remaining gas is then used for fuel, either on site or is marketed. Steam distillation is then used to strip the oils from the straw oil that was previously the absorbent. The wash oil is then cooled and returned to the scrubbers, as illustrated in Figure 4-12. Hydrogen sulfide is removed from the coke oven gas after the light oil scrubbers.

Sources of Wastes

The production of coke creates considerable solid, airborne, and waterborne wastes. Phenolic compounds, which make up a considerable portion of coal, are found in wastes discharged to all three media. It is essential, then, to determine the status regarding the hazardous nature of all wastes as part of wastes management.

Solid Wastes

Solid wastes from the production of coke include reject coal, reject coke, sludges from clarification of quench water, and normal packaging and shipping wastes. These wastes are in

addition to the normal solid waste stream from most typical industrial facilities, which includes construction debris from plant maintenance, repair, and expansion. Also, broken or worn-out equipment must be managed.

Airborne Wastes

Air pollution is a major concern at coke production facilities. Blowing coal dust must be controlled by containment. Because the coking process is a heating and vaporization process, there is the need to control emissions from the oven stacks. Also, there is the need to contain the vapors to prevent loss via fugitive emissions or directly out one or more stacks. Electrostatic precipitators, bag houses, and wet scrubbers are used in conjunction with aggressive preventive maintenance to avoid leaks.

Waterborne Wastes

The principle sources of wastewater from the production of coke are as follows:

- Excess flushing liquor
- Final cooling water overflow
- Light oil recovery wastes
- Condenser wastes from the crystallizer
- Gas stream desulfurization
- Sludges from air pollution control equipment
- Coal pile runoff
- Overflows from sumps, including the quench sump

The major source of wastewater is flushing liquor. The quantity of this wastewater varies with the moisture content of the coal and with the process used for recovery of ammonia. Because it is the first water to come into contact with the coke oven gases, it has the highest concentrations of pollutants. Contaminants include ammonia, phenol, sulfides, thiocyanates, and cyanides.

Final cooling water overflow results from spraying the gas stream with water to remove remaining water-soluble components and naphthalene crystals. After the naphthalene has

been removed from the stream, the water can be used for cooling. Some process wastewaters have been recycled by using them for quenching; however, caution must be exercised. As the water is evaporated during quenching, pollutants remaining in the process wastewater may be volatilized, causing air pollution. Those contaminants that are not volatilized stay with the quenched coke and thus represent a potential problem during subsequent use of the coke.

Wastes Minimization

Cover and containment are extremely important in order to minimize wastes generated at a coke production facility. If at all possible, the coal pile should be covered to prevent contamination of stormwater. Also, it is important to cover the quenching system and to contain the quench water; that is, to not allow quench water sumps to overflow. In addition, the following wastes minimization measures should be strictly adhered to:

- Drips must be contained and returned to the source.
- Aggressive maintenance must be practiced to eliminate the occurrence of leaks or other accidents that could lead to noncontainment of chemicals and other substances.
- Dry methods of clean-up, including brooms, shovels, and dry vacuuming, should be used to the maximum extent possible.
- Purchasing should be guided by aggressive selection of raw materials in order to obtain the cleanest possible materials.
- Purchasing should be guided to demand that packaging of materials delivered to the plant be recyclable or otherwise of low solid waste nature.
- There should be a constant and consistent program to substitute less-polluting and nonpolluting substances for those that require expensive treatment and expensive disposal. For instance, low-sulfur coal should be used to the extent that financial feasibility allows to minimize the quantity of sulfides and other sulfur compounds in the waste air and water.

Air Pollution Control

Control of blowing coal dust and coke fines can only be accomplished by covering the sources. Covering has the dual benefit of reducing wastewater by preventing contamination of stormwater.

Scrubbers, both wet and dry, are used extensively at coke production facilities. Also, bag houses are used in conjunction with systems that maintain clean air within the work areas of the production facilities. The blow-down from the wet scrubbing systems is a significant source of wastewater that must be managed.

Wastewater Treatment

Biological treatment systems have been used to successfully treat wastewaters from the coking process, even though these wastewaters normally contain significant amounts of toxic substances. Two procedures are used to overcome the toxic effects of these substances; the first is to remove some of them by use of a pre-treatment step. The second is to employ the process of gradual acclimation of the biological treatment system to the wastewaters.

The removal step involves combining wastewaters from light oil recovery, final cooling, air pollution control blow-down, and excess flushing liquor. This combined wastewater stream is then passed through the free leg of the ammonia still. The waste from this process is then increased in pH by addition of lime. It is then passed through the fixed leg of the ammonia still, where ammonia is removed and recovered. The effluent from this process is then combined with wastewater from the crystallizer (see Figure 4-11) and held in a storage tank for a period. The pH of the effluent from this holding tank is then lowered with acid to the neutral range. The pretreated wastewater is now ready for treatment by a properly acclimated biological system.

The acclimation step involves subjecting the biological treatment system, activated sludge, for instance, to gradually increasing levels of the toxic substances in the full-strength wastewater, until full-strength wastewater is being treated. One way to accomplish acclimation is

to develop the activated sludge system using domestic wastewater until it is fully functional as a wastewater treatment system. Then, the pretreated industrial wastewater is added to the domestic wastewater starting with a mix of about 10% pretreated industrial wastewater and 90% domestic wastewater. When it has been established that the treatment system is working well on the 10%–90% mixture, the proportion of pretreated industrial wastewater is increased, and so on, until the treatment system is receiving and operating well on full-strength pretreated wastewater. What happens during the acclimation procedure is that those microorganisms that can develop the capability to produce enzymes that can metabolize the toxic materials in the pretreated industrial wastewater grow and flourish in the activated sludge (or other biological treatment medium). Those that cannot metabolize gradually die off or are replaced over time. The result is an acclimated biological treatment system that is able to successfully treat the pretreated industrial wastewater.

An acclimated biological treatment system that consists of three extended aeration basins in series has been developed. Phenols are removed in the first basin, oxidation of both ammonia and cyanide takes place in the second basin, and the third basin (nonaerated) is used to remove nitrogen via the denitrification process. It is necessary to maintain favorable concentrations of other nutrients such as phosphorus in each of the biological treatment basins.

Chemical–physical treatment systems have been used with some success. One version of chemical–physical treatment has been to use chemical oxidation to destroy organics, ammonia, and cyanide, then to use activated carbon to remove unreacted substances as well as partially treated substances. Oxidation is accomplished by adding chlorine to the pretreated wastes in an aeration basin. Oxygen from air and chlorine are the oxidizing agents. Spent activated carbon can then be recovered (partially) by the process of heating (incinerating).

The Wine-Making Industry

Production of wine is one of the oldest endeavors of human industry. The historical record

shows that the Egyptians and the Assyrians were making wine from grapes by 3500 B.C. The basic process has remained unchanged for centuries; however, some new wine products have been developed during more modern times.

In the year 2000, approximately 12% of the world's production of wine was taking place in the United States. About 80% of the world production was in Europe. California produced more than 20% of U.S. wine. Other wine-producing states, in approximate order of quantity, were New York, Washington, Pennsylvania, and Oregon.

The most widely used grape for wine production is *Vitis Vinifera*, known as the European grape. It is grown throughout Europe, the United States, Australia, Chile, and in regions of Asia. Other grapes used for wine production include *Vitis rotundifolia* and *Vitis Labrusca*, but it is widely agreed that superior wines are produced from vinifera varieties.

The Wine Production Process

The basic, age-old process for producing wine includes six steps: destemming, crushing, pressing, fermentation, racking, and bottling. Although some destemming takes place before crushing, destemming is also accomplished simultaneously with the crushing process.

When the grapes are ripe, they are picked by hand or by mechanical harvesters. They are transported to the winery that is typically close by and are destemmed, then crushed. The amount of destemming that takes place before crushing depends on the type of wine to be made. The stems impart tannins to the wine, thus influencing the color and flavor. The product of the grape-crushing process becomes what is called *must*, sometimes before and in some cases after the solids are removed from the juice. The must is what then enters the fermentation process. If white wine is to be produced, the solids, including the skins, seeds, and the quantity of stems that remain, are removed before fermentation. If red wine is to be produced, the solids are considered part of the must. Most of the pigments

in grapes are located in the skins. Depending on the characteristics desired in the wine product, varying degrees of care are exerted to avoid breaking the seeds during the crushing process.

Sulfur dioxide is often used to treat the must before fermentation. In some cases, sufficient sulfur dioxide treatment is used to kill all of the yeast and other microorganisms naturally present in the must. Then, a desired species of yeast is added. Other effects of treating the must with sulfur dioxide include the following: settling characteristics for solids removal are improved, thus improving clarification, desired for some white wines; the color of red wines is changed somewhat; and, in some cases, storage characteristics are improved by inhibition of undesirable enzyme activity.

After treatment, if any, the must is pumped into tanks for fermentation. Typically, some of the juice is pumped over the top of the cap that forms as a result of skins and other solids collecting on the surface. This is done to increase the extraction of pigments from the skins. As ethanol increases in amount during the fermentation process, it increases the rate of extraction of pigments.

When the desired intensity of color has been achieved, the partially fermented must is pressed to separate solids from the juice, as is done before fermentation for white wines. Many types of presses are used, but all have the common objective of gently squeezing juice from the skins, seeds, pulp, and other solids without extracting undesirable substances. At this point, the solids become part of the waste stream, whereas the juice is returned to tanks to complete the fermentation process. When fermentation is complete, the process called racking is initiated. The objective of racking is as follows: After pressing to remove the skins, stems, seeds, and most of the pulp and the juice has been returned to vats for completion of fermentation, a layer of sediment called the lees, composed of dead yeast cells and bits of grape fragments, forms on the bottom of the vat. If the developing wine is allowed to remain in contact with the lees, off flavors develop from decomposition of the lees. Consequently, the

developing wine is drawn off and placed in clean vats, a process called racking.

When fermentation has proceeded to completion, various substances are often added, which are referred to as fining agents. Fining agents act to remove colloidal solids and include bentonite clay, egg whites, and gelatin. After clarification by sedimentation, the wine is normally filtered, then aged in wooden vats or bottled.

Variations on the wine process include those processes for making brandy, dessert wines, sparkling wines, and champagne. Brandy is made by first distilling the alcohol from the waste materials such as the solids or pomace left after pressing. Then, this alcohol is added to the wine, to raise the total alcohol content to about 20%. In some cases, brandy is added to other wines along with sugar and possibly other substances to produce dessert wines.

Sparkling wines are made by allowing the fermentation process to take place in a closed container. The CO_2 produced during the fermentation process dissolves into the wine under pressure. In some cases, compressed CO_2 is added to enhance the natural CO_2 content of the sparkling wine.

Champagne is normally produced by adding sugar and more yeast to finished wine. The yeast ferments the added sugar to produce more alcohol and CO_2 . The process takes place in a closed container in order to retain the CO_2 as explained previously for sparkling wines.

Wine-Making Wastes

The six major steps in wine production all produce wastes, either solid or liquid or both. Air pollution is not a normal problem in winemaking, unless unusual circumstances result in a problem with emissions from boilers or in the production of odors. Figure 4-13 presents a schematic diagram of an example winery, where production of both wine and brandy take place. As illustrated in Figure 4-13, plant clean-up operations produce plant washdown wastes from essentially all the wine-making steps.




Figure 4-13 Production of wine and brandy.

The destemming step produces waste stems and dirt that can be land applied. This can usually be done without causing pollution problems. The next step, crushing, results in normal plant clean-up wastes. The waste lees that

result from the pressing step represent varying quantities of waste material depending on whether or not by-product recovery is practiced. Fermentation also results in normal plant clean-up wastes, plus the dregs from the

fermentation process itself (dead yeast cells and various settled or filtered solids from the grapes themselves).

Racking results in sediment in the bottom of the vats, as well as normal plant washdown wastes. Finally, bottling results in more plant washdown wastes. All of these wine-making steps, except for destemming, contribute wastes in the form of lost product, including the final step, bottling, where lost wine product from spillage, overfilling, bottle breaking, and other unintentional releases contribute to the BOD level of the overall plant waste stream.

Wastes Minimization

Similar to many food processing industries, by-product recovery can reduce the quantity of wastes that require treatment. One example is the recovery of tartrates, salts of tartaric acid, which occur in lees, pomace, and on the surfaces of wine storage tanks. Tartrates are rinsed off the surfaces of storage tanks and extracted from pomace using water and are then precipitated with calcium carbonate or lime. The dried precipitates are used in cooking as cream of tartar.

Another example is the recovery of an edible oil from grape seeds.

Pomace is sometimes used for animal feed. Otherwise, it can be mixed with the stems and other solids and returned to the vineyards for use as a soil conditioner and fertilizer.

Treatment of Winery Wastes

The principal liquid waste from wineries is the washwater from general plant clean-up as well as vat cleaning, bottle cleaning, and product loss. In general, biological treatment processes have been used with success, including anaerobic processes and aerobic processes. In 1989, Farmer reported on a pilot plant project in which an upflow anaerobic sludge blanket (UASB) and an anaerobic contact process were used to treat high-strength wastes (COD of about 15,000 mg/L) from a winery.

Both processes were successful in removing 98% of the soluble COD. Following the processes with aerobic treatment increased overall COD removal to more than 99%. As expected, the principal advantages of the anaerobic processes over using only aerobic treatment were that the anaerobic processes produced about 80% less sludge and occupied a significantly smaller footprint.

One of the most popular methods for treating winery wastes has been that of land disposal, especially the ridge and furrow method. Russell et al. reported on a land application system that treated up to 50,000 gallons of wastewater per day in California. The operation was called an unqualified success, with negligible contamination of groundwater.

Ryder reported on the successful use of an aerobic lagoon to treat winery wastes. Ryder emphasized the value of the aerated lagoon effluent as irrigation water for the vineyards.

An aspect of winery waste treatment that is different from most other industrial wastes is that the destruction of any waste containing alcohol must be in accordance with regulations of the Bureau of Alcohol, Tobacco, and Firearms (BATF). The law specifically regulates disposal of lees, requiring that wine must be completely pressed or drained from the lees before it can be used for animal feed or production of cream of tartar or other uses.

The Synthetic Rubber Industry

Many different types of synthetic rubber are produced today, and a host of products are made from them. Annual (world) production in the year 2000 exceeded 20 million tons, accounting for well over 80% of all rubber products produced, including natural rubber.

Nearly 300 years after Columbus discovered Haitian children playing with what would later be known as rubber balls, Joseph Priestly, an English chemist, discovered that the gum from certain trees grown in South America, Haiti, and nearby islands would rub out pencil marks. Hence, the name, rubber was born. During the next 100 years, use for this remarkable

substance, produced from the sap of *Hevea Brasiliensis* that were still confined to the jungles of South America and nearby islands, developed slowly. In 1876, the British transplanted thousands of these trees in southeastern Asia and began large-scale production of rubber, now known as natural rubber. The milky sap from which natural rubber is made has, since that time, been called latex, from the latin word for milk, *lactic*.

Shortages during the war years, from World War I through the early 1950s, prompted the development of synthetic rubber. During World War II, the effort put forth by the United States to develop its synthetic rubber manufacturing capability was second only to its efforts to develop the atomic bomb. The principal synthetic rubber produced during that period was called GR-S, for Government Rubber Styrene, which is still produced as SBR, Styrene Butadiene Rubber.

The many different types of synthetic rubber produced in the early 2000s include silicone rubbers, used in the aerospace industry for their usefulness over wide ranges of temperature; butyl rubber, used for the manufacture of inner tubes; chloroprene rubber, used to line tanks to prevent corrosion; latex (foam rubber), used for the manufacture of cushions, padding, and other things; nitrile rubber, used in the manufacture of oil-resistant and heat-resistant hoses, gaskets, and other things; and styrene butadiene rubber (SBR), the most commonly used type of synthetic rubber. SBR is used in the manufacture of automobile tires, conveyor belts, noise and vibration insulators, foul weather gear, and many other things. More than 500 different types of SBRs are produced, most for the automobile industry.

For purposes of regulation, the EPA has divided the rubber manufacturing industry into two categories, the Tire and Inner Tube Industry and the Synthetic Rubber Industry. Both categories make extensive use of SBR. Because the raw materials from which SBR is manufactured are derived from petroleum, the synthetic rubber industry tends to be located within two clusters. The plants that produce synthetic rubber are clustered in the oil-producing states,

mainly Louisiana and Texas, whereas those that produce products made from synthetic rubber are located in industrialized areas, especially those associated with the automobile industry.

Production of Synthetic Rubber

So-called tire rubber, which is also used for many other products, is produced as a substance known as crumb rubber. There are two principle methods for producing crumb rubber: solution crumb production and emulsion crumb production. Solution crumb production involves mixing the raw materials in a homogeneous solution wherein polymerization takes place. Emulsion crumb production involves producing an emulsion of the raw materials, resulting in bulk polymerization of droplets of monomers suspended in water. The mechanisms of solution polymerization are those of ionic interaction. The mechanisms of emulsion polymerization require sufficient emulsifier, in the form of a soap solution, to maintain a stable emulsion and proceed as follows.

Emulsion Crumb Production

Production of crumb rubber by emulsion polymerization has been the traditional process for production of synthetic rubber. It is still the most commonly used process, accounting for 90% of the world's production of SBR. Figure 4-14 is a schematic diagram of the emulsion crumb rubber production process.

As illustrated in Figure 4-14, raw materials in the form of monomers, produced by the petroleum industry, are delivered to tank farm. The monomers include styrene and butadiene. Because production facilities such as these operate 24 hours per day, 365 days per year, the tank farm always maintains a constant supply. Other materials delivered and stored in tank farms include soap (or detergent), activator, catalyst, modifier, extender oil, and carbon black. Butadiene, as well as certain other polymers, is delivered with polymerization inhibitors mixed in, to prevent premature polymerization during delivery and storage.

GENERAL WATER FLOW DIAGRAM FOR AN EMULSION POLYMERIZED CRUMB RUBBER PRODUCTION FACILITY




Figure 4-14 General water flow diagram for an emulsion polymerized crumb rubber production facility.

The production process begins with removal of the polymerization inhibitors, by passage of the monomer through a caustic scrubber. The monomers to be polymerized are mixed with soap solution, deionized water, catalyst, activator, and modifiers before entering the first of a series of reactors. The purpose of the soap solution (or detergent) is to hold the entire mixture in a stable emulsion throughout the polymerization process. Rosin acid soap or fatty acid soap is typically used. The purpose of the catalyst is to generate free radicals to initiate and maintain polymerization. Typical catalysts used are hydroperoxides or peroxyulfates.

The function of the activator is to assist the catalyst in generating free radicals, as well as to enable reaction at a lower temperature. The modifier acts to control the length of the polymerized chain and, consequently, the size (and molecular weight) of the polymer. The process is operated as either cold (40–45°F at 0–15 psig) or hot (122°F at 40–60 psig), to produce cold SBR or hot SBR, respectively. Cold SBR processes are stopped at 60% polymerization. Hot SBR processes, the older of the two, are allowed to proceed to near completion of the polymerization process.

Cold rubbers have improved properties, compared to hot rubbers, but require more extensive process management. The emulsified mixture resulting from the initial mixing of monomers and additives must be kept cool by means of an ammonia refrigerant before entering the reactors. Also, a shortstop solution must be added to the solution exiting the reactor, in order to halt the polymerization process at 60% completion. Then, the unreacted monomers, as well as the catalysts, activators and modifiers, water, and emulsifiers, must be separated from the polymerized material, reconditioned, and returned for continued use.

The shortstop solution is made up of sodium dimethyl dithiocarbonate and hydroquinone. The 60% reacted mixture, at the point of being stopped, is milky-white in appearance and is called latex. Although it resembles the sap from the natural rubber tree in appearance, the two are not to be confused with each other.

The next step is recovery of unreacted butadiene by use of a vacuum flash tank. Recovery of styrene is accomplished by use of perforated plate stripping columns. The stripped latex must be protected from oxidation by oxygen or ozone. This is accomplished by adding an antioxidant in a blend tank. The polymerized material is then separated from the remaining latex by coagulation, which is brought about by addition of dilute sulfuric acid (pH 4–4.5) and sodium chloride (brine). At this point, the product is called crumb. Carbon black and various oils are added to the crumb to produce desired properties, including color.

Separation of the coagulated crumb is accomplished on a shaker screen. The liquor is then returned for reuse, after reconditioning by addition of fresh acid and brine. The crumb is washed by resuspension in water in a reslurry tank. Gravity separators, called crumb pits, are used as clarifiers to recover floatable crumb rubber from both the liquor having passed through the shaker screen and overflow from the reslurry tank.

The filtered and washed crumb rubber is dried by use of hot air, then weighed, baled, and stored for shipping.

Solution Crumb Production

Production of crumb rubber by the solution crumb process allows the use of stereo-specific catalysts that are able to produce polymers nearly identical to natural rubber. In the proper organic solvent, as opposed to an emulsion, as used in emulsion polymerization, the *cis* structure can be obtained in an amount up to 98% of the total.

Figure 4-15 is a schematic diagram of a solution polymerized crumb rubber production facility. As can be seen, there are similarities to the emulsion polymerization process but several important differences. Solution polymerization requires that the monomers be of a very high degree of purity. The solvent in which the monomers, catalyst, and modifiers are dissolved must also be absolutely anhydrous. The polymerization process proceeds to over 90% completion, in contrast to the emulsion

GENERAL WATER FLOW DIAGRAM FOR A SOLUTION POLYMERIZED
CRUMB RUBBER PRODUCTION FACILITY




Figure 4-15 General water flow diagram for a solution polymerized crumb rubber production facility.

polymerization process, which is stopped by the introduction of the shortstop solution at the point of 60% completion.

Figure 4-15 shows that the stored monomers are pumped from the tank farm through caustic soda scrubbers to remove polymerization inhibitors. The monomers proceed to fractionator-drying towers, where water is removed. These towers are also used to remove water from recycled as well as fresh solvents. The monomers and solvents are mixed to produce mixed feed, and catalysts are added. This begins the polymerization process, which is exothermic. For this reason, the reaction vessels must be cooled, typically by an ammonia refrigerant. The shortstop solution is added after the reaction has reached 90% or more completion.

After the polymerization reaction has been halted, additional substances are added, including antioxidants and oil for oil extension. The mixture is then transferred to a coagulation vessel, where the polymerized material precipitates as the crumb. Carbon black is typically added at this point.

The mixture is now ready for separation of the crumb from the liquor and separation of some of the components of the liquor for reuse. A series of strippers is used to strip off solvents and unreacted monomers. The vapors of monomers and solvents are condensed and sent to a decant system. The organic portion is returned to the fractionator. Decant is discharged as wastewater. The stripped crumb slurry is separated further and proceeds to a vibrating screen, where it is washed with water. Most of the washwater recycles to the coagulation stage, and the rest is discarded as blow-down. The crumb is dried, baled, and stored for shipment to a processor.

Specialty Products

Far less important in terms of annual production totals, but important in terms of pollutant generation, are the specialty rubbers. These products have more diverse composition as well as end uses. The largest of these, in terms of production volume, are the butadiene

rubbers, which are sold by producers in a latex form as opposed to the crumb rubber form.

Production of latex is the same as emulsion crumb production, except that the coagulation step for separation of the crumb rubber from the liquor is not carried out. Another difference, important in terms of pollutants generated, is that in latex production, polymerization is allowed to proceed essentially to completion. This is in contrast to the production of crumb rubber, in which the polymerization process is stopped at the point of 60% completion. Consequently, recovery of unpolymerized monomer is not feasible. Figure 4-16 presents a schematic of the latex production process.

Wastes Generation

The generation of wastes at manufacturing facilities engaged in the production of synthetic rubber depends to an unusually high degree on how well the entire facility is managed to prevent such generation. Raw materials are delivered as bulk liquids, and the delivery process can be pollution free if there are no spills and fumes are contained. The entire process, except for the clarification and decant steps, is contained within tanks, pumps, piping systems, and mixing vessels; therefore, the only opportunities for air pollution are from leaks and sloppy handling. The only solid material involved in the production process that is of significant volume is the product rubber itself. Any loss of this material to solid waste is a loss of valuable product.

Solid Wastes

Solid wastes requiring management at a typical synthetic rubber production facility should be only those nonproduction-related wastes such as packaging and shipping wastes, construction debris from plant maintenance, modifications, expansions, and periodic facility upgrade projects. In addition, sludges from wastewater treatment and waste resins from process water deionization require management.

GENERAL WATER FLOW DIAGRAM FOR AN EMULSION LATEX RUBBER PRODUCTION FACILITY




Figure 4-16 Schematic of the emulsion latex production process.

Airborne Wastes

The many scrubbers and strippers used at synthetic rubber production facilities are potential sources of air pollutants. Vents on tank farm storage facilities are also potential sources of wastes.

Waterborne Wastes

Figures 4-14 through 4-16 show principle sources of wastewater from each of (1) the emulsion crumb production process, (2) the solution crumb production process, and (3) the emulsion latex production process, respectively. As shown in these figures, essentially every major processing unit is a source of wastes during the normal processing schedule. For instance, Figure 4-14 shows that as the monomers are being transferred from storage to the polymerization reactors, they are passed

through the caustic scrubbers to effect removal of the polymerization inhibitors. There is a blow-down of spent caustic wash solution, contaminated with the polymerization inhibitor material, entering the wastewater stream. What is not shown is that each of these processing units is a source of wastewater as a result of periodic washdown; however, these figures do show that additional areas of the plant are at least potential sources of wastewater as the result of spills or overflows. When these largely unnecessary events occur, they must be managed properly to avoid damage to the environment.

The sources of wastewater from the emulsion crumb production process, as illustrated in Figure 4-14, are presented in Table 4-19.

The sources of wastewater from the solution crumb production process, as illustrated in Figure 4-15, are presented in Table 4-20.

Table 4-19 Summary of Potential Process-associated Wastewater Sources from Crumb Rubber Production via Emulsion Crumb Production

<i>Processing Unit</i>	<i>Source</i>	<i>Nature of Wastewater Contaminants</i>
Caustic soda scrubber	Spent caustic solution	High pH, alkalinity, and color Extremely low average flow rate
Monomer recover	Decant water layer	Dissolved and separable organics
Coagulation	Coagulation liquor overflow	Acidity, dissolved organics, suspended and high dissolved solids, and color
Crumb dewatering	Crumb rinse water overflow	Dissolved organics, and suspended and dissolved solids
Monomer strippers	Stripper cleanout and rinse water	Dissolved organics, and high suspended and dissolved solids High quantities of uncoagulated latex
All plant areas	Area washdowns	Dissolved and separable organics, and suspended and dissolved solids

Table 4-20 Summary of Potential Process-associated Wastewater Sources from Crumb Rubber Production via Solution Polymerization Processing

<i>Processing Unit</i>	<i>Source</i>	<i>Nature of Wastewater Contaminants</i>
Caustic soda scrubber	Spent caustic solution	High pH, alkalinity, and color Extremely low average flow rate
Solvent purification	Fractionator bottoms	Dissolved and separable organics
Monomer recovery	Decant water layer	Dissolved and separable organics
Crumb dewatering	Crumb rinse water overflow	Dissolved organics, and suspended and dissolved solids
All plant areas	Area washdowns	Dissolved and separable organics, and suspended and dissolved solids

The sources of wastewater from the emulsion latex production process as illustrated in Figure 4-16, are presented in Table 4-21.

Wastes Minimization

Maintaining a very high level of attention to containment of fumes and prevention of spills, overflows, leaks, and other unintended discharges is of paramount importance. Containment of the ammonia refrigerant, which is used to prevent the exothermic polymerization reactions from attaining too high a temperature, is also important.

Several of the processing steps in all three of the production procedures involve separation of product from liquor, by screening, gravity separation, or combinations of these processes. These steps are followed by liquor renovation and recycle for reuse, integrated with a blow-down. Close attention to the characteristics of the blow-down, ensuring that it is not a larger fraction of the total quantity of liquor than it needs to be, is an important wastewater minimization procedure.

In all of the variations (emulsion and solution) for production of crumb, there is a procedure for washing and rinsing the product crumb with water. The spent washwater enters the wastewater stream. Development of counter-current washing and rinsing procedures, by which fresh water is used only for the

final rinse and maximum recycle of all effluents is practiced, is imperative. For instance, the effluent from the first rinse should be used as makeup for the washwater used in conjunction with the vibratory screen separation process, as discussed previously.

There are success stories involving wastes minimization by use of substitution in the synthetic rubber production industry. For instance, coagulation of latex with acidpolyamine rather than brine solution results in significantly lower TDS in the wastewater. As another example, the use of a steam grinding technique for the addition of the carbon slurry has resulted in a significant reduction in spillage of carbon black. This, in turn, has resulted in significant reduction in washdown and runoff wastewaters contaminated with carbon black. As still another example, the use of alum, on the spot, to coagulate crumb material from spilled latex solution can reduce the amount of washdown water required. Finally, use of dual crumb pits can effectively avoid resuspension of colloids during cleaning.

Wastewater Treatment

In general, all of the raw materials used in the production of synthetic rubber are biodegradable, and all of the wastewaters are amenable to biological treatment. Also, as a general rule,

Table 4-21 Summary of Potential Process-associated Wastewater Sources from Latex Production via Emulsion Polymerization Processing

<i>Processing Unit</i>	<i>Source</i>	<i>Nature of Wastewater Contaminants</i>
Caustic soda scrubber	Spent caustic solution	High pH, alkalinity, and color Extremely low average flow rate
Excess monomer stripping	Decant water layer	Dissolved and separable organics
Tanks, reactors, and strippers	Cleanout rinse water	Dissolved organics, suspended and dissolved solids High quantities of uncoagulated latex
Tank cars and tank trucks	Cleanout rinse water	Dissolved organics, suspended and dissolved solids High quantities of uncoagulated latex
All plant areas	Area washdowns	Dissolved and separable organics, and suspended and dissolved solids

those wastewaters generated by emulsion crumb and emulsion latex production procedures require chemical coagulation (to break the emulsions) before chemical treatment. This is not true of the solution polymerized production wastewaters. Following appropriate preliminary treatment, conventional primary treatment by gravity clarification, possibly aided by settling aids, secondary treatment by any of the variations of the activated sludge processes, with appropriate addition of nitrogen and phosphorus as nutrients, and additional treatment as required for compliance with receiving water classification requirements, has been successful. Those additional treatment technologies have included sand filtration and mixed media filtration.

An equalization system preceding the wastewater treatment system can effectively even out the flows and loads, and allow construction and operation of a smaller treatment system. Also, pH control in conjunction with the equalization system has been effective in improving the performance of primary clarification. Settling aids such as cationic polymers may improve the performance of primary clarification.

Wastewater characterization parameters that have been of significance are the conventional parameters, namely, pH, TSS, BOD₅, COD, and O&G. Other parameters have included TDS, acidity, alkalinity, surfactants, color, and temperature. The COD-to-BOD ratio is typically high because of COD demand of inorganic constituents. COD values have ranged from about 9 pounds per thousand pounds of product for wastewaters from the solution crumb process to about 35 pounds per thousand pounds of product for the emulsion latex process. BOD values have ranged from about one pound per thousand pounds of product (solution crumb) to about 5 pounds per thousand pounds of product in the case of the emulsion crumb process.

Wastewaters from emulsion crumb and latex plants are characterized by high values of TSS, due, usually, to uncoagulated latex. In general, TSS values have ranged from about 3 pounds per thousand pounds of product, for solution

crumb wastewaters, to about 6 pounds per thousand pounds of product for emulsion latex wastewaters. Total dissolved solids are typically attributable to carbonates, chlorides, sulfates, phosphates, and nitrates of calcium, magnesium, sodium, and potassium. Traces of iron and manganese can also be present. A major source of TDS from the emulsion crumb process has been the liquor from the coagulation process that was used to separate the crumb. High TDS values are also characteristic of wastewaters from the solution crumb and emulsion latex processes.

O&G in wastewaters from all synthetic rubber production processes have been attributed to undissolved monomers and extender oils. Leaked or spilled machine lubricating oils and hydraulic fluids are also potential sources.

The Soft Drink Bottling Industry

In the late 1800s, the then fledgling U.S. soft drink industry was party to the introduction of a new drink made from African kola nut and cocoa extracts and water saturated with carbon dioxide. The first cola drink thus began what is now one of the world's major industries. This industry is still experiencing significant growth in the early 2000s.

Production of Bottled Soft Drinks

The soft drink industry's products (in the U.S.) are divided into two categories: soda water and colas, also known as peppers. Soda water is simply water saturated with carbon dioxide. Saturation is defined as that amount of carbon dioxide dissolved, at equilibrium, under a pressure of one atmosphere (about 15 psig) at a temperature of 60°F. This quantity is referred to as one volume of carbon dioxide. A cola (or pepper) must contain caffeine from the kola nut or from extracts of other natural substances. In the United States, the quantity of caffeine is not allowed to exceed 0.02% by weight. The exact formula for most commercial beverages is proprietary and closely guarded; however, the two formulas in Table 4-22 are said to be representative.

Table 4-22 Typical Soft Drink Formulas

<i>Carbonated Cola Beverage</i>	
Sugar syrup, 76 Brix	305.00 ml
Phosphoric Acid, 85%	1.25 ml
Caffeine solution, 4%*	10.00 ml
Caramel color, double strength	4.00 ml
Natural cola flavor	2.00 ml
Water	177.75 ml
<i>*Caffeine solution, 4% (wt/wt)</i>	
Sodium benzoate	5%
Water	91%
Caffeine	4%
<i>Pale Dry Ginger Ale</i>	
Pale dry ginger ale flavor	2.00 ml
Citric acid solution, 50%	9.20 ml
Sodium benzoate solution, 18%	5.00 ml
Carmel color 2X, 20% solution	0.30 ml
Sugar syrup, 76 Brix	248.00 ml
Water	235.50 ml

Table 4-23 presents a general summary of the ingredients of various types of carbonated soft drinks.

Sweeteners include dry or liquid sucrose, invert sugars, dextrose, fructose, corn syrup, glucose syrups, sorbitol, or an artificial substitute. Flavorings are often used in a carrier such as ethanol, propylene glycol, glycerin, or may be in the form of fruit juice extracts, or the juices themselves, dehydrated or full strength, or extracts from bark, vegetables, roots, or leaves. Edible acids used include acetic, citric, fumaric, gluconic, lactic, malic, tartaric, or phosphoric. This statement of ingredients is by no means intended to be complete; rather, it is intended to illustrate the variety of substances the environmental engineer may be confronted with in situations involving spills, leaks, or sloppy management of the production plant.

Figure 4-17 presents a flow diagram of a typical soft drink bottling industrial facility. The term bottling is used generically to include packaging, under a pressure of about one atmosphere, in bottles, cans, plastic containers, kegs, or other bulk containers. The first significant activity is delivery of raw materials to the receiving and storage facilities, usually a relatively small tank farm. Also, water is significant activity is delivery of raw materials

Table 4-23 Types of Soft Drinks*Soft Drink Ingredients (General)*

<i>Soft Drink</i>	<i>Flavors</i>	<i>Color</i>	<i>Sugar (%)</i>	<i>Edible Acid</i>	<i>Carbon Dioxide (CO₂) (volume of gas)</i>
Cola	Extract of kola nut, lime oil, spice oils, and caffeine	Caramel	11–13	Phosphoric	3.5
Orange	Oil of orange and orange juice	Sunset yellow FCF with some Tartrazine	12–14	Citric	1.5–2.5
Ginger ale	Ginger root oil or ginger, and lime oil	Caramel	7–11	Citric	4.0–4.5
Root beer	Oil of wintergreen, vanilla, nutmeg, cloves, or anise	Caramel	11–13	Citric	3




Figure 4-17 Flow diagram of standard manufacturing process—bottled and canned soft drinks.

to the receiving and storage facilities, usually a relatively small tank farm. Also, water is stored, after treatment to the specifications of the bottling company on the one hand and the requirements of applicable agencies and federal, state, and local regulations on the other hand. Carbon dioxide may be delivered to the site or may be generated on site.

Treatment of the water may include simple filtration or activated carbon adsorption, or it may include extensive treatment such as coagulation, flocculation, and sedimentation, followed by filtration, activated carbon adsorption, disinfection, and dechlorination. In addition to high-quality water from the standpoint of health, the concerns of the bottling company are any substances in the water that may affect taste, or high carbonate hardness, which can cause the beverages to go flat in a short amount of time. Also, certain heavy metal ions can cause rapid loss of carbonation. Desirable characteristics of the water to be used in soft drink production include complete absence of bacteria, turbidity, dissolved carbon dioxide, and chlorine.

Preparation of the bottles (or other containers) includes washing and sterilization. As will be discussed later, this process represents one of the most important and largely unavoidable (but not amenable to minimization) sources of wastewater. Reusable bottles require washing in a hot caustic solution. They are then subjected to the washing and rinsing procedures used on new bottles.

The mixing of ingredients by transferring them from storage to blending systems is one of three major operations in the soft drink production process. However this is accomplished, whether by means of pumps and pipes, or by use of transfer vessels, clean-up operations at the end of each processing day, and, in some cases, throughout the processing day, it represents a major source of waste generation.

The next steps after mixing are carbonation and bottling, usually done concurrently. Here, again, no true wastewater is generated, except unintentionally as from spills, leaks, broken bottles or other containers, or, in very rare

instances, the need to discard a bad batch because of contamination. Daily washdown of equipment, of course, is an ever-present major source of wastewater.

After bottling, the filled and sealed containers are labeled, then packaged for storage and/or shipment.

Wastes Generation

Except for boiler operation, the bottled soft drink industry is not a significant source of air pollutants. Both solid wastes and waterborne wastes, however, are of major concern to plant and environmental managers.

Solid Wastes

There are several significant sources of solid wastes from the bottled soft drink industry. The first, using the flow-through of materials from receipt and storage to shipment of final product as the approach, is the discarded (and not recycled) material used for packaging and shipping raw materials to the facility. There are also the materials intended for recycle that are found to be unacceptable for recycling. Next, there are the residuals from treatment of the water to be used in the product. Then, there are the substances cleaned from the processing facility floor during clean-up operations. This can include broken bottles or other objects, lost caps, and discarded personal items from employees. The residuals from wastewater treatment constitute a major source of solid wastes. Finally, there are the items discarded from labeling and packaging the product for storage and/or shipment.

Nonprocess-related solid wastes include construction debris from plant upgrades, facility expansions, general facility repair, and upkeep, and incidental wastes such as garbage and trash from the cafeteria. In general, there are no hazardous wastes from these facilities.

Waterborne Wastes

The major sources of wastewater from soft drink bottling operations include plant washdown wastewater and the wastewater from washing

bottles (and other containers), as shown in Figure 4-17. Plant washdown water includes the water used to clean the machines, pumps, pipes, and mixing and bottling equipment, as well as to wash the floors and the general work area.

Wastes Minimization

Wastes minimization at soft drink bottling facilities is best accomplished by the following:

- Installing overflow warning devices on all storage tanks, mixing tanks, blending tanks, and holding tanks.
- Using biodegradable detergents.
- Containing drips and returning them to the source.
- Practicing aggressive maintenance to eliminate the occurrence of leaks or other accidents that could lead to noncontainment of sweeteners, finished product, and other substances.
- Using dry methods of clean-up, including brooms, shovels, and dry vacuuming, to the maximum extent.
- Rinsing bottles after cleaning in a counter-current manner, with respect to freshwater makeup and spent rinsewater overflow.

Wastewater Treatment

Because no nonbiodegradable substances are used at soft drink bottling facilities, all wastewaters are amenable to biological treatment. As a general rule, no pretreatment other than screening and pH adjustment is required before secondary treatment by either an on-site biological treatment system or at a POTW. Adjustment of pH is required because of the caustic used for cleaning bottles, pipes, tanks, floors, and mixing and bottling machinery.

A two-stage aerated lagoon has been used with success at a bottling plant in New England. The layout and characteristics of this system are as follows:

- The first lagoon is operated as a sequencing batch reactor.
- The second lagoon is operated as a conventional aerobic lagoon.

- Potassium is added to both lagoons as a nutrient.

The primary reasons for selecting the two-lagoon system were as follows:

- Lagoons, because of their relatively large volume, are capable of withstanding large variations in flows and loads, pH, and concentrations of chlorine.
- The sandy nature of the soil in the area of the plant would allow percolation of liquid into the ground and to the groundwater for removal from the area.
- There was ample distance to the groundwater for complete treatment (renovation of the wastewater) before reaching the groundwater.
- The sandy nature of the soil allowed free movement of oxygen into the soil to support the in situ, on-site biological treatment.
- It was calculated that sludge would have to be removed only once every 5 to 10 years.

The Pepsi Corp. has patented a wastewater treatment system having the following layout and operational characteristics:

- Waste from the returned bottle prerinse was directed to a trickling filter operated as a roughing filter.
- The effluent, along with the sloughings from the roughing filter, were directed to an oxidation tank, which also received flow from the bottling area in the processing plant, the plant washdown water, and the wastewater from a solids separator used for the process water filter backwash.
- The oxidation tank was aerated with air for biological treatment as well as ozone for chemical oxidation.
- The effluent from the oxidation tank flowed to an aerated mixing tank, where it mixed with wastewater from the final bottle rinse.
- This mixture flowed to an activated sludge aeration tank followed by a final clarifier, then a disinfection tank, where ozone was added as the disinfectant and pH was given a final adjustment before discharge.

Production and Processing of Beef, Pork, and Other Sources of Red Meat

In the United States, more than 90% of the protein consumed by the population was derived from animals in the year 2000. This compares to about 55% in Western Europe, about 40% in Eastern Europe, about 40% in Japan, and about 20% in Africa. As a general rule, people appear to increase their consumption of animal-derived protein as their standard of living increases. It is therefore expected that as so-called underdeveloped countries develop, the raising, slaughtering, processing, and consumption of animals will increase.

Processing animals for use as food results in very large quantities of wastes that must be managed. Many of the processes discussed in this section are applicable, with some modification of actual characteristics, to the processing of goats, sheep, and other animals processed throughout the world for the purpose of producing edible protein.

The Production and Processing of Beef

Cattle are grown, processed, and eaten around the world. Table 4-24 presents a summary of the leading producers by country of beef and veal as of 1998 (MHR-Viandes, 1998). As a general rule, cattle are processed for market in facilities owned and operated by parties other than those that breed and raise cattle. Beef-processing plants have receiving and holding facilities to which cattle are delivered by truck or by rail car, generally on the day they will be slaughtered and processed.

Plants engaged in the processing of beef range from those that only slaughter (slaughterhouses) to those that perform many operations, including killing, sticking, bleeding, dressing, trimming (hide removed), washing, processing, and packaging (processing plants). Many plants perform all of the functions of a processing plant, plus engage in what is known as further processing, which includes cooking, curing, smoking, pickling, and canning, and produce other products (packinghouses).

Table 4-24 Leading Producers of Cattle and Per Capita Consumption of Beef. World Beef and Veal Production in 1998

<i>The four major areas of production are:</i>	
North America	
35.5% of world production, i.e., 14.7 million tons.	
United States with 11.7 million tons—Mexico 1.8—Canada 1.0.	
South America	
19.1% of world production, i.e., 7.88 million tons.	
Brazil with 4.96 million tons—Argentina 2.55—Uruguay 0.37.	
Western Europe	
18.0% of world production, i.e., 7.46 million tons.	
France with 1.640 million tons—Germany 1.438—Italy 1.000—U.K. 0.740—Ireland 0.500—The Netherlands 0.490—Spain 0.485—Belgium-Luxembourg 0.325—at less than 0.200 Austria, Denmark, Sweden, Portugal and Greece.	
Asia	
12.6% of world production, i.e., 5.22 million tons.	
China with 4.400 million tons—Japan 0.485—Korea 0.233.	
Miscellaneous	
Russia with 2.633 million tons.	
Australia with 1.775 million tons.	
New Zealand with 0.616 million tons.	

Figure 4-18 presents a flow diagram of a “typical” packinghouse. As shown, a typical slaughterhouse, processing plant, or packinghouse has facilities at which animals are received and held in pens. It is here that wastes are first generated, consisting of excrement and washdown water.

The slaughtering operation begins with stunning, usually with electric shock or plastic bullet to the brain, followed by hanging, sticking, and bleeding. Blood is collected on the killing floor. The animals are then dressed (disemboweled), trimmed, or skinned, washed, then hung in cooling rooms.

The finished product from slaughterhouses consists of the cooled carcasses, plus hearts, livers, and tongues. The hides are salted, folded, and piled, then shipped to a tannery.

Viscera, feet, and head bones are either sent to a rendering facility, or, in many cases, processed in an on-site rendering facility. Wastes from rendering are discussed in a separate chapter.

The next series of operations is referred to as processing. The carcasses are cut into smaller sections or into individual cuts. At some plants, curing, smoking, canning, and possibly many additional activities take place.

Packinghouses are also capable, typically, of performing many by-product processing operations, such as processing blood collected just after the animals are killed, and rendering the inedible materials. Rendering refers to separating the fats and proteinaceous materials by use of heat and sometimes pressure. Fats are harvested as lard and other products. Protein material is harvested as animal feed supplement.




Figure 4-18 Flowchart for packinghouse. (From North Star Research & Development Institute, "Final Report, Industrial Waste Study of the Meat Products Industry," EPA Contract No. 68-01-0031.)

The Production and Processing of Pork

Similar to the processing of beef, plants engaged in the processing of swine range from those that only slaughter (slaughterhouses) to those that perform many operations, including killing, scalding, dehairing, washing, eviscerating, processing, and packaging (processing plants). Many plants perform all of the functions of a processing plant, plus engage in what is known as further processing, which includes cooking and producing bacon, sausage, and many other products (packinghouses). Many specialty plants receive processed swine and produce items such as summer sausage and specialty meats, all of which can be categorized as “further processing.”

Production Processes

In the slaughterhouse portion of the operation, the animals are first stunned, usually by electric shock, then are hung over a bleeding trough. Movement of the animals is continuous through the next several steps, enabled by a moving conveyor, to which the hooks that hang the animals are attached. As the animals move over the bleeding trough, they are stuck (jugular vein is cut), and the draining blood is collected in a trough. The animals are then passed through a scalding tank, where very hot water softens the hair follicles. After emerging from the scalding tank, the animals are dehaired, usually by abrasion from some type of rotating rubber fingers in a machine that becomes extremely loaded with hair, bits of hide, and blood throughout the processing day. An open flame singes the carcasses to remove the last traces of hair, and then they are sprayed with water for cooling and washing.

At an increasing number of slaughtering facilities, the animals are subjected to skinning, which eliminates the scalding and dehairing; however, the hides eventually have to be cleaned and dehaired, which amounts to transferring the waste management problem to another location.

The next step is to open the carcasses (by handheld knives) for disemboweling, referred to as the eviscerating procedure. The carcasses

are cut in half and hung in a cooler for 24 hours or more. They are then cut into smaller sections or into individual cuts, and major differences occur from one packinghouse to another at this point. Swine (usually called hogs in the U.S.) are cut into hams, sides, shoulders, and loins. At some plants they are cured. Loins, however, are usually packaged without curing.

Heart, liver, and kidneys are washed and processed as edible meat products. Meat for sausage is ground and emulsified, then blended with herbs, spices, and nitrite and nitrate preservatives. The sausage mix may then be packaged or extruded into casings that have been removed from the outside of hog or other animal intestines. Cellulose materials are also used for sausage casings. The sausage may then be cooked or smoked, or packaged for sale as fresh. Smoking is accomplished by hanging the meat or meat product in an atmosphere of smoke generated by burning hardwood sawdust (above 137°F to prevent botulism). The cresols from this burning process are responsible for the characteristic flavor of smoked meat. An alternative process is to soak or inject the meat or meat product in a solution of salt, sugar, and natural and/or artificial flavorings.

Wastes Generation

Animal slaughtering operations result in large quantities of solid, airborne, and waterborne wastes. Even when all possible materials are contained and processed as by-products, there are large quantities of solid wastes from paunch manure and sludges from wastewater treatment to be managed. There are many airborne substances in the form of odors, and very large amounts of strong waterborne wastes from blood, plant washdown, and by-product operations such as on-site rendering facilities.

Solid Wastes

Generation of solid wastes begins in the receiving and holding pen area. Wastes include excrement, washwater, and often, rainfall runoff. Unless the holding pen area is covered and has a well-engineered, constructed, and

maintained stormwater management system, the runoff can become heavily contaminated and represent a significant management problem. Well managed, the excrement can remain as solid waste and be treated and disposed of by use of composting (see Chapter 8) or applied directly to farmland.

Hides are major products of animal slaughtering facilities. Although the hides themselves are not solid waste, they typically contain large amounts of excrement and dirt. This material must be removed and managed as waste material somewhere, either at the slaughterhouse or at the tannery.

Airborne Wastes

Air pollution from animal-processing facilities is typically a significant issue only if the release of odors is not controlled. If a rendering plant is operated on site, it is a major issue. Rendering facilities are almost always sources of generation of nuisance odors. Typically, containment and treatment by use of wet scrubbers can keep the problem under control.

Waterborne Wastes

Almost every operation involving slaughtering and processing animals results in wastewater. Certain operations, such as the scalding of hogs as part of the cleaning and hair removal process, produce large volumes directly. Other operations, such as butchering, produce most of the wastewater during clean-up activities.

Components of wastewater are blood, paunch manure, fat solids, meat solids, grease, oil, and hair. In-house laundry operations also contribute to wastes. Each beef stomach contains 55 to 80 pounds of paunch manure. One hundred gallons or more of water are typically required to wash out a single paunch. This quantity can be reduced by using dry removal and handling systems.

Blood, a major contributor to the high strength of wastewater, has more than 150,000 mg/L of BOD₅. Sources of blood within an animal-processing facility begin at the killing and bleeding facility and continue on through the

processing facility. Normally, each successive processing operation at a (complete) packinghouse is a less important source of blood than the one before it; however, it is the usual practice to combine wastewater from all sources at animal-processing facilities before treatment.

Cutting and packaging operations (butchering, or further processing) include additional operations that contribute to wastewater. Intestinal casings require squeezing or pressing to remove the contents. The casing used for production of edible foods such as sausages and hot dogs has to be removed from the outside of the intestine. The intestine itself is sent to the rendering facility. The intestine casing is salted, then drained. This operation, as a whole, results in wastewater that is high in grease as well as sodium chloride.

Scalding is used to process tripe, the muscular part of an animal's stomach. This process results in wastewater containing grease and TSS. Again, all processing stations are washed down each processing day, some several times each day. The washdown water is a major source of wastewater from any animal-processing facility.

In the case of slaughtering and processing hogs, the freshly killed and bled carcasses are scalded by immersion in a tank of near boiling water to wash and prepare them for removal of hair. The scalding tanks overflow at a certain constant rate in order to prevent solids and dissolved materials (pollutants) from building up to an unacceptable level. This overflow constitutes a major source of wastewater from the processing of hogs. It is comparable to the scalding overflow encountered in the processing of chickens, turkeys, and ducks. The BOD₅ of any of these scalding overflow wastewaters is typically in the range of 2,000 to 5,000 mg/L.

Wastes Minimization

Washing the cattle, hogs, or other animals before delivery to the slaughtering facility can best minimize solid wastes produced in holding pens. A second major source of solid materials to be managed is the sludges from wastewater treatment and from air pollution

control; however, if the processes that create these residuals are managed properly, they can be used as raw material to the rendering facility. The result will be twofold: a very large decrease in solid wastes to be disposed of and an increase in the animal feed supplement produced by the rendering facility.

Paunch manure should be handled by dry methods, such as dry conveyors and dry collection systems. In addition, daily (or more often) plant clean-up should begin by thorough sweeping, squeegeeing, air blast, or other feasible dry method. All of the material thus removed from the killing, bleeding, and processing equipment and floors can be processed into animal feed supplement in an on-site or off-site rendering facility.

Regarding airborne wastes, and, more specifically, nuisance odors, the best minimization strategy is to maintain a scrupulously clean facility, in order to minimize putrefaction of organic substances. The products of biodegradation, such as fatty acids, amines, amides, and reduced sulfur compounds such as hydrogen sulfide and mercaptans, are responsible for bad odors from meat-processing facilities.

Treatment and Disposal

Considerable similarity exists between the management of wastes from all types of red meat production and processing facilities. Beef, pork, and most other red meat source animals result in solid, airborne, and waterborne wastes that are appropriately managed in very much the same ways.

Solid Wastes

Most solids from meat-packing facilities are organic. As such, they have a potential use. The excrement, and possibly the paunch manure, has been successfully processed in composting facilities and thus converted to useful material such as fertilizer or soil improvement agent. Another use for paunch manure is as feed to appropriate rendering facilities.

All other solid materials resulting from the slaughtering and processing of animals can be

managed as feed for an appropriate rendering facility.

Airborne Wastes

The treatment of nuisance odors—the only air pollutants of consequence at red meat processing facilities—is done by containment and wet scrubbing. Containment usually means prevention of the release of fugitive emissions. If there is a rendering facility on site, containment definitely includes maintenance of a negative pressure in side buildings (compared to the atmospheric pressure outside the buildings). During windy periods, a greater differential pressure is required. Blowing significant quantities of air from the inside of the buildings to the outside, at a constant rate, creates the negative pressure. Control of nuisance odors is accomplished by exhausting the blowers through wet scrubbers. This technology is discussed more completely in the section titled Rendering of By-Products from the Processing of Meat, Poultry, and Fish.

Waterborne Wastes

Treatment of wastewaters generated at slaughterhouses, processing plants, and/or packinghouses, where red meat is produced and processed, typically consists of biological treatment preceded by screening and primary sedimentation. In some instances, dissolved air flotation (DAF) has either replaced primary sedimentation or has been placed between primary sedimentation and biological treatment. The solids harvested from the DAF process (flot) can be used as raw material for rendering facilities, resulting in production of a valuable animal feed supplement.

Primary Treatment

Screening should be used to the maximum extent feasible because the solids captured by screening are excellent raw material for the rendering process. Many different types of screens have been used successfully, including shaking screens, tangential screens, conveyor screens, rotary screens, and static screens. It

may be necessary to place a grease trap ahead of the screening system to prevent blinding.

Flow equalization has been found to be valuable and even necessary in some cases, to enable screening systems, gravity clarifiers, and DAF systems to operate successfully. Many occurrences during the processing day cause significant change in both rate of wastewater flow and wastewater strength. These occurrences include periodic plant washdown, daily plant washdown, spills, and dumps of unacceptable product or intermediate.

Flow equalization systems must be equipped to cope with floating and settling solids. The variable quantities of fats, oils, and settleable solids can cause debilitating problems if they are not so equipped.

Secondary Treatment

Wastewaters from the processing of red meat are well suited to biological treatment because of their very high organic content. Either anaerobic or aerobic methods can be used; however, the high strength of these wastes, in terms of BOD₅, TSS, and O&G make them particularly well suited to anaerobic treatment. The elevated temperature of these wastewaters is also a factor. Higher temperatures decrease the oxygen transfer efficiency of aeration equipment but tend to increase the rate of anaerobic treatment. These considerations are discussed more fully in Chapter 8.

As discussed in Chapter 8, the more recently developed anaerobic treatment technologies, such as the upflow anaerobic sludge blanket (USAB) and the anaerobic contact process, have had significant success treating wastewaters from the dairy industry. Although there has not been significant success reported for the USAB process, it appears obvious that significant potential exists.

Anaerobic contact systems have been used with success. These systems consist of a conventional anaerobic digester, with mixing equipment and a clarifier portion. With detention times of only 6 to 12 hours, 90% BOD₅ removals have been typical. Using the 6- to 12-hour detention time, solids have been separated

in the clarifier portion and, for the most part, returned to the active digester. It has been necessary to waste only a relatively small fraction of the biological solids. In order to achieve good separation, it is necessary to de-gas the solids as they are transferred from the active digester to the settling component.

Anaerobic lagoons have long been used to treat wastewaters from the processing of cattle and hogs. The most successful of these treatment systems have been designed with low surface-to-volume ratios to conserve heat and to minimize aeration. Depths of 12 to 18 feet have been used. Covers are required for odor control. In some cases, the natural cover formed by floating greases has sufficed, but it has typically been necessary to place covers made of Styrofoam or other floating material. Polyvinyl chloride and nylon-reinforced hypalon have been used with success. These lagoons, of course, must be lined to prevent contamination of the groundwater.

BOD₅ loading rates of 15 to 20 pounds per 1,000 cubic feet have been common. Detention times of 5 to 10 days have resulted in effluent BOD₅ concentrations of 50 to 150 mg/L, amounting to removals of 70% to 85%. Additional treatment, usually by means of an aerobic stabilization pond or another aerobic biological treatment system, is generally required to enable compliance with EPA standards. Ammonia is another issue. Anaerobic lagoons as described here typically discharge effluents having up to 100 mg/L of ammonia.

Placing the inlet to the anaerobic lagoon near the bottom of the lagoon is often helpful. This arrangement allows the incoming wastewater to contact the sludge blanket containing active microorganisms.

Aerobic lagoons have been used for secondary treatment; however, because of the high cost of providing the large quantity of oxygen required by these high-strength wastewaters, they are most often used as a step following another technology, such as an anaerobic lagoon or anaerobic contact system. Aerated lagoons used for treatment following anaerobic systems have operated with detention times of

2 to 10 days. Depths of 8 to 18 feet have been used with mechanical or diffused air systems.

In appropriate climates, oxidation ponds have been used as a final (polishing) treatment step, following either anaerobic or aerobic biological treatment systems. Oxidation ponds having depths of 4 to 8 feet, sized for organic loadings of 20 to 40 pounds of BOD₅ per acre-day, and having detention times of 1 to 6 months have worked with success.

When preceded by effective equalization, the activated sludge process has successfully treated wastewaters from red meat processing facilities. Various modifications have been used, including tapered aeration, step aeration, extended aeration, and contact stabilization. Extended aeration appears to have had the most success.

Trickling filters have been used as roughing filters and as components of nitrogen management systems. As roughing filters, the trickling filters receive a relatively heavy load of BOD₅ for a relatively short period. In this mode, trickling filters are capable of removing 25% to 40% of the BOD₅, at relatively low cost per unit of BOD₅ removed. As components of nitrogen management systems, trickling filters are appropriate media for the nitrification step, preceding denitrification.

Rendering of By-Products from the Processing of Meat, Poultry, and Fish

Rendering is a process for separating fat from animal tissue. Heat is very often used, and sometimes one or more of chemicals, pressure, and vacuum are used as well. Rendering serves the invaluable function of converting what would otherwise be waste materials into useful products, including animal, poultry, or fish feed supplements and oils for industrial and household use such as soaps and rust-proofing paints. A material made from rendering feathers obtained from the processing of poultry has long been used to manufacture a foam product used in firefighting. Edible rendering produces edible lard, chicken fat, or specialty fats or oils.

The rendering process itself results in considerable, sometimes difficult, wastes to manage. In total, however, wastes resulting from rendering are a small fraction of the wastes it makes use of. A huge number of rendering plants operate in the U.S. and around the world. Virtually all facilities that manufacture foods derived from animal, poultry, or fish produce by-products that can be used as raw materials at a rendering plant.

The Rendering Process

The rendering process is customized, depending on the products and the raw materials; however, the following discussion is applicable to the rendering process in general. The wastes that result from most rendering operations are remarkably similar. Figure 4-19 presents a generalized schematic of a "typical" rendering plant. There are both "wet" and "dry" rendering processes. In the wet rendering process, live steam is injected into the rendering tank, along with the material being rendered. In dry rendering, steam is confined in a jacket that surrounds the tank containing the material being rendered.

As illustrated in Figure 4-19, rendering plants have facilities for receiving and storing the raw material. The materials are taken from storage and are usually ground and blended. The ground and blended material is then pumped, conveyed, or placed by use of a bucket loader into a tank in which the rendering process takes place (the rendering system). Live steam at 40 to 60 psig is introduced, and the rendering process, not to be confused with cooking, takes place. In some cases, pH is adjusted. Sometimes, other chemicals are introduced. As the rendering process proceeds, fats and oils are drawn off the top of the tank. The remaining liquid, called "stick water," contains the protein material. The stick water is typically evaporated and added to animal feed.

Dry rendering typically involves placing the materials to be rendered in a steam-jacketed rendering system that is placed under vacuum. Screening and centrifugation are used to separate the fats and oils from the solids, which contain the protein matter.




Figure 4-19 Schematic of a "typical" rendering plant.

A large rendering plant in the Northeast rendered a variety of materials, including by-products (the mostly inedible substances remaining after slaughtering and processing) from beef, poultry, and fish packing operations. Table 4-25 presents a list of materials rendered by this facility. Fat and bone, poultry by-products (heads, feet, entrails, blood, and carcasses of rejected birds), fish, and fish by-products were converted to high-protein meal by use of a continuous dry rendering process. In this system, diagramed in Figure 4-20(a), a slurry of recycled fat (from restaurants, butcher shops, and from beef-packing plants) and ground up bones, meat, and other substances was dehydrated in a multiple-effect evaporator. Vapors were vented to a barometric condenser. Expellers (centrifuges) were used to separate the hot fat product from the protein meal. The process is often referred to as “cooking;” however, temperatures were maintained at 140°F or lower.

Feathers from chicken processing plants were handled in a separate system. A schematic diagram of the feather processing system is shown in Figure 4-20(b). The feathers were hydrolyzed using high-temperature and pressure and then dried in a steam tube rotary dryer.

A variation of the rendering process is low-temperature rendering, in which the raw materials are heated to just above the melting point

of the fat. Centrifugation is used to separate the fats and oils from the protein matter.

Wastes Generation

Solid, airborne, and waterborne wastes are generated at rendering plants in considerable quantities. Some of these wastes are relatively difficult to manage, largely because of their nuisance odor-causing potential.

Solid Wastes

Solid wastes are generated at the receiving and storing area in the form of containers that are no longer usable and broken pallets. Also, construction debris from plant maintenance, modifications, expansions, and periodic facility upgrade projects contributes to the solid wastes that must be managed.

Airborne Wastes

Airborne wastes are an ever-present potential at typical rendering plants. All objects with which the raw material for the rendering plant comes in contact are subject to becoming the source of a nuisance odor problem. The process of anaerobic biodegradation of the easily degraded animal flesh proteins causes the odors. This process is referred to as “putrefaction,” and it produces foul-smelling amines, amides, indole,

Table 4-25 Material Received and Produced by Rendering Facility

<i>Raw Material</i>	<i>Mode of Delivery</i>	<i>Processing Steps</i>	<i>Final Product</i>
Fat, bone viscera	Drum and truckload	Carver-Greenfield	Beef meal*
Poultry by-product	Trailer truck	Carver-Greenfield	Poultry meal*
Sludge from treatment plant (poultry processing)	Trailer truck	Carver-Greenfield	Poultry meal*
Fish by-products (gurry)	Trailer truck	Carver-Greenfield	Poultry meal*
Whole fish	Trailer truck and boat	Carver-Greenfield	Fish meal*
Menhaden	Trailer truck and boat	Carver-Greenfield	Fish meal*
Feathers extinguisher foam	Trailer truck	Feather cooker and dryer	Feather meal* for fire
Restaurant grease	Drum	Steam table and filtration	Poultry feed supplement

* Poultry feed supplement




Figure 4-20 Schematic of rendering systems.

skatole, various volatile acids, and reduced sulfur compounds such as hydrogen sulfide and methyl as well as ethyl mercaptans.

Waterborne Wastes

Primary sources of wastewaters from rendering plants are as follows:

- Blood and other “juices” that drain from the animal, poultry, and fish by-products that are the raw material for the rendering facility
- Plant washdown water that is constantly in use to control air pollution by foul odors
- Blow-down from wet scrubbers used for air pollution control

Plant washdown, as part of housekeeping practices implemented to control nuisance odors, is the major source of wastewater in terms of volume. Constant washdown of the plant equipment and floors is necessitated by the nature of the equipment and the material handled. Most rendering plants produce nothing for human consumption. For this reason, the equipment is not the easily cleaned, relatively expensive type used in edible food-processing plants. The material handling equipment typically consists of screw conveyors and open impeller pumps. This equipment handles poultry and animal entrails, fish and fish parts, and sludge from wastewater treatment plants (both on-site treatment plants and treatment plants located at off-site meat, poultry, and fish processing plants). This combination of sloppy material along with the types of handling equipment leads to almost continuous dripping and spilling.

In addition, oil vapors within the processing areas continually condense on surfaces, resulting in a biodegradable film that gets thicker as time goes on if it is not regularly washed off. The consequence is that plant washdown must continue in a never-ending fashion. As soon as an area is cleaned, it begins to downgrade. Wet scrubbers must also be constantly in operation to control odors.

Wastes Minimization

Notwithstanding the fact that plant washdown water creates most of the wastewater that requires treatment, good housekeeping practices are still the most important wastes minimization technique for rendering facilities. The key is to make use of drip pans and other containment devices to decrease as much as possible the quantity of material that is required to be cleaned from unconfined areas such as floors, walls, and surfaces of the machinery.

Dry methods of cleaning must always be used to the maximum extent feasible. Dry methods of cleaning, using brooms, shovels, vacuum cleaners, and air blowers, is an important wastes minimization technique in any industrial setting. It is especially important in the setting of a meat, poultry, or fish by-product rendering facility because of the ever-present “juices” of very high organic content.

Whenever possible, liquid drainings and juices should be disposed of before they get to the rendering facility. This, of course, involves a tradeoff because these liquids must be managed somewhere. From the point of view of the rendering facility, the less of this material the better.

One example of this type of wastes minimization occurred at a trash fish (“inedible” fish, such as Menhaden) rendering facility on the east coast of the U.S. Before the wastes minimization measure was instituted, fishing boats would catch fish by use of the “purse-seine method” and load them aboard boats. The boats would transport them to shore, where they were transferred to trucks by use of a vacuum pump. During the earlier days of this industry, the vacuum pump routinely pumped the fish, as well as the “fish juice,” out of the boat. Because of the high water content of the fish juice, it was sent overboard into the harbor, rather than put into the trucks and carried to the rendering facility. Evaporation of this water was too costly.

Eventually, however, it became illegal to dump this fish juice in the harbor. At this point, the juice was pumped into the trucks, then

dumped on the receiving room floor at the rendering facility. This caused a massive wastewater problem at the rendering facility. The solution that was eventually worked out was to handle and dispose of this fish juice at dock-side, in a nonpolluting manner.

In the case of wet rendering, there may be excess tank water at the end of the rendering process. This water, which typically has a BOD₅ in the range of 50,000 mg/L and a TSS value in the range of 2% should be evaporated and blended into animal feed supplement.

Treatment and Disposal

Treatment and disposal of wastes from meat, poultry, and fish by-product rendering facilities is a matter of minimizing contact between organic material and the solid wastes, in order to control odors from the solid wastes, and handling and disposal of the solid wastes as ordinary (nonhazardous) waste. Regarding air pollutants, the key is containment and treatment by means of wet scrubbers. Wastewaters are entirely organic, with the possible exception of wet scrubber blow-down and chemicals used for pH adjustment and for cleaning the plant. Biological treatment should, therefore, be appropriate.

Solid Wastes

The principle solid wastes from meat, poultry, and/or fish by-products consist of packaging and transport materials such as 55-gallon drums, broken pallets, steel strapping, and nonrecyclable containers previously used for chemicals, detergents, lubricants, and laboratory supplies. After aggressive wastes minimization and recycling, these materials can be disposed of as ordinary solid wastes. There should be no organic materials in the solid waste stream because any such wastes should simply have been added to the feed to the rendering system.

Airborne Wastes

For many rendering facilities, the most troublesome problem is nuisance odors from the

anaerobic biodegradation of protein matter. The solution is to rigorously contain any odors so generated, and to treat them by the oxidative action of the chemical solutions in wet scrubbers.

The foul odors that require containment, collection, and treatment emanate from handling and storage of the raw material, as well as from the handling and processing equipment on the processing floor. The rendering process itself, as well as subsequent processes such as pressing and drying, is generally agreed to be the source of strongest odors. These “high-intensity” sources emit varying concentrations of odors, depending on the type and age of the raw material, and the temperature of the raw material during the hours or days before its placement in the rendering system. In general, the older the raw material, and the higher its temperature, the more concentrated or “stronger” the bad odors.

Odors from rendering operations have been generally described as those of ammonia, ethylamines, and hydrogen sulfide. Skatole, other amines, sulfides, and mercaptans also contribute to the blend of “rendering plant odors.”

The types of equipment normally used for controlling odors in the rendering industry are afterburners, condensers, adsorbers, and wet scrubbers. Gases from wet rendering processes are almost always condensed. Removing condensable odors results in as much as a 10-fold volume reduction. The condensed gases can then be directed to additional treatment.

Flame incineration (after burning) offers a positive method of odor control; however, the cost of fuel makes afterburner operation expensive. Scrubbing with chemical solutions is the primary method for controlling odors. Activated carbon has also been used to remove odors by the mechanism of adsorption; however, its application is limited to treatment of relatively cool and dry gases.

The typical situation at large rendering plants is to have from two to four wet scrubbers. Air from any location within the plant must go through one of these scrubbers before reaching the outside. Figure 4-21 is an illustrative diagram of a typical scrubbing system used




Figure 4-21 Schematic diagram of wet-scrubber system.

for this purpose. The system shown in Figure 4-21 consists of a venturi (fixed throat opening) section followed by a packed tower. A large induced-draft fan pulls air from within the building that houses the rendering system and forces it through the venturi-scrubber system shown in Figure 4-21. Process gases are also forced to pass through a venturi-scrubber system, similar to the system shown in Figure 4-21.

The wet scrubber portion of the venturi-scrubber system is typically a tower packed with plastic tellerettes, which provide a very large surface area. A solution of hypochlorite, with the pH adjusted for maximum effectiveness, is sprayed onto the top of the tellerettes. This solution flows down over the (very large) surface area of the packing. At the same time, gases are forced up through the packing by the action of the fan. As the gases contact the scrubbing solution, the oxidizing action of the hypochlorite changes the chemical nature of the odor-causing substances. Also, many of these substances become dissolved in the scrubbing solution.

One of the most important objectives of the odor control system described previously is maintaining a "negative pressure" within the rendering plant building. If the barometric pressure inside the building is less than the barometric pressure outside the building, it is more difficult for fugitive emissions to pass from inside to outside. This negative pressure (negative inside relative to outside) is maintained simply by keeping all the doors and windows closed while operating the wet scrubber systems. It is necessary for the buildings to have good structural integrity; that is, to be free of leaks in the walls and to have good, reasonably tight fits regarding doors and windows. If the building is relatively sound, it is a simple matter to maintain a negative pressure and to maintain effective control over fugitive emissions. Occasional opening and closing of doors for human and truck traffic can be tolerated.

Waterborne Wastes

Wastewaters from rendering plants using red meat, poultry, and/or fish by-products as raw

material are amenable to biological treatment because these wastewaters are almost entirely organic. The only sources of inorganic chemicals are the blow-down wastes from the air pollution control systems and possibly inorganic agents used for cleaning.

Anaerobic as well as aerobic technologies are valid potential treatment technologies. The normally very high-strength character of these wastewaters, as well as elevated temperatures, makes them particularly well suited to anaerobic treatment technologies; however, aerobic treatment has been used with success as well. A large rendering facility in New England successfully treated wastewaters by making use of chemical coagulation and dissolved air flotation (DAF) to remove most of the protein, fats, and oils (which accounted for about 80% of the BOD₅), followed by activated sludge for removal of the dissolved fraction of waterborne pollutants.

This rendering facility used by-products from red meat processing, poultry processing, fish processing, and sludge from wastewater treatment as raw material. Two rendering systems were used. One was a continuous flow dry rendering system that operated at about 140°F and under a vacuum. The second was a batch-type dry rendering system. On a typical day, the continuous flow system was started up on poultry (offal, heads, feet, and blood) and operated at the rate of 30,000 lb/hr for 7 hours. It would be switched to fat and bone and run at the rate of 23,000 lb/hr for 2.5 hours. It would then be switched to fat, bone, and meat scraps from red meat processing and butcher shops, as well as grease from restaurants in the area. It would then be switched to by-products from fish processing plants and operated at 50,000 lb/hr for 3 hours or so. Finally, it would be switched to menhaden, a particularly oily fish, for 4 to 10 hours, depending on supply.

The batch rendering system would be started up on feathers from poultry processing plants on Monday afternoons and run at a rate of about 3,000 pounds per hour until the supply of feathers was exhausted on Saturday.

The characteristics of the combined wastewaters from this plant, including plant wash-down water were as follows:

- Flow 96,000 gpd
- BOD₅ 85,000 mg/L
 68,000 lb/day
- TSS 6,000 mg/L
 4,800 gpd

Chemical coagulation in combination with DAF removed about 80% of the BOD₅ and about 90% of the TSS. About 95% of the oil and grease was also removed by DAF. All of the sludge (flot) from this system was used as raw material in the continuous feed dry rendering system.

The aerobic, activated sludge system that followed the DAF system was operated by use of mixed liquor volatile suspended solids (MLVSS) concentrations between 9,000 and 11,000 mg/L, and a hydraulic retention time of about 3 days. An integral clarifier was attached directly to the aeration tank, and sludge was wasted from the aeration tank. Sludge age was maintained at 10 days. All of the waste sludge was used as raw material in the continuous flow dry rendering system.

Overall, BOD₅ removal for the combined DAF-complete-mix activated sludge system consistently exceeded 99%. TSS and oil and grease removals exceeded 95%.

The Manufacture of Lead Acid Batteries

A battery, as the name is used in this section, is a modular source of electric power in which all or part of the fuel is contained within the unit and the electrical power is generated by a chemical reaction within the unit. The primary components are the anode, the cathode, and the electrolyte. The function of the anode and cathode, called the electrodes, is to convert chemical energy into electrical energy. If an electrical circuit outside the unit is connected between the anode and the cathode, electric current is caused to flow through the circuit.

The EPA has divided the manufacturing of batteries into eight categories: cadmium, calcium, lead, leclanche, lithium, magnesium, nuclear, and zinc. The lead subcategory is the largest in terms of number of manufacturing plants and volume of batteries produced. Products that utilize batteries included in the lead subcategory include automobiles, portable hand tools, lanterns, and various implements used in industry and the military.

There are four common types of lead acid batteries: wet-charged, dry-charged, damp, and dehydrated. Wet-charged batteries are shipped after manufacture with electrolyte. All others are shipped without electrolyte.

Lead Battery Manufacture

Only production of the anode, the cathode, and ancillary devices are considered part of battery manufacture. Production of the structural components such as the cases, terminal fittings, electrode support grids, seals, separators, and covers are all included in other manufacturing categories; however, any or all of them may be manufactured at the same plant that manufactures the electrodes.

Anodes are metals when in their fully charged state in a battery. In the case of most lead acid batteries, anodes are manufactured by applying a paste of lead oxide to a support. The paste-support structure is allowed to dry. Cathode active materials are typically metal oxides. The lead oxide substance used to make cathodes for lead acid batteries is called leady oxide within the battery manufacturing industry. This substance is a specific oxidation state of lead oxide that is 24% to 30% lead free. It is used for the manufacture of both the anodes and cathodes in lead acid batteries and is manufactured by the so-called Barton process or by a ball mill process.

Cathodes for use in lead acid batteries are manufactured by applying a paste of the leady oxide to a structural grid. The grid must be able to carry the desired electrical current and support the leady oxide. Thus, the fabrication of anodes and cathodes for use in lead acid batteries is very similar. There is a difference,

however, in that cathodes remain in the lead peroxide state.

Ancillary operations are those operations of the battery manufacturing process other than fabrication of the anodes and cathodes. Included are battery assembly, production of leady oxide, battery washing, and washing of floors, manufacturing equipment, and personnel.

Figure 4-22 presents a flow diagram for the process of manufacturing wet-charged lead acid batteries using a closed formation process. It is more or less typical of all lead acid battery manufacturing processes as far as wastes generation is concerned. As illustrated in Figure 4-22, there are two initial processes. One is the production of leady oxide to be used in fabricating anodes and cathodes. The other is casting of the grids to be used for this same purpose.

Leady Oxide Production

Finely divided metallic lead is mixed with lead oxides to produce the active materials used for manufacturing the battery electrodes or plates. So-called leady oxide is produced by placing high-purity lead particles in a ball mill. The friction within the ball mill generates heat, and a forced flow of air provides oxygen. The result is particles of red lead letharge and a certain percentage of unoxidized metallic lead. Non-contact cooling, along with regulation of the air flow, governs the speed of oxidation of the lead.

An alternative process, the Barton process, produces leady oxide by feeding molten lead into a pot and vigorously agitating it to break the lead into small droplets. Oxygen from a stream of air oxidizes a certain percentage of the lead into a mixture of yellow lead, red letharge, and metallic lead.

Grid Manufacturing

Grids are fabricated by casting lead alloys such as lead-antimony and lead-calcium. Trace amounts of arsenic, cadmium, selenium, silver, and tellurium are also added.

Paste Preparation and Pasting

The anodes are fabricated by applying a paste of lead oxides mixed with binders and other substances to the grids. The paste is prepared by mixing leady oxide and granular lead, or red lead. The cathodes are prepared in the same manner, except that the paste is prepared by mixing leady oxide, lead, sulfuric acid, water, and expanders such as lampblack, barium sulfate, and various organic materials. One of the principle objects in fabricating the electrodes is to create a very large surface area by preparing the paste to have a porous, very rough texture. The paste is often applied by hand. Some facilities use mechanized equipment.

Curing

A principle objective of the curing process is to induce the electrodes to obtain proper porosity and strength. To this end, the curing process is strictly controlled. The plates are flash dried, stacked, and covered or placed in a humidity-controlled room for several days. Small crystals of tribasic lead convert to lead peroxide. One technique is to soak the plates in sulfuric acid to enhance sulfation and improve mechanical properties. This soaking is done in the battery case or in a separate tank.

Stacking and Welding

The cured plates are stacked for convenient access at the assembly line. Separators are placed to prevent short-circuiting. Separators are made from plastic, rubber, fiberglass, or paper.

Assembly

The assembly process involves placing the stacked, alternating anode-cathode plates within the battery case, welding the connecting straps, and installing the covers and vents. Also, the connections are made to the battery posts.




Figure 4-22 Production of wet-charged lead acid batteries using the closed formation process.

* Not considered in battery manufacturer category.

There are two types of assembly: open formation and closed formation (formation refers to charging the battery as a result of acid reacting with substances on the electrodes). Figure 4-22 is appropriate to the closed-formation process. In the closed-formation process, the top and vents of the battery are installed before the acid (electrolyte) is added. The opposite is true for the open-formation process, which allows visual inspection of the plates, separators, strap welds, and posts after the electrolyte has been added.

Electrolyte Preparation and Addition (Acid Fill)

The electrolyte solution for the battery is prepared by diluting concentrated sulfuric acid with water. This acid-cutting process is typically performed in two steps: The first is dilution to 45% acid, by weight. This acid solution is used for preparation of the paste, as described earlier. The second acid cut is dilution to 25% to 30%. This acid solution is used for battery formation and filling.

With respect to the quantity of wastewater generated, there are several different methods used for filling lead acid batteries. One is to fill each battery to overflowing, to ensure that filling is complete. Another is to immerse the batteries in a tank of the electrolyte, after which the batteries are rinsed. A third is to make use of sensing and relay equipment to automatically stop the filling process at the proper time.

Formation

The active substance for the cathode is lead peroxide, although it is not a component of the paste that is applied to the cathode grids during fabrication of the cathodes. The formation of lead peroxide takes place after the newly fabricated cathodes are immersed in the electrolyte and an electric current is applied. In the case of the closed-formation battery manufacturing process, this process takes place just after the acid fill step.

The forming process consists of applying an electric current between the anodes within a

newly filled battery and the cathodes. When this is done, lead oxide and sulfate are converted to lead peroxide on the cathode, and lead oxide is converted to lead on the anode. The final composition on the cathode is 85% to 95% lead peroxide, and the composition on the anode is greater than 90% lead.

The formation process takes time. Several methods are used to ensure proper formation. Two of them are as follows: In one method, each battery is filled with full-strength electrolyte, and the battery is ready for shipment after 1 to 7 days, depending on the type of battery and the characteristics desired. The second method involves filling each battery with a more dilute electrolyte, then emptying and refilling with full-strength electrolyte before shipment. A boost charge is applied before shipment. The entire process takes place in one day or less.

Battery Washdown

Typically, batteries are washed before shipment. This washdown removes electrolyte and other materials from the outside surfaces of the batteries resulting from filling and forming. Detergents are usually used to remove oils and dirt.

Battery Testing and Repair

Testing batteries seldom generates wastes; however, when testing determines that a battery is faulty, it is taken apart for repair. When this is done, faulty parts are replaced, and the faulty parts become solid waste. Electrolyte drained from the battery becomes waterborne waste.

Wastes Generation

Lead acid battery manufacturing plants are highly variable in terms of wastes generated. For instance, work done in preparation of producing the EPA's Development Document for the battery manufacturing point source category determined that total plant discharges of wastewater ranged from 0 to 390,000 gpd, with a median of 22,000 gpd.

Solid Wastes

Solid wastes are generated from packaging and shipping wastes, construction debris from plant maintenance, modifications, expansions, and periodic facility upgrade projects. In addition, sludges from wastewater treatment and waste resins from process water deionization require management. Lead acid battery manufacturing plants also generate solid wastes as a result of reject batteries and faulty battery parts, including cases, tops, posts, electrode grids, straps, and separators.

Airborne Wastes

The major source of air pollutants from lead acid battery manufacturing plants is acid fumes. Typically, these substances are controlled by the use of scrubbers. There is always a discharge because of the less than 100% efficiency of the scrubbers; therefore, an aggressive operation and maintenance program, including aggressive preventive maintenance, is necessary.

Scrubbers are located throughout the processing plant, including those processes carrying out the following production steps: leady oxide production, grid manufacturing, electrolyte preparation and addition, formation, battery washdown, battery testing and repair, and any acid storage and dispensing facilities.

Waterborne Wastes

Wastewater generated from the production of lead acid batteries has three primary sources: the paste preparation and pasting operations, the electrode-forming operations, and the washing of finished batteries; however, there are wastewaters generated from each of the manufacturing steps, as illustrated in Figure 4-22, in the production of lead acid batteries.

Leady Oxide Production

Leady oxide production results in wastewaters from cooling and leakage from ball mills, contact cooling during grinding of oxides, and wet scrubbers used for air pollution control.

Paste Preparation and Pasting

Paste preparation and pasting results in wastewaters from washdown of the equipment as well as the production area. These washdown wastewaters typically contain high concentrations of suspended solids and lead, as well as additives used in making the paste.

Electrolyte Preparation and Addition (Acid Fill)

There is almost always dripping, spilling, and overflowing of acid in the electrolyte preparation and addition (acid fill) area. Therefore, washdown and rinsewaters are typically highly acidic. Also, wet scrubbers are normally used in this area because of the fumes from the dripped, leaked, spilled, or overflowed acid.

Formation

The formation production area is subject to acid spills, similar to the fill area. The wastewaters generally contain significant concentrations of various metals. Copper and iron in the wastewater result from corrosion, caused by the acid of process equipment and charging racks. Oil and grease also result from equipment washdown. Wet scrubbers in this area generate significant wastewater.

Battery Washdown

The battery washdown process is the site of considerable wastewater generation. Wet scrubbers are used in this area as well.

Battery Testing and Repair

When faulty batteries are detected, they are often drained. The drained electrolyte can be a major source of wastewater. Wet scrubbers are often used in this area.

Wastes Minimization

There are many opportunities for wastes minimization at lead acid battery manufacturing facilities. Most fall within the category of good plant housekeeping. Similar to many other industries, the key to minimizing the cost for eventual waste treatment and disposal is to aggressively implement the following:

- Whenever possible, nontoxic substances should be used for degreasing and cleaning.
- If toxic substances, for instance, chlorinated volatile organics, must be used for degreasing or other cleaning processes, containment, recycle, and reuse must be practiced to the maximum extent possible.
- Biodegradable detergents should be used.
- Drips must be contained and returned to the source.
- Aggressive maintenance must be practiced to eliminate leaks and accidents that could lead to noncontainment of chemicals and other substances.
- Reconstitution of cleaning baths, acid baths, alkali baths, and plating baths should be done on an as-needed basis according to the work performed, rather than on a regular timing or other schedule.
- Water used for the first stages of battery washdown should be recycled water from other processes.
- Dry methods of clean-up, including brooms, shovels, and dry vacuuming, should be used to the maximum extent possible.
- Techniques such as treating wastewater from washdown of the pasting area should be treated in multistage clarifiers. At some plants, this technique has enabled total reuse of the water. The clarified water has been used for washdown, and the solids have been reused in new batches of paste.
- Rinsing should be counter-current, with respect to freshwater makeup and spent rinse-water overflow.
- Purchasing should be guided by aggressive selection of raw materials in order to obtain the cleanest possible materials.
- There should be a constant and consistent program to substitute less-polluting and nonpolluting substances for those that require expensive treatment and expensive disposal.
- In concert with the above, there should be a constant and consistent program for replacing process controls, including

sensors, microprocessors, and hardware, with the objective of decreasing waste and maximizing retention, containment, recycle, and reuse of all substances. For instance, the battery-filling system must be constantly maintained and upgraded to keep overflowing to a minimum.

- Technologies for recovering and regenerating acids, lead, and other chemicals as well as for separating and removing contaminants should be aggressively employed. Ultrafiltration to effect removal of oils from alkaline cleaning solutions is an example. Centrifugation has also been used for this purpose. Activated carbon can be used to remove organic impurities.

Both filtration and centrifugation produce concentrated impurities that offer the possibility of recovery. If recovery of substances is not feasible, the concentrated impurities are in a form that is more easily disposed of.

Wastewater Treatment

Wastewaters from the manufacture of lead acid batteries are typically acidic, as the result of contamination by sulfuric acid, which is used as the electrolyte. In addition, dissolved lead and suspended solids containing lead are major components. Differences from one plant to another regarding the presence of pollutants other than acid and lead depend on whether or not lead oxide is produced at the plant, whether or not the electrode grids are produced at the plant, and the type of grids fabricated; i.e., antimony alloy, pure lead, or calcium alloy. Other factors include differences in the method of plate curing, forming, and assembly. Parameters that are regulated and, therefore, have been found in wastewaters from plants manufacturing lead acid batteries include antimony, cadmium, chromium, copper, lead, mercury, nickel, silver, zinc, iron, oil and grease, and TSS. pH value is also regulated. Some plants pretreat and discharge to a POTW. Others treat and discharge on site. Either way, the wastewater treatment system must be capable of pH control and removal of multiple metals.

In general:

- Wastewaters containing significant quantities of oil and grease should be isolated, treated for removal of oil and grease—for instance, by reverse osmosis—then combined with other wastes for removal of metals.
- Wastewater, including equipment wash-down water from the paste makeup and pasting areas should be isolated, treated on-site by multiple clarifiers, and both the clarified water and the solids reused. The water should be used for paste makeup and for acid dilution in the electrolyte makeup area. The solids should be returned to paste makeup. As usual, a certain amount of blow-down will probably be required.
- The final wastewater stream from a typical lead acid battery manufacturing facility, after wastes minimization, wastes segregation and pretreatment, and combining of the pretreated flows, can best be treated by use of precipitation for removal of metals, sedimentation for removal of precipitated metals and other suspended solids, and chemical coagulation, sedimentation, sand or mixed media filtration, final pH adjustment, and ion exchange as necessary to achieve required levels of metals, TSS, pH, and oil and grease. It may be necessary to perform the metals removal operations in two or more stages, in series, using different values of pH for each stage, to remove all the metals (some of which have different values of pH for lowest solubility). These wastewater treatment techniques are discussed in detail in Chapter 8.

Bibliography

- ABMS Non-Ferrous Metal Data, 1988.
- Amerine, M.A., H.W. Berg, R.E. Kunkee, C.S. Ough, V.L. Singleton, and A.D. Webb, *The Technology of Wine Making*, 4th ed. AVI Publishing, Westport, Connecticut, 1980.
- Anonymous, "California Wine: On the Grapevine," *Economist*, Vol. 307, No. 7547, April 23, 1988.
- Apotheker, S. "Plumbing Lead from the Waste Stream," *Resource Recycling*, April 1992, pp. 34.
- Azad, H.S., *Industrial Waste Management Handbook*, McGraw-Hill, New York, 1976.
- Bagot, B. "Brand Report No. 161-Domestic Wine: Wine Tastings," *Marketing & Media Decisions*, Vol. 24, No. 5, May 1989.
- Baker, D.A. and J.E. White, "Treatment of Meat Packing Waste Using PVC Trickling Filters," Proceedings of the 2nd National Symposium on Food Processing Wastes, U.S. Environmental Protection Agency, Denver, Colorado, 1971.
- Bethea, R.M., B.N. Murthy and D.F. Carey, "Odor Control for Rendering Plants," *Environmental Science and Technology*, Vol. 7, June 1973.
- Bishop, P.I., *Pollution Prevention: Fundamentals and Practice*, New York, 2000, p. 426.
- Blanc, F.C. and S.H. Corr, "Treatment of Beef Slaughtering and Processing Waste Waters Using Rotating Biological Contactors," Proceedings of the 38th Industrial Waste Conference, Purdue University, 1983, pp. 133-140.
- "Bottling Breakthrough at 1000 to 2000 BPM," *Food Engineering*, March 1969.
- Bramer, H.C., *Industrial Wastewater Management Handbook*, New York, McGraw-Hill, 1975.
- Brooks, C.S., "Metal Recovery from Waste Sludges," Proceedings of the 39th Purdue Industrial Waste Conference, Purdue University, 1985, pp. 545-553.
- Carron, H., *Modern Synthetic Rubbers*, Van Nostrand Reinhold, New York, 1937.
- Chadwick, T.H. and E.D. Schroeder, "Characterization and Treatability of Pomace Stillage," *Journal of the Water Pollution Control Federation*, Vol. 45, 1978.
- Considine, D.M., *Chemical and Process Technology Encyclopedia*, McGraw-Hill, New York, 1974.
- Considine, D.M. and G.D. Considine, *Foods and Foods Production Encyclopedia*. Van Nostrand Reinhold, New York, 1982.
- Crandall, C.J. and J.R. Rodenberg, "Waste Lead Oxide Treatment of Lead Acid Battery Manufacturing Wastewater," Proceedings of the 29th Purdue Industrial Waste Conference, Purdue University, 1974, pp. 194-206.

- Crow, D.R. and R.F. Secor, The Ten Steps of Deinking, *TAPPI Journal*, 70, 7 (July 1987).
- Current Industrial Reports*, U.S. DOC, Bureau of the Census, 1986, 1989.
- Cushnie, G.C. Jr., *Removal of Metals from Wastewater Neutralization and Precipitation*, Noyes Publications, Park Ridge, New Jersey, 1984.
- Eldridge, E.F. "Michigan Engineering Experiment Station Bulletin #60," 1934.
- Ellis, J. and R.W. Whitton, "Recovery of Tin from Electroplating Solutions and Rinsewaters," *Effluent and Water Treatment Journal*, Vol. 18, N8, 1978, p. 389.
- Etzel, J.E., Private Conversation, March 1989.
- Farmer, J.K., A.A. Friedman, and W.C. Hagen, "Anaerobic Treatment of Winery Wastewaters," Proceedings of the 43rd Industrial Waste Conference, Purdue University, May 1988.
- Food Science*, 3rd Edition, Potter, N.N., AVI Publishing, 1978.
- "Frozen Foods," *Supermarket Business*, 44, 9, 175, September 1989.
- Fukuyama, Yoji, Y. Misaka, and K. Kato, "Recovery of Aluminum Hydroxide from Fabricating Plant of Aluminum Products," Proceedings of the 29th Industrial Waste Conference, Purdue University, May 1974.
- Gillies, M.T., "Soft Drink Manufacture," *Food Technology Review*, (8), 1973.
- Graham, A.K., *Electroplating Engineering Handbook*, Van Nostrand Reinhold Company, New York, 1971.
- Gudger, C.M., and J.C. Bailes, "The Economic Impact of Oregon's Bottle Bill," Oregon State University, Corvallis, Oregon, March 1974.
- Hamilton, J.O.C., Abstract No. 88-17491, "What Slump? It's a Vintage Year for Premium California Wines," *Business Week* (Industrial Technology Edition), Issue 2947, May 1986.
- Hunt, G.E., et al. "Cost-Effective Waste Management for Metal Finishing Facilities," Proceedings of the 39th Industrial Waste Conference, Purdue University, 1985, pp. 545-553.
- "Increasing Wastewater Treatment," *Food Engineering*, 59, 8, 97, August 1987.
- Jones, D.D., "Biological Treatment of High-Strength Coke-Plant Wastewater", Proceedings of the 38th Industrial Waste Conference, Purdue University, 561, 1983.
- Kanicki, D.P., "Casting, Advantages, Applications and Market Size," *45M Handbook V. 15: Castings*, ASM International 1988.
- Krofta, M., and L.K. Wang, Total Closing of Paper Mills with Reclamation and Deinking Installations, 43rd Purdue Industrial Waste Conference Proceedings, Lewis Publishers Inc., Chelsea, Michigan, May 1988.
- Labella, S.A., I.H. Thaker, and J.E. Tehan, "Treatment of Winery Waste by Aerated Lagoon, Activated Sludge and Rotating Biological Contactor," Proceedings of the 27th Industrial Waste Conference, Purdue University, May 1972.
- Loehr, Raymond C., *Pollution Control For Agriculture*, 2nd ed., Orlando, Florida, Academic Press, 1984.
- "The Looming Battle for Center of the Plate," *Advertising Age*, 60, 49, S10, November 13, 1989.
- Lowenheim, F.A., *Electroplating*, Sponsored by the American Electroplaters' Society, McGraw-Hill, New York, 1978.
- Macauley, M.N., W.T. Stebor, and C.L. Berndt, "Anaerobic Contact Pretreatment of Slaughterhouse Waste," Proceedings of the 42nd Industrial Waste Conference. Purdue University, 1987, pp. 647-655.
- Manzione, M.A., D.T. Merrill, M. McLearn, and W. Chow, "Meeting Stringent Metals Removal Requirements with Iron Adsorption/Coprecipitation," Proceedings of the 44th Purdue University Industrial Waste Conference, Purdue University, 1989.
- Maxwell, J.C., Jr., "Coolers Have Chilling Effect on Wine Sales," *Advertising Age*, Vol. 59, No. 27, June 27, 1988.
- Medbury, H. (ed.), *The Manufacture of Bottled Carbonated Beverages*, American Bottlers of Carbonated Beverages, Washington, D.C., 1945.

- Mermelstein, N.H., "Water Purification for Beverage Processing," *Food Technology*, February 1972.
- Metal Finishing 55th Guidebook Directory*, Issue 1987, Vol. 85 No. 1A, Mid-January 1987.
- Metals Handbook*, 9th ed., ASM International, 1988.
- MHR-VIANDES, *World Beef and Veal Production in 1996: Meat Industry Statistics*, Rond Point de l'Europe, France, 1998.
- Modern Pollution Control Technology, Vol. 1, Air Pollution Control*, Research and Education Association, New York, 1978.
- Morton, M., *Rubber Technology*, American Chemical Society, Van Nostrand Reinhold, New York, 1973.
- Nemerow, N.L., *Liquid Waste of Industry*, Addison-Wesley, Reading, Massachusetts, 1971.
- Neveril, R.B., J.U. Price, and K.L. Engdahl, "Capital and Operating Costs of Selected Air Pollution Control Systems IV," *Control Technology News*, Vol. 28, November 1978.
- Niles, C.F., and H. Gordon, "Operation of an Anaerobic Pond on Hog Abattoir Wastewater," Proceedings of the 26th Industrial Waste Conference, Purdue University, 1971.
- Norcross, K.L., S. Petrice, R. Bair, and G. Beaushaw, "Start Up and Operation Results from SBR Treatment of a Meat Processing Wastewater," Proceedings of the 42nd Industrial Waste Conference, Purdue University, 1987.
- Osag, T.R. and G.B. Crane, *Control of Odors from Inedibles Rendering Plants*, EPA 450/1-74-006, July 1974.
- "PAC-Activated Sludge Treatment Coke-Plant Wastewater," Proceedings of the 40th Industrial Waste Conference, Purdue University, 33, 1985.
- Pandey, R.A., "Wastewater Characteristics of LTC Process of Coal," *Journal of Environmental Science and Health*, A24(6), 633 (1989).
- Parsons, Dr. W.A., *Chemical Treatment of Sewage and Industrial Wastes*, Bulletin No. 215, National Lime Association, Washington, D.C., 1965.
- Patrick, G.C. et al., "Development of Design Criteria for Treatment of Metal-Containing Wastewaters at Oak Ridge National Laboratory," Proceedings of the 42nd Purdue Industrial Waste Conference, Purdue University, 1988, pp. 819-830.
- Patterson, J.W. *Industrial Wastewater Treatment Technology*, Butterworth-Heinemann, Boston, 1985.
- Patterson, J.W., "Metals Separation and Recovery," *Metals Speciation, Separation, and Recovery*, Lewis Publishers, Chelsea, Michigan, 1987.
- Perry, R.H., *Perry's Chemical Engineers' Handbook*, 6th ed. McGraw-Hill, New York, 1984.
- Peters, R.W. and Young Ku. "The Effect of Citrate, A Weak Chelating Agent, on the Removal of Heavy Metals by Sulfide Precipitation," *Metals Speciation, Separation, and Recovery*, Lewis Publishers, Chelsea, Michigan, 1987.
- "Pilot Study of Upgrading of Existing Coke Oven Waste Treatment Facility With Trickling Filter," Proceedings of the 41st Industrial Waste Conference, Purdue University, 586, 1986.
- Porges, R., and E.J. Struzeski, "Wastes from the Soft Drink Bottling Industry," *Journal of the Water Pollution Control Federation*, Vol. 33, p. 167, 1961.
- Potter, N.N., *Food Science*. AVI Publishing, Westport, Connecticut, 1978.
- Prokop, W.H., "Plant Operations," *Renderer Magazine*, October, 1979.
- Prokop, W.H., "Wet Scrubbing of High Intensity Odors from Rendering Plants," presented at the APCA Specialty Conference, State-of-the-Art of Odor Control Technology II, Pittsburgh, Pennsylvania, March 10-11, 1977.
- Pulp and Paper Manufacture, Vol. II: Control, Secondary Fiber, Structural Board, and Coating*, Joint Textbook Committee of the Paper Industry, 1969.
- Ramirez, E.R. and O.F. D'Alessio, "Innovative Design and Engineering of a Wastewater Pretreatment Facility for a Metal Finishing Operation," Proceedings of the 39th Purdue

- Industrial Waste Conference, Purdue University, 1985, pp. 545-553.
- "A Report on Bottled and Canned Soft Drinks, SIC 2086, and Flavoring Extracts and Syrups, SIC 2087," Associated Water and Air Research Engineers, Inc., August 1971.
- Robertson, W.M., J.C. Egide and J.Y.C. Huang, "Recovery and Reuse of Waste Nitric Acid from an Aluminum Etch Process," Proceedings of the 35th Industrial Waste Conference, Purdue University, May 1980.
- Rudolfs, W. *Industrial Wastes: Their Disposal and Treatment*, L.E.C. Publishers, New York, 1961.
- Russell, J.M. and R.N. Cooper, "Irrigation of Pasture with Meat-Processing Plant Effluent," Proceedings of the 42nd Industrial Waste Conference, Purdue University, 1987, pp. 491-497.
- Russell, L.L., J.N. DeBoice, and W.W. Carey, "Disposal of Winery Wastewater," Proceedings of the 7th National Symposium on Food Processing Wastes, EPA 600/2-76-304, December 1976.
- Ryder, R.A., "Winery Wastewater Treatment and Reclamation," Proceedings of the 28th Industrial Waste Conference, Purdue University, May 1973.
- Sawyer, C.N. and P.L. McCarty, *Chemistry for Environmental Engineers*, 3rd Edition, McGraw-Hill, New York, 1978.
- Sell, N.J., *Industrial Pollution Control*, Van Nostrand Reinhold, New York, 1981.
- Sirrinc, K.L., P.H. Russell, Jr., and J. Makepeace, *Winery Wastewater Characteristics and Treatment*, EPA 600/2-77-102.
- Snoeyink, V.L. and D. Jenkins, *Water Chemistry*, John Wiley & Sons, New York, 1980.
- Stander, G.T., "Treatment of Wine Distillery Waste by Anaerobic Digestion," Proceedings of the 22nd Industrial Waste Conference, Purdue University, May 1967.
- Steffan, A.J. and M. Bedker, "Operations of a Full Scale Anaerobic Contact Treatment Plant for Meat Packing Wastes," Proceedings of the 16th Industrial Waste Conference, Purdue University, 1971.
- Steffen, A.J., *In-Plant Modifications To Reduce Pollution And Pretreatment Of Meat Packing Wastewater For Discharge To Municipal Systems*, Environmental Protection Agency, West Lafayette, Indiana, 1973.
- Stevenson, T., *Southby's World Wine Encyclopedia*, Little Brown, Boston, 1988.
- Supermarket Business*, 44, 3, 85, March 1989.
- Synthetic Rubber: The Story of an Industry*, International Institute of Synthetic Rubber Production, New York, 1973.
- Title 40, Code of Federal Regulations, Effluent Guidelines and Standards, Part 430, Subpart Q Deink Subcategory, published January 30, 1987.
- U.S. Bureau of the Census, *Statistical Abstract of the United States: 1988*, Washington, D.C., 1987.
- U.S. Bureau of the Census, *Statistical Abstract of the United States: 1990 (110th Annual Edition)*, January 1990.
- U.S. Department of Energy, *Quarterly Coal Report*, October-December 1989.
- U.S. Department of Health, Education, and Welfare, *An Industrial Guide to the Meat Industry*, U.S. Government Printing Office, Publication No. 386, Washington, D.C., 1954.
- U.S. Environmental Protection Agency, *Biological Removal of Carbon and Nitrogen Compounds from Coke Plant Wastes*, EPA, April 1973.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitation Guidelines and New Source Performance Standards for the Red Meat Processing Segments of the Meat Products Point Source Category*, EPA, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitation Guidelines and Standards for the Foundries (Metal Molding and Casting)*, EPA 440/1-80/070a, 1980.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitations Guidelines and Standards for the Iron and Steel Manufacturing Point Source Category*, Vol. II. EPA, December 1980.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitations Guidelines and Standards for the Pulp, Paper and Paperboard Point Source*

- Category*, U.S. EPA Office of Water, EPA 440/1-82/025, October, 1982.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitations Guidelines and Standards of Performance for the Battery Manufacturing Point Source Category*, EPA 440/1-82/067-b, Washington, D.C., 1982.
- U.S. Environmental Protection Agency, *Development Document for Effluent Limitations Guidelines and Standards of Performance, Rubber Processing Industry*, EPA 440/1-74-013-A, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Proceedings 8th National Symposium on Food Processing Wastes*, U.S. EPA, Washington, D.C., August 1977.
- U.S. Environmental Protection Agency, *Treatability Manual*, EPA 600/2-82-001b, 1982.
- U.S. Environmental Protection Agency, *Upgrading Meat Packing Facilities to Reduce Pollution*, EPA, Washington, D.C., 1973.
- U.S. Environmental Protection Agency, *Wastewater Characteristics for the Specialty Food Industry*, U.S. EPA, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, Office of Water Regulation and Standards, Effluent Guidelines Division, *Proposed Development Document for Effluent Limitations Guidelines and Standards for the Copper Forming Point Source Category*, EPA 44011-82/074-b, October 1982.
- Van Nostrand, N.J., *Van Nostrand's Scientific Encyclopedia*, John Wiley & Sons, New York, 1983.
- Varley, P.C., *The Technology of Aluminum and Its Alloys*, CRC Press, Cleveland, Ohio, 1970.
- Ward, Roger C., "Aluminum Anodizing Wastewater Treatment and Reuse," Proceedings of the 36th Industrial Waste Conference, Purdue University, May 1981.
- Ward, Roger C., "Aluminum Anodizing Wastewater Treatment and Reuse," *Proceedings of the 36th Industrial Waste Conference*, Purdue University, May 1981.
- Westra, M.A. and B.L. Rose, "Oil and Grease Removal from a Concentrated Source in the Metal Finishing Industry," Proceedings of the 44th Purdue University Industrial Waste Conference, Purdue University, 1989.
- Whitby, G.S., *Synthetic Rubber*, John Wiley & Sons, New York, 1954.

5 Industrial Stormwater Management

General

Precipitation of all types falls on industrial facilities and, in so doing, transports chemicals and inert solids from wherever it physically contacts them to other parts of the environment. Any industrial facility will have some contamination on all surfaces, including roofs, parking lots, storage facilities, roads, sidewalks, and grassy areas.

Because all substances are soluble, to some extent, in water (the universal solvent), any chemical substances in either liquid or solid form will become dissolved (to an extent equal to or less than the solubility limit for that substance) and will either percolate into the ground or be carried with the rainfall runoff. Some particles that are not dissolved will be carried along with the runoff, and some amount of gases will be dissolved in the runoff. Most, if not all, of that which percolates into the ground will eventually join the groundwater.

The type and amounts of materials that become incorporated into the runoff depend on the state of cleanliness of the industrial facility, the area of the roofs, parking lots, roadways, etc., as well as the characteristics of the precipitation itself, in terms of intensity, duration, pH, temperature, and chemical constituents. Factors such as the topography of the plant site, the characteristics of the surfaces over which the runoff flows, and the stormwater management facilities that have been constructed will also have a major influence on the quality of the stormwater runoff as it leaves the industrial site or percolates into the ground.

The quality and, in some cases, the quantity of the water that leaves the industrial site, whether via overland flow to surface waters or via percolation into the groundwater, is of importance in the context of compliance with

environmental regulations. More to the point, the quality and quantity of the stormwater runoff before it leaves the site is the subject of stormwater management, as it relates to a pollution prevention program, the design of collection and treatment facilities, and regulatory compliance monitoring.

Control and, indeed, prevention of contamination of groundwater and surface water by stormwater percolation or runoff is a matter of preventing or controlling the following activities:

- Contamination of surfaces with which stormwater can come into contact, such as roofs, parking areas, storage areas, roads, industrial yard areas, tanks, piping systems, and outdoor equipment
- Contamination of unpaved areas by spills, leaks, and drips, either by accident or as a routine consequence of inadequate preventive maintenance
- Accidents

Prevention of accidents is best accomplished through a vigorous safety program. Prevention of leaks and drips is best accomplished through an exemplary preventive maintenance program.

Federal Stormwater Regulations

By Karen Townsend

Background

Federal regulation of stormwater originated with the *1987 Clean Water Act* amendments that established the authority for the U.S. EPA to develop a phased approach to stormwater discharge permitting and management. Two

stormwater rules followed in 1990 and 1992: the “stormwater application rule” and the “stormwater implementation rule.” The stormwater application rule of November 1990 identified the types of facilities subject to permitting under the National Pollutant Discharge Elimination System (NPDES) program (found at *40 CFR Part 122*), and the stormwater implementation rule of April 1992 described the requirements for NPDES stormwater permits.

Phase I of the stormwater application rule is applicable to heavy industrial dischargers, as identified by the Standard Industrial Classification (SIC) code, as well as large and medium municipal separate storm sewers and operators of large construction sites (i.e., disturbing 5 or more acres of land area). The Phase II rules, finalized in October 1999, expanded the Phase I authority to include small municipal separate storm sewers and small construction sites (i.e., that disturb between 1 and 5 acres of land).

Industrial facilities are required to comply with the stormwater rules if they meet the following three criteria:

- Discharge stormwater via one or more point sources (e.g., a pipe, swale, or ditch) into waters of the U.S. (either directly or through a municipal separate storm sewer) and
- If the facility falls within one of the following categories:
 - either engaged in industrial activity (defined by SIC code)
 - already covered under a NPDES permit or
 - identified by the EPA as contributing to a water quality violation

Note that the federal stormwater rules are not applicable in the following situations (although state or local rules may be applicable):

- Nonpoint source discharges of stormwater
- Discharges of stormwater to municipal sewer systems that are combined stormwater and sanitary sewers
- Discharges of stormwater to groundwater

There are currently two types of stormwater discharge permits issued to industrial dischargers

by the NPDES permitting authority (either the U.S. EPA region or the state administrator, in the case of states with delegated NPDES permitting authority): the Multi-Sector General Permit and the Individual Permit.

Multi-Sector General Permit

The NPDES Stormwater Multi-Sector General Permit (MSGP) is the simplest form of NPDES permit coverage that an industrial facility can obtain, although there are circumstances that would cause a facility to be ineligible for MSGP coverage. The original MSGP was issued in the Federal Register on September 29, 1995, and incorporates requirements for 29 industrial sectors. On September 30, 1998, the modified MSGP was issued to cover additional industrial dischargers not previously included in the MSGP. Industrial facilities that have activities covered under one or more of the industrial sectors in the MSGP are eligible for coverage.

To obtain MSGP coverage, the facility must submit a Notice of Intent (NOI) for coverage and prepare and implement a Stormwater Pollution Prevention Plan (SP3). The MSGP contains industry-specific requirements for stormwater monitoring, reporting, and, in some cases, specific best management practices (BMPs) to minimize contamination of runoff.

Individual Permit

The NPDES Individual Permit requires the preparation and submittal of NPDES Forms 1 and 2F, which request specific information about the facility; the industrial operations; and the results of stormwater sampling, analysis, and flow measurement. A facility-specific Individual Permit is issued by the NPDES permitting authority and typically contains discharge limits, monitoring and reporting requirements, and may require implementation of BMPs or pollution prevention measures. Industrial facilities that are required to apply for an Individual Permit include:

- Facilities that are not covered under the MSGP

- Facilities that have previously had an NPDES permit for stormwater
- Facilities that are determined by the permitting authority to be contributing to a violation of a water quality standard

Because of the backlog of applications and the lengthy application review and permit writing process for Individual Permits, permitting authorities typically recommend that dischargers seek coverage under the MSGP, if eligible. In some U.S. EPA regions, applicants seeking Individual Permits have waited 3 to 5 years or more to receive their permits.

Construction General Permit

One additional stormwater permitting issue that an industrial or environmental manager must be aware of is the NPDES Stormwater Construction General Permit. This permit is applicable to construction projects at industrial facilities that disturb 1 or more acres of land area. The permitting process is the same as for the MSGP; submittal of an NOI for coverage and implementation of an SP3 that focuses on BMPs (such as sediment and erosion control measures) during construction.

Stormwater Pollution Prevention Plan (SP3)

Among the important requirements of the MSGP is the development and implementation of an SP3. The goal of the SP3 is to reduce or eliminate the amount of pollutants in stormwater discharges from an industrial site. The SP3 must be developed with input from a designated Pollution Prevention Team, consisting of facility staff representing key manufacturing, operations, and environmental management areas. The SP3 must identify all potential pollutant sources and include descriptions of control measures to eliminate or minimize contamination of stormwater. The SP3 must contain the following:

- A map of the industrial facility identifying the areas that drain to each stormwater discharge point
- Identification of the manufacturing or other activities that take place within each area

- Identification of the potential sources of pollutants within each area
- An inventory of materials that can be exposed to stormwater
- An estimate of the quantity and type of pollutants likely to be contained in the stormwater runoff
- A history of spills or leaks of toxic or otherwise hazardous materials for the past 3 years

Best Management Practices (BMPs) must be identified. BMPs should include good housekeeping practices, structural control measures where needed, a preventive maintenance program for stormwater control measures, and procedures for spill prevention and response. Traditional stormwater management controls, such as oil/water separators and retention/equalization devices, must also be included as needed.

- For facilities that are subject to EPCRA 313 reporting, the SP3 must address those areas where the listed Section 313 “water priority chemicals” are stored, processed, or handled. These areas typically require stricter BMPs in the form of structural control measures.
- A certification of Nonstormwater Discharges. In order to make this certification, the facility must have piping diagrams that confirm no nonstormwater connections to the storm sewer. Otherwise, all outfalls must be tested, by dye or other tracer, to ensure that there are no connections of sewers that carry other than stormwater.
- A recordkeeping system must be developed and maintained, as well as an effective program for training employees in matters of controls and procedures for pollution prevention.

Prevention of Groundwater Contamination

Measures and facilities to prevent contamination of groundwater should be developed concurrently with those that have the purpose

of protecting against surface water contamination. The most important are as follows:

- Construction of impermeable barriers such as concrete pads to prevent percolation of stormwater after it has become contaminated
- Installation of fool-proof automatic shut-off devices to prevent spills from overflowing tanks
- Alarms
- An aggressive preventive maintenance program to prevent the occurrence of leaks
- Control of particulate and aerosol emissions and routine cleaning of all surfaces on the industrial site

The foregoing work seeks to eliminate and/or reduce contamination of stormwater runoff at the site to the point where compliance with all applicable regulations occurs without the necessity of expensive collection, retention, treatment, and discharge facilities.

A thorough program should be carried out to eliminate leaks, spills, and uncovered storage areas. Also, spill containment devices should be carefully designed and constructed. It is very important to segregate uncontaminated runoff from contaminated or potentially contaminated runoff. For instance, roofs that have a reasonable potential to become contaminated with dust or other fallout should be fitted with gutters and ancillary piping. The piping should segregate this runoff from any and all runoff that will not become contaminated. Paved and unpaved areas should be surveyed, and those areas that are not subject to contamination should be isolated, regarding runoff collection and conveyance. Certainly, a safe approach would be to design and construct a retention basin for runoff that is expected to be clean and to sample and analyze this water before it is discharged.

Stormwater Segregation, Collection, Retention, and Treatment

The collection system for contaminated runoff consists of rain gutters, catch basins, pumping stations, open channels, and pipes. This system must always be well maintained, kept clean,

and free of leaks. Also, easy access to the collection system for sampling and analysis should be designed and built into the system. Because this water undergoes retention and treatment, its volume should be minimized by careful segregation from uncontaminated stormwater. Careful segregation will also maximize the concentration of contaminants because, presumably, the quantity of contaminants at a given industrial site at a given time is fixed by the circumstances and events that have occurred before the storm event. Therefore, the smaller the amount of stormwater in which the contaminants are dissolved or suspended, the more concentrated they will be. For most treatment devices, such as oil skimmers and sedimentation facilities, this higher concentration will lead to more effective treatment.

Control of the quantity and quality of stormwater discharges is possible only if effective segregation, collection, retention, and treatment facilities are in use. Furthermore, the effectiveness—from both a cost perspective and a physical perspective—depends on proper design. Opportunities for segregation of “clean” runoff from “contaminated” runoff should be exposed as the first step in developing an effective stormwater management program. Source segregation can be effective in reducing the volume of runoff to be collected and treated. In general, the sizes of the collection, retention, and treatment facilities are derived from precipitation records and selection of a design storm. Because the concept of a design event implies periodic “failure,” it is necessary to include, within the design of the stormwater management facilities, provisions to prevent damage to those facilities or violations of permits.

Design Storm

The 25-year, 24-hour storm event has been shown to be an appropriate design basis for stormwater management facilities for an industrial plant when “conventional” pollutants are the only substances of concern. (In situations where PCBs or other toxic substances are potential pollutants, a 50- or 100-year storm

would be more appropriate, as discussed later.) The total volume of runoff, calculated by use of the “rational method” or another more sophisticated runoff modeling procedure, is used to determine the capacity of the retention device. The peak runoff rate is used to size the collection and piping, ditching, pumping, or other conveyance facilities.

By definition, there is a 4% probability that the 25-year storm will be exceeded in any given year. For this reason, a type of risk assessment or alternatives analysis should be carried out to determine if the benefits of designing for a storm event that would yield a greater volume and/or peak flow rate such as the 50-year, 24-hour storm or even the 100-year storm would outweigh the risk of an overflow and, potentially, a permit exceedance. Factors to be considered in such a risk assessment include the water quality standards of the receiving water, the discharge permit limits, and the potential enforcement consequences, should an exceedance of permit limits occur. If the receiving stream winds through a public park, for instance, the presence of an oil sheen would likely result in a permit exceedance, not to mention unfavorable publicity for the responsible party.

System Failure Protection

Because, by definition, the stormwater management system will “fail” periodically, in terms of capacity of the retention device, and/or the conveyance facilities, it is extremely important to design and construct overflow devices and other excess water management facilities. The overflow and excess water conveyance devices must protect against erosion and contamination of groundwater. These devices must also be maintained and kept clean and they should, therefore, be designed to allow easy access. The capacity of these facilities should accommodate any conceivable storm event.

Stormwater Retention

Stormwater retention facilities retain contaminated stormwater until it can be treated

to concentration limits specified in the appropriate discharge permit or to quality characteristics required for use of the process makeup water in the industrial plant (see Stormwater as a Source of Process Water Makeup). Retention can be accomplished in lined, earthen basins or in above- or below-ground concrete or steel tanks. An industrial plant in a nonurban location having large areas of unused land would consider the cost effectiveness of a lined, earthen basin first, whereas a plant in an urban location with limited available unused land might first consider an above- or below-ground concrete basin.

As explained earlier, the size of the stormwater retention facility is based on a design storm event. Additional factors that must be included are as follows:

- Precipitation that falls directly into the retention device
- The rate at which water is taken out of the basin, as it relates to the probability of another storm event taking place very soon after the design storm has occurred

The rate at which water is removed from the retention basin is a function of the capacity of the treatment system and the rate of use of this water, if it is indeed used as a source of makeup water in one or more processes in the manufacturing facility. The procedures presented in Chapter 8 for designing the size (volume) of a flow equalization facility are appropriate to be used for the design of a stormwater retention basin, once the volume and characteristics of the design storm have been determined.

Stormwater Treatment

Design of treatment systems for stormwater runoff is always based on the degree and type of treatment required, which depend on:

- The water quality limits specified in the discharge permit
- The water quality criteria required for use in the plant

Almost always, pH adjustment is required, which normally involves pH measurement and recording, chemical feeding and mixing, and flow measurement and control. Oil skimming is also very common. If simple skimming proves inadequate, sand or other filtration, possibly with chemical augmentation, might be necessary. Dissolved air flotation (DAF) is another potential treatment strategy for meeting fats, oils, and greases (FOG) limitations.

If the total suspended solids (TSS) must be controlled to low limits, there is a possibility that retaining the stormwater runoff for a considerable period will provide for this control by sedimentation in the retention basin. If this method is to be used, the design of the retention device must include provision for removal of the solids and maintenance of sufficient freeboard to contain the next one or more storms while the sedimentation process is taking place.

If sedimentation within the retention basin is not sufficient for the degree of TSS removal required, chemical coagulation facilities, as described in Chapter 8, possibly followed by sand or other filtration, may be the best solution. Again, DAF might also be appropriate, in which case TSS and FOG removal would take place simultaneously.

If the stormwater is to be used as a source of process water makeup, the total dissolved solids (TDS) content may be an important consideration. If such is the case, it is likely that dilution is the only feasible solution, rather than any of the methods for removal of TDS such as those shown on the left side of Figure 8-1, presented in Chapter 8.

Design of treatment facilities for stormwater runoff must always include consideration of future requirements, such as more stringent limits in future NPDES permits. Such consideration might result in simply providing room to add additional treatment devices; however, the most cost-effective procedure might be to provide a high level of treatment and to use and reuse the stormwater in one or more processes within the industrial plant. This solution would require a certain amount of blow-down to control TDS and/or temperature, which would

have to be discharged as treated process water, within compliance with the appropriate permit(s).

Stormwater as a Source of Process Water Makeup

If collected stormwater is to be used as makeup water for one or more manufacturing, cleaning, cooling, or other processes in the industrial plant (or by a neighboring industrial or other facility), treatment considerations can become much different from those that are appropriate to simple discharge within compliance with an NPDES permit. For one thing, a storage facility for the *treated* stormwater will likely be needed. In addition, if it is elected to recycle and reuse the stormwater (plus water from other sources), provisions must be included to prevent buildup of TDS, BOD, and heat to undesirable levels.

Dissolved Solids (TDS)

As explained in Chapters 7 and 8, recycling water in an industrial plant results in increasing TDS concentration because of evaporation. High levels of TDS can lead to scaling and/or corrosion of facilities and equipment. Often, the most cost-effective solution is to discharge a certain quantity of the recycle water each day (blow-down) and make it up with water of low TDS concentration; however, in locations where water of low TDS concentration is not available, or is available at high cost, the best solution may be to remove TDS by either side-stream treatment or full-flow treatment by one of the methods presented in Chapter 8. A solids balance analysis must be performed, as presented later, to properly design the blow-down, makeup, and/or treatment facilities.

Biological Oxygen Demand (BOD)

The buildup of BOD in a water recycle system occurs in exactly the same manner as TDS, described earlier. Rather than a scaling or corrosion problem, however, the buildup of organic solids that are associated with BOD

results in the growth of microbes in the water conveyance and use system. This condition, referred to as “biological fouling,” can result in disaster and is to be avoided to say the least. In general, there are three approaches to avoiding the problem of biological fouling:

- Employing sufficient blow-down and makeup so that biological fouling can be controlled with disinfection
- Removing dissolved organics by activated carbon, ultrafiltration, or other physical treatment process, probably in conjunction with blow-down, makeup, and disinfection
- Removing BOD with biological treatment, by one of the methods presented in Chapter 8, probably in conjunction with blow-down, makeup, and disinfection

Again, mass balances must be performed, as was the case for TDS, to properly design BOD control facilities for water recycle and reuse systems.

Heat

In certain situations, heat can build up to undesirable levels in a water recycle/reuse system. There are, in general, three approaches to solving this problem:

- Passing the recycle water through a heat exchanger to transfer some of the heat to a process stream or to plant washdown waters
- Making use of a cooling tower to waste some of the heat
- Diluting the recycle stream with cold water from another source

In all three of these approaches, the quantity of water in the recycle system must be maintained within an acceptable range by adding makeup water or discharging excess water. Also, whether or not it is intended to ever discharge any stormwater, an NPDES permit should be obtained because the possibility, in fact, the probability, of discharging stormwater runoff as a result of an unexpectedly large storm or a problem with the stormwater recycle/reuse system is always present.

Case History

A metals forging manufacturing facility is located on a 189-acre parcel of land alongside a river having a 7Q10 flow of 240 cfs. The plant performs various metal-working operations such as forging, heat treating, chemical etching, and grinding. The manufacturing complex consists of two primary manufacturing buildings: a forge shop and a process and maintenance (P&M) building. Other support buildings include an office and administration building, several air pollution control (APC) buildings, a rinsewater pretreatment plant (RPP), and an oily wastewater treatment plant (OWTP), as shown in Figure 5-1.

Stormwater runoff from the building roof and yard areas in the northern, eastern, and northwestern portions of the plant site flow by gravity to an existing impoundment (Impoundment 001) and are discharged at an NPDES-permitted Outfall 001. Remaining roof and yard areas are collected and directly discharged at four other NPDES-permitted outfalls on site. In addition to stormwater runoff, Impoundment 001 receives some pretreated process wastewaters from the forge shop and P&M building, fire protection water from the forge shop, and noncontact cooling water. The plant uses lubricating and cutting oils, greases, coolants, and acids in its forging and associated processes.

Forge Shop Area Stormwater Project

The Forge Shop Area Stormwater Project addressed the stormwater and process wastewater that drained to NPDES Impoundment 001. The objectives of this project were threefold:

- Segregate uncontaminated and contaminated stormwaters
- Construct a new Runoff Management Facility (RMF) to replace Impoundment 001
- Identify BMPs to manage stormwater quality

Preliminary Engineering Studies

As a result of studies to identify and characterize the sources of flows to Impoundment 001,




Figure 5-1 Site plan.

it was determined that the storm drainage system had been used for the discharge of some process wastewaters, that there was a potential for spills to enter the system, and that a limited number of source areas were responsible for a large portion of the total constituent loading to Impoundment 001.

Next, an evaluation was conducted of available options for eliminating or segregating process wastewaters and contaminated stormwater from uncontaminated stormwater. The results of this work indicated that:

- Many sources could be eliminated at low capital cost.
- The eastern half of the P&M building roof was not contaminated and could be segregated, thereby eliminating 7.2 acres of runoff area from the total 29-acre drainage area to Impoundment 001.

Treatability studies were conducted on the expected influent stream to Impoundment 001, based on elimination of the identified process sources and the clean portion of the P&M building roof. A stormwater management concept of containment of the design storm, treatment, and controlled release of the effluent to meet mass-based permit limits was developed as the initial basis of design for the Runoff Management Facility (RMF).

Initial Design of RMF

Piping system modifications were designed and constructed that would eliminate process wastewater and segregate the clean portion of the P&M building roof. The uncontaminated roof runoff was discharged without treatment at NPDES Outfall 009. The areas that were subject to impact from industrial activities remained tributary to NPDES Outfall 001.

The RMF design included runoff collection, treatment, and direct discharge at a new NPDES Outfall 001. The treatment concept consisted of grit removal, sedimentation, oil skimming, and pumped discharge of the effluent at a rate that would meet current mass-based NPDES permits, as follows:

Total Suspended Solids (TSS)	70 lbs/day
Fats, Oil, and Grease (FOG)	50 lbs/day

Provisions were included for containment of spills within the drainage area of the RMF, and consideration was given to future effluent polishing (by means of polymer addition and adsorption clarification) in the event that the RMF was not able to meet the limits of the NPDES permit. Subsequent to the development of this concept, the U.S. EPA issued a renewed NPDES permit containing the water quality-based limits presented in Table 5-1, which could not be met with the proposed treatment scheme.

Revised Design of RMF

Because of the high cost for an advanced treatment system and lack of guarantee of meeting the new discharge limits, it was decided to institute a stormwater recycle program to eliminate the regular discharge at Outfall 001 and reduce the demand for water from process water supply sources. The design concept was thus revised to incorporate sand filtration and recycle of the treated water for use in the manufacturing process. The original design features of grit and oil removal, sedimentation, and equalization were retained.

The following design criteria for the RMF were agreed upon:

<i>Design Storm:</i>	25-year, 24-hour storm event
<i>Mode of operation:</i>	Incorporate process water effluent into stormwater retention and treatment system. Recycle and reuse continuously. Blow-down as necessary to maintain desired water quality.
<i>Recycle Water Quality:</i>	TSS: <1–10 mg/L FOG: <1 mg/L pH: 5.0–8.0

In order to determine the buildup of TDS, TSS, BOD, and heat caused by the “cycles of concentration” effect, mass balances of water, constituent substances, and heat were performed.

Table 5-1 Existing NPDEs Outfall 001 Permit Limits

<i>Constituent</i>	<i>Monthly Avg.</i>	<i>Daily Max.</i>
Oil & Grease	—	15
pH (range)	6.5–8.0	
Temperature, °C	20	28.3
Total suspended solids (lb/day)	70	210
Total Aluminum	0.087	0.75
Total Arsenic	< 0.01	< 0.01
Ammonia	0.096	0.122
Total Copper	0.006	0.0084
Total Iron	0.3	0.3
Total Lead	< 0.010	< 0.010
Total Mercury	< 0.0002	0.0002
Total Molybdenum	0.004	0.004
Total Selenium	0.010	0.05
Total Thallium	0.0136	0.0136
Total Zinc	0.054	0.059
Total Cyanide	0.005	0.022
Trichloroethylene	0.0027	0.005
2,4,6-Trichlorophenol	0.0012	0.0036
Methylene chloride	0.05	0.05
Tetrachloroethylene	0.0008	0.0008
Biological Toxicity:		
C-NOEC	> 100% Effluent	
LC50	> 100% Effluent	

(Limits stated in mg/L except as indicated.)

Water Balance

Because the RMF would receive both stormwater runoff and process wastewaters, dry and wet weather flows had to be considered. A water balance was performed to represent the flow of waters before and after the recycle system was put into effect. Incoming water to the site originated from several sources:

- Onsite wells for process use and fire protection
- Municipal water for process and sanitary use
- River water for process use and fire protection
- Stormwater

Flow measurement data were collected, and average annual rainfall data were used to

estimate average wet weather flow. The water balance representing the “before recycle” scenario is presented in Figure 5-2.

Discharges from the site originated from the following sources:

- NPDES permitted outfalls
- RPP effluent
- Sanitary wastewater
- Miscellaneous losses

As with the incoming flows, flow data were collected and water use records were used to estimate sanitary and process wastewater flows. An internal cooling water tower was responsible for most of the losses because of evaporation. Also, some water was lost from the system as dilution water for acid and caustic solutions. The “after recycle” water balance, presented in Figure 5-3, shows that all stormwater runoff could be used as process water makeup. In addition to reducing the water withdrawn from the river, less municipal water would be used (68,000 vs. 160,000 GPD).

Mass Balance

Although the existing levels of TDS, TSS, and BOD were very low, the mass balance showed that levels of BOD in the recycle loop could reach 10 to 15 mg/L, indicating a need for disinfection to prevent biological fouling of the water distribution piping and equipment. It was determined that TDS would not reach problematic levels, and, because of the sand filter in the treatment train, TSS was not expected to be a problem. A heat balance showed that the temperature within the recycle loop could reach 102°F during the summer, indicating the possible need for a heat exchanger or cooling tower. A cooling tower, of course, would have the effect of increasing the concentration of TDS, TSS, and BOD, and would require revision of the mass balances if considered further.

Stormwater Collection and Retention

The RMF was designed to serve three storm drain lines and the effluent from the proposed oily wastewater pretreatment system (OWPS),

a pretreatment system that was being designed to remove free oils and emulsified oils from presswaters. All of these flows were routed to the eastern portion of the site to Outfall 001 but required interception prior to the Outfall and rerouting to the northeast to the proposed RMF location. This was accomplished via the design of a cast-in-place concrete junction chamber at the head end of the Impoundment. The junction chamber was designed to intercept and reroute the flows without “throttling” the storm drainage system or allowing solids to settle out. The structure was designed to be constructed in a phased approach that would maintain the discharges to Impoundment 001 until the RMF was ready to receive flow.

The sedimentation basin was sized to retain the design storm volume, to provide the surface area and retention time for solids settling, and to serve as an equalization tank. Design of the basin (configuration and depth) was controlled by site hydraulic limitations imposed by the invert elevations of the existing storm drain lines relative to the water surface elevation of the receiving water for the overflow discharge.

Treatment and Recycle Storage

The unit processes of the RMF are represented in Figure 5-4. The process flow diagram and the layout of the RMF site are shown Figure 5-5. The unique design aspects of each unit process are described in the following sections.

PLC Control and Operator Interface

Control of the RMF is semiautomatic with the use of a programmable logic controller (PLC) for pump control and alarms. An operator interface terminal (OIT) was placed in the RMF for operator control. A second OIT was placed in the plant engineering office for monitoring purposes.

Grit Chamber

The grit chamber was designed to lower the influent flow velocity, thereby allowing for the removal of particles with a specific gravity greater than 2.65 and of a size that would be retained on a 100-mesh screen. Initial oil




Figure S-2 Water balance before recycle.




Figure 5-3 Water balance after recycle.




Figure 5-4 RMF site layout.

skimming was also performed by means of a slotted pipe skimmer that drained the skimmed oil and water mixture to the sump within the RMF treatment building, where the oil was removed. The grit chamber also provided added storage capacity (188,000 gallons).

Sedimentation Basin

The sedimentation tank was a below-grade concrete tank, open to the air and divided by a center wall. The tank was sized to contain the design storm runoff volume of 2.06 million gallons and allow for 2 feet of freeboard, for a total capacity of 2.34 million gallons. The tank size (100 feet by 180 feet by 17 feet) and configuration provide the surface area and retention time for additional settling of solids. Because of a high groundwater table elevation, the structural design of the tank incorporated a combination of antifoatation techniques that added mass to offset buoyant forces.

Oil Skimming


Oil skimming is accomplished in two locations: (1) the grit chamber (as previously

described), and (2) in the baffled effluent sump located inside the RMF treatment building. A floating tube-type oil skimmer removes floating oils, which are temporarily stored for use as a fuel source in a waste oil burner in the RMF treatment building. In the state where the facility is located, waste oil is considered a hazardous waste; therefore, secondary containment of 100% of the storage tank volume was required.

pH Adjustment

Because of the acidic nature of rainfall in the Northeast (pH levels as low as 5.8 had been measured in the existing Impoundment 001), provisions for pH adjustment were included in the RMF design. Sodium carbonate was fed into the line as the wastewater was pumped from the sedimentation tank to the sand filters. In addition to meeting the process water pH needs, a more neutral pH would meet the NPDES permit limit range of 6.5 to 8.0 in the event of an overflow, intended or not, through the Outfall 001.

Process flow diagram.



Sand Filtration

Filtration was achieved by two Parkson upflow sand filters. This type of filter was selected because the continuous backwash system eliminated the need for large volumes of backwash water (backwash flow was approximately 5% to 7% of the forward flow for the upflow filter).

Recycle Water Disinfection

It was recognized that recycle of the treated runoff could result in increased BOD concentrations in the recycle water and create a problem with biofouling in the process water distribution system. A sodium hypochlorite feed system was therefore included.

Recycle Water Storage and Distribution

Recycle water was stored in two A.O. Smith glass-fused-to-steel above-ground storage tanks (ASTs) with aluminum domes, each with a capacity of 1.5 million gallons. This type of tank requires no sandblasting, welding, or painting and, therefore, little maintenance. Recycle water was pumped from the ASTs to the existing process water distribution system as needed. In the event that there is not enough recycle water in storage, the existing river water pumps receive a signal to provide supplemental water.

Hydraulic Overflow

The RMF was designed to handle the 25-year, 24-hour design storm without a discharge to NPDES Outfall 001. In the event that a storm in excess of the design storm, or a series of small storms occurring in rapid succession so as to exceed the capacity of the RMF, two options have been included for hydraulic relief. Minor overflows (up to 1.4 cfs) can be routed to NPDES Outfall 010 via an existing outfall pipe that discharges directly to the river. Hydraulic overflows in excess of 1.4 cfs spill over a knee-wall in the overflow channel and discharge at NPDES Outfall 001, in a location tributary to the river. Flow measurement at Outfall 010 is achieved using an orifice plate located in the floor of the overflow channel. An H-flume can

be used to handle the larger range of flows that may be experienced at Outfall 001.

Spill Containment

A spill containment tank has been located at the influent end of the sedimentation tank, adjacent to the grit chamber, to provide plant personnel the opportunity to divert a spill from the sedimentation basin. Spill-contaminated runoff can be contained separately rather than allowed to further contaminate a potentially large volume of runoff contained in the sedimentation basin.

Treatment Residuals

Wastewater treatment residuals that are generated by the RMF consist of skimmed oil, grit, and sludge from the sedimentation tank. Skimmed oil is burned in the RMF waste oil burner to recover the heat value. The grit chamber and sedimentation tank are cleaned on an annual basis. The method of disposal of grit and sludge depends on their characteristics.

Operations Strategy

In order to minimize the size of the sedimentation basin, it was designed for an operating depth between 1.5 and 3.0 feet during dry weather conditions. The 3.0 feet level gives the treatment system 8 hours of continuous operation, thereby avoiding frequent equipment starts and stops. With this type of operations strategy, the sedimentation basin has been capable of containing the 25-year, 24-hour design storm runoff volume without an overflow; however, it was also necessary to consider what would happen during a storm event in excess of the design storm. The approach was to fully utilize both the in-ground and above-ground storage capabilities by stopping the pumps that fill the ASTs if they are at the overflow level and the sedimentation basin is not full. At the point where the sedimentation basin reaches its capacity, treatment will resume and overflow should occur from the ASTs to Outfall 010 (depending on the overflow rate), therefore eliminating the discharge of untreated stormwater runoff.

Summary

The design of the RMF, which was the subject of this case history, was driven by a need to comply with NPDES permit limits at Outfall 001. The benefits, however, that have been realized include the following:

- Reduced rates of water withdrawal from the river and potable water supply
- Reduced annual costs for potable water supply usage
- Increased ability to capture spills within the drainage area of the RMF
- Reduced potential for discharge of pollutants to the environment and NPDES permit excursions
- Reduced capital and operating costs for compliance with the NPDES permit

Bibliography

- Aron, G., and C.E. Egborge, "A Practical Feasibility Study of Flood Peak Abatement in Urban Areas," Report to U.S. Army Corps of Engineers, Sacramento District, Sacramento, California, 1973.
- Chow, V.T., *Open Channel Hydraulics*. McGraw-Hill, New York, 1959.
- Chow, V.T. (ed.), *Handbook of Applied Hydrology*. McGraw-Hill, New York, 1964.
- Federal Aviation Agency, "Department of Transportation Advisory Circular on Airport Drainage," Rep. A/C 150-5320-SB, Washington, D.C., 1970.
- Henderson, F.M. *Open Channel Flow*. Macmillan, Toronto, 1966.
- Hydrologic Engineering Center, U.S. Army Corps of Engineers, "Storage Treatment, Overflow, Runoff Model, STORM." *User's Manual*, Davis, California, 1976.
- Kibler, D.F., et al., *Recommended Hydrologic Procedures for Computing Urban Runoff from Small Developing Watersheds in Pennsylvania*. Institute for Research on Land and Water Resources, University Park, Pennsylvania, 1982.
- Morgali, J.R., and R.K. Linsley, "Computer Simulation of Overland Flow," *Journal of Hydraulics Division ASCE*, 91, 1965.
- Rantz, S.E., "Suggested Criteria for Hydrologic Design of Storm-Drainage Facilities in the San Francisco Bay Region, California," U.S. Geological Survey Professional Paper 422-M, 1971.
- Schulz, E.F., and Lopez, O.G. "Determination of Urban Watershed Response Time," Colorado State University Hydrology Paper No. 71, Fort Collins, Colorado, 1974.
- Soil Conservation Service, "A Method for Estimating Volume and Rate of Runoff in Small Watersheds," TP-149, U.S. Department of Agriculture.
- U.S. Soil Conservation Service, "Urban Hydrology for Small Watersheds," SCS Technical Release No. 55, Washington, D.C., 1975.
- Viessman, W. Jr., T.E. Harbaugh, and I.W. Knapp, *Introduction to Hydrology*. Intext Educational Publishers, New York, 1972.
- Wanielista, M.P., *Storm Water Management: Quantity and Quality*. Ann Arbor Science Publishing, Ann Arbor, Michigan, 1978.

6 Wastes Characterization: The Wastes Characterization Study, Wastes Audit, and the Environmental Audit

Wastes Characterization Study

Wastes characterization is the term used for the process of determining the chemical, biological, and physical characteristics, as well as the quantity, mass flow rates, strengths (in terms of concentration), and discharge schedule of a wastewater stream, air discharge, or solid waste stream. A wastes characterization program must be carefully thought out and properly executed. The foundation of the study is a sampling and analysis program, which must be performed on representative samples. The equipment used to measure rates of flow and to physically obtain samples must be appropriate to the application and accurately calibrated.

There are three general categories of wastes characterization study in common use: The Wastewater (or Air Discharge, or Solid Waste Stream) Characterization Study, the Environmental Audit, and the Wastes Audit. The appropriate choice among these three categories, for a given application, depends on the principal purpose of the study. A Wastes Characterization Study (Wastewater, Air Discharge, or Solid Wastes Stream) is usually carried out to obtain design criteria for a wastes treatment facility, with a concurrent pollution prevention program. An Environmental Audit is performed to assess a plant's state of compliance with various environmental regulations. A Wastes Audit is carried out to assess opportunities to minimize the amount of wastes generated through improved efficiency or substitution of nonhazardous substance(s) for one or more of those that are classified as hazardous. In each

case, choices are made about the location of sampling points, equipment to be used, the sampling schedule, and the laboratory and field analyses to be performed. There is always a balance to be struck between the cost of the program and the ultimate value of the data obtained.

Choice of Sampling Location

Because pollution prevention is always a primary objective of any wastes management program, wastes sampling programs should always be designed to determine at what locations in an industrial processing plant significant amounts of wastes are generated. Otherwise, it would be necessary to sample only the final composite effluent from the entire plant. The following example illustrates some of the choices to be made when designing a wastes sampling program:

Figure 6-1 is a schematic of an electroplating shop having four different plating processes, designated Process 1, Process 2, Process 3, and Process 4. At the present time, all four processes discharge to a common drain that leads to the municipal sewer system. The task at hand is to develop a wastes sampling and analysis program to provide data for a wastes reduction program, as well as to enable calculation of design criteria for one or more treatment devices to pretreat the wastewater before discharge to the municipal sewer system within compliance with all applicable regulations. If the sole objective were to treat the wastewater to within compliance with the regulations, it




Figure 6-1 Schematic of an electroplating shop having four different processes.

would make sense to locate one composite sampler at the end of the building to sample the mixed effluent from all four plating processes. The questions, then, would be: “How many days should the sampling period cover?” and “Over how long a time should each compositing period take place?” The answer to the first question depends on the processing schedule and whether or not different processes are run on a campaign basis in one or more of the four processing units. It is more or less standard practice to sample the wastes from a given process (or set of processes) over a three-consecutive-day period. Five would be better than three, but a decision has to be made between the greater cost for the longer sampling period and the greater risk associated with the shorter sampling period. A prudent engineer develops more conservative design criteria if the risk of not having accurate waste characteristics is higher. The higher cost for the more conservatively designed treatment system may well be more than the higher cost for the longer sampling period.

The second question is about the length in time of each compositing period. Four 6-hour composites per day produce four discrete samples to be analyzed, whereas two 12-hour composite samples taken each day will cost only half as much to have analyzed. Using any statistical approach available, the more discrete

samples taken during the 24-hour operating day (that is, the shorter the compositing periods), the more accurate the results of the wastes characterization study will be. Here, again, a prudent engineer recognizes that more conservatism and, therefore, higher cost will have to be designed into a system when the compositing periods are long, the number of discrete samples each day is low, and the risk of not having accurate, detailed characterization information is higher.

If the four plating processes are quite different from each other, then a less expensive overall treatment system might result if one or more are treated separately. If such is the case, it would be appropriate to locate composite samplers at the discharge point of each of the four processes. Now, the number of samples to be analyzed for a given number of sampling days and a given number of composites each day is multiplied by four. Still, the considerations of risk, conservatism in design, and total cost apply, and it is often cost effective to invest in a more expensive wastes characterization study to obtain a lower total project cost.

It is seldom prudent to consider that the sole reason for carrying out a wastes characterization study is to obtain data from which to develop design criteria for a wastes treatment system. Rather, pollution prevention should almost always be a major objective, as it should

be with any wastes management initiative. As discussed in Chapter 7, the many benefits of pollution prevention include lower waste treatment costs and lower costs for disposing of treatment residuals.

When taken in the context of a pollution prevention program, a wastes characterization study takes on considerations in addition to those discussed previously. Using the example illustrated in Figure 6-1, it is seen that locating only one composite sampler to sample the combined wastewater from all four plating processes would yield little useful information for pollution prevention purposes. For these purposes, it is necessary to locate at least one composite sampler at the wastes discharge from each of the four plating processes. Furthermore, there is an important consideration of timing regarding execution of the sampling program. In order to enable measurement of the effectiveness and, therefore, the value in terms of cost savings of the pollution prevention program, a complete wastes characterization study should be carried out before wastes minimization, or other aspects of pollution prevention, take place. These data, however, will not be useful for developing design criteria for wastes treatment because it is hoped that implementation of the pollution prevention program will significantly change the characteristics of the waste stream to be treated.

A second wastes characterization study should be conducted after implementation and stabilization of the pollution prevention program. Stabilization is emphasized here because improved housekeeping (in the form of spill control, containment, and immediate in-place clean-up), water conservation, containment and recycling of "out of spec. product or intermediate," (rather than dumping these "bad batches" to the sewer), and other process efficiency improvement measures are implemented (as part of the pollution prevention program). If some of the former sloppiness and materials control inefficiency creeps back into the industry's routine operations, treatment processes designed using data obtained during full implementation of the pollution prevention program will be overloaded and will fail.

The principal objectives of a wastes management program, which include pollution prevention along with wastes characterization, are to ensure (1) that truly representative samples are taken, (2) that the appropriate samples are taken and the appropriate analyses performed, regarding the *Clean Water Act* and *RCRA*, (3) that the information obtained is appropriate and sufficient to produce an optimal wastes minimization result, and (4) that the optimum balance is struck between the cost of the wastes characterization study and the cost for the treatment facilities ultimately designed and constructed.

Sampling Equipment

In general, there are two types of automatic samplers: discrete and integrated, or totalizing. Discrete samplers place each individual sample into its own container. These samplers are used when it is deemed to be worth the extra expense to determine the variability of the waste stream over the sampling period. Integrated samplers place each individual sample into a common container. Figure 6-2 shows a picture of a typical automatic sampler.



Figure 6-2 Illustration of a typical automatic wastewater sampling device. (Courtesy of ISCO.)

Sample Preservation

It is always desirable to perform laboratory analyses of samples as soon as possible after the sample is taken; however, appropriate measures must be taken to ensure that the sample will not change with respect to the characteristics that are to be measured in the laboratory, no matter how soon, or late, the analyses are performed after the samples are taken. One of the most common problems that results in changes in sample characteristics is bacterial action. If conditions within the sample allow bacterial metabolism, the sample will not be representative of the waste stream from which it was taken when it arrives at the laboratory.

Two common methods of preventing or minimizing bacterial growth are: lowering the temperature of the sample and reducing the pH of the sample.

The rate of bacterial metabolism or, indeed, the metabolism of most life forms decreases by half for every 10°C decrease in temperature. Metabolism essentially stops at 0°C. For this reason, refrigeration, mechanically or with ice, is accepted as a good method for preserving samples. It must be determined before sampling, however, whether or not refrigeration will change the characteristics of the sample. A possible reason for such change is decreased solubility of one or more substances in the sample, which might then result in precipitation of that substance.

A second method of preserving samples is to lower the pH to between 1 and 2. Here, again, care must be taken not to change the character of the sample. The best way to determine the effect of sample preservation is to perform a few laboratory analyses immediately after taking a sample and comparing the results to samples subjected to exactly the same preservation protocol, including elapsed time between sample taking and preservation and laboratory analyses, as is anticipated for the actual wastes characterization program.

Sampling for Oil and Grease

Special sampling techniques must be used when assaying a waste stream for certain

substances. Nonmiscible substances in wastewater such as oils, greases, and waxes are examples. In general, these substances must be sampled for by taking grab samples using a dipping action that ensures taking some liquid from throughout the depth of wastewater flow, including the surface. The current edition of "Standard Methods," as well as any special instructions issued by the EPA or another appropriate authority, must always be consulted to determine the currently accepted techniques.

Volatile Substances

Substances such as trichloroethylene (TCE) that have vapor pressures significantly higher than water and will volatilize at ambient temperatures are additional examples of substances that require special sampling techniques. Again, the current edition of "Standard Methods," in addition to any special instructions (current) issued by the EPA or another appropriate authority must be consulted before embarking on a sampling program.

Wastes Audit

A Wastes Audit has the primary purpose of assessing opportunities to improve efficiencies, decrease wastes, or substitute nonhazardous materials for hazardous materials, thereby minimizing wastes generation. An accounting procedure is to be used, along with a materials balance approach to account for the fates of as many important substances as possible. Figure 6-3 presents a suggested work plan for a wastes audit whose focus is on hazardous substances.

Identify the Hazardous Substances that are Purchased

The records of the Purchasing Agent or the Purchasing Department plus inventory records can be examined to determine all basic and proprietary chemicals and products that are brought in to the plant. In some cases, some of

1. Identify the hazardous substances that are purchased by the facility. Include all substances that are ingredients of mixtures.
2. Identify all the hazardous substances in the water, air, and solid wastes that leave the facility.
3. Determine the source of each hazardous substance.
4. Prioritize the waste streams to be reduced.
5. Analyze the technical and economic feasibility of reducing the toxic load in each waste stream.
6. Evaluate the economics of pollution prevention vs. other approaches to waste management.

Figure 6-3 Wastes audit procedure.

these records are maintained at corporate headquarters. Materials purchased for research and development use and for laboratory use must also be scrutinized. It is most important, especially in the case of proprietary products, to determine each individual chemical component.

For example, at a very large aluminum dye cast plant belonging to one of the giants of the automobile industry, there was a problem with excessive quantities of phenolic compounds in the effluent from the wastewater treatment facility. Noncompliance problems forced employees to perform extensive work to try to improve removal of phenolics by the wastewater treatment equipment. At the same time, a thorough search for the source of the phenolics was carried out, but to no avail. Finally, the facility management decided to purchase and install a large activated carbon system to use as tertiary treatment to remove the phenolic substances. It was also determined that the activated carbon system would have to be preceded by a large sand filter system. While the preliminary engineering for the new tertiary system was in progress, the search for the source of the phenolic substances was greatly intensified. It was

finally determined that a detergent that was used every night by an outside contractor cleaning service was the source. The contractor changed to a different detergent, and the entire problem disappeared. Fortunately, the sand filter-activated carbon tertiary treatment system had not yet reached the construction stage.

Identify all Hazardous Substances that Leave the Facility

All discharges of wastewater, solid wastes, and air must be thoroughly characterized to determine each hazardous substance that leaves the facility and in what form. Some of the hazardous materials are a portion of those that were purchased but were not consumed in process or were not completely accounted for in process consumption, plus that which became included in one or more of the products from the facility. Chlorine, for instance, is used in the manufacture of paper from wood pulp. One of the uses of chlorine is to solubilize lignin fragments that cause the pulp and, consequently, the paper to be brown.

Another function that chlorine performs is to add across the double bonds in the organic structure of the lignin molecule, which changes the molecule (or molecular fragment) from being brown to being colorless. In summary, chlorine is used to "bleach" wood pulp in order to make white paper by allowing the removal of a portion of the lignin (that which becomes solubilized, then rinsed away with water and caustic). Another portion simply becomes colorless and stays with the pulp, and ultimately with the paper. The rinsewater is then wastewater that must be treated and discharged. The chlorine that enters into the process of adding across double bonds goes out of the plant with the paper (product).

For each pound of chlorine purchased, a portion leaves the plant as a component of the wastewater, and a portion leaves the plant as a component of the salable product of the plant. Closer scrutiny reveals that yet another portion leaves the plant as a component of the airborne emissions, some with the fugitive emissions and some with the bleach plant vent and

scrubber emissions, because chlorine is a gas at ambient temperatures, and it volatilizes at every opportunity. A very thorough and detailed study is required to determine the fate of chlorine that is purchased by an integrated pulp and paper mill.

Determine the Source of Each Hazardous Substance

Once each solid, liquid, and airborne waste stream leaving the facility has been thoroughly characterized, and all hazardous substances are identified and/or accounted for, the next step is to determine the source of each one. This can be done by use of an accounting procedure, together with principles of chemistry and knowledge of the individual industrial processes. The accounting procedure is used as a format to ensure that all chemical reactants and products are accounted for.

For some large industrial facilities, such as a detailed accounting is a very significant undertaking. In the long term, however, the entire process is almost guaranteed to produce a financial gain, rather than a long-term loss, for the industrial facility. The example of the floor-washing detergent given previously is a graphic example of the benefit of being tenacious in determining the source of each hazardous substance.

Prioritize the Waste Streams to be Reduced

The objective of this step is to identify, in order of degree of adverse effect on the environment, which waste streams should be addressed first, to achieve maximum benefit to the environment. Although, in some cases, such prioritization is obvious, in other cases, it requires an in-depth study of the affected environment to determine proper prioritization. For instance, if chlorinated (halogenated) organics are being discharged to an extremely large river, and at the same time, a much smaller quantity per day of chlorine gas is being discharged to the atmosphere, but the plant is in a nonattainment area for ozone (another strong oxidizing substance), the waste stream that

should receive the higher priority is not obvious. On the other hand, if the facility has a solid waste stream that is very concentrated in a chlorinated solvent that could be reduced dramatically by installation of a new, highly efficient vapor degreaser plus a new still for recovery and reuse of the solvent, the choice of top priority for action is more easily identified.

Analyze the Technical and Economic Feasibility of Reducing Toxic Loads

To continue with the example of the paper mill, an alternative process for bleaching wood pulp to obtain white paper is to use oxygen as the bleaching agent to remove about 50% of the lignin, rather than chlorine. However, to make the change, new equipment would have to be purchased and installed at significant capital expense, and the value of the paper (product) may well be less because of a lesser degree of whiteness, although not necessarily so. In order to make an informed decision, then, a detailed analysis of both technical feasibility and economic feasibility must be carried out.

Regarding technical feasibility, there are many questions, including:

- Can the oxygen process, known as “oxygen delignification,” produce pulp that can ultimately be “bleached” to the desired degree of whiteness?
- Will other properties of the paper, such as strength, be negatively impacted to an unacceptable degree?
- Is the necessary equipment available?
- Can the existing water pollution, air emission, and solid waste control facilities function properly if the change is made? Will they perform better? Will any components be redundant?
- Will other facilities and/or equipment in the plant have to be changed?

Regarding financial feasibility, the questions include:

- Can the facility actually obtain sufficient capital to make the change?

- Can the facility survive the period between the time of initial investment and the time when overall net savings become a reality?
- Does the change conform to the facility's long term plan?

Evaluate the Economics of Pollution Prevention

It is one thing to ascertain the financial feasibility of a project; it is quite another thing to determine the short-term and long-term effects on the overall profit and loss position of the company. Evaluation of economics of pollution prevention versus other approaches to waste management means evaluating the financial effects on all phases of the product, from initial production, throughout the useful life, to final disposal. This evaluation is a very extensive undertaking, and interim findings must be continuously updated as new information becomes available.

Continuing with the pulp mill example, the decision to be made is whether to continue with the (ever-increasing) expense of managing the wastes from the bleaching process using compounds of chlorine, such as chlorine dioxide, or to invest a large capital expenditure in a non-chlorine alternative, such as ozone system, thereby reducing wastes management costs. In this case, the costs of management throughout the useful life and the costs for final disposal will not be affected because the product is, for practical purposes, identical whether chlorine bleaching is used as opposed to "oxygen delignification." However, there are large differences in the following:

- Costs for the "bleaching agent" itself (chlorine compounds versus oxygen compounds)
- Costs for processing equipment
- Costs for air pollution control
- Costs for wastewater treatment
- Costs for management of the solid wastes. (Certain chlorine wastes must be managed as "hazardous waste.")
- Costs for obtaining discharge permits

- Costs for monitoring air discharges, wastewater discharges, and solid wastes disposal facilities

There are many more categories of costs that are affected by a major change in industrial process, especially one that changes from a process that generates hazardous wastes to a process that does not. In the final analysis, the decision to change or not change a process should be based on the size of the long-term net financial gain or loss.

A properly executed Wastes Audit, should result in an overall savings in the cost of operation of an industrial facility, especially regarding the impact of the cost of wastes handling and disposal on the annual cost of plant operations.

Environmental Audit

An Environmental Audit is normally conducted to assess the state of compliance of an industrial facility with laws and regulations. As such, there is no need to sample and analyze waste streams at locations other than final discharge points, unless it is desired to determine which individual processes are responsible for noncompliance, if any exist. What is important, however, is ensuring that the sampling and analysis work is appropriate to the law or regulation under consideration.

The two federal laws that wastes (solid and liquid) discharged from industrial facilities must comply with are the *Clean Water Act (CWA)* and the *Resource Conservation and Recovery Act (RCRA)*. These two laws not only place restrictions on different substances, but they also require different protocols for sampling and analysis work in the case of some of the substances.

Table 6-1 presents lists of substances for which the *CWA* and the *RCRA*, respectively, specify restrictions. Notice, for instance, that the *CWA* (through NPDES permits) restricts the discharge of 24 metals, whereas the *RCRA* restricts 8 metals.

Table 6-1 Requirements for Chemical, Physical, and Bacterial Analysis

<i>PARAMETERS</i>	<i>CWA NPDES List (1)</i>	<i>RCRA Hazardous Waste (2)</i>	<i>SDWA SDWA List (3)</i>
VOLATILE ORGANICS			
Acrolein	X		
Acrylonitrile	X		
Benzene	X		P-R
Bromobenzene			U
Bromochloromethane			U
Bromodichloromethane	X		U
Bromoform	X		U
Bromomethane	X		U
n-Butylbenzene	X		U
sec-Butylbenzene	X		U
tert-Butylbenzene	X		U
Carbon tetrachloride	X		P-R
Chlorobenzene	X		U
Chloroethane	X		U
2-Chloroethylvinyl ether	X		
Chloroform	X		U
Chloromethane	X		U
2-Chlorotoluene			U
4-Chlorotoluene			U
Dibromochloromethane	X		P-R
1,2-Dibromoethane	X		U
Dibromomethane	X		U
Dichlorodifluoromethane	X		U
1,1-Dichloroethane	X		U
1,2-Dichloroethane	X		P-R
1,1-Dichloroethene	X		U
cis-1,2-Dichloroethene	X		U
trans-1,2-Dichloroethene	X		U
Dichloromethane	X		P-R
1,2-Dichloropropane	X		U
1,3-Dichloropropane	X		U
2,2-Dichloropropane	X		U
1,1-Dichloropropene	X		U
cis-1,3-Dichloropropene	X		U
trans-1,3-Dichloropropene	X		U
Ethylbenzene	X		U
Isopropylbenzene	X		U
4-Isopropyltoluene	X		U
Methylene chloride	X		U
n-Propylbenzene	X		U

Table 6-1 Requirements for Chemical, Physical, and Bacterial Analysis (continued)

<i>PARAMETERS</i>	<i>CWA NPDES List (1)</i>	<i>RCRA Hazardous Waste (2)</i>	<i>SDWA SDWA List (3)</i>
Styrene	X		U
1,1,1,2-Tetrachloroethane	X		U
1,1,2,2-Tetrachloroethane	X		U
Tetrachloroethene	X		U
Toluene	X		U
1,2,3-Trichlorobenzene	X		U
1,1,1-Trichloroethane	X		P-R
1,1,2-Trichloroethane	X		U
Trichloroethene	X		P-R
Trichlorofluoromethane	X		U
1,2,4-Trimethylbenzene	X		U
1,3,5-Trimethylbenzene	X		U
Vinyl chloride	X		P-R
m-Xylene	X		U
o-Xylene	X		U
p-Xylene	X		U
SEMIVOLATILE ORGANICS			
Acenaphthene	X		
Acenaphthylene	X		
Anthracene benzidine	X		
Benzo(a)anthracene	X		
Benzo(a)pyrene	X		
Benzo(b)fluoranthene	X		
Benzo(g,h,i)perylene	X		
Benzo(k)fluoranthene	X		
bis(2-Chloroethoxy)methane	X		
bis(2-Chloroethyl)ether	X		
bis(2-Ethylhexyl)phthalate	X		
4-Bromophenyl-phenylether	X		
Butylbenzylphthalate	X		
Carbofuran	X		P-R
4-Chloro-3-methylphenol	X		
2-Chloronaphthalene	X		
2-Chlorophenol	X		
4-Chlorophenyl-phenylether	X		
Chrysene	X		
Di-n-butylphthalate	X		
Di-n-octylphthalate	X		
Dibenz(a,h)anthracene	X		
1,2-Dibromo-3-chloropropane			U

Table 6-1 Requirements for Chemical, Physical, and Bacterial Analysis (continued)

<i>PARAMETERS</i>	<i>CWA NPDES List (1)</i>	<i>RCRA Hazardous Waste (2)</i>	<i>SDWA SDWA List (3)</i>
1,2-Dichlorobenzene	X		U
1,3-Dichlorobenzene	X		U
1,4-Dichlorobenzene	X		P-R
3,3'-Dichlorobenzidine	X		
2,4-Dichlorophenol	X		
Di(2-ethylhexyl)adipate			P-R
Diethylphthalate	X		
2,4-Dimethylphenol	X		
Dimethylphthalate	X		
4,6-Dinitro-2-methiphenol	X		
2,4-Dinitrophenol	X		
2,4-Dinitrotoluene	X		
2,6-Dinitrotoluene	X		
Fluoranthene	X		
Fluorene	X		
Hexachlorobenzene	X		
Hexachlorobutadiene	X		U
Hexachlorocyclopentadiene	X		
Hexachloroethane	X		
Indeno(1,2,3-cd)pyrene	X		
Isophorone	X		
Naphthalene	X		U
Nitrobenzene	X		
2-Nitrophenol	X		
4-Nitrophenol	X		
N-Nitroso-di-n-propylamine	X		
N-Nitrosodimethylamine	X		
N-Nitrosodiphenylamine	X		
2,2'-oxybis(1-Chloropropane)**	X		
Pentachlorophenol	X		
Phenanthrene	X		
Phenol	X		
Pyrene	X		
Simazine			P-R
1,2,4-Trichlorobenzene	X		U
2,4,6-Trichlorophenol	X		
1,2,3-Trichloropropane			U
PESTICIDES/PCBS			
Arochlor-1016 (PCB-1016)	X		
Arochlor-1221 (PCB-1221)	X		

Table 6-1 Requirements for Chemical, Physical, and Bacterial Analysis (continued)

<i>PARAMETERS</i>	<i>CWA NPDES List (1)</i>	<i>RCRA Hazardous Waste (2)</i>	<i>SDWA SDWA List (3)</i>
Arochlor-1232 (PCB-1232)	X		
Arochlor-1242 (PCB-1242)	X		
Arochlor-1248 (PCB-1248)	X		
Arochlor-1254 (PCB-1254)	X		
Arochlor-1260 (PCB-1260)	X		
Polychlorinated biphenyls (as Arochlors) (as decachlorobiphenyl)			P-R
Aldrin	X		U
alpha-BHC	X		
beta-BHC	X		
delta-BHC	X		
gamma-BHC (Lindane)	X	X	P-R
Chlordane	X		
4,4'-DDD	X		
4,4'-DDE	X		
4,4'-DDT	X		
Dieldrin	X		
Endosulfan I	X		
Endosulfan II	X		
Endosulfan sulfate	X		
Endothall			P-R
Endrin	X	X	P-R
Endrin aldehyde	X		
Endrin ketone			
Heptachlor	X		P-R
Heptachlor epoxide	X		P-R
Methoxychlor			P-R
Toxaphene	X		P-R
HERBICIDES			
2,4-D		X	P-R
Dalapon			P-R
Diquat (as Diquat dibromide monohydrate)			P-R
2,4,5-TP (Silvex)			P-R
METALS			
Aluminum, total	X		S-R
Antimony, total	X		P-R
Arsenic, total*	X	X	P-R
Barium, total*	X	X	P-R
Beryllium, total	X		
Boron, total	X		

Table 6-1 Requirements for Chemical, Physical, and Bacterial Analysis (continued)

<i>PARAMETERS</i>	<i>CWA NPDES List (1)</i>	<i>RCRA Hazardous Waste (2)</i>	<i>SDWA SDWA List (3)</i>
Cadmium, total*	X	X	P-R
Calcium	X		P-R
Chromium, total*	X	X	P-R
Cobalt, total	X		
Copper, total	X		P-R
Iron, total	X		S-R
Lead, total*	X	X	P-R
Magnesium, total	X		R
Manganese, total	X		S-R
Mercury, total*	X	X	P-R
Molybdenum, total	X		
Nickel, total	X		U
Selenium, total*	X	X	P-R
Silver, total*	X	X	S-R
Sodium, total			P-R
Thallium, total	X		P-R
Tin, total	X		
Titanium, total	X		
Zinc, total	X		S
GENERAL CHEMISTRY			
Ammonia (as N)	X		
Asbestos	X		P-R
Biochemical oxygen demand (BOD)	X		
Bromide	X		
Chemical oxygen demand (COD)	X		R
Chloride	X		S-R
Chlorine, total residual	X		
Coliform, fecal	X		P-R***
Coliform, total	X		P-R
Color	X		S-R
Corrosivity	X		S-R
Cyanide	X		P-R
Flow	X		
Fluoride, soluble	X		P-R
Ignitability	X	X	
Langelier saturation index	X		P-R
Nitrate	X		P-R
Nitrite	X		P-R
Nitrogen, total organic	X		
Odor	X		S-R

Table 6-1 Requirements for Chemical, Physical, and Bacterial Analysis (continued)

<i>PARAMETERS</i>	<i>CWA NPDES List (1)</i>	<i>RCRA Hazardous Waste (2)</i>	<i>SDWA SDWA List (3)</i>
Oil and Grease	X		
pH	X		P-R
Phenols	X		
Phosphate, ortho	X		P-R
Phosphorus, total (as P)	X		
Radioactivity, total alpha	X		P-R
Radioactivity, total beta	X		P-R
Radium 226, total	X		P-R
Radium 228	X		P-R
Radium, total	X		
Radon, 222	X		P-R
Reactivity	X	X	
Silica	X		P-R
Sulfate (as S04)	X		P-R
Sulfide (as S)	X		
Sulfite (as S03)	X		
Surfactants	X		R (California only)
Temperature	X		P-R
Total dissolved solids (TDS)	X		S-R
Total organic carbon (TOC)	X		
Total suspended solids (TSS)	X		
Turbidity	X		P-R
OTHER			
2,3,7,8-Tetrachloro-dibenzo-p-dioxin	X		

* RCRA regulates based on toxic characteristic leaching procedure (TCLP).

** CAS # 108-60-1 is sometimes incorrectly identified as bis (2-chloroisopropyl) ether.

*** Only required if total Coliform analysis is positive.

P = Primary drinking water analyte.

R = Regulated parameter.

S = Secondary drinking water analyte.

U = Unregulated parameter.

X = Parameter regulated by this list.

(1) This table is a convenient reference only; for details see the specific rule/regulation: 40 CFR Part 504, Vol. 53, No. 235. Wednesday, December 7, 1988.

NPDES = National Pollutant Discharge Elimination System.

(2) Current reference list: 40 CFR Part 261, July 1, 1988. The regulations also include "Acute Hazardous and "Toxic Waste Parameters," which are not included in this list.

(3) Current reference list: 52 FR 25946, July 9, 1987. RCRA = *Resource Conservation and Recovery Act*.

(4) Information provided by Katahdin Analytical Services, Westbrook, Maine, (800) 683-3994.

The Safe Drinking Water Act (SDWA) contains a list of restricted substances that is different in some respects from either CWA or RCRA and requires different protocols to analyze for some substances. It is very important when engaging the services of an analytical laboratory to inform the analysts of the appropriate law (i.e., CWA, RCRA, or SDWA) to which the analyses should conform.

RCRA requires waste generators to determine whether each segregable waste stream is a "hazardous waste." The determination can be made by sampling and specified analyses or based on the generator's knowledge of the process generating the waste and the chemistry of the waste. For purposes of determining whether a waste stream is "hazardous waste," the determination must be made at the point of generation as opposed to after it has been commingled with other (separate) waste streams. In some cases, it is necessary to store certain waste streams and manage them separately, rather than discharge them to an industrial waste treatment facility or to a POTW.

Characteristics of Industrial Wastes

Industrial wastes are classified as wastewater, air discharges, or solid wastes. There is some overlap of physical characteristics of the substances contained in each of these three classifications of wastes because wastewater can contain dissolved gases and suspended and settleable solids; air discharges can contain vaporized liquids, liquids in the aerosol state, and solid particles known as particulate emissions; and solid waste streams can include containers of compressed gases, and/or liquids. The basis of the classification is the environmental medium to which the waste is discharged, and the characterization of the waste is normally based on the body of laws and regulations that govern that medium.

Characteristics of Industrial Wastewater

Priority Pollutants

Whereas the term "hazardous waste" is normally associated with solid waste and is

regulated under 40 C.F.R. Subpart C, the term "priority pollutant" is used in association with wastewater constituents that are of a hazardous nature. At the writing of this text, there were 126 substances, in the five categories of (1) Metals, (2) Pesticides/PCBs, (3) Semivolatile Organics, (4) Volatile Organics, and (5) General Chemistry, designated by the EPA as priority pollutants, as shown in Table 6-2.


As explained previously, atomic adsorption analysis is the standard method used to determine concentrations of metals. A technique that combines gas chromatography with the mass spectrometer, referred to as "GC-mass spec," is used to analyze for the organics listed in Table 6-3. In this technique, the gas chromatograph is used to separate the organics from each other, and the mass spec is used to determine the concentration of each specific organic compound.

The characteristics of industrial wastewaters are determined in accordance with several sets of laws and regulations that govern the quality of water bodies, both surface water and ground-water. These laws and regulations include the *Clean Water Act* (CWA), the *Resource Conservation and Recovery Act* (RCRA), and the *Safe Drinking Water Act* (SDWA), as explained previously. Each of these laws defines several physical, chemical, and biological characteristics and specifies a protocol to be used in determining each of the characteristics. The following are general descriptions of many of the characteristics regulated by one or more of the CWA, the RCRA, or the SDWA.

BOD

The standard 5-day BOD test is the most commonly used method to estimate the total quantity of biodegradable organic material in wastewater. The results of the 5-day BOD test (abbreviated BOD₅) are considered to be estimates of the amount of oxygen that would be consumed by microorganisms in the process of using the organic materials contained in a wastewater for food for growth and energy. Some of the organic material will thus be

converted to additional microorganisms. Some will be converted to carbon dioxide and some to water. Oxygen is needed for all three purposes, as seen in Equation 6-1.

**Table 6-2** Priority Pollutants

<i>PARAMETER</i>	<i>USEPA Method #</i>	<i>Typical Laboratory PQL</i>
VOLATILES		Ug/L
Acrolein	624	5
Acrylonitrile	624	50
Benzene	624	5
Carbon tetrachloride (tetrachloromethane)	624	5
Chlorobenzene	624	5
1,2-Dichloroethane	624	5
1,1,1-Trichloroethane	624	5
1,1-Dichloroethane	624	5
1,1,2-Trichloroethane	624	5
1,1,2,2-Tetrachloroethane	624	5
Chloroethane	624	10
2-Chloroethyl vinyl ether (mixed)	624	10
Chloroform (trichloromethane)	624	5
Chloromethene	624	5
1,1-Dichloroethylene (dichloroethene)	624	5
1,2-trans-Dichloroethene	624	5
1,2-Dichloropropane	624	5
cis-1,3-Dichloropropene	624	5
trans-1,3-Dichloropropene	624	5
Ethylbenzene	624	5
Methylene chloride (dichloromethane)	624	10
Methyl chloride (dichloromethane)	624	5
Methyl bromide (bromomethane)	624	10
Bromoform (tribromomethane)	624	5
Chlorodibromomethane (dibromochloromethane)	624	5
Dichlorobromomethane (bromodichloromethane)	624	5
Tetrachloroethene	624	5
Toluene	624	5
Trichloroethene	624	5
Vinyl chloride (chloroethene)	624	10
SEMIVOLATILES		Ug/L
Acenaphthene	625	5
Benzidine	625	25

Table 6-2 Priority Pollutants (continued)

<i>PARAMETER</i>	<i>USEPA Method #</i>	<i>Typical Laboratory PQL</i>
1,2,4-Trichlorobenzene	625	5
Hexachlorobenzene	625	5
Hexachloroethane	625	5
bis(2-Chloroethyl) ether	625	6
2-Chloronaphthalene	625	5
2,4,6-Trichlorophenol	625	5
2-Chlorophenol	625	5
1,2-Dichlorobenzene	625	5
1,3-Dichlorobenzene	625	5
1,4-Dichlorobenzene	625	5
3,3-Dichlorobenzidine	625	10
2,4-Dichlorophenol	625	5
2,4-Dimethylphenol	625	5
2,4-Dinitrotoluene	625	5
2,6-Dinitrotoluene	625	5
Fluoranthene	625	5
4-Chlorophenyl phenyl ether	625	5
4-Bromophenyl phenyl ether	625	5
bis(2-Chloroisopropyl) ether	625	5
bis(2-Chloroethoxy) methane	625	5
Hexachlorobutadiene	625	5
Hexachlorocyclopentadiene	625	5
Isophorone	625	5
Naphthalene	625	5
Nitrobenzene	625	5
2-Nitrophenol	625	5
4-Nitrophenol	625	5
2,4-Dinitrophenol	625	25
4,6-Dinitro-o-cresol (4,6-dinitro-2-methylphenol)	625	25
n-Nitrosodimethylamine	625	5
n-Nitrosodiphenylamine	625	5
n-Nitrosodi-n-propylamine	625	5
Pentachlorophenol	625	5
Phenol	625	5
bis(2-Ethylhexyl) phthalate	625	5
Butyl benzyl phthalate	625	5
Di-n-butyl phthalate	625	5
Di-n-octyl phthalate	625	5
Diethyl phthalate	625	5
Dimethyl phthalate	625	5
1,2-Benzanthracene (benzo(a) anthracene)	625	5
Benzo(a)pyrene (3,4-benzo-pyrene)	625	5

Table 6-2 Priority Pollutants (continued)

<i>PARAMETER</i>	<i>USEPA Method #</i>	<i>Typical Laboratory PQL</i>
3,4-Benzofluoranthene (benzo(b) fluoranthene)	625	5
11,12-Benzofluoranthene (benzo(k) fluoranthene)	625	5
Chrysene	625	5
Acenaphthylene	625	5
Anthracene	625	5
1,1,2-Benzoperylene (benzo(ghi) perylene)	625	5
Fluorene	625	5
Phenanthrene	625	5
1,2,5,6-Dibenzanthracene (dibenzo(a,h) anthracene)	625	5
Indeno(1,2,3-cd) pyrene (2,3-o-pheynylene pyrene)	625	5
Pyrene	625	5
PESTICIDES/PCBs		Ug/L
Aldrin	608	0.05
Dieldrin	608	0.1
Chlordane (technical mixture and metabolites)	608	0.05
4,4'-DDT	608	0.1
4,4'-DDE (p,p-DDX)	608	0.1
4,4'-DDD (p,p-TDE)	608	0.1
Alpha-endosulfan (Endosulfan I)	608	0.05
Beta-endosulfan (Endosulfan II)	608	0.05
Endosulfan sulfate	608	0.1
Endrin	608	0.1
Endrin aldehyde	608	0.1
Heptachlor	608	0.05
Heptachlor epoxide (BHC-hexachlorocyclohexane)	608	0.05
Alpha-BHC	608	0.05
Beta-BHC	608	0.05
Gamma-BHC (lindane)	608	0.05
Delta-BHC (PCB-polychlorinated biphenyls)	608	0.05
PCB-1016 (arochlor 1016)	608	0.5
PCB-1221 (arochlor 1221)	608	1.0
PCB-1232 (arochlor 1232)	608	0.5
PCB-1242 (arochlor 1242)	608	0.5
PCB-1248 (arochlor 1248)	608	0.5
PCB-1254 (arochlor 1254)	608	0.5
PCB-1260 (arochlor 1260)	608	0.5
Toxaphene	608	1.0
METALS		Mg/L
Antimony	200.7	0.008
Arsenic	200.7	0.005

Table 6-2 Priority Pollutants (continued)

<i>PARAMETER</i>	<i>USEPA Method #</i>	<i>Typical Laboratory PQL</i>
Beryllium	200.7	0.005
Cadmium	200.7	0.010
Chromium	200.7	0.015
Copper	200.7	0.025
Lead	200.7	0.005
Mercury	245.1	0.2 ug/L
Nickel	200.7	0.040
Selenium	200.7	0.010
Silver	200.7	0.015
Thallium	200.7	0.015
Zinc	200.7	0.025
OTHER		
2,3,7,8-tetrachloro-dibenzo-p-dioxin (TCDD)	613	10 ppt
Cyanide, total	335.4	0.2mg/L
Asbestos	100.2	7MF/L >10um

Notes:

40 CFR Part 423-126 Priority Pollutants, Appendix A.

PQL = Practical Quantitation Limit

Laboratory limits are from a commercial laboratory, Katahdin Analytical Services, Inc., Westbrook, Maine.

Laboratory limits are 3- to -5 times higher than actual detection limits.

COD

Chemical oxygen demand (COD) is a second method of estimating how much oxygen would be depleted from a body of receiving water as a result of bacterial action. Whereas the BOD test is performed by using a population of bacteria and other microorganisms to attempt to duplicate what would happen in a natural stream over a period of 5 days, the COD test uses a strong chemical oxidizing agent, potassium dichromate or potassium permanganate, to chemically oxidize the organic material in the sample of wastewater under conditions of heat and strong acid. The COD test has the advantage of not being subject to interference from toxic materials as well as requiring only 2 or 3 hours for test completion, as opposed to 5 days for the BOD test. It has the disadvantage of being completely artificial, but is nevertheless considered to yield a result that may be used as the basis on which to calculate a reasonably accurate and reproducible estimate of

the oxygen-demanding properties of a wastewater. The COD test is often used in conjunction with the BOD test to estimate the amount of nonbiodegradable organic material in a wastewater. In the case of biodegradable organics, the COD is normally in the range of 1.3–1.5 times the BOD. When the result of a COD test is more than twice that of the BOD test, there is good reason to suspect that a significant portion of the organic material in the sample is not biodegradable by ordinary microorganisms. [It is noted here that the sample vial resulting from a COD test can contain leachable mercury above regulatory limits. If such is the case, the sample must be managed as a toxic hazardous waste.]

Ultimate BOD

The term “ultimate BOD,” designated by BOD_u, refers to the quantity of oxygen that would be used by microorganisms in converting the entire amount of organic material in a

given volume of wastewater to carbon dioxide and water, given unlimited time, as opposed to a time limit of 5 days. The BODu of a known substance can be estimated as shown in the following example.


Example 6-1:

Estimate the BODu of a waste stream containing 100 mg/L of pure ethanol.

Solution:

The first step is to write out and balance an equation depicting the complete oxidation,

with oxygen, of a molecule of the appropriate substance, ethanol in this case:



Next, using the mole ratio of oxygen to ethanol as calculated by balancing the equation, as well as the respective molecular weights of each substance, multiply the concentration, in mg/L, of ethanol in the wastewater by this mole ratio, and by the molecular weight of oxygen divided by the molecular weight of ethanol, to obtain the BODu of that wastewater:

Table 6-3 Heavy Metals Regulated by the *Clean Water Act* (CWA)

PARAMETER	USEPA Method No. (4)	Priority Pollutants List (1)	Typical Laboratory PQL (2)
METALS			MG/L
Aluminum, total	200.7		0.10
Antimony, total	200.7	X	0.008
Arsenic, total	200.7	X	0.005
Barium, total	200.7		0.005
Beryllium, total	200.7	X	0.005
Boron, total	200.7		0.10
Cadmium, total	200.7	X	0.010
Chromium, total	200.7	X	0.015
Cobalt, total	200.7		0.030
Copper, total	200.7	X	0.025
Iron, total	200.7		0.025
Lead, total	200.7	X	0.005
Magnesium, total	200.7		0.050
Manganese, total	200.7		0.015
Mercury, total	245.1	X	0.20 ug/L
Molybdenum, total	200.7		0.10
Nickel, total	200.7	X	0.040
Sodium, total	200.7		0.010
Selenium, total	200.7	X	0.005
Silver, total	200.7	X	0.015
Thallium, total	200.7	X	0.005
Tin, total	200.7		0.10
Titanium, total	200.7		0.015
Vanadium, total	200.7		0.025
Zinc, total	200.7	X	0.025

Current reference list: 40CFR Part 136, Inorganic Test Procedures.

PQL = Practical Quantitation Limit.

PQLs are from Katahdin Analytical Services, Inc., Westbrook, Maine.

Other Approved USEPA Methods are available; please refer to the regulation for optional methods.

Mole ratio, oxygen / ethanol = $2/1 = 2.0$

mol. wt. of ethanol = 38

mol. wt. of oxygen = 16

Therefore, ratio of molecular weights,

oxygen/ethanol = 0.42

and the BODu of the solution of ethanol is calculated by:

$$\begin{aligned} 100 \text{ mg/L} \times 2 \text{ mole } O_2 \text{ mole ethanol} \\ \times 0.42 = 84 \text{ mg/L} \end{aligned} \quad (6-3)$$

pH, Acidity, and Alkalinity

The term pH refers to the concentration of hydrogen ions in an aqueous solution, where "aqueous solution" means either pure water or water with small (in terms of molar amounts) quantities of substances dissolved in it. Strong solutions of chemicals such as one molar sulfuric acid or a saturated solution of sodium chloride do not qualify as aqueous solutions. In those solutions the normal pH range of 0 to 14, which equals the negative logarithm of the hydrogen ion concentration in moles per liter, has no meaning. Because the pH of an aqueous solution is numerically equal to the negative log of the hydrogen ion concentration (in moles per liter) and can be readily calculated using the following equation,

$$pH = \log \frac{1}{[H^+]} \quad (6-4)$$

it is therefore indicative of the acidic or basic condition of a wastewater (pH values between 0 and 7.0 indicate acidic conditions, and pH values between 7.0 and 14 indicate alkaline conditions). However, pH is not equivalent to acidity or alkalinity. A wastewater may have a pH of 2.0 but have lower acidity than another wastewater having a pH of 4.0. Likewise, a wastewater having a pH of 9.0 may, or may not, have more alkalinity than a wastewater having a pH of 10.6.

Alkalinity and acidity are defined as the ability of an aqueous solution to resist a change in pH. Alkalinity and acidity are measured by determining the quantity of a solution of acid

or base, as appropriate, of known concentration, that is required to completely neutralize its alkalinity or acidity.

Aqueous solutions (wastewaters, for example) that are high in either acidity or alkalinity are said to be highly buffered and will not readily change in pH value as a result of influences such as bacterial action or chemical reaction. Depending on the anion species involved in the alkalinity or acidity, an aqueous solution can be buffered in low pH ranges, high pH ranges, or neutral (near pH 7) pH ranges.

D.O.

Dissolved Oxygen (D.O.) concentration is usually determined by either a wet chemistry method known as "the azide modification of the Winkler method," or by use of a probe and meter. The wet chemistry method is considered to be the standard for comparison, when the color and other properties of the aqueous solution (industrial waste, etc.) do not preclude its use; however, the probe and meter method is the most commonly used.

The standard D.O. probe consists of two solid electrodes emersed in an electrolyte and separated from the solution being tested by a plastic membrane that is permeable to oxygen. The oxygen can be in the dissolved state or the gaseous state. When the probe is emersed in the test solution, oxygen passes from the solution, through the membrane, and into the electrolyte in direct proportion to its concentration in the solution. As the oxygen enters the electrolyte, it changes the conductivity. This change is detected by the two electrodes, and the change is registered on the meter.

Oxygen is only sparingly soluble in water, and its solubility decreases with increasing temperature. Increasing dissolved solids concentrations also decrease the solubility of oxygen. The saturation concentration of oxygen in deionized water at 1°C and standard air pressure is 14.2 parts per million (ppm), equivalent to about 200 feet of the distance between New York City and Los Angeles. This compares to the concentration of oxygen in air, which is about 230,000 ppm. Still, the species that live

in water are sensitive to relatively small changes in the already extremely low quantity of oxygen available to them. Trout, for instance, do very well when the D.O. concentration is 7 ppm but die when the D.O. concentration falls below 5 ppm. The microorganisms in activated sludge thrive when the D.O. concentration is 1.5 ppm, a seemingly negligible amount (equivalent to less than 1 mile of the trip to the moon). Moreover, small differences in D.O. concentration in aerobic wastewater treatment systems, such as activated sludge, result in significant changes in the populations of different species of microorganisms. These changes, in turn, change the settleability of the sludge, the clarity of the treated effluent, and the overall performance of the treatment system.

Metals

The heavy metals are those elements located in or near the middle of the periodic table. Figure 6-4 shows the periodic chart with the elements considered heavy metals highlighted. Many of these heavy metals are toxic to living entities, including humans and bacteria. For this reason, heavy metals are regulated through the various environmental laws.

Table 6-1 shows the heavy metals that are regulated by the *Clean Water Act (CWA)*, *RCRA*, and the *SDWA*. Table 6-2 lists all the metals that are regulated by the *CWA*, as well as the applicable U.S. EPA Method Number, and the corresponding "Practical Quantitation Limit," which is essentially the limit of detection for that method. The standard method for measuring the concentration of all of the heavy metals listed in Table 6-3 is by atomic adsorption analysis (AA).

Color

Color is measured using visual comparison to an arbitrary standard. The standard is normally made by dissolving potassium chloroplatinate (K_2PtCl_6) and cobalt chloride in deionized water. The color produced by 1 mg/L of potassium chloroplatinate is taken as one standard

unit of color. The cobalt chloride is used in very small amounts to tint the color standard to match the test solution. The cobalt chloride does not affect the intensity of the color of the standard.

In some cases, an agreement can be made with regulatory authorities to make the arbitrary standard by simply diluting the receiving water serially with deionized water or by serially diluting the effluent in question with deionized water.

Turbidity

Turbidity refers to the light-scattering properties of a sample. Turbidity can be described as "haziness" or "milkyiness" and is caused by fine particles scattering light at more or less 90 degrees to the direction from which the light enters the sample. Turbidity is not to be confused with color, nor color with turbidity.

Turbidity is normally measured using an electronic device in which a beam of ordinary white light is directed through a certain path length of the sample. Photometers placed at right angles to the direction of travel of the light beam detect the amount of light diverted, which is directly proportional to the turbidity, expressed in Nephelometric Turbidity Units (NTUs).

Compounds Containing Phosphorus

When treated wastewaters are discharged to natural water systems, various effects can result, depending on what substances remain in the treated effluent and in what form. One of the more significant effects is enhancement of eutrophication within the receiving water system, if significant quantities of phosphorus, in forms available to algae, are discharged.

Eutrophication, or the growth and proliferation of plant life, including algae, is always under way in any natural water system (e.g., rivers, streams, ponds, or lakes) but is limited by the scarcity of nutrients such as phosphorus and nitrogen. At a minimum, plants, including algae, need carbon, nitrogen, and phosphorus in relatively abundant amounts, and potassium,

The periodic table.

Mokeur's Periodic table of the elements

[illegible]

sodium, calcium, magnesium, sulphur, and a host of additional elements in smaller amounts. Any one of these required substances can be the limiting substance that holds growth to a given level when it becomes depleted as a result of that growth. In most cases in the natural environment, that limiting substance is phosphorus.

If treated wastewater discharged to a natural water system significantly increases the inventory of phosphorus, the natural control on the quantity of plant growth that can be supported by that natural water system is removed, and a disastrous level of eutrophication can result. For this reason, many waste discharge permits include a restriction to limit the discharge of phosphorus.

Phosphorus exists in wastewater in many forms, the most basic of which is orthophosphate, $\text{PO}_4^{=}$. Several forms of orthophosphate are encountered in industrial wastewater. A list of the most common is presented in Table 6-4. Table 6-4 also lists several polyphosphates encountered in industrial wastewater treatment. Polyphosphates are simply chains of orthophosphate ($\text{PO}_4^{=}$) units, formed by dehydration. All polyphosphates in aqueous solution gradually hydrolyze and revert back to the orthophosphate form in the natural environment (1).

Table 6-4 Phosphorus Compounds Commonly Encountered in Environmental Engineering Practice

Name	Formula
Orthophosphates	
Trisodium phosphate	Na_3PO_4
Disodium phosphate	Na_2HPO_4
Monosodium phosphate	NaH_2PO_4
Diammonium phosphate	$(\text{NH}_4)_2\text{HPO}_4$
Polyphosphates	
Sodium hexametaphosphate	$\text{Na}_3(\text{PO}_3)_6$
Sodium tripolyphosphate	$\text{Na}_5\text{P}_3\text{O}_{10}$
Tetrasodium pyrophosphate	$\text{Na}_4\text{P}_2\text{O}_7$

Compounds Containing Nitrogen

As explained in the section on Compounds Containing Phosphorus, disastrous eutrophication can result in a natural water body if the substances that constitute the growth-limiting nutrients for algae and other plants are augmented in quantity by the discharge of treated wastewaters. Because nitrogen, which is needed for production of proteins and other components of living cells, can limit the level of algae growth, it is often one of the substances restricted in wastewater discharge permits. Nitrogen can exist in as many as seven valence states, as shown:

3 ⁻	0	1 ⁺	2 ⁺	3 ⁺	4 ⁺	5 ⁺
NH_3	N_2	N_2O	NO	N_2O_3	NO_2	N_2O_5

All but the valence states of 1⁺ and 4⁺ are often encountered in industrial waste discharge management (the 2⁺ valence state is very often encountered in discharges to the air), and each valence state can be converted to any other valence state by natural biological processes. Accordingly, the total amount of nitrogen, or the sum of all the different forms, is commonly limited by wastewater discharge permits.

Total Solids

Substances can exist in aqueous solution in either the dissolved or the undissolved state. The residue that is left after evaporating a sample of water at 103°C is referred to as the total solids value of that sample. It is generally regarded as everything that was in the sample that was not water; however, any of the substances originally present, organic or inorganic, that volatilized at 103°C or less will not be in the residue. Figure 6-5 presents a schematic breakdown of substances that can be measured as total solids in a sample of wastewater.

Suspended Solids

Solids that will not pass through a 0.45 micron filter are referred to as total suspended solids (TSS). Because the standard method for measuring TSS involves shaking the sample thoroughly before filtering, the TSS actually includes all undissolved solids as opposed to simply the dissolved solids that will not settle




Figure 6-5 Schematic: Solids in wastewater.

under the influence of gravity. Results of the test for settleable solids cannot be subtracted from the results of the test for TSS to obtain the value of the quantity of undissolved solids in a sample that will not settle under the influence of gravity, because the standard test for settleable solids yields a value in terms of ml/L, whereas the standard test for TSS yields a value in terms of mg/L. If it is desired to estimate the quantity of nonsettleable TSS, a special procedure must be devised and then described thoroughly in the presentation of results.

Settleable Solids

Settleable solids are undissolved solids that settle to the bottom of a container under the influence of gravity. The standard device for measuring settleable solids is the Imhoff cone, pictured in Figure 6-6. The standard test for settleable solids involves shaking a sample thoroughly, filling the 1-liter Imhoff cone to the full mark, and allowing the sample to settle for 1 hour under quiescent conditions. Settleable solids is reported as milliliters of settleable materials per liter of sample (ml/L). In order to obtain a value of the weight of settleable material, it would be necessary to remove the supernatant and to evaporate to dryness that volume of sample that contained the settleable solids. The result will include the dissolved solids contained in the liquid remaining with the settled solids. If this volume is small compared to the total (1-liter) sample, the "error" will be small. This procedure is never done in the context of a wastewater discharge permit, but may be done for the engineering or planning purposes of the discharger.



Figure 6-6 Imhoff cones used to measure settleable solids. (Courtesy of Wheaton Science Products.)

Total Volatile Suspended Solids (TVSS)

The standard method for estimating the quantity of undissolved organic material in a wastewater sample is to perform a TSS test, as explained previously, and then to place the 0.45 micron filter with the solids deposited thereon in a furnace at 600°C for a sufficient time to "burn" all of the material that will oxidize to carbon dioxide at that temperature. The material that remains on the filter after this procedure will not combine with oxygen and volatilize as carbon dioxide at 600°C. These solids are referred to as "fixed" solids and are considered to be the inorganic portion of the suspended solids in the wastewater sample. This value, subtracted from the TSS value, produces the TVSS portion of the wastewater sample and is an estimate of the quantity of undissolved organic material in the original wastewater sample.

Oil and Grease

There are three methods, each of which is considered a standard method for estimating the quantity of oil and grease in a wastewater sample. When reporting results, however, the method used is actually part of the result. In other words, as stated in "Standard Methods," "... oils and greases are defined by the method used for their determination." The three methods are:

1. Partition-gravimetric method
2. Partition-infrared method
3. Soxhlet method

All three methods involve extracting the oil and grease substances from the raw sample by use of a solvent. Also, all three methods require that the sample be acidified to pH 2.0 or lower, by adding hydrochloric or sulfuric acid, before the extraction process takes place.

The Partition-Gravimetric Method

The partition-gravimetric method involves extracting dissolved or emulsified oil and grease by intimate contact with an extracting solvent, which can be one of the following:

- n-Hexane
- Methyl-tert-butyl ether (MTBE)
- Solvent mixture, 80% n-hexane/20% MTBE, v/v

The sample and the solvent are placed together in a separatory funnel and shaken. Then, the solvent (with dissolved oil and grease from the sample) is drawn off and passed through a funnel containing filter paper and 10 g sodium sulfate. The solvent is evaporated at 85°C, and the quantity of oil and grease is determined gravimetrically.

The Partition-Infrared Method

The partition-infrared method makes use of trichlorofluoroethane as the extraction solvent. Use of this solvent allows use of infrared, which is absorbed by the carbon-carbon double bond that is characteristic of oil and grease substances. Thus, substances that are dissolved by n-hexane and trichlorofluoroethane and are volatilized at 85°C are detected by this method. The extraction procedure is the same as for the partition-gravimetric method. Following the extraction, the quantity of oil and grease is determined using photometric techniques with light in the infrared zone (3200 cm⁻¹ to 2700 cm⁻¹).

The Soxhlet Extraction Method

The Soxhlet extraction method uses the same three choices of solvent as for the partition-gravimetric method (n-hexane, MTBE, or an 80/20 v/v mixture of the two). The extraction procedure, however, is carried out in a reflux apparatus as opposed to a separatory funnel. After extraction, the quantity of oil and grease is determined gravimetrically.

The oil and grease tests are subject to large error because anything that will dissolve in the extraction solvent, whether it is truly oil or grease or not (in the sense that it will cause problems by coating sewerage, forming greaseballs, or exhibiting resistance to biodegradation), will be measured as oil and grease. In addition to this problem, the difficulty of obtaining a representative sample of the wastewater for measurement of oil and grease

content must be kept in mind when interpreting or evaluating laboratory results. The reason for this is that oil and grease substances are only sparingly soluble in water and tend to either float on the surface, as is the case with animal fat, or sink to the bottom, as is the case with trichloroethylene. Accordingly, an automatic sampler that takes samples from the bulk flow is not useful. To take samples for laboratory determination of fats, oil, and grease (FOG) content, it is necessary to hand dip to obtain grab samples, and in doing so, attempt to obtain portions of the flow from throughout the depth of wastewater flow.

“Other Characteristics” (Pollutants)

Chlorine Demand And Chlorine Residual

Chlorine, in the form of either chlorine gas or one of the hypochlorites, is routinely added to wastewaters for disinfection. However, if there are substances in the wastewater that will quickly react with chlorine or hypochlorite, becoming oxidized themselves and reducing the chlorine to chloride ion (Cl⁻), which is non-reactive, disinfection will not take place. These substances are “reducing agents,” relative to chlorine. Therefore, enough chlorine must be added to react with all of the reducing agents before any chlorine becomes available for disinfection. “Contact time” is then required for the chlorine to kill the microorganisms and thus accomplish disinfection. The amount of contact time required is in inverse proportion to the concentration of chlorine residual, which is the concentration of chlorine that remains at any point after reactions with other chemicals or substances (reducing agents) have taken place. The mathematical relationship between chlorine dose, chlorine residual, and chlorine demand is as follows:

$$\text{chlorine residual} = \text{chlorine dose} - \text{chlorine demand} \quad (6-5)$$

The quantity of chlorine “used up” as a result of the disinfection process is considered part of the chlorine demand. Therefore

chlorine demand = chlorine reacted with reducing agents +
chlorine used for disinfection

(6-5.5)

Chlorides

The importance of the presence of chlorides in wastewaters relates to their ability to participate in the conduction of electric current and, therefore, their active role in enhancing corrosion, particularly galvanic corrosion. Chlorides are otherwise benign, being unreactive, and unlikely to participate in any precipitation activity, except the salting out process. Chlorides do affect the osmotic pressure of an aqueous solution and, as such, can have a deleterious effect on a biological wastewater treatment system. It has been determined through both laboratory experimentation and full-scale treatment plant operation that biological treatment systems are able to operate under conditions of chloride concentrations up to 2,000 mg/L, but the chloride concentration must be reasonably stable. Once the population of microorganisms acclimates to a given range of chloride concentration, a significant increase or decrease in chloride concentration adversely affects the treatment process, probably because of the change in osmotic pressure and its effect on the microbial cell membranes.

Hardness

The test for hardness in water was originally developed to determine the soap-consuming properties of water used for washing. The original test involved placing a measured amount of a standard soap in a bottle containing the water being tested, shaking the mixture in a standard manner, then observing the nature of the suds, if any, on the surface of the water. Then, more soap was added, using a step-by-step procedure, until a permanent layer of suds remained on the surface of the water. The total quantity of soap required to produce the stable suds layer was proportional to the hardness of the water. It was eventually realized that the hardness resulted almost entirely from the presence of calcium and magnesium ions in the water, and as soon

as analytical procedures were developed that would analyze for the concentrations of these ions directly, rather than indirectly as with the shaking bottle test, the newer analytical procedures became the standard for the hardness test. In the context of water use in industrial processes, however, and especially the reuse of treated wastewaters in a recycle and reuse system, the significance of hardness is in the scale-forming properties of calcium and magnesium salts.

Iron and Manganese

Iron and manganese are normally considered together as problems in raw water supplies for industrial process use, as well as in process effluents, because these metals are very often found together in groundwater supplies and in some surface water supplies under certain conditions. Iron and manganese are objectionable for two principal reasons. First, iron can be oxidized by oxygen in water to insoluble ferric oxide, which precipitates to form fine granules that can foul distribution systems and cooling devices. Second, both iron and manganese react with chlorine to form highly colored chlorides that stain many of the objects with which they come in contact.

Characteristics of Discharges to the Air

There are three categories of air pollutant characterization work: (1) stack discharge characterization, (2) fugitive emissions characterization, and (3) ambient air quality characterization. The three categories involve quite different sampling procedures but similar, and in most cases identical, analysis methods. Stack discharge and fugitive emission characterization work are done primarily to determine the state of compliance with one or more discharge permits. Ambient air quality characterization is done primarily to determine the quality of air in a given area.

Ambient air quality data is used for many purposes, including:

- Issuance of construction permits for industrial projects

- Determination of state of compliance with National Ambient Air Quality Standards (NAAQS)
- Determination of the effectiveness of ameliorating activities
- Establishment of baseline information before construction of a significant contributor of substances to the atmosphere

Stack Sampling

The most common reason for conducting a stack sampling program is to determine the state of compliance with regulatory requirements. As such, the substances sampled for are usually dictated by the list of substances included in the air discharge permits issued to the facility.

The purpose of stack sampling is to determine, with as much accuracy as is practicable, the quantity (magnitude) of the total gas source flow rate and the quality (types and amounts of air contaminants) of the total source gas discharge. The equipment included in a typical stack sampling station includes devices to measure characteristics from which gas flow rate can be calculated, devices to measure certain characteristics directly, and equipment to collect and store samples for subsequent analyses in the laboratory.

In general, the equipment used to obtain data from which to calculate gas flow rate includes pitot tubes to measure gas velocity, a device to measure the static pressure of the stack gas, and devices to measure barometric pressure, moisture content, and temperature. Equipment used to characterize stack discharges in terms of specific substances is classified in two broad categories: particulate and gaseous. The objective of this equipment in both categories is to quantitatively remove air contaminants in the same condition as they occur when they are discharged to the air. Many individual devices as well as integrated systems are commercially available to accomplish this objective.

Sample Collection

Samples of ambient air or gas streams (including stack emissions and fugitive emissions) are

sampled to determine the presence of, and concentrations of, particulate and gaseous pollutants by use of the following equipment and mechanisms:

- Use of a vacuum pump, hand-operated or automatic
- Vacuum release of an evacuated collection container
- Tedlar bags
- Adsorption on a solid
- Condensation (freeze-out) in a trap

Vacuum Pumps

Vacuum pumps are the standard type of equipment used to draw samples of ambient air of stack gas or another gas stream through or into collection devices. Hand-operated vacuum pumps are used extensively to obtain grab samples. Motor-driven vacuum pumps are the standard for continuous or intermittent monitoring. Vacuum pumps can be fitted with, or connected in series with, gas flow meters to obtain data for calculation of concentrations.

Vacuum Release of an Evacuated Collection Container

Containers (having appropriate linings) can be evacuated by use of a vacuum pump before traveling to sampling locations. The collection apparatus (soil gas sampling well, for instance) can be connected to the evacuated container, the valve on the container can be opened, and a sample of known volume is collected.

Tedlar Bags

Tedlar bags are made of a nonreactive, non-adsorbing (relatively) material and are standard equipment for sampling for gaseous substances in air of a stack or other emission. They are purchased as a completely empty bag and are inflated with the collected sample of air or other gas. Samples should be analyzed as soon as possible after being collected in the Tedlar bag. Tedlar bags can be purchased in different volume capacities, including 1-liter and 10-liter bags.

Adsorption on a Solid

Solid adsorbents, such as activated carbon, can be used to collect certain airborne substances, after which the substances can be desorbed for further analysis or other work. Normally, a vacuum pump is used to draw a volume of air or other gas through a container of the adsorbent. In the case of certain substances, carbon monoxide, for instance, an indicator chemical can be incorporated with the adsorbent to directly indicate the presence of the substance.

Condensation (Freeze-out) in a Trap

Certain substances that are present in air or another gas stream as a result of volatilization can be collected by drawing a stream of the carrier air or other gas through a trap held at low temperature.

Equipment used to collect particulate matter and to determine the concentration, in ambient air as well as stack emission and other gas streams, uses one or more of the following mechanisms:

- Filtration
- Electrostatic impingement
- Centrifugal force
- Dry impingement
- Wet impingement
- Impaction

Filtration

The standard method for determining the concentration of particulate matter in emissions from stationary sources, as published in the Federal Register (40 CFR Part 60, July 1, 1998) is to withdraw, isokinetically, particulate-laden air (or other gas) from the source and collect it on a glass fiber filter maintained at a temperature in the range of $120 \pm 14^{\circ}\text{C}$ ($248 \pm 25^{\circ}\text{F}$) or such other temperature as specified by an applicable subpart of the published standards, or approved by "the Administrator, U.S. EPA" for a particular application. The total quantity of particulates sampled is then determined by weighing the

dried filter. The standard sample train for this determination, illustrated in Figure 6-7, includes equipment to measure gas flow rate, as well as total gas volume sampled. These data can then be used to calculate particulate matter concentration.

Electrostatic Impingement

Figure 6-8 shows a schematic of a typical electrostatic impingement device for collecting particulate matter from ambient air or another gas source. In order to determine the concentration of particulate matter in the gas source sampled, additional equipment, discussed previously, must be used to determine the flow rate of the gas sampling system, or the total volume of source gas from which the particulates were extracted. Then, the total weight of particulate matter collected must be determined by weighing.

The principle of operation of the electrostatic impingement apparatus is that of electrostatic attraction. The electrostatic impingement surface is given an electrostatic charge of polarity opposite to the polarity (positive or negative) of the particles in question.


Centrifugal Force

A typical particulate matter collector that operates on the principle of centrifugal force is shown in Figure 6-9. This device accepts the sample of particulate-laden air, which can be ambient air, stack gas, or another gas stream, and directs it through a circular path on its way to the outlet. In traveling the circular path, particulates are forced, by centrifugal action, into the collection device shown. As with other particulate collection devices, equipment to measure the flow rate of sample taken, or total volume from which the particulates were extracted, must be used to enable calculation of particulate matter concentration.

Dry Impingement

Figure 6-7 shows a "sample train" that contains four impingers. These impingers can be

Figure 6-7 Particulate sampling train.






Figure 6-8 Schematic of a typical electrostatic impingement collector.

used either wet or dry and can be used to collect particulates from ambient air or stack gases or particulates from other gas streams.

Wet Impingement

Wet impingement methods for collecting particulate samples from ambient air, a stack emission, or another gas train operate by trapping the particulates in a liquid solution. The total weight of particulate matter is then determined by filtration and weighing the entire volume of the liquid, or by evaporating the liquid and weighing. A volume of fresh liquid is also evaporated, and the residual (if any) is weighed and compared to the weight of the dried sample to determine the actual weight of particulate matter. Again, equipment to measure the sample flow rate or the total volume sampled is necessary in order to determine particulate concentration.

Impaction

Figure 6-10 shows a schematic of a typical impaction particulate collector. The principle

on which this collection device operates is that of entrapment on a plate having a film of sticky material on its surface. Collection of pollen for assay purposes makes use of this type of equipment.

Particulates can be physically extracted from glass fiber filters or from the other collection devices for analysis as to individual constituents, such as metals, radioactive elements, or other materials. The analyst should consult the appropriate Code of Federal Regulations to determine acceptable procedures.

Figure 6-11 presents a schematic example of a stack sampling system and illustrates several of the methods employed for data management.




Figure 6-9 Schematic diagram of a centrifugal particle collector.




Figure 6-10 Schematic of a typical impaction particle collector.




Figure 6-11 Continuous monitoring system.

Sample Analysis

Although it is realized that, once a sample is collected, it is subject to change as a result of chemical reaction, chemical degradation, absorption or adsorption onto the walls of the container or to other substances in the container, or other phenomena, not much is presently known with certainty about how much change takes place in a sample once it is collected. Therefore, it is extremely important to perform the chemical or other analyses as soon as possible after the samples are collected.

Ambient Air Sampling

Determination of the quality of ambient air as it relates to the presence and concentration of substances regarded as pollutants is the objective of ambient air sampling. The specialized devices and techniques for carrying out this task have been developed over half a century. Here, again, obtaining representative samples is a major objective of the work plan. Decisions to be made, which must strike a balance between the cost of the characterization program and the value of the data, include the duration of the sampling period, number of discrete samples taken, the size of each sample, and the number of substances sampled for.

Particulate matter in ambient air is measured by use of a "high-volume sampler," which is an integrated filter holder–vacuum pump (high-volume). A glass fiber filter is held in the filter holder, and a high flow rate of ambient air is drawn through it over a measured period. Calculations of particulate matter concentration in the ambient air are carried out using the weight of particulate matter collected on the filter and the flow rate (or total volume) of air drawn through the filter.

Air Pollutants

The following paragraphs present a brief discussion of the major air pollutants that are regulated by the *Clean Air Act*, as amended.

Air Toxics

Control of the release of so-called air toxics took on a new importance, in fact, a dominant importance, with promulgation of *Title III of the 1990 Clean Air Act Amendments (CAA)*. Previous to these amendments, the EPA had issued standards for only eight hazardous substances over a 20-year period. The 1990 CAA lists 188 substances that must be controlled.

The designated "air toxics" are required to be managed by use of Maximum Achievable Control Technology (MACT). In addition, residual risk after implementation of MACT must be assessed. Industries are also subject to a time schedule, by source category, for implementation of MACT. Seven hundred source categories have been identified, and the EPA was required to have published MACT standards for all source categories, or subcategories, by November 2000. All sources must be in compliance with the applicable standard within a published time schedule.

There are significantly different requirements for sources that qualify as a "major source" compared to those that do not. A "major source" is any stationary source that emits in excess of 10 tons per year of any of the listed 188 hazardous substances, or 25 tons per year or more of any combination of those substances.

The list of 188 "air toxics" includes pesticides, metals, organic chemicals, coke oven emissions, fine mineral fibers, and radionuclides. The EPA is required to add to this list pollutants that may be shown to present, through inhalation or other routes of exposure, a threat of adverse effect on human health or the environment. The EPA may also remove substances from the list if it can be shown that the reasons for placing them on the list were in error.

There are also significantly elevated control requirements for those sources that represent 90% of the area sources that emit the 30 hazardous air pollutants presenting the greatest threat to public health in the largest number of urban areas.

Ozone

Ozone has the chemical formula O_3 and is a relatively strong oxidizing agent. Ozone is emitted directly by some sources and is a product of chemical and/or photochemical reaction between other air pollutants in the atmosphere. Ozone is an irritant and can damage sensitive tissues in animals (including humans) and plant tissues.

Oxides of Sulfur

Sulfur dioxide is the major sulfur oxide of concern in the atmosphere, although sulfur trioxide (SO_3) and sulfate (SO_4) are also important. The primary source of sulfur oxides in the nation's atmosphere is the burning of fossil fuels (oil and coal) for generation of electrical power and heat. Because sulfur is an important component of protein, and protein is an important component of virtually all plants and animals, sulfur is consequently a component of the fossil remains of these once-living entities. When oil or coal are burned, oxygen combines with the sulfur and the resulting sulfur oxides are emitted with the gaseous releases from the combustion process. The principal harmful effects are their eventual reaction with atmospheric moisture and return to the earth as acid rain and their participation in photochemical reactions in the atmosphere to produce smog.

Oxides of Nitrogen (NO_x)

Nitrogen oxides, principally nitrogen dioxide, NO_2 , and nitric oxide, NO , are produced during the combustion of all types of fuels. These gases are referred to together as NO_x . Because air consists of nitrogen in the N_2 gas form, and about 21% oxygen in the O_2 gas form, there is an unlimited supply of both nitrogen and oxygen available to react with each other, which they will do at elevated temperatures.

The other source of nitrogen that results in the formation of significant amounts of NO_x is the nitrogen content of the fuel itself. For instance, Number 6 fuel oil typically contains from 3% to 7% by weight of nitrogen. It has

been observed that the NO_x content of stack gases increases linearly with a linear increase in the nitrogen content of the fuel oil. It is therefore to be concluded that (1) the nitrogen content of fuel oil is converted to NO_x during the combustion process, and (2) a reasonable strategy for helping to comply with limits on NO_x emissions is to obtain and burn fuel oil having relatively low nitrogen content.

The source of nitrogen in fossil fuels is similar to that of sulfur; namely, the living tissue from which the fossil remains were derived. All living entities, since life began, have had deoxyribonucleic acid (DNA), ribonucleic acid (RNA), and protein materials as key components. Nitrogen has always been a component of these three substances, and the fossil remains contain nitrogen as well.

The principal harmful effect of the nitrogen oxides is their reaction with atmospheric hydrocarbons and other substances to form smog.

Carbon Monoxide (CO)

Carbon monoxide is the product of incomplete combustion of organic matter, including fossil fuels. Whereas complete combustion of material composed of organic carbon produces carbon dioxide, CO_2 , incomplete combustion caused by inadequate supply of oxygen results in the production of some carbon monoxide, CO . Carbon monoxide is hazardous to the health of humans and other animals.

Carbon Dioxide (CO_2)

Carbon dioxide is a product of complete combustion. The principal sources of carbon dioxide in the atmosphere are the respiration of plants, animals, and microorganisms that use oxygen as an electron acceptor, and the burning of fossil and other fuels for generation of heat and power.

The principal harmful effect of carbon dioxide in the atmosphere is its contribution, along with methane, to the promotion of global warming, caused by the so-called greenhouse effect.

Particulates

Particulates, known as “fine particulate matter,” or “PM10,” are very small particles of any substance. The harmful effects of particulates are their tendency to lodge in the lungs and their objectionable effect on visibility.

The sources of particulate matter in the atmosphere are many and varied. Every time something is burned, particulate matter is generated and released. Wind generates particulate matter by blowing dust and other particulates from places of deposition into the ambient air. Automobiles and moving heavy equipment disturb land and generate airborne particulate matter.

Volatile Organic Carbon Compounds (VOCs)

Volatile organic carbon compounds (VOCs) are a class of chemicals that are emitted directly to the air as a result of evaporation or another type of volatilization. Sources include stored gasoline, stored solvents and other industrial chemicals, and certain industrial processes. Incomplete combustion of fuels of many types is also an important source of VOC discharge to the ambient air.

The principal harmful effects of VOCs are toxicity, possible contribution to smog via photochemical reactions in the atmosphere, and possible contribution to the “greenhouse effect” and consequent global warming.

Malodorous Substances

There are many substances, including compounds of sulfur in the reduced state, such as hydrogen sulfide, methyl and ethyl mercaptans, and dimethyl sulfide, and degradation products of proteins, such as amines, amides, putricine, and cadaverine, that have extremely objectionable odors. Many of these compounds can be detected by the human olfactory apparatus in atmospheric concentration ranges of only a few parts per billion by volume. Although their common objectionable property is their bad smell, some of them are toxic.

Hydrogen Sulfide (H_2S)

Hydrogen sulfide (H_2S) is toxic as well as malodorous. Worse yet, it has the characteristic of being able to desensitize the olfactory apparatus in a few minutes if the concentration is higher than a few parts per billion by volume. Persons who have entered confined spaces containing hydrogen sulfide gas have died because soon after entering the space they were unable to smell the H_2S , did not realize they were breathing it, and were overcome by a fatal dose.

Other Reduced Sulfur Compounds

A reduced sulfur compound is a chemical substance of low molecular weight that contains one or more sulfur atoms in the minus two (sulfide) valence state. These substances, along with hydrogen sulfide, are referred to in the aggregate as total reduced sulfur (TRS). Many air discharge permits contain restrictions on TRS. Some TRS compounds are toxic. All are objectionable because of their extremely strong, foul odors.

Common sources of hydrogen sulfide and other reduced sulfur compounds include tanneries, rendering plants, Kraft pulp mills, and malfunctioning POTWs.

Organics

Several categories of organic material are regulated through restrictions contained in air discharge permits.

Hydrocarbons

Low-molecular-weight organic compounds consisting of carbon and hydrogen are discharged to the air as a result of incomplete combustion of fossil fuels, including gasoline, and via evaporation. These substances undergo photochemical reactions with other substances in the atmosphere to form smog.

Methane

Methane, the lowest-molecular-weight hydrocarbon, enters the atmosphere as a result of natural gas extraction, coal extraction,

management of solid waste, anaerobic degradation of organic material in the natural environment, and the gaseous expulsions of cattle and other animals associated with agriculture.

The principal harmful effect of methane released to the atmosphere is its contribution, along with carbon dioxide, to the cause of global warming, or the “greenhouse effect.”

Sampling Methods for Air Toxics

Compliance with the requirements of *Title III of the CAA* is based on the implementation of specified (MACT) control technologies, as opposed to the sampling and analyses of discharges; however, sampling and analysis work is required to determine whether or not one or more of the 189 listed substances are present in the discharge. This information is needed, in some cases, to determine whether or not a given MACT must be installed.

The *CAA* contains no guidance as to what methodologies are acceptable for sampling and analyzing for some of the air toxics. As a result, it is common to use the sampling and analysis methods acceptable to the industrial hygiene profession.

Characteristics of Solid Waste Streams from Industries

The *Resource Conservation and Recovery Act*, (*RCRA*), as amended, is the primary law governing the handling, transportation, and disposal of solid and hazardous wastes. The law is contained in its entirety, including the regulations that specifically regulate the sampling and analyses of hazardous and non-hazardous solid waste streams, in volume 40 of the *Code of Federal Regulations*. Subtitles *C* and *D* are addressed to the management of hazardous and nonhazardous wastes, respectively.

Hazardous Wastes

Any industrial facility that generates 100 kilograms of hazardous waste or 1 kilogram of acutely hazardous waste per month is

considered a “generator” and must manage those wastes in compliance with the requirements of Subtitle *C*. A very important first order of business, then, is to determine whether or not a given industrial facility qualifies as a “generator,” a situation that could change at any time because of changes in raw materials used, production chemicals and other materials used, manufacturing processes, and even changes in state or federal laws and/or regulations.

RCRA defines hazardous wastes in terms of specific properties. According to *RCRA*, a solid waste is hazardous if it meets one of three conditions and is not excluded from regulation as a hazardous waste:

1. Exhibits, on analysis, any of the characteristics of a hazardous waste
2. Has been named a hazardous waste and appears on an appropriate list
3. Is a mixture containing a listed hazardous waste and any other solid waste material

RCRA has identified four characteristics that, if exhibited by a solid waste, designates it as a hazardous waste:

- Ignitable
- Corrosive
- Reactive
- Toxic

These four characteristics are described as follows:

Ignitable

- A liquid, except aqueous solutions containing less than 24% alcohol, that has a flash point of less than 60°C (140°F).
- A substance that is ignitable per Department of Transportation (DOT) regulations.
- An oxidizer per DOT regulations.
- Examples of ignitable substances are waste solvents, paints, and some waste oils.

Corrosive

- An aqueous material having a pH less than 2.0 or greater than 12.5.

- A liquid that corrodes steel at a rate greater than one-quarter inch per year at a temperature of 55° C (130° F).
- Examples of corrosive wastes are automobile battery acid and waste pickle liquor from the manufacturing of steel.

Reactive

- Reacts violently with water.
- Normally unstable and reacts violently without detonating.
- Generates toxic gases, vapors, or fumes on mixing with water.
- Forms an explosive mixture with water.
- Contains cyanide or sulfide and generates toxic gases, vapors, or fumes at a pH of between 2.0 and 12.5.
- Capable of detonation if heated under confinement or subjected to a strong detonating force.
- Capable of detonation at standard temperature and pressure.
- Listed as a Class A or B explosive by DOT.

Toxic

The Toxic Characteristic Leaching Procedure (TCLP) test was developed as a method for determining whether a waste material, after being placed in a landfill, would leach metals or other substances at rates greater than what was considered acceptable. The TCLP test attempts to simulate “worst-case” landfill leaching conditions, where low pH precipitation (acid rain) would percolate down through the landfilled wastes and cause metals to dissolve into solution.

In performing the TCLP test, the material to be landfilled is first pulverized to particle sizes no larger than 1 mm in diameter. Then, 5.0 grams of the solid phase of the waste is placed in a 500-ml beaker or Erlenmeyer flask; 96.5 ml of “reagent water” (deionized water) is added, the beaker or flask is covered with a watchglass, and the mixture is stirred vigorously for 5 minutes. This procedure is normally

carried out in a beaker, with a magnetic stirrer keeping the granules of waste material suspended and well mixed with the reagent water.

After 5 minutes of stirring, the pH of the mixture is determined. If the pH is below 5.0, the mixture is subjected to the specified extraction procedure using “extraction fluid #1,” prepared by mixing 5.7 ml glacial acetic acid, 500 ml of reagent water, and 64.3 ml 1N sodium hydroxide. The pH of this mixture is 4.93 ± 0.05 . If the pH of the mixture of pulverized waste and reagent water (after mixing for 5 minutes) is higher than 5.0, the mixture is subjected to the specified extraction procedure using extraction fluid #2, prepared by diluting 5.7 ml glacial acetic acid to a volume of 1 liter with reagent water. Extraction fluid #2 has a pH of 2.88 ± 0.05 , is thus a stronger acid solution than extraction fluid #1 (no sodium hydroxide is added during preparation of extraction fluid #2), and will more strongly dissolve metals from the waste material.

It is very important that the instruction “cover with a watchglass” be followed because carbon dioxide gas will either escape from, or dissolve into, the mixture, causing the pH to change and possibly resulting in the requirement to use the stronger extraction solution. Analysts sometimes do not use the watchglass in order to enable leaving pH probes in the mixture during the stirring process.

After the extraction process has been carried out, the extract is analyzed for suspected or possible substances. If the results of this analysis show that any of the substances are present in the extract in an amount exceeding the published limit, the waste is deemed to be “hazardous” and must be handled and disposed of in accordance with all the applicable hazardous waste laws and regulations.

Exemptions

Certain materials under certain circumstances have been specifically exempted from having to be handled and disposed of as hazardous waste. When applicable conditions are met, these exempted materials can be handled and disposed of as ordinary solid wastes.

Delisting

Some solid wastes can be removed from the “hazardous waste” category by going through a process that enables the waste to be “delisted.” Any generator or waste handler can petition the EPA to exclude a listed waste from regulation under Subtitle C. The petitioner must prove to the EPA that, because of facility-specific differences in raw materials, processing, or other factors, the waste is not hazardous and will not pose a risk to persons, animals, or the environment. If the EPA, after examining all other factors in addition to those cited by the petitioner, finds no reason for not delisting the waste, the waste may be handled and disposed of as ordinary solid waste as regulated under 40 C.F.R., *Subtitle D*. It is noted here that the delisting process can be time consuming and expensive. Delisting is typically sought for high-volume waste streams.

Cradle-to-Grave Manifesting

A significant requirement for all hazardous wastes subject to the regulations of Subtitle C is that they be accompanied by a written document called a manifest. Figure 6-12 shows an example of the standard form titled “Uniform Hazardous Waste Manifest.” The generator of any hazardous waste must initiate the manifest by writing in the appropriate information. If the waste is hauled away from the generator’s facility by a second party, the hauler assumes possession of and responsibility for the manifest, although the generator retains a copy. Then, when the waste reaches the place of ultimate treatment, storage, or disposal (the grave) the manifest again changes hands, with the hauler retaining a copy.

As shown on the standard form presented in Figure 6-12, information contained on the completed manifest includes the following:

- Name and EPA identification number of the generator, the hauler(s), and the facility where the waste is to be treated, stored, or disposed
- U.S. EPA and U.S. DOT descriptions of the waste

- Quantities
- Complete address of the treatment, storage or disposal facility

In addition, the manifest must certify that the generator has in place a program to reduce the volume and toxicity of hazardous wastes, to the degree that is economically practicable, as determined by the generator, and that the treatment, storage, or disposal method chosen by the generator minimizes the risk to human health and the environment.

Once the waste is delivered to the final place of disposition (treatment, storage, or disposal facility), the owner or operator of that facility must sign the manifest, retain a copy, and return a copy to the generator of that waste. If 35 days pass from the date on which the waste was signed for by the initial transporter and the generator has not received a copy of the manifest from the final site of disposition, the generator must contact the initial transporter to determine the fate of the waste. If 45 days pass and the generator still has not received a copy of the manifest, the generator must submit an exception report.

Nonhazardous Solid Wastes from Industries

Some industrial solid wastes can be disposed of in municipal solid wastes landfill facilities (MSWLFs). The federal law that governs such disposal is contained in its entirety in 40 CFR part 258. (Part 257 contains the provisions for hazardous wastes.) Within part 257, “industrial solid waste” means solid waste generated by manufacturing or industrial processes that is not a hazardous waste regulated under Subtitle C of RCRA. Such waste may include, but is not limited to, waste resulting from electric power generation, fertilizer/agricultural chemicals production, food and related products or by-products production, inorganic chemicals manufacturing, iron and steel manufacturing, leather and leather products production, nonferrous metals manufacturing, organic chemicals production, plastics and resins manufacturing, pulp and paper manufacturing,

Please print or type (Form designed for use on elite (12 - pitch) typewriter) Form Approved. OMB No. 2050 - 0039 Expires 9 - 30 - 91

UNIFORM HAZARDOUS WASTE MANIFEST		1. Generator's US EPA ID No.	Manifest Document No.	2. Page 1 of	Information in the shaded areas is not required by Federal law	
3. Generator's Name and Mailing Address				A. State Manifest Document Number		
				B. State Generator's ID		
4. Generator's Phone ()						
5. Transporter 1 Company Name		6. US EPA ID Number		C. State Transporter's ID		
				D. Transporter's Phone		
7. Transporter 2 Company Name		8. US EPA ID Number		E. State Transporter's ID		
				F. Transporter's Phone		
9. Designated Facility Name and Site Address		10. US EPA ID Number		G. State Facility's ID		
				H. Facility's Phone		
11. US DOT Description (Including Proper Shipping Name, Hazard Class, and ID Number)				12. Containers No.	13. Total Quantity	14. Unit Wt/Vol
a.						1. Waste No.
b.						
c.						
d.						
j. Additional Descriptions for Materials Listed Above				k. Handling Codes for Wastes Listed Above		
15. Special Handling Instructions and Additional Information						
16. GENERATOR'S CERTIFICATION: I hereby declare that the contents of this consignment are fully and accurately described above by proper shipping name and are classified, packed, marked, and labeled, and are in all respects in proper condition for transport by highway according to applicable international and national government regulations. If I am a large quantity generator, I certify that I have a program in place to reduce the volume and toxicity of waste generated to the degree I have determined to be economically practicable and that I have selected the practicable method of treatment, storage, or disposal currently available to me which minimizes the present and future threat to human health and the environment; OR, if I am a small quantity generator, I have made a good faith effort to minimize my waste generation and select the best waste management method that is available to me and that I can afford.						
Printed/Typed Name				Signature		
				Month Day Year		
17. Transporter 1 Acknowledgement of Receipt of Materials						
Printed/Typed Name				Signature		
				Month Day Year		
18. Transporter 2 Acknowledgement of Receipt of Materials						
Printed/Typed Name				Signature		
				Month Day Year		
19. Discrepancy Indication Space						
20. Facility Owner or Operator: Certification of receipt of hazardous materials covered by this manifest except as noted in item 19.						
Printed/Typed Name				Signature		
				Month Day Year		

EPA Form 8700 - 22 (Rev. 9 - 88) Previous editions are obsolete.

Figure 6-12 Uniform Hazardous Waste Manifest.

rubber and miscellaneous plastic products manufacturing, stone, glass, and concrete products manufacturing, textile manufacturing, transportation equipment manufacturing, and water treatment. Not included are wastes resulting from mining or oil and gas production.

MSWLFs are required by Subtitle D regulations to have, as a minimum, a liner system composed of a single composite liner that is part of a leachate collection and removal system. A low-permeability cover must be installed when the landfill reaches maximum capacity. In addition, a groundwater monitoring system must be used to detect liner failure during the 30-year mandated post-closure care period.

States may promulgate laws and regulations that are more restrictive than the federal laws and regulations. Again, the owner of the facility is responsible for determining which set of laws and regulations is the most restrictive and should be used as the basis for design of discharge control equipment.

Bibliography

- American Society for Testing and Materials, *A Standard Guide for Examining the Incompatibility of Selected Hazardous Waste Based on Binary Chemical Mixtures*, Philadelphia, Pennsylvania, 1983.
- De Renzo, D.J., *Solvent Safety Handbook*, Noyes Publications, Park Ridge, NJ, 1986.
- Dyer, J.C., A.S. Vernick, and H.D. Feiler, *Handbook of Industrial Wastes Pretreatment*, Garland STPM Press, New York, 1981.
- Flick, E.W., *Industrial Solvents Handbook*, 3rd ed., Noyes Publications, Park Ridge, New Jersey, 1985.
- Grant, D.M., *Open Channel Flow Measurement Handbook*. Instrumentation Specialties Co., Lincoln, Nebraska, 1979.
- Harris, J.P., and S.A. Kacmar, "Flow Monitoring Techniques in Sanitary Sewers," *Deeds and Data*, Water Pollution Control Federation, July 1974.
- Higgins, I.J., and R.G. Burns, *The Chemistry and Microbiology of Pollution*, Academic Press, New York, 1975.
- Jain, R.K., L.V. Urban, G.S. Stacey, and H.E. Balbach, *Environmental Assessment*, McGraw-Hill, New York, 1993.
- Leupold and Stevens, Inc., *Stevens Water Resources Handbook*, Beaverton, OR, 1975.
- The Merck Index*, 9th ed., Merck and Co., Inc., Rahway, New Jersey, 1976.
- Merrill, W.H. Jr., "Conducting a Water Pollution Survey," *Plant Engineering*, October 15, 1970.
- Merrill, W.H. Jr., "How to Conduct an Inplant Wastewater Survey," *Plant Engineering*, January 7, 1971.
- Sax, N.I., *Dangerous Properties of Hazardous Materials*, 6th ed., Van Nostrand Reinhold, New York, 1984.
- Shelley, P.E., *Sampling of Wastewater*, U.S. Environmental Protection Agency, Technology Transfer, June 1974.
- Shelley, P.E., *An Assessment of Automatic Sewer Flow Samplers*, U.S. Environmental Protection Agency, Office of Research and Monitoring, EPA-R2-73-261, June 1973.
- Shelley, P.E., and G.A. Kirkpatrick, "Sewer Flow Measurement—A State of the Art Assessment," EPA 600/2-75-027, 1975.
- Sittig, M., *Handbook of Toxic and Hazardous Chemicals and Carcinogens*, 2nd ed., Noyes Publications, Park Ridge, New Jersey, 1985.
- Sittig, M., *Priority Toxic Pollutants—Health Impacts and Allowable Limits*, Noyes Publications, Park Ridge, New Jersey, 1980.
- Standard Methods for the Examination of Water and Wastewater*, 20th ed., American Public Health Association, New York, 1998.
- Thompson, R.G., "Water-Pollution Instrumentation," *Chemical Engineering*, June 21, 1976, pp. 151–154.
- U.S. Department of the Interior, *Methods for Collection and Analysis of Water Samples for Dissolved Minerals and Gases*, Techniques of Water Resources Investigations of the United States Geological Survey, Book 5, Chapter A1, 1970.

- U.S. Department of the Interior, Bureau of Reclamation, *Water Measurement Manual*, Denver, Colorado, 1979.
- U.S. Environmental Protection Agency, *Manual of Methods for Chemical Analysis of Water and Wastes*, Methods Development and Quality Assurance Research Laboratory, National Environmental Research Center, Cincinnati, Ohio, 1974.
- U.S. Environmental Protection Agency, *Method for Chemical Analysis of Water and Waste*, EPA 600/4-79/020, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, "Announcement of the Drinking Water Contaminant Candidate List," 63 FR 10273, U.S. Government Printing Office, Washington, D.C., March 1998.
- U.S. Environmental Protection Agency, "Designation of Hazardous Substances," Code of Federal Regulations, Title 40, Part 116, U.S. Government Printing Office, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, "Drinking Water Program Redirection Strategy," Office of Water, EPA 810-R-96-003, Washington, D.C., June 1996.
- U.S. Environmental Protection Agency, "General Provisions for Effluent Guidelines and Standards," Code of Federal Regulations, Title 40, Part 401, U.S. Government Printing Office, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, "Guidelines Establishing Procedures for Analysis of Pollutants," Code of Federal Regulations, Title 40, Part 136, U.S. Government Printing Office, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, "Hazardous Waste Management System: General," Code of Federal Regulations, Title 40, Part 260, U.S. Government Printing Office, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, "Identification and Listing of Hazardous Waste," Code of Federal Regulations, Title 40, Part 261, U.S. Government Printing Office, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, "Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," Code of Federal Regulations, Title 40, Part 265, U.S. Government Printing Office, Washington, D.C., 1987.
- U.S. Environmental Protection Agency, "National Primary Drinking Water Regulations," Code of Federal Regulations, Title 40, Part 141, U.S. Government Printing Office, Washington, D.C., 1975.
- U.S. Environmental Protection Agency, "National Secondary Drinking Water Regulations," Code of Federal Regulations, Title 40, Part 143, U.S. Government Printing Office, Washington, D.C., 1988.
- U.S. Environmental Protection Agency, "Standards Applicable to Transporters of Hazardous Waste," Code of Federal Regulations, Title 40, Part 263, U.S. Government Printing Office, Washington, D.C., 1986.
- U.S. Environmental Protection Agency, "Toxic Pollutant Effluent Standards," Code of Federal Regulations, Title 40, Part 129, U.S. Government Printing Office, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, "Standards Applicable to Generators of Hazardous Waste," Code of Federal Regulations, Title 40, Part 262, U.S. Government Printing Office, Washington, D.C., 1980-1987.
- U.S. Environmental Protection Agency, *A Method for Determining the Compatibility of Hazardous Wastes*, Office of Research and Development, EPA 600/12-80/076, Cincinnati, Ohio, 1980.
- U.S. Environmental Protection Agency, *Analytical Methods for Determination of Asbestos Fiber in Water*, Washington, D.C., 1983.
- U.S. Environmental Protection Agency, *Handbook for Monitoring Industrial Wastewater*, Technology Transfer, August 1973.
- U.S. Environmental Protection Agency, *Handbook for Monitoring Industrial Wastewater*, Technology Transfer, Washington, D.C., 1973.

- U.S. Environmental Protection Agency, *Handbook for Sampling and Sample Preservation of Wastewater*, EPA 60014-82/029, Washington, D.C., 1982.
- U.S. Environmental Protection Agency, *Handbook for Sampling and Sample Preservation of Water and Wastewater*, Office of Research and Development, Environmental Monitoring and Support Laboratory, EPA 60014-82/029, Cincinnati, Ohio, 1982.
- U.S. Environmental Protection Agency, *Microbiological Methods for Monitoring the Environment*, EPA 60018-78/017, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, Office of Public Awareness, "Hazardous Waste Information," SW-737, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, Office of Water and Waste Management, "Hazardous Waste Information—Identification and Listing," SW-850, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, Office of Water and Waste Management, "Hazardous Wastes Information—Transporters," SW-830, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, Office of Water and Waste Management, "Hazardous Waste Information—Facility Permits," SW-852, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, Office of Water and Wastes Management, "Hazardous Wastes Information—Generators," SW-839, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, *Samplers and Sampling Procedure for Hazardous Waste Streams*, EPA 60012-80/018, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, *Sampling and Analysis Procedure for Screening of Industrial Effluents for Priority Pollutants*, Effluent Guidelines Division, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Test Methods for Evaluating Solid Waste—Physical/Chemical Methods*, 2nd ed., SW-846, Washington, D.C., 1985.
- U.S. Environmental Protection Agency, *Water Quality Standards Handbook, Second Edition*, EPA 823-B-94-005a, Washington, D.C., 1994.
- U.S. Environmental Protection Agency, "Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," Code of Federal Regulations, Title 40, Part 264, U.S. Government Printing Office, Washington, D.C., 1980–1987.
- Vernick, A.S., "How to Conduct a Wastewater Survey," *Plant Engineering*, July 7, 1977.
- Vernick, A.S., "How to Conduct a Wastewater Survey," *Plant Engineering*, August 4, 1977.
- Weiss, G., *Hazardous Chemical Data Book*, 2nd ed., Noyes Publication, Park Ridge, New Jersey, 1986.

7 Pollution Prevention

Wastes minimization has been a primary objective of wastewater, air discharge, and solid wastes management since the earliest days of industrial wastes treatment. Many academic programs have taught, either overtly or inadvertently, that the first duty of an environmental engineer is to reduce, to an absolute minimum, those pollutants that require treatment before discharge. The ultimate goal, of course, is “zero discharge,” as required in the United States by the 1972 amendments to the *Clean Water Act* (*Public Law 92-500*).

What has not been included in many of the environmental engineering curricula is the concept of decreasing overall costs with a consequent increase in profitability as a result of reducing wastes generation. During the 1980s, the U.S. Congress authorized in-depth studies of the financial impacts on U.S. businesses and industries of wastes minimization and other activities related to reducing the quantity of pollutants released to the environment. The result was the development of the concept of pollution prevention.

Pollution prevention includes all of the aspects of wastes minimization, whereby pollutants are generated during the manufacturing process, plus all of the effects of the product throughout its life cycle from initial product development to final disposal. Minimization of the flows and loads, and especially the toxicity, of wastes discharged from any industrial facility to the atmosphere, the nation’s water bodies, or the land are to be considered in all contexts of the life cycle of any given product. Existing processes and facilities must minimize flows and loads wherever possible, and non-toxic substances must be substituted for toxic substances wherever possible.

The “findings and policy” that resulted from the investigative work on these matters is stated in Chapter 133, “Pollution Prevention,” of Title 42 of the *United States Code of Federal*

Regulations, and is quoted (as of January 2000) as follows.

§ 13101. Findings and Policy

Findings

The Congress finds that:

1. The United States of America produces millions of tons of pollution and spends tens of billions of dollars per year controlling this pollution.
2. There are significant opportunities for industry to reduce or prevent pollution at the source through cost-effective changes in production, operation, and raw materials use. Such changes offer industry substantial savings in reduced raw material, pollution control, and liability costs as well as help protect the environment and reduce risks to worker health and safety.
3. The opportunities for source reduction are often not realized because existing regulations, and the industrial resources they require for compliance, focus upon treatment and disposal, rather than source reduction; existing regulations do not emphasize multi-media management of pollution; and businesses need information and technical assistance to overcome institutional barriers to the adoption of source reduction practices.
4. Source reduction is fundamentally different and more desirable than waste management and pollution control. The Environmental Protection Agency needs to address the historical lack of attention to source reduction.
5. As a first step in preventing pollution through source reduction, the Environmental Protection Agency must establish

a source reduction program, which collects and disseminates information, provides financial assistance to States, and implements the other activities provided for in this chapter.

Policy

The Congress hereby declares it to be the national policy of the United States that pollution should be prevented or reduced at the source whenever feasible; pollution that cannot be prevented should be recycled in an environmentally safe manner, whenever feasible; pollution that cannot be prevented or recycled should be treated in an environmentally safe manner whenever feasible; and disposal or other release into the environment should be employed only as a last resort and should be conducted in an environmentally safe manner.

During the 1990s, it became well-established that conscientious application of pollution prevention, including all of the influences and activities and their costs, resulted in increased profitability to industries and the business community as a whole, rather than a net cost. Environmental engineers, environmental scientists, and all others in the field of environmental protection are obliged to bear this message to clients, regulators, the business community, and the general public. It must be realized that emissions of all forms (i.e., water pollutants, air pollutants, or solid wastes) are, in fact, materials that have been paid for as raw materials, and that the emission represents an actual loss. The cost of environmental protection cannot be viewed as simply the cost to treat and dispose. It is the net cost (or, rather, the net result of complete accounting) after complete accounting for costs and savings resulting from recycle and reuse and costs not expended for treatment and disposal. For instance, a pound of hydrocarbon that might have gone out the stack at a power-generating station was previously paid for as a pound of coal or oil. If it can be for as a pound of coal

or oil. If it can be captured and burned, rather than lost as a consequence of less than 100% combustion performance of the burner, the cost for a pound of fuel is saved plus the cost for treating to prevent the hydrocarbon from being emitted from the stack and becoming air pollution.

General Approach

Whenever a pollution prevention program is implemented in an existing industrial facility, whether for its own sake or because of changing discharge requirements, or the need for significant upgrade or retrofit work on the end-of-pipe treatment system, the general approach that has become recognized as standard includes the following key elements:

1. Unequivocal support from top management
2. An explicit scope and clear objectives
3. An accurate cost accounting system
4. A companywide philosophy of waste minimization
5. An effective technology transfer program

Support from Top Management

Any program as far-reaching and all-inclusive of the raw materials, equipment, wastes, and products as a pollution prevention program must have the enthusiastic, active support of the top managers of an industrial facility in order to succeed. In cases when top management has assigned or delegated the "responsibility" for wastes reduction or another comprehensive endeavor, little real progress has resulted. There have been numerous attempts to institute wastes minimization programs in the absence of overt support from top management. Typically, significant progress is made soon after implementation of a program, only to gradually reverse and revert to former wastefulness and inefficiency. The unequivocal and visible support of top management, to the point where those who are instrumental in helping the program succeed are rewarded and those who hinder progress are penalized, is

required to make the paradigm shifts that are needed to implement an effective pollution prevention program.

The key to gaining enthusiastic support of the top management of an industrial facility is to educate those top managers regarding potential increased profitability. Managers must be taught that emissions of “pollutants” are more properly regarded as lost materials that have been paid for. Once pollutants are placed on the accounting ledger as lost resources, their reduction shows up as a smaller loss. Managers must also be coached into realizing that the costs for treatment and disposal of pollutants decreases as the quantity and especially the toxicity of those pollutants decreases. Again, environmental management professionals must carry this message forward and spearhead the paradigm shift from pollution control as a bottomless pit of expense to pollution prevention as a way to increase company profits.

Explicit Scope and Clear Objectives

A clear road map is needed by anyone traveling in unfamiliar territory to ensure that the correct turns are taken and that the travelers do not get lost. Pollution prevention, unfortunately, does not come naturally to everyone involved in industrial production. If it did, the pollution prevention initiative would not exist; it would be unnecessary.

Significant work is involved in developing an explicit scope for a pollution prevention program. In fact, it is best to go through, step by step, at least two successive times, the entire program initially envisioned, in order to develop the scope. The first time through reveals activities that are more difficult than originally thought and opportunities for wastes minimization that were not thought of during concept development. The second iteration is needed as a check on feasibility, value, and completeness.

It is critically important that all of the “stakeholders” be actively involved in development of the scope. The worst approach is for an individual to be assigned the task of developing the scope. Not only will it forever be

regarded as that individual’s demands on the other stake-holders, but worse, the individual assigned the task may not be sufficiently familiar with the industrial processes that create the pollutants as, say, the superintendent of production would be. The entire cast of stakeholders includes all those managers whose work influences the quantity and characteristics of wastes produced. Each and all of those stakeholders must be involved in developing an explicit scope and clear objectives of the pollution prevention program for *their* facility. The team of stakeholders must be completely cross-functional, thus representing all of the activities at the facility that in any way affect the quantity and characteristics of wastes produced. At a typical industrial facility, the stakeholders would include:

- The plant manager
- Middle management
- Operations managers
- Engineering
- Maintenance
- Purchasing
- Environmental management
- Operators of waste treatment systems

The following example explains how purchasing, for instance, can be directly involved in the wastes minimization aspect of pollution prevention. Purchasing is directly involved in communicating with suppliers regarding packaging of items that are delivered to the industrial facility. On one end of the scale there are returnable (and reusable) containers. On the other end of the scale are multilayered, nonrecyclable packages characterized by excessive bulk that must all be discarded and disposed of. For instance, it is not unusual for electronic equipment to be delivered in plastic wrapping, surrounded by foam blocks, packed inside a box, covered by paper, covered in turn by plastic, and all bound by plastic or metal strapping. In many cases, purchasing agents must be guided to “think outside the box” (so to speak) and to demand packaging from suppliers that minimizes creation of solid wastes.

After a detailed scope has been worked out, a clear set of objectives for the pollution prevention program can be developed. Here, it is important to shoot high, but not so high as to intimidate those who will carry out the program. It is imperative that the stated objectives can be understood, achieved, and evaluated by readily understood measurements and comparisons.

Once a clear set of objectives has been developed and measurement methods determined and agreed upon, action must begin and be sustained. Measurements that are truly indicative of success or failure must be taken. "What gets measured gets done" is a good guiding rule. A meaningful reward system should be implemented to acknowledge success and to encourage continuous improvement.

Accurate Cost Accounting System

For a pollution prevention program to be successful, prevailing attitudes that wastes reduction and environmental compliance cost money and cut into company profits must be replaced with an understanding that a well-designed and executed pollution prevention program can reduce costs, add value to the product, and thus bolster company profits. An accounting system that can accurately track all the true costs of production, distribution, and final disposal of the product, as well as the costs of handling and disposal of all wastes (i.e., solid, liquid, and air), is essential to convince both management and production people of the true value of a pollution prevention program.

In order to enable advantageous application of an accurate cost accounting system, an accurate materials balance inclusive of the entire life history of a product is needed. Although this may seem a daunting task, and costly in itself, a materials balance is a necessary ingredient in the total picture of cost effectiveness. It is another example of an investment that leads to significant savings in the long run.

Another necessity is establishing a base-line from which to evaluate the degree of success

or failure of the pollution prevention program. Whatever accounting system is agreed upon must be applied to the facility before implementation of the pollution prevention program. The cost accounting system must also be applied at regular intervals in order to keep track of progress, or lack of progress.

Employing activity-based costing (ABC) to evaluate the degree of success or failure of a given pollution prevention program has been found to be highly advantageous. ABC involves meticulous identification of each of the cost items within the general ledger that are related in any way to a given activity. For example, in identifying all costs related to pollution prevention, the costs for chemicals used in wet scrubbers are identified. Wet scrubbers are part of the air pollution control system; they are, therefore, part of the overall pollution control system, and thus are part of the pollution prevention program. As another example, the proportion of each person's time spent performing duties related to pollution control is determined. Then, that proportion of the individual's salary and benefits is allocated to the pollution prevention program.

Companywide Philosophy of Waste Minimization

In addition to the absolute requirement for unequivocal support from top management for a pollution prevention program to succeed, it is equally important that everyone involved in receiving, preparation, production, packaging, storage, and shipping believe in wastes minimization as a necessary component to the financial success and thus the security of their jobs. As explained later, a pollution prevention program consists of active wastes minimization at each stage of the life of a product, from initial development, through manufacturing, and on to final disposal of the product at the end of its life. Every person involved in every stage of the product has an influence on the efficiency of use of raw materials, leaks and spills, clean-up, and damage to raw materials, intermediate stages, or final product, and containment of wastes. A

pervasive, companywide belief in the direct influence of a well-executed pollution prevention program on the security of each person's job is needed for success of the program.

An Active Technology Transfer Program

New technology is being developed and brought to light through various publications on a continuing basis. New and improved techniques and technologies for enhancing efficiencies in product production, materials handling, substitution of nontoxic substances for toxic substances, and wastes handling and disposal can significantly aid in furthering the objectives of a pollution prevention program. Key participants in an industry's pollution prevention program should attend seminars, short courses, and regional and national meetings at which new techniques and technologies are presented. These key participants should then hold in-house seminars and meetings in which the new information is shared with other participants in the pollution prevention program.

Source Reduction

There are two types of wastes minimization that should take place at the source of their generation to further the goals of a pollution prevention program:

1. Minimize the total quantity, or mass, of wastes.
2. Minimize the toxicity of wastes.

In general, reduction of wastes, both in quantity and toxicity, at the source is done by thorough and intense application of the following techniques:

- Immaculate housekeeping
- Substitution of nontoxic substances for toxic substances
- Changing manufacturing processes and/or equipment
- Recycle (and reuse)
- Waste exchanges

Immaculate Housekeeping

The adjective "immaculate" is used here to emphasize that extra effort, beyond the daily "good" category, is required to achieve and maintain the levels of performance in housekeeping that are expected for an effective pollution prevention program. Constant attention must be given to avoiding leaks through preventive maintenance before they occur. Spills must be minimized and cleaned up immediately if they occur (then an analysis should be conducted to determine why the spill occurred, followed by action taken to prevent the same type of spill from occurring again), and procedures must be developed whereby spills are cleaned using as little water as possible. Also, spill containment and isolation techniques must be devised and continually improved.

A key characteristic of "immaculate" housekeeping is that no leak, spill, or correctable inefficiency occurs more than once. An effective program must be in place, whereby each undesirable occurrence is reported, analyzed, its cause determined, and a corrective action devised and implemented.

Substitution of Materials

There are many, many instances where nontoxic substances can be substituted for toxic substances in industrial processes. Many more substitutions will be available in the future, as research and development efforts produce alternatives to former processes that use toxic materials. Keeping up with these new developments is the purview of the technology transfer program, described previously.

A few highly successful examples of nontoxic or less toxic materials replacing toxic materials throughout industry are as follows:

- The use of ozone, rather than chlorine dioxide, to bleach wood pulp.
- The use of alcohol rather than acid for pickling in the manufacture of copper wire.
- The use of ozone or ultraviolet light rather than chlorine for disinfection.

- The use of water-based rather than oil-based paints. (Eliminates the need for hydrocarbons for clean-up.)
- The use of nonphenolics containing industrial detergents rather than those that contain phenolics.
- The use of water-soluble cleaning agents rather than organic solvents.

Changing Manufacturing Processes and/or Equipment

Many products can be manufactured by use of two or more alternative processes. Often, one of the process types involves the use of substances of less toxicity than the others. In addition, within any single process type, there is usually a choice to make among several sources for the equipment, and one type may be more desirable from a pollution prevention standpoint than others. For instance, an item of equipment that is air-cooled might perform as well as an item that is water-cooled, and would thus preclude the need to discharge wasted cooling water. Of course, it should be ascertained that the air used to cool the equipment would not become degraded in quality before a decision is made regarding replacement.

In cases where equipment is old, worn, and subject to leaks, spills, and inefficient use of materials, it might be cost effective to replace it, based on the savings in cost of materials, cost of operation, and cost of handling and disposing of the wastes. Here, again, a comprehensive and accurate materials balance around the entire life cycle of the product, from initial development to final disposal, is needed to make the correct decisions.

Cleaning is one of the processes within an industrial system that almost always produces wastes that must be handled and disposed of. Often, the clean-up wastes contain the same substances as the production wastes, plus whatever substances the cleaning agent(s) are composed of.

Recycle (and Reuse)

Parentheses are placed around the words “and reuse” here because, although it is recognized

that these words have traditionally been used in conjunction with recycle, it is difficult to imagine allowing recycled process water, for instance, to simply pile up after being recycled, for want of being reused. At any rate, recycling of process materials, such as water, after non-consumptive use in one or more processes, is certainly superior to once-through use.

Even if some degree of treatment is required before a second or many reiterative uses, that may be much less costly than the once-through-use approach. The quality of water, in terms of conventional and/or priority or other pollutants, may not need to be nearly as “good” for the industrial process as for discharge within compliance regarding an NPDES or other permit. Therefore, treatment for recycle purposes might be less costly than treatment for discharge.

Additionally, if the plant’s freshwater supply has to be treated before use in the process, it might be less expensive to treat the wastewater and reuse it rather than treat the wastewater for discharge, in addition to treating more fresh water for once-through use.

There is a limit to the extent to which water, or any other substance, can be recycled because water evaporates and leaves non-volatile substances, such as salts, behind. The result is that nonvolatile substances build up, increasing one or more undesirable characteristics such as corrosivity and/or scaling.

Example 7-1 illustrates a methodology for determining the rate of blow-down required to maintain a minimum desired level of water quality for the water undergoing recycle for reuse.

Example 7-1:

The schematic diagram presented in Figure 7-1 shows a water recycle loop in use at a factory. There is a treatment system for removal of organics and TSS; however, dissolved inorganics, such as chlorides, are not removed. These dissolved inorganics, therefore, build up in the recycle loop and can be prevented from building to above a desired maximum concentration only by use of a blow-down, also illustrated in Figure 7-1.




Figure 7-1 Example of a water recycle loop with treatment and blow-down.

Problem:

For a blow-down rate of 10%, calculate the equilibrium concentration of chloride ion in the water in the recycle loop, given the following information:

- Total volume of water in the entire factory recycle loop, including the in-line treatment system, equals 1.0 million gallons.
- Chloride ion (Cl^-) concentration in raw water supply equals 10 mg/L as Cl^- .
- Chloride ion (Cl^-) added by factory equals 90.5 lb/day.
- Zero mg/L Cl^- removed by in-line treatment.
- Blow-down equals 10% equals 100,000 gpd.
- Evaporative loss equals 5% equals 50,000 gpd.

Solution:

Chloride in system on first day:

$$10 \text{ mg/L} \times 8.34 \times 1.0 = 83.4 \text{ lbs}$$

Chloride added each day in makeup water:

$$10 \text{ mg/L} \times 8.34 \times (0.1 + 0.05) = 12.5 \text{ lb/day}$$

Chloride removed each day via blow-down:

$$X \text{ mg/L} \times 8.34 \times 0.1 = 12.5 + 90.5 = 103 \text{ pounds}$$

The concentration, X, of chloride ion in the blow-down must equal the concentration (x) in the recycle loop:

$$X = \frac{103}{8.34 \times 0.1} = 123 \text{ mg/L}$$

Segregation of Waste Streams

In many cases it is advantageous to isolate one (or more) waste streams in an industrial plant and treat it separately from the other waste streams (i.e., gaseous, liquid, or solid, as the case may be) rather than allowing it to mix with other waste streams before treatment. The segregated waste stream can then be treated and recycled, mixed with other treated effluents for discharge to the environment, or

discharged separately. The following are among many advantages of wastes segregation:

- Many substances are readily removed by specialized techniques when they are in the relatively pure and relatively concentrated state but are difficult to remove after being mixed with other substances and diluted by being mixed with other waste streams. For instance, certain organics such as chlorophenols that are very slowly biodegradable are efficiently removed by activated carbon. Treating a waste stream containing these substances at the source may well be more cost effective than mixing with other substances that are biodegradable and on their way to a biological treatment system.
- There is more likelihood of producing a usable by-product from a segregated, relatively pure waste stream.
- There is more likelihood that the stream can be recycled if it has not been mixed with other waste streams.
- The segregated stream can be treated on a batch basis, or other campaign basis, depending on the operating schedule of the process.

Selective Mixing of Waste Streams

A variation of the wastes segregation approach, selective mixing of certain waste streams can take advantage of commonality in compatibility to certain treatment processes. Also, acid waste streams can be mixed with caustic waste streams for mutual neutralization before additional treatment.

Waste Exchanges

One industry's waste might be a valuable resource for another. For instance, waste acid from one industry might be suitable either for a processing step or for neutralization of caustic wastes from another industry. Participation in waste exchanges is an attractive alternative to wastes treatment and disposal. Many networks of business are constantly seeking uses for the wastes they generate. In addition, waste

exchange brokers may be operating in a given industry's geographic area.

The Waste Audit

Whereas an environmental audit (Chapter 6) assesses a company's compliance (or risk of noncompliance) with environmental regulations, and a waste minimization audit assesses opportunities to improve materials utilization efficiency at an operating industrial facility or individual process, a waste audit is a more comprehensive program, conceived to determine each source at which hazardous wastes are generated, from product development through manufacturing, use of the product, and through to the end of the life of the product. The general approach of a wastes audit has two phases. The first is to identify and quantify the types of waste generated and to analyze the manner in which those wastes are generated. The second phase involves performing a materials balance on each of those sources and to determine alternatives for reducing or eliminating those wastes and to analyze the benefits and costs of each alternative. The following step-by-step process outlines the sequence of a wastes audit program.

Phase I

1. Identify the hazardous substances involved in the life cycle of the product being analyzed.
2. Identify all wastes or emissions (i.e., air, liquid, and solid) from initial product development through manufacturing to final disposal of product.
3. Identify each waste stream at each stage of the life of the product.
4. Identify the sources of these hazardous substances.

Phase II

1. Quantify each source and perform a comprehensive materials balance around each stage of the life of the product.

2. Prioritize the sources.
3. Analyze the technically and economically feasible alternatives for eliminating or minimizing those source waste streams by:
 - a. elimination of the source
 - b. substitution of nonhazardous for hazardous substances
 - c. improved housekeeping
 - d. increased efficiency of use of materials
4. Perform a life cycle cost-benefit analysis on the complete set of feasible alternatives.

Summarized Procedure for Achieving Reduction of Wastes at the Source

Figure 7-2 presents a flowchart that summarizes a methodology for achieving effective reduction of wastes at the source. This flowchart is a modified version of the flowchart titled "The Waste Minimization Procedure," presented in the EPA's Waste Minimization Opportunity Manual.

Once a need to minimize wastes is fully recognized by top management, the focus of wastes discharge reduction is moved from the end-of-pipe treatment back into the process and process equipment within the plant. Here, the term "end of pipe" is expanded to include air and solid wastes streams as well as wastewater. The next step is to embrace the principles of pollution prevention, which moves the focus another level to include all contributions of wastes to all environmental media (i.e., air, water, land) from initial phases of product development, through manufacturing, to final disposal of the product.

The planning and organization stage may be initiated by staff personnel or top management. Whichever is the case, the first requirement is to obtain the unequivocal commitment and support of top management. The required result of the planning and organization stage is an explicit scope and a clear set of objectives for the waste minimization or source reduction program.

The assessment process can begin only after the Assessment Program Task Force has

completed organization of the process itself and has obtained unequivocal commitment to proceed. The assessment program and the subsequent stage, "feasibility analysis," follow the general procedure outlined previously for a wastes audit.

The product of the wastes audit is a final report presenting details, data, and results of the wastes audit procedure. The feasible options should be discussed in detail, including a full description of each option, the requirements for implementation, and the costs and benefits. Implementation of the option or options finally agreed upon must include a thorough and accurate performance evaluation. An accurate cost accounting system must be in place for this process to produce results of value.

Benefits of Pollution Prevention

In addition to satisfying key policy requirements of federal and state regulatory agencies, an effective pollution prevention program can have major benefits. A new look at existing and traditional production methods can lead to improvements in production efficiencies, reduced costs for treatment and disposal, and reduced risk. Other benefits can include the following:

- Reduced liability as a potentially responsible party (PRP) at off-site final disposal locations
- Improved relations with customers seeking associations with environmentally conscious or "greener" suppliers
- Improved public image
- Increased production capacity
- Reduced costs for handling and storage of wastes

Bibliography

Miller, H., "In-Plant Water Recycling—Industry's Answer to Shortages and Pollution," *Design News—Original Equipment Manufacturer (OEM)*, November 5, 1973, pp. 81–88.




Figure 7-2 Procedure to assess and implement source reduction.

- Schmidheiny, S., Business Council for Sustainable Development (BCSD), *Changing Course: A Global Business Perspective on Development and the Environment*, MIT Press, Cambridge, Massachusetts, 1992.
- U.S. Environmental Protection Agency, *RCRA Waste Minimization National Plan*, EPA 530-D-94-001, Washington, D.C., 1994.
- U.S. Environmental Protection Agency, *Summary of the RCRA Hazardous Waste Minimization National Plan-Draft*, EPA 530-5-94-002, Washington, D.C., 1994.
- U.S. Environmental Protection Agency, *Waste Minimization National Plan*, EPA 530-F-97-010, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, *Waste Minimization Opportunity Assessment Manual*, Hazardous Waste Engineering Research Laboratory, EPA 625/n-88/1003, Cincinnati, Ohio, 1988.
- U.S. Environmental Protection Agency, *Waste Minimization—Environmental Quality with Economic Benefits*, EPA 530-SW-87-026, Washington, D.C., 1987.

8 Methods for Treating Wastewaters from Industry

General

Technologies for treating industrial wastewaters can be divided into three categories: chemical methods, physical methods, and biological methods. Chemical methods include chemical precipitation, chemical oxidation or reduction, formation of an insoluble gas followed by stripping, and other chemical reactions that involve exchanging or sharing electrons between atoms.

Physical treatment methods include sedimentation, flotation, filtering, stripping, ion exchange, adsorption, and other processes that accomplish removal of dissolved and undissolved substances without necessarily changing their chemical structures. Biological methods are those that involve living organisms using organic, or in some instances, inorganic, substances for food, completely changing their chemical and physical characteristics.

Most substances found as pollutants in industrial wastewaters can be categorized as to whether chemical, physical, or biological treatment should be the most appropriate. For instance, dairy wastewater should most appropriately be treated by biological means because the bulk of the pollution load from a typical dairy is organic material from whole milk, which is readily biodegradable. As a general rule, biological treatment is more economical than any other type of treatment, when reasonably complete treatment is required, and whenever it can be made to work successfully.

It is often possible to make preliminary selections of candidate treatment technologies based on fundamental properties of the pollutants and experience. For instance, when considering candidate treatment technologies to treat wastewaters from a metal-plating operation, any of the biological treatment

technologies would be inappropriate because metal ions are not biodegradable; however, both chemical precipitation, a chemical treatment technology, and ion exchange, a physical treatment technology, should work well, based on the fundamental properties of the substances to be removed (dissolved inorganic cations and anions). The question then reduces to a comparison between the advantages and disadvantages of these two technologies, and experience provides much of the information appropriate to this evaluation.

For example, experience has shown that, for most metal-plating wastewaters:

1. Chemical precipitation is far less costly than ion exchange; however,
2. Chemical precipitation is not reliably capable of reducing metal concentrations to less than 5 or so mg/L.
3. A principal reason for the previous point is that the process of removing precipitated metals by settling in a clarifier typically does not remove the very small particles of precipitate.
4. Sand (or other) filtration effectively removes most of those particles of metal precipitate that will not settle.
5. The concentrations of dissolved metals even after chemical precipitation and sand filtration are still no lower than 1 to 2 mg/L, at best. Furthermore,
6. Ion exchange can “polish” the effluent from chemical precipitation and sand filtration to very low concentrations (20 to 50 ppb).
7. Ion exchange could do the entire job of removing metals from industrial wastewater to very low concentrations without being preceded by chemical precipitation and sand filtration, but, usually, at a cost

much higher than for the three processes in combination.

It follows, then, that it would not be prudent to spend effort, time, and money to conduct a large-scale investigation into technologies for treating wastewaters from metal plating, beyond the line of thinking outlined previously. The pollutants in these wastewaters are not organic, are, therefore, not biodegradable, and extensive experience has shown that:

1. Chemical precipitation is the most cost-effective method for removing the bulk of the dissolved metals.
2. Sand, diatomaceous earth, or other media filtration is the most cost-effective “next step” to follow the chemical precipitation process.
3. If still further reduction in metals concentration is required, ion exchange is the best candidate.

Having said that, it must now be said that, in many cases, substances in certain metal-plating wastewaters require more than straightforward alkaline precipitation, filtration, and ion exchange. For instance, if chelating agents are present, it may be necessary to destroy or otherwise inactivate them, in order to expose the metal ions to the full effect of the precipitating anions. In other cases, if the concentration of organic matter is high, it may interfere with the precipitation process and have to be removed by biological or other treatment before the metals removal steps.

Figure 8-1 presents a categorization of the components of industrial wastewater and preliminary selections of treatment technologies, based on the appropriateness of the mechanism of each technology compared to the fundamental properties of the pollutants. Different versions of Figure 8-1 could be generated by beginning with a characterization other than dissolved or undissolved; for instance, organic or inorganic, but all versions would ultimately result in the same list of appropriate treatment technologies.

In Figure 8-1, the first level of categorization of pollutant characteristics is that of dissolved or undissolved state. For instance,

trichloroethylene as a pollutant in wastewater would be dissolved (albeit to only very low concentrations), organic, nonbiodegradable, and volatile. Candidate technologies, then, would be stripping, activated carbon adsorption, and chemical oxidation.

Figure 8-2 presents a schematic of “the industrial waste system,” showing that raw materials, water, and air enter the system, and as a result of the industrial process(es), products and by-products exit the system, along with airborne wastes, waterborne wastes, and solid wastes. Because discharge permits are required for each of the waste-bearing discharges, treatment systems are required. Each of the treatment systems has an input, the waste stream, and one or more outputs. The output from any of the treatment systems could be an air discharge, a waterborne discharge, and/or a solid waste stream.

Principle and Nonprinciple Treatment Mechanisms

Most treatment technologies remove substances other than the target substances. For instance, “biological treatment” can effectively remove a certain amount of metal ions from wastewater. Because metal ions do not particularly like to be dissolved in water (they are hydrophobic), they are driven by the second law of thermodynamics to be adsorbed on the surface of solids—just about any solid—including activated sludge solids.

This mechanism for removing metals from wastewater is often undesirable because the presence of the metal ions in the waste sludge may render the sludge unsuitable for a desired disposal method. Composting with wood chips to produce a horticultural soil conditioner is an example. Another example is simple disposal in an ordinary municipal landfill. In other instances, the removal of metal ions by absorption on biological solids from a wastewater that has very low concentrations of them may serve as a fortuitous polishing step. In any case, biological treatment is a “principle” technology for removing organics from wastewaters, and its unintended removal of metal ions is a “non-principle” mechanism.




Figure 8-2 The "industrial waste system."

Waste Equalization

Among the most effective waste management procedures is equalization of the waste stream. Equalization can be of two types: flow equalization and constituent equalization. Flow equalization refers to changing the variations in rate of flow throughout the processing and clean-up cycles to a more steady flow rate that is more nearly equal to the average flow rate for that period. Constituent equalization refers to the concentration of the target pollutants in the waste stream. Throughout the 24-hour day, the concentrations of individual constituents in a given industrial waste stream typically vary over wide ranges as processes are started up, operated, shut down, and clean-up takes place. Waste treatment systems that are designed for given ranges of concentration of target pollutants often do not perform well when those constituents are in concentrations significantly different from the design values.

Equalization can be either online, as diagrammed in Figure 8-3(a), or offline, as diagrammed in Figure 8-3(b). Online flow equalization is accomplished by allowing the

waste stream to flow into a basin. The waste is then transferred from the basin to the treatment system at a constant, or more nearly constant, rate. The basin must be sufficiently large that it never overflows and must always contain enough waste that it never becomes empty, causing the flow to the treatment system to stop.

As shown in Figure 8-3(b), offline equalization is accomplished by restricting the flow into the treatment system by means of either a flow-regulating valve or a constant speed, positive displacement pump. When there is excess waste flow, it is directed to the equalization tank. When there is insufficient flow, it is made up from the equalization tank.

With respect to constituent equalization, off-line equalization can be used advantageously when wastes generation at night is significantly less than during the day. A portion of the strong daytime wastes can be stored in the equalization facility, then directed to the treatment system at night. The treatment system can be significantly smaller because it is not required to treat wastes at the high rate that they are generated during the daytime.




Figure 8-3 Flow equalization configurations.

A certain amount of constituent equalization will take place as a consequence of flow equalization, but this amount will not be optimal. Flow equalization is best done within a cycle in which the equalization basin is close to overflowing during highest flows and close to empty during lowest flow rates. Constituent equalization, in contrast, is best done by dilution. There are several different approaches to constituent equalization by dilution, ranging from dilution to a constant concentration of the target substance with clean water to simply retaining the waste stream in a completely mixed basin of constant volume.

The following are alternative approaches to constituent equalization:

1. Batch treatment. This is the ultimate in constituent equalization. The processing and clean-up wastewaters are collected in a well-mixed basin that is large enough to contain the entire processing and clean-up flows. Treatment can take place subsequently, either in the same tank, or by being pumped at a constant rate through a continuous flow treatment system.
2. Offline equalization tank. As described previously, a portion of the flows containing high concentrations of pollutants are diverted to an offline equalization basin and are mixed with less concentrated flows at a later time.
3. Completely mixed, inline equalization tank. A tank equipped with sufficient mixing capability to maintain completely mixed conditions and having sufficient volume to hold the flow between peak high and low flow rates is the most common type of constituent equalization device. The larger the volume, the better the constituent equalization, but the higher the cost to both construct, maintain, and mix. The tank is maintained full; therefore, flow equalization is not achieved by this device.
4. Dilution with clean water or treated effluent. Stormwater runoff, cooling water, or other previously used but clean water relative to the wastewater being treated may

be used. Target substances that can readily be measured with a probe and meter, such as a specific ion probe and meter, are the best candidates for this type of substance equalization. This method of constituent equalization, of course, increases the total flow through the treatment system.

As mentioned earlier, the principal value of waste equalization is that, in most cases, the treatment system can be made smaller because the maximum values for both flow rate and constituent concentration are reduced (method No. 4 is an exception). The treatment system will, therefore, have a lower capital cost as well as lower operating and maintenance costs; hence, by definition, a lower life cycle cost.

Flow Equalization

Figure 8-3(a) illustrates flow equalization by means of an online flow equalization basin. Flow into the basin is by gravity and varies as the waste generation rate varies. Flow out of the basin to the treatment system is made constant by either an appropriate valve or a positive displacement pump. An aerator and/or a mixer are provided to prevent undesirable occurrences such as settling out of solids or biological activity that would result in anaerobic conditions with consequent odor problems or chemical or biological reactions that would change the nature of the wastes.

The principal design parameter of a flow equalization basin is size. Because the cost of the basin is a direct function of its size, and because operation of the basin, in terms of maintaining complete mixing and aerobic conditions, is also a direct function of basin size, the flow equalization basin should be no larger than necessary to accomplish the required degree of equalization.

Development of a "mass diagram" is an excellent method for determining the required size of a flow equalization basin. A mass diagram is developed by plotting accumulated quantity of flow of the waste stream versus time.

A truly representative period may be one day, one week, or even longer. Then, as illustrated in Figure 8-4, the line that represents a constant rate of flow for the accumulated volume flowing at a steady rate over the total time period is drawn. Then, lines are drawn that are (1) parallel to the line that represents the average rate of flow and (2) tangential to the mass diagram at points that are the maximum distances above and below the average rate of flow line. The storage volume required for the equalization basin is that volume represented by the vertical distance between the two tangent lines. In some cases, the mass diagram may be at all points below, or in

other cases, at all points above, the average rate of flow line. In these cases, only one tangent line will be drawn at the point on the mass diagram that is farthest from the average rate of flow line. The volume required for the equalization basin in these cases is that volume represented by the vertical distance between the single tangent line and the average rate of flow line.

As with many other unit processes, it is usually prudent to increase the size of the equalization basin by 10% to 20% over that determined by the mass diagram method, to account for changes in flow rate greater than experienced when the data was taken for the mass diagram,




Figure 8-4 Mass diagram with illustration of the method used to determine the required volume of equalization basin.

or other uncertainties. In fact, the percent increase in size should be inversely proportional to the degree of confidence the design engineer has in how accurately the data obtained is representative of the full range of conditions to be experienced by the treatment system.

Example 8-1 illustrates the procedure for determining the size of a flow equalization basin. Example 8-2 illustrates how a flow equalization basin can significantly reduce the size of treatment facility required for a given industrial facility.

Example 8-1: Flow Equalization

The flow of wastewater from a poultry processing plant is shown in the following table. If it is desired to pump this flow at a constant rate over a 24-hour day, what is the minimum size required for an online flow equalization tank?

Hour Ending	Cumulative flow, Thousands of gallons
0100	5
0200	11
0300	14
0400	20
0500	25
0600	31
0700	62
0800	120
0900	200
1000	240
1100	309
1200	320

Example 8-2:

Determine the size in terms of design flow rate of a dissolved air flotation (DAF) system to treat the wastewater described in Example 8-1: (a) without an equalization tank and (b) with the equalization tank of 310,000 gallons, plus 10% to 20%.

- a. The data presented in Example 8-1 and diagramed in Figure 8-5 show that the

maximum hourly rate of flow occurs between 9:00 and 10:00 p.m. when clean-up operations and probably dumping baths are taking place. This equates to 154,000 gallons per hour or 2,600 gpm. Thus, a DAF facility would have to be sized for at least 2,600 gpm if no flow equalization is provided.

- b. If an inline tank of at least 310,000 gallons is provided, the design flow for the DAF system should be that of the average rate of flow for the 24-hour period, or 1.2 mg/24 hr. = 834 gpm. Thus, the inclusion of a flow equalization tank allows the treatment facility to be 68% smaller.

Constituent Equalization

As stated previously, some amount of constituent equalization always takes place during flow equalization. In fact, it is standard practice to design for flow equalization, then operate to attain the degree of constituent equalization needed to achieve treatment objectives. One way this is done is to manually, or automatically, decrease rates of flow during periods when constituent concentrations are high. The simple dilution equation shown as equation 8-1 can be used to calculate concentrations of constituents that result when volumes of a given concentration of that constituent are mixed with known volumes of the same constituent at a different concentration.

$$\frac{C_1(V_1) + C_2(V_2)}{V_1 + V_2} = C_3 \quad (8-1)$$

where:

- C_1 = Concentration of constituent in question in the first considered volume.
- V_1 = First considered volume.
- C_2 = Concentration of constituent in question in the second considered volume.
- V_2 = Second considered volume.
- C_3 = Concentration of the constituent in question when the volumes V_1 and V_2 are mixed together.





Figure 8-5 Mass diagram of cumulative volume of wastewater flow over time.

pH Control

Although pH control is a form of chemical treatment, it is presented here in the general section because, like flow equalization, it is used with biological and physical treatment systems as well as with chemical treatment systems.

Water, the basic substance of all industrial wastewaters, is composed of hydrogen and oxygen. Water dissociates into hydrogen ions and hydroxide ions, as shown in equation 8-2.



In accordance with the law of mass action, discussed in the section entitled Reaction to Produce an Insoluble Solid, the quantities of hydrogen and hydroxide ions are such that the mathematical product of the hydrogen ion concentration, expressed as moles per liter ($[H^+]$),

and the hydroxide ion concentration ($[OH^-]$) is always 10^{-14} , as shown in equation 8-3.

$$[H^+][OH^-] = 10^{-14} \quad (8-3)$$

The hydrogen ion concentration is thus a fundamental property of any aqueous solution. Any liquid for which equation 8-3 does not hold is not an "aqueous solution." A strong solution of sulfuric acid is an example. It is a strong acid solution, not an aqueous solution, and its pH value really has no meaning.

The hydrogen ion concentration of an aqueous solution, such as an industrial wastewater, has a major influence on its characteristics. What substances will dissolve in a given wastewater, as well as how much of a given substance can be dissolved, is one important characteristic. Another is that pH strongly influences the corrosivity of wastewater. The value of the pH of an aqueous solution must be

within a certain range for bacteria and other microorganisms to live and thrive, and for fish and plants to live and thrive. A host of other characteristics that influence the success of wastewater treatment methods, such as chemical coagulation, activated carbon adsorption, ion exchange, chemical oxidation, and the release of gases such as hydrogen sulfide and ammonia are absolutely dependent for success on the proper range of pH.

Because the hydrogen ion concentration of wastewaters is so commonly dealt with, and because it is cumbersome to express hydrogen ion concentration in terms of molar concentrations, the concept of pH was developed. Very simply, the term "p" preceding any item means "the negative logarithm of that item." Thus, pK_a means "the negative log of the numerical value of K_a , and pH means "the negative log of the numerical value of the hydrogen ion concentration, in moles per liter." Equation 8-4 illustrates the pH concept.

$$pH = -\log[H^+] = \log 1/[H^+] \quad (8-4)$$

Example 8-3:

Calculate the pH of an aqueous solution that has a concentration of hydrogen ions equal to 2.3×10^{-3} moles per liter.

Solution:

$$pH = \log \frac{1}{[H^+]} = \log \frac{1}{2.3 \times 10^{-3}} = 2.64$$

or,

$$pH = \log[H^+] = -\log(2.3 \times 10^{-3}) = 2.64$$

Example 8-4:

Calculate the hydroxide ion concentration of an industrial waste having a pH of 5.4.

Solution:

$$pH = \log \frac{1}{[H^+]} = -\log[H^+] = 5.4$$

The concentration of hydrogen ion in this wastewater, then, is $10^{-5.4}$ moles/liter but,

$$(10^{-5.4}) \times [OH^-] = 10^{-14}$$

or,

$$[OH^-] = \frac{10^{-14}}{10^{-5.4}} = 10^{-8.6} \text{ moles/liter}$$

Thus, it is seen that the pH scale, which, in accordance with equation 8-3, is a logarithmic scale, ranges between the values of 0 and 14, and a change in pH value of 1.0 equates to a change in concentration of hydrogen ion of a factor of ten. If the pH of a wastewater changes from 5.1 to 7.1, the molar concentration of hydrogen ions will have decreased by two orders of magnitude.

Typically, industrial waste discharge permits require that the pH be within the values of 6.5 and 8.5, and many industrial waste treatment processes require that the pH be held within a range of plus or minus 0.5 pH units. Some treatment processes require an even smaller pH range for successful operation. For these reasons, pH control is one of the most important aspects of industrial wastewater treatment.

The standard procedure used to control pH in industrial waste treatment is illustrated in Figure 8-6. Basically, a mixing chamber is used to mix acidic and/or basic reagents with the wastewater. pH electrodes are placed either in the discharge from the mixing chamber or, in some cases, in the chamber itself. The electrical signal from the pH electrodes is amplified and relayed to a controller, which activates valves or pumps to regulate the flow of acidic or basic reagent into the mixing tank.

Many pH control applications are simple, straightforward, and require only that the electrodes be kept clean and well calibrated and the control system well maintained for success. If the system is "well behaved" (the pH of the wastewater entering the mixing tank does not change very often, or very much), then a simple control system such as that shown in Figure 8-6 is adequate; however, if the pH, as well as the acidity and/or the alkalinity of the wastewater entering the mixing tank do change appreciably throughout the

processing and clean-up day, then the simple control system depicted in Figure 8-6 may be inadequate. In fact, pH control can be extremely difficult and require a much more extensive control system than that shown in Figure 8-6.

A basic reason for the potential difficulty with satisfactory pH control relates to the extremely large range of values of hydrogen ion concentration within the 0 to 14 pH scale range. Fourteen orders of magnitude is a range that few, if any, other detection devices must contend with. Another reason relates to the high sensitivity of commonly available pH detection electrodes. These electrodes typically can respond to changes in pH as small as 0.001.

The extremely large range of the substance detected (hydrogen ion), coupled with the high sensitivity of detection capability, must be relayed electronically and, ultimately, mechanically to a control system that regulates the flow of reagent to the mixing tank. If the system is not well behaved, two complete control systems in series, and, in some cases, three, are required to attain satisfactory results. The multiple systems should have successively smaller control valves or pumps in order to overcome the difficulty in translating, on the one hand, a change of several orders of magnitude in hydrogen ion concentration, and on the other hand, a very small change in a valve setting. Figure 8-7 illustrates a pH control system with two control subsystems in series.




Figure 8-6 Diagram of a pH control system.




Figure 8-7 Two control subsystems in series.

Chemical Methods of Wastewater Treatment

Chemical methods of wastewater treatment take advantage of two types of properties: (1) the chemical characteristics of the pollutants, regarding their tendency to react with, or interact with, treatment chemicals, and (2) the chemical characteristics of the products of reaction between pollutants and treatment chemicals, regarding their solubilities, volatilities, or other property that relates to the inability of the product to remain in water solution or suspension.

In general, six chemical processes can be used to remove substances from wastewater:

1. Reaction to produce an insoluble solid.
2. Reaction to produce an insoluble gas.
3. Reduction of surface charge to produce coagulation of a colloidal suspension.
4. Reaction to produce a biologically degradable substance from a nonbiodegradable substance.
5. Reaction to destroy or otherwise deactivate a chelating agent.
6. Oxidation or reduction to produce a non-objectionable substance or a substance that can be removed more easily by one of the previous methods.

Table 8-1 presents an enumeration of chemical treatment technologies and classifies them in these six categories.

Reaction to Produce an Insoluble Solid

The industry standard procedure for removing metals from wastewaters is alkaline precipitation. Alternative methods include precipitation of the metal as the sulfide, precipitation as the phosphate, precipitation as the carbonate, or co-precipitation with another metal hydroxide, sulfide, phosphate, or carbonate. All of these technologies use the law of mass action, illustrated as follows:

When a chemical system is in equilibrium as expressed by



it must obey the equation

$$\frac{[C][D]}{[A][B]} = K \quad (8-6)$$

Table 8-1 Chemical Treatment Technologies and Appropriate Technology Category

<i>Chemical Treatment Technology</i>	<i>Technology Category</i>
Alkaline precipitation of metals	1
Alkaline chlorination of cyanide	2
Breakpoint chlorination removal of ammonia	2
Precipitation of metals as the sulfide	1
Precipitation of metals as the phosphate	1
Precipitation of metals as the carbonate	1
Chemical coagulation	3
Chemical oxidation of nitrite	2
Hydroxyl free radical oxidation of organics, including toxic substances such as solvents, pesticides, and by-products of manufacture of phenol-formaldehyde resins	4, 5, 6
• Ozone + hydrogen peroxide • Ozone + ultraviolet light • Hydrogen peroxide + ultraviolet light • Fenton's reagent ($\text{H}_2\text{O}_2 + \text{Fe}^{++}$)	
Precipitation of phosphorus as the metal phosphate	1
Removal of arsenic by first, oxidation of arsenite to arsenate, followed by co-precipitation of arsenate with ferric salt	1,6
Reduction of ionic mercury to the metallic form using hydrazine, sodium borohydride, or other reducing agent	1,6
Precipitation of barium as the sulfate	1
Reduction of hexavalent chromium to insoluble trivalent chromium, pH adjustment to 8.2–8.6	1,6
Precipitation of fluoride as calcium fluoride, insoluble at high pH	1
Oxidation of ferrous to ferric, precipitation of ferric oxide, insoluble in the neutral pH range	1,6

where K is a constant. In words, equation 8-6 states that, for a given system of chemical substances that have reacted to the point of equilibrium, the mathematical result of multiplying the products, each expressed as moles per liter, divided by the mathematical product of the reactants, is always the same number. Consequently, in order to not change the value of K , an increase in either A or B will shift the equilibrium to the right, causing a corresponding decrease in B or A , respectively. Likewise, removal of some or all of either C or D will

shift the equilibrium to the right, causing decreases in both A and B .

It follows, then, that if substance A is a pollutant, substance B will react with A to produce an insoluble precipitate (C or D), and because precipitation constitutes removal from solution, then substance B can be added until substance A has essentially disappeared.

A step-by-step procedure that can be used to develop an effective, efficient, cost-effective treatment technology is as follows:

1. Identify one or more insoluble compounds of which the target pollutant is an ingredient.
2. Identify one or more soluble compounds that are reasonably inexpensive sources of the remaining substances in the insoluble compound(s).
3. Perform experiments in the laboratory to confirm the technical and financial feasibility of each promising treatment method.

As an example of the foregoing procedure, consider that lead is the target pollutant. Review of Langels, or another appropriate handbook, shows that the following compounds of lead are highly insoluble:

COMPOUND	SOLUBILITY IN WATER (mg/L)
Lead hydroxide ($\text{Pb}(\text{OH})_2$)	2.1
Lead carbonate ($\text{Pb}(\text{CO}_3)$)	7.0×10^{-3}

Lead phosphate ($\text{Pb}_3(\text{PO}_4)_2$)	20×10^{-3}
Lead sulfide (PbS)	3.8×10^{-9}

And of these three compounds, lead carbonate and lead sulfide are seen to be essentially insoluble in water. Executing the second step, it is determined that a relatively inexpensive source of carbonate ions is common soda ash, Na_2CO_3 , and a somewhat more expensive material, sodium sulfide, is a source of sulfide ions. A promising treatment method for removing lead from an industrial wastewater, then, would be to add soda ash and precipitate the lead as the insoluble carbonate.

Table 8-2 presents a list of heavy metals with theoretical solubilities of their hydroxides, carbonates, and sulfides. Figure 8-8 illustrates the importance of the correct range of pH. Table 8-3 presents a summary of pH range and other conditions that have been found to produce good removals of iron, aluminum, arsenic, and cadmium, respectively, from typical industrial wastewaters.

Table 8-2 Theoretical Solubilities of Hydroxides, Sulfides, and Carbonates for Selected Heavy Metals (Palmer et al., 1988)

<i>Metal</i>	<i>Solubility of metal ion; mg/L</i>		
	<i>As hydroxide</i>	<i>As carbonate</i>	<i>As sulfide</i>
Cadmium (Cd^{++})	2.3×10^{-5}	1.0×10^{-4}	6.7×10^{-10}
Chromium (Cr^{+++})	8.4×10^{-4}	—	No precipitate
Cobalt (Co^{++})	2.2×10^{-1}	—	1.0×10^{-8}
Copper (Cu^{++})	2.2×10^{-2}	—	5.8×10^{-18}
Iron (Fe^{++})	8.9×10^{-1}	—	3.4×10^{-5}
Lead (Pb^{++})	2.1	7.0×10^{-3}	3.8×10^{-9}
Manganese (Mn^{++})	1.2	—	2.1×10^{-3}
Mercury (Hg^{++})	3.9×10^{-4}	3.9×10^{-2}	9.0×10^{-20}
Nickel (Ni^{++})	6.9×10^{-3}	1.9×10^{-1}	6.9×10^{-8}
Silver (Ag^+)	13.3	2.1×10^{-1}	7.4×10^{-12}
Tin (Sn^{++})	1.1×10^{-4}	—	3.8×10^{-8}
Zinc (Zn^{++})	1.1	7.0×10^{-4}	2.3×10^{-7}




Figure 8-8 Precipitation of heavy metals as hydroxides. (From Lanouette, 1977.)

Table 8-3 Summary of pH Ranges and Conditions Found to Produce Good Removals of Indicated Metals

	SUBSTANCE TO BE REMOVED			
	Iron	Aluminum	Arsenic	Cadmium
pH and other condition	7–8 all Fe oxidized to Fe+++	6–7, but up to 8.5 may be o.k.	co-ppt w/ iron, therefore, pH 7–8	10 or so, but pH 8 w/ carbonate is best

Table 8-4 presents treatment methods that are most commonly used for removing nine metals in addition to those shown in Table 8-3. Figure 8-8 presents relationships between pH value and solubility for six common heavy

metals. Notice that Figure 8-8 shows that chromium and zinc exhibit optimum pH values of 7.5 and 10, respectively, whereas iron, copper, nickel, and cadmium show ever-decreasing solubility with increasing pH.

Table 8-4 Common Methods and pH Values for Removal of Heavy Metals

Chromium	Reduction to trivalent state by bisulfite or metabisulfite, followed by precipitation at pH 8–9.5.
Copper	pH 10–12, or as the sulfide (by adding sodium sulfide). Evaporative recovery, or ion exchange for recovery.
Lead	pH 10–11, or precipitation as the carbonate (by adding soda ash) or as the phosphate (by adding phosphoric acid or a soluble phosphate).
Manganese	Oxidation to insoluble manganous dioxide by chemical oxidants (free chlorine residual, ozone, potassium permanganate), ion exchange.
Mercury	Precipitation as the sulfide, at pH values between 5 and 8. Also, ion exchange, coagulation, and activated carbon.
Nickel	Generally, pH 11–12. In some cases, pH values ranging from 5–10 have produced good results. Precipitation as the carbonate or sulfide has worked well at pH values close to neutral.
Selenium	Dissolved selenium is removed by precipitation at pH 11–12, or by co-precipitation with iron at pH 5.5–8, or with alum at pH 6 or so. Undissolved selenium is removed by sedimentation and/or filtration.
Silver	Because of the value of silver, ion exchange removal followed by recovery of the silver is very common.
Zinc	Wide range of pH values, depending on other substances in the wastewater. Phosphate precipitation at pH 8–9 has worked well.

When an insoluble precipitate is formed, individual atoms share electrons to build a crystal lattice structure that results in particles that “grow” to a size that will settle in a clarifier under the influence of gravity. Often, two distinct processes take place. The first is the formation of small crystals of the substance being precipitated. The second is coagulation of the small crystalline particles, which is the clumping together of many small particles to form larger particles that settle well. Sometimes a coagulant or a coagulant aid can assist with this process.

It is common practice to include a deep bed granular filter, or, in some cases, ultrafiltration, as the final step in removing substances by forming an insoluble solid. Typically, chemical precipitation followed by sedimentation results in 10 mg/L or less of the target substance remaining in the treated effluent. Polishing this effluent normally reduces the residual to 1 to 3 mg/L.

It is always necessary to confirm a chemical treatment process by laboratory experimentation. Even though there are voluminous books and research papers that describe how

various substances, such as heavy metals “are removed,” the presence of interfering substances such as chelating agents, complexing substances, and substances that will compete for the proposed treatment chemical can sometimes render a given method ineffective in any given application.

A suggested procedure for determining, in the laboratory, optimum doses of reagent chemicals and ranges of pH is as follows:

Using a “jar test apparatus,” shown in Figure 8-9:

1. Place wastewater, pretreated by sedimentation or otherwise, as anticipated for a full-scale treatment plant, in “jars” of about 1200 ml volume. 1000-ml beakers can be used, but jars of square cross-section produce better mixing action.
2. Determine reagent doses to bracket the anticipated optima, regarding;
 - a. pH
 - b. Precipitant
 - c. Coagulant (if any)
 - d. Coagulant aid (if any)




Figure 8-9 Jar test apparatus. (Photo courtesy of ©Phipps & Bird, Inc., 2000.)

- (These determinations have to be made on the basis of (1) experience, (2) the literature, or (3) educated guesses.)
3. With all stirrers in the “rapid mix” mode, add the decided-on doses to each jar as nearly simultaneously as possible. One method is to place each dose in a small beaker and have several people, each with a beaker in each hand, dose each jar at the same time.
 4. “Rapid mix” for 30 seconds.
 5. “Slow mix” to achieve good coagulation. Observe the coagulation process (appearance of particles in the test solutions) and the flocculation process (building of particles into large, flocculent solids with attendant decrease in the turbidity of the test solution). Record observations. Carry on for up to 30 minutes.
 6. Allow to settle. Observe flocculation and settling characteristics. Record observations.
 7. Measure results of the following:
 - a. Target substance concentration
 - b. pH
 - c. Turbidity
 - d. TSS
 - e. Residual reagents, if desired

Table 8-5 presents a listing of chemicals that have been used successfully to produce insoluble precipitates and thus effect removal of pollutants such as metals, phosphorus, sulfide, and fluoride.

The Use of Carbamate

Carbamates, a class of organic compounds that was developed for use as pesticides during the 1940s and later, have been found to function extremely well as precipitants for certain metals. In some cases, one or more carbamates have been found to be capable of precipitating metals in the presence of chelating agents and

Table 8-5 Chemical Substances Commonly Used for Industrial Wastewater Treatment by Removal of Target Pollutants as a Precipitate

CHEMICAL	APPLICATION
Lime	Heavy metals, fluoride, phosphorus
Soda ash	Heavy metals
Sodium sulfide	Heavy metals
Hydrogen sulfide	Heavy metals
Phosphoric acid	Heavy metals
Fertilizer grade phosphate	Heavy metals
Ferric sulfate	Arsenic, sulfide
Ferric chloride	Arsenic, sulfide
Alum	Arsenic, fluoride
Sodium sulfate	Barium
Carbamates	Heavy metals

other substances that interfered with removal of the metals using more conventional methods such as pH adjustment. Several chemical manufacturers now market proprietary substances, which are carbamates, as effective precipitants.

Figure 8-10 presents a suggested sequential procedure for developing a treatment system, from initial concept to the point of initiating final design documents. Although the process depicted in Figure 8-10 is addressed to develop a treatment system for removing target substances by forming an insoluble substance, it can be easily adapted to the development of many other types of treatment systems.

Disadvantages of Treatment by Production of an Insoluble Compound

Certain problems are common to treatment processes wherein the mechanisms of removal are formation of an insoluble solid, followed by separation of the solids from the liquid by sedimentation. One problem is the occasional

inability of the precipitated solid to build into particles that are sufficiently large to settle, under the influence of gravity, in the clarifier. Another is the often voluminous sludge that is difficult to dewater.

Often, sludge produced by precipitation of heavy metals must be handled and disposed of as "hazardous waste" because of its inability to "pass" the TCLP test (see Chapter 6), although there are methods of treating or conditioning these sludges to render them capable of passing. Some of these methods are proprietary; some are not. For instance, under certain circumstances, the phosphate precipitate of zinc will pass the TCLP test. Each individual sludge must be experimented with in the laboratory, using principles discussed in this text, to develop a precipitation process that yields a sludge that can be dewatered economically to produce a residual that can be disposed of as nonhazardous.

One method of avoiding the expense and future liability of disposing of sludge as hazardous waste is to dewater, dry, then store the dried material for later recycle and reuse. Even though this would require licensing as a hazardous material storage facility, it might prove to be the most cost-effective option.

Suggested Approach for Treatment of Industrial Wastewater by Formation of an Insoluble Substance

Figure 8-11 presents a suggested approach, or model, for treatment of industrial wastewaters for removal of substances by formation of an insoluble substance. First, as in all industrial wastewater treatment applications, the cost effectiveness of primary treatment, including plain sedimentation, should be evaluated. The second step should be pH adjustment to that range required for optimum effectiveness of the third step, which should include whatever conditioning steps are to take place before the principal treatment process. Examples are reduction of hexavalent chromium to the trivalent state, oxidation of arsenite to arsenate, and destruction of chelating agents by oxidation with Fenton's reagent.

Next, a second pH adjustment step may be required for optimum performance of the principal treatment process, shown in Figure

8-11 to be chemical precipitant addition, mixing, flocculation, sedimentation, and finally, filtration.




Figure 8-10 Suggested procedure for developing a treatment system.





Figure 8-11 Schematic of suggested model for design of facility for removal by forming an insoluble substance.

Reactions to Produce an Insoluble Gas

Considering, again, equations 8-5 and 8-6, it can be seen that if product C or D is a gas that is very poorly soluble in the wastewater being treated, it will remove itself from solution as it is formed, thus forcing the equilibrium to the right until the target substance (A or B) has essentially disappeared. An example of this treatment technology is the removal of nitrite ion by chlorination, as shown by equation 8-7.



As chlorine is added in the form of chlorine gas or hypochlorite, or another chlorine compound that dissolves in water to yield free available chlorine, the nitrite ions are oxidized to nitrogen gas and water. Nitrogen gas, being only sparingly soluble in water, automatically removes itself from the chemical system, driving the equilibrium to the right until all of the nitrite ion has been removed.

Table 8-6 presents a listing of chemical substances that can be added to remove the appropriate pollutants as an insoluble gas.

Breakpoint Chlorination to Remove Ammonia


For many years, breakpoint chlorination has been used to produce a free chlorination residual in drinking water. The basic process of breakpoint chlorination is that chlorine reacts with ammonia in four different stages to ultimately produce nitrogen gas, hydrogen ions,

Table 8-6 Chemical Substances that can be Applied to Remove Appropriate Target Substances as an Insoluble Gas



CHEMICAL SUBSTANCE	TREATMENT TECHNOLOGY
Chlorine gas or other chlorine compound (hypochlorite, or chlorine dioxide, for instance)	(1) Breakpoint chlorination to remove ammonia (2) Alkaline chlorination of cyanide
Sulfuric or hydrochloric acids (technical grade or waste acids)	Removal of sulfide as hydrogen sulfide gas

chloride ions, and possibly some nitrous oxide, and some nitrate, as shown in equations 8-8 through 8-12.

First, chlorine reacts with water to yield hypochlorous and hydrochloric acids:



Then, hypochlorous acid reacts with ammonia:




Breakpoint chlorination can be used to convert ammonia to nitrogen gas in wastewater treatment; however, because many substances that are stronger reducing agents than ammonia will exert their demand, this method is suitable only if such substances are not present in significant amounts.


Alkaline Chlorination of Cyanide

Cyanide has been used for many years as the anion to associate with metals used in metal plating baths because many metal cyanides are soluble in water to relatively high degrees. Because of the extreme toxicity of cyanide, its removal from industrial wastewaters was one of the earliest industrial wastewater treatment processes to be developed and used widely.


Chlorine reacts instantaneously with cyanide, at all pH levels, to produce cyanogen chloride, as follows:



At pH levels other than alkaline, that is, below 8.5, the cyanogen chloride persists as a volatile, toxic, odorous gas. In the presence of hydroxide alkalinity, however, cyanogen chloride is converted to cyanate, which is a thousand times less toxic than cyanide:



If chlorine is present in excess, that is, in an amount significantly greater than that required for stoichiometric completion of the reaction indicated in equation 8-13, plus that chlorine that will be consumed in reactions with reducing reagents and organics present in the wastewater (side reactions), it will oxidize the cyanate (produced as shown in equation 8-14) to carbon dioxide and nitrogen gasses, both only sparingly soluble in water:



which accounts for the effectiveness of the so-called alkaline-excess chlorine process for destruction of cyanide.

Because chlorine is subject to side reactions as indicated previously, the chlorine dose required to produce satisfactory destruction of cyanide must be determined in the laboratory, and extreme caution must always be exercised to never allow the cyanide solution to attain an acidic pH, which will allow development of cyanide gas:



another sparingly soluble gas, but an extremely toxic one.

Usually, the caustic-excess chlorine process for destruction of cyanide is carried out at pH 8.5. Automatic pH control is normally employed, with suitable fail-safe processes. Automatic chlorine dosing can be accomplished by use of an ORP probe and controller.

Reduction of Surface Charge to Produce Coagulation of a Colloidal Suspension

A very high percentage of industrial wastewaters consists of colloidal suspensions. In fact, it is often possible to destabilize industrial wastewaters by chemical coagulation, allow separation of the destabilized colloidal material from the water, further treat the water to discharge quality by a polishing step, if necessary, and then recover the coagulant from the separated waste substances. The coagulant can be reused, and the waste substances can be further treated, if necessary. The advantage is that the polishing step can be significantly more economical than if it were used to treat the raw wastewater, and, in some cases, the separated colloidal material can be recovered as a by-product.

A colloidal suspension consists of one substance in a fine state of aggregation evenly dispersed throughout a second. The first phase, which may consist of single polymers or aggregates of smaller molecules, is called the dispersed or discontinuous phase, and the second phase is called the dispersing medium or continuous phase. The distinguishing characteristics of a colloid system are the size of the dispersed particles and the behavior of the system, which is governed by surface phenomena

rather than the chemical properties of the components. The size of the dispersed particles ranges between 1 and 100 μ , placing them between molecules and true particles. Colloidal systems can be further classified into emulsions, gels, or sols. Emulsions consist of two immiscible liquids, one being finely dispersed throughout the other. They must be stabilized by a surface-active agent, called an emulsifier, which reduces the surface tension at the interface between the two phases. Free energy from the increased surface area otherwise would tend to destabilize the emulsion. When an emulsifier is present, the repulsive forces caused by like electrostatic charges on each of the dispersed aggregates exerts the principal stabilizing force. These charges arise by several different means, depending on the nature of the emulsion. The principal destabilizing forces are the Brownian movement, which causes the aggregates to come into contact with each other, and the London-van der Waal forces of attraction, which tend to cause the emulsified aggregates to coalesce after moving to within a critical distance from each other.

A gel results when organic colloids of long, thin dimensions are dispersed in a liquid medium, with the resulting formation of a non-uniform lattice structure, when suitable groups on the colloidal particles come into contact. The dispersed phase is like a "brush heap" in this respect, and the gel assumes a semi-solid texture. Gelatin is a familiar example of a substance that forms a gel.


The most common colloidal system encountered in industrial wastes consists of organic particles or polymers, and/or inorganic particles, dispersed in a liquid to yield a fluid system known as a sol. This differs from an emulsion in that an emulsifying agent is not required. The particles or polymers belong to one of two classes, depending on whether or not they have an attraction for the dispersing medium. These classes are lyophobic (solvent-hating), for those substances that do not have an attraction, and lyophilic (solvent-loving), for those substances that do. In the case of industrial wastes for which the dispersion medium is water, the classes are called hydrophobic and hydrophilic.

Lyophobic Sols

Giant molecules or polymers that have no attraction for a particular liquid, and thus possess no tendency to form a true solution with the liquid, can be induced to form a hydrophobic sol by applying sufficient energy to uniformly disperse the particles throughout the liquid medium. If the dispersed particles contain groups that are ionizable in the dispersing medium, or if certain electrolytes are present in the dispersing medium, the anion or cation of which is preferentially adsorbed by the dispersed particles, the sol will be stabilized by mutual repulsion of like electrostatic charges on each of the particles of the dispersed phase.

Figure 8-12 illustrates a colloidal suspension wherein particles (which can be organic or inorganic, macromolecules or aggregates of smaller molecules, or finely divided solids) are dispersed in water. The dispersed particles have a surface charge, negative in all cases, which can have resulted from ionization of certain groups, breaking of covalent bonds, or adsorption of previously dissolved ions from the water medium.

An example of a hydrophobic sol, which owes its surface charge to selective adsorption of ions from solution, is the silver bromide sol, which results from mixing potassium bromide and silver chloride in water. Both potassium bromide and silver chloride are soluble in water. Silver bromide is not. Therefore, when potassium bromide and silver chloride are mixed together in water, silver bromide is formed as an insoluble product and precipitates from solution in the form of many tiny silver bromide crystals in accordance with equation 8-17:



When potassium bromide is in excess, the silver ions are all tied up as the silver bromide precipitate. There are therefore unprecipitated bromide ions in solution, which are adsorbed to the precipitated silver bromide crystalline particles. The sol, consequently, possesses a negative surface charge. At the exact equivalence point (equivalent silver and bromide), the

silver bromide precipitates from solution because neither bromide ions nor silver ions are present in excess. When silver nitrate is in excess, the sol possesses a positive charge. Mutual electrostatic repulsion results when either silver or bromide is present in excess.

Soap micelles are examples of colloid systems whose stabilizing surface charge arises from ionization of certain groups on the micelles. Long hydrocarbon “tails” of the soap molecules clump together to escape water, as illustrated in Figure 8-13 (the absence of the




Figure 8-12 Illustration of a colloidal suspension.




Figure 8-13 Colloidal suspension of soap micelles.

hydrocarbon chain in the water allows the water to form more hydrogen bonds, thus lowering the free energy of the entire system). Clumping together of the hydrocarbon chains of many soap molecules creates a micelle having many ionizable groups at its periphery. Because the charge caused by the dissociated ions is the same for each micelle, electrostatic repulsion prevents the micelles from agglomerating.

Lyophobic sols are thus characterized by two phenomena: the absence of an attraction of the dispersed particles for the dispersing medium, and stabilization by mutual repulsion of like electrostatic charges on each of the suspended particles.

Lyophilic Sols

If, in the formation of a sol, the dispersed particles have an attraction for the molecules of the dispersing medium, each dispersed particle adsorbs a continuous layer of solvent molecules on its surface. The usual driving force involved in forming a hydrophilic sol is the reduction of free energy in the system as a result of stronger bonding between the solvent molecules and the dispersed particles than between the solvent molecules themselves. This adsorbed layer serves as a protective shell for each of the dispersed particles, thus constituting the principal stabilizing factor for the sol. Additional stability can result from repulsion of like electrostatic charges on each particle, if chemical groups on these particles ionize, or if ions are adsorbed onto the surfaces of the particles from the solution. These charges originate in a manner similar to those in lyophobic sols but are far less important to the stability of lyophilic sols than of lyophobic sols.

Electrokinetics of Lyophobic Sols

A graphical representation of the charge distribution on a lyophobic colloidal particle is presented in Figure 8-14. The model colloidal particle used for this figure has a negatively

charged surface. This negative charge could have arisen from one or more of several electrochemical activities undergone by the particle when placed in the suspending medium, including those explained previously, or simply from the adsorption of OH⁻ or other anions because of the greater affinity of the suspending medium for cations.

The negatively charged particle attracts a layer of positive ions that may originate either from dissociated electrolytes present in the suspending medium or from dissociated groups on the particle itself. These ions, oppositely charged to the inherent charge of the colloidal particle, are called "counter-ions." They are drawn to the particle by electrostatic attraction, whereas thermal agitation or Brownian motion tends to distribute them uniformly throughout the solution. The layer of counter-ions is relatively rigid and is referred to as the "Stern layer." The Stern layer does not entirely neutralize the charge on the colloid; and the excess charge creates a diffuse layer of co- and counter-ions, intermingled, but having a higher density of counterions close to the colloid and a higher density of co-ions at the outer reaches of the layer. This diffuse layer is often referred to as the "Gouy-Chapman layer." The Stern layer-Gouy-Chapman layer combination is called the "Helmholtz double layer" or the "diffuse double layer."

When the suspended colloid shown in Figure 8-14 is placed in an electric field, it migrates toward the positive pole. As it moves through the suspending medium, the ions in the Stern layer move as a fixed part of the colloid, whereas those in the diffuse Gouy-Chapman layer tend to slough off, or stay behind. A plane of shear is developed at a certain distance from the surface of the colloid, and this plane of shear, or "slipping surface," defines the boundary between the Stern and Gouy-Chapman layers. Immediately below the colloid particle in Figure 8-14 is a graphical representation of the electrical potential at increasing distance from the surface of the colloid. The potential decreases linearly between the surface of the

particle and the inner periphery of the Stern layer of counter-ions. From the inner periphery of the Stern layer outward, the potential drops at a decreasing rate. The potential at the outer periphery of the Stern layer, that is, at the surface of shear, is termed the “zeta potential.” The value of the zeta potential directly depends on the same factors that determine the thickness

of the Stern layer, namely, the strength of the charge at the surface of the colloid; the nature—especially the value of the ionic charge—and degree of solvation of the ions in the Stern layer; and the frictional drag exerted by the suspending medium on the double layer as the particle migrates under the influence of an applied electric field.




Figure 8-14 “Layers” or “shells” surrounding a negatively charged colloid.

Each of the ions in the Stern layer is solvated; thus, a layer of tightly bound solvent molecules surrounds each lyophobic colloid. In contrast to the water layer associated with hydrophillic colloids (a detailed discussion of which follows), the water layer in the case of a hydrophobic colloid is bound only by attraction to the ions in the Stern layer and not by attraction to the colloid surface itself. The zeta potential in the case of hydrophobic colloids gives a direct indication of the distance over which the colloidal particles can repel each other and thus of the stability of the colloid system.

Electrokinetics of Lyophillic Sols

When an organic macromolecular solid is placed in a given liquid, one of three possible states of solute-solvent interaction results (solubility in this instance is defined as a limited parameter indicating compatibility with the solvent but not true solubility in the strict sense of the definition):

1. The macromolecular solid is insoluble in the liquid.
2. The solid swells but has a limited solubility.
3. The substance is soluble in the liquid.

In cases 1 and 2, the systems are always lyophobic, whereas in case 3, the only possibility is that of a lyophillic sol. As an example of case 3, when amylose is placed in water, hydrogen bonds are formed between molecules of water and the hydroxyl groups on amylose that are at least as strong or stronger (that is, involve at least as much or more bond energy) than hydrogen bonds between the molecules of water itself. If a charge exists on the macromolecule because of factors similar to those accounting for the charge on lyophobic colloids, and if an electric field is applied across a portion of the sol, the particle will migrate toward one of the poles. As the particle moves, water molecules that are bound to the macromolecules by hydrogen bonds plus those interlaced, again by hydrogen bonding, migrate as an integral part of the particle. This layer of

water, usually monomolecular, defines what is known as the "solvated solvent layer" around the macromolecules and serves as a protective shell against influences that could be exerted by the chemical and physical properties of the suspending environment.

Secondary stabilizing forces possessed by a charged hydrophillic colloid arise principally from ionic dissociation of constituent groups on the macromolecule rather than by adsorption of ions. It is convenient to picture a charged lyophillic colloid as having a diffuse double layer of ions collected around it. The zeta potential is interpreted in the same manner as for lyophobic colloids, being the potential at the surface of shear in the diffuse double layer, and is measured in the same way, that is, by use of a zeta potential meter or by electrophoresis techniques.

Coagulation of Colloidal Waste Systems

Lyophobic Colloids

Coagulation, or agglomeration of the particles in a lyophobic colloidal system, can be brought about by neutralization of the surface charge on each particle to the point where the repulsive forces will be less than the London-van der Waal forces of attraction. Because the zeta potential directly indicates the strength of the net charge on each particle, a reduction of the zeta potential is synonymous with a reduction of the stabilizing forces of the sol. A zeta potential of zero (the isoelectric point of the system) corresponds to minimum stability; however, the zeta potential need not be zero for coagulation to take place. It must be reduced only to within a certain minimum range, referred to as the "critical zeta potential zone."

The zeta potential can be reduced by one or a combination of several methods, including increasing the electrolyte concentration of the sol, reducing the potential on the surface of the dispersed solid by external manipulation of the pH, and/or by adding multivalent counterions. The Schulze-Hardy rule states that the sensitivity of a colloid system to destabilization by addition of counter-ions increases far more

rapidly than the increase of the charge of the ion. That is, in increasing from a divalent charge to a trivalent charge, the effectiveness of a coagulant increases far more than a factor of 3/2. Overbeek illustrated this rule by showing that a negatively charged silver iodide colloid was coagulated by 140 millimoles per liter of NaNO_3 , 2.6 millimoles per liter of $\text{Mg}(\text{NO}_3)_2$, 0.067 millimoles per liter of $\text{Al}(\text{NO}_3)_3$, and 0.013 millimoles per liter of $\text{Th}(\text{NO}_3)_4$.

The distinction between primary stability, imparted by the surface charge, and secondary stability, pertaining to the effective repulsion of colloidal particles because of the magnitude of the zeta potential, is useful for interpreting the coagulation of these particles by the addition of multivalent ions counter to the surface charge of the colloid. The presence of the multivalent counter-ions brings about a condition whereby the charges in the double layers are so compressed that the counter-ions are eventually contained, for the most part, within the water layers that originally contained the solvated ions in the double layer. The primary stability is thus reduced as a consequence of neutralization of the charge on the surface of the colloid, and the secondary stability is reduced because the particles can now approach each other to within a distance corresponding to coalescence of their water sheaths (water solvating the counter-ions and co-ions in the diffuse double layer) (recall that, if an ion is dissolved, it has, by definition, many water molecules surrounding it and "bonded" to it by "hydrogen bonding") without prohibitive repulsion between their respective diffuse double layers of ions.

Lyophilic Colloids

The principal stabilizing factor in the case of lyophilic sols is the solvating force exerted on the particles (not on the ions in the diffuse double layer) by the suspending medium. Electrolytic repulsion between the particles, although of lesser importance to the total stabilizing force, must also be dealt with for the ultimate coagulation of a lyophilic colloid system. Two methods can be employed to desolvate lyophilic colloids. In the first method, a liquid can be added to the system that is both a poor solvent

for the suspended particle and highly miscible with the suspending medium. When this is done the colloid is no longer able to form bonds with the medium that are stronger than the internal bonds between elements of the medium, and the principal stabilizing factor is removed.

This process is called "coacervation." The other method is to add a substance, such as a sulfate salt, which can form stronger solvation bonds with the solvent than the solvent can with the suspended colloids. When this is done, the added salt effectively pulls the hydrated water layer from the surface of the colloid, again, destroying the principal stabilizing factor. This process is known as "salting out." The actual destabilizing mechanism as well as the overall effect of both of these methods is the same. In each case, the dispersing medium is able to form stronger bonds (thus decrease its free energy more) with the additive than with the dispersed phase. If the previously solvated particles carry no net charge at this point, that is, have either zero, or very small zeta potential, they will flocculate and separate from the dispersing phase, once coacervation has been accomplished.

If they do possess a net charge, resulting in a significant zeta potential and thus repulsive forces stronger than the London-van der Waal forces of attraction, the colloids will not coagulate but will remain in suspension as a lyophobic sol. Coagulation must then be effected according to the methods presented in the section on Lyophobic Sols.

Figure 8-15 presents a diagrammatic representation of the various types of colloidal systems and how destabilization results in removal.

Coagulants such as alum, ferric sulfate, and cationic polyelectrolytes all work by suppressing the zeta potential of the colloidal system to a value sufficiently low that the colloidal particles will collide, and then coalesce, under the influence of slow stirring. Anionic and non-ionic polyelectrolytes can greatly aid in building much larger flocculated particles that will both settle faster and produce a less turbid effluent. Used in this manner, the anionic and

nonionic polyelectrolytes are referred to as "coagulant aids."

When alum ($\text{Al}_2(\text{SO}_4)_3 \cdot 18\text{H}_2\text{O}$) dissolves in water, some of the aluminum goes into true solution as the trivalent aluminum ion, Al^{+++} . If some colloidal particles have a negative surface charge, the trivalent aluminum ions, plus other aluminum species such as $\text{Al}(\text{OH})^{++}$ and $\text{Al}(\text{OH})_2^+$, will be attracted to these negatively charged surfaces and will suppress the net negative surface charge, which is to say they will suppress the zeta potential. Other metal salts that dissolve to yield trivalent ions, such as ferric sulfate, ferric chloride, and aluminum chloride, coagulate colloidal suspensions with effectiveness similar to that of alum.

Salts that dissolve to yield divalent ions, such as calcium chloride or manganous sulfate, also reduce the zeta potential and eventual

coagulation, but with an efficiency far less than the difference in ionic charge might indicate. As explained previously, the Shultz-Hardy rule states this effect.

Laboratory experimentation is always required to determine the optimum doses of coagulants and coagulant aids. There is no characteristic, substance, or property of a wastewater that can be measured, then used as an indicator of the quantity of coagulant required. There is no substitute for performing "jar tests."

A suggested procedure for conducting a jar test program to determine the optimum quantities of reagents and pH range is presented in the section on Reactions to Produce an Insoluble Solid. This procedure is identical to that recommended for determining the optimum doses of coagulants. The observations made




Figure 8-15 Diagrammatic representation of the various types of colloids. The colloids in the upper row are lyophillic; those below are lyophobic. pH increases from right to left.

during steps 5 and 6 will be oriented toward the disappearance of the turbidity originally present in the test solution, as opposed to the turbidity caused by the initial appearance of precipitated target substances as in the case of the reactions to produce an insoluble solid.

Reaction to Produce a Biologically Degradable Substance from a Nonbiodegradable Substance

Some substances that are resistant to biodegradation can be chemically altered to yield material that is biodegradable. Examples are long-chain aliphatic organics made soluble by attachment of ionizable groups, and cellulose or cellulose derivatives.

Hydrolysis, under either acidic or alkaline conditions, can be used to break up many large organic molecules into smaller segments that are amenable to biological treatment. Heat may be required for effective hydrolytic action, and consideration of proper reaction time is very important.

Certain fats and oils are made water soluble by chemically attaching ionizable groups such as sulfonates or ammonium groups to their long-chain hydrocarbon structures, for use in leather tanning, conditioning and finishing, and other industrial uses. These water-soluble fats and oils are found in wastewaters from the industries that produce them, as well as in the wastes from the industries that use them. They are characteristically resistant to biodegradation, which is one of the reasons for their usefulness.

Hydrolysis of these water-soluble fats and oils can break them into small segments that are still soluble in water and readily degradable by anaerobic microorganisms, aerobic microorganisms, or both. Laboratory experimentation is required to determine the technological feasibility for a given industrial waste, as well as a cost-effective process.

Substances that are made from cellulose or derivatives of cellulose are resistant to biological degradation, even though the basic building block for cellulose is glucose, a substance that is among the most readily biodegraded substances

in existence. The reason for the nonbiodegradability of cellulose is that microorganisms found in aerobic biological treatment systems are not capable of producing an enzyme that can break the particular linkage structure, known as the "beta link," that joins the individual glucose molecules end-to-end to produce the very long chain that ultimately winds around itself to become cellulose.

Acid hydrolysis, usually requiring some heat, is capable of breaking cellulose into small segments. Just how small depends on the conditions of the hydrolysis process, as regards acidity, heat, catalysts, and reaction time. In general, anaerobic microorganisms are capable of rapidly biodegrading segments of cellulose that are in the size range of a few hundred glucose units, whereas aerobic microorganisms require that the cellulose be broken down into much smaller units.

A patented process that is based on the principles described earlier uses hydrolysis to alter the structures of refractive organics that remain in wasted biological treatment sludge after aerobic or anaerobic digestion has been carried out to essential completion. As an alternative to dewatering and disposing of this digested sludge, which, by definition, is not biodegradable, it can be broken into smaller organic units by hydrolysis, then sent back through the industry's biological treatment process from whence it came. Advantage can be taken of periods of low loading, such as weekends, holidays, periods of plant shutdown for maintenance, or during shifts when loadings to the treatment plant are low.

Reaction to Destroy, or Otherwise Deactivate, a Chelating Agent

Often, removal of metals from an industrial wastewater by simple pH adjustment, with or without addition of sulfide, carbonate, phosphate, or a carbamate, is ineffective because of the presence of chelating agents. Chelating agents, discussed in Chapter 2, are of various makeup and include organic materials, such as EDTA, or inorganic materials, such as polyphosphates. The following sections enumerate

methods that are candidates for solving this type of wastewater treatment problem.

Organic Chelating Agents

1. Destroy the chelating agent by acid hydrolysis.
2. Destroy the chelating agent by hydroxyl free radical oxidation, using one of the following technologies, as discussed in the section entitled Oxidation or Reduction to Produce a Nonobjectionable Substance.
 - a. Fenton's reagent (H_2O_2 + Ferrous ions)
 - b. Hydrogen peroxide + Ultraviolet light
 - c. Ozone + Hydrogen peroxide
 - d. Ozone + Ultraviolet light
3. Destroy the chelating agent by adding potassium permanganate and heating. (The manganese ions will then have to be removed along with the target metals.)
4. Pass the wastewater through granular activated carbon. In some cases, the chelating agent will adsorb to the carbon. In some of those cases, the chelated metal will remain chelated and thus be removed on the carbon. In other cases, adsorption to the carbon effects release of the metals, which can then be precipitated without interference from the chelating agents.


Inorganic Chelating Agents

1. Add a stronger chelating agent, such as heptonic acid, or EDTA, both of which are organic. Then, use one of the methods given in step 1 for organic chelating agents.
2. Add a stronger chelating agent, such as heptonic acid or EDTA. Then it is sometimes possible to remove the metals by passing the wastewater through a strong cationic exchange resin generated on the hydrogen (acid) cycle.
3. If the chelating agent is polyphosphate, it may be feasible to hydrolyze it with acid and heat.

As with most cases involving industrial wastewater treatment, a proper program of laboratory experimentation, followed by truly representative pilot plant work, must be conducted to develop a cost-effective treatment scheme. The "throwsome method," wherein one throws some of a candidate reagent into a sample of wastewater to "see if anything good happens," is perfectly proper to do during periods of break or frustration, but must never be used to forever eliminate consideration of a reagent or technology that comes to mind based on fundamental properties or chemistry.

Oxidation or Reduction to Produce a Nonobjectionable Substance

Some highly objectionable substances can be chemically oxidized and some can be reduced to produce nonobjectionable substances such as carbon dioxide and water. An example is the destruction of the common rodenticide warfarin by potassium dichromate, acid, and heat, as represented by equation 8-18.



As shown in equation 8-18, highly toxic warfarin is oxidized to harmless carbon dioxide and water. Also shown in equation 8-18 is the presence of Cr^{+++} in the effluent, which may have to be removed in a subsequent step.

The removal of chromium from industrial wastewaters by chemically reducing hexavalent chrome ions, which are soluble in water and highly toxic, to the trivalent state, which is neither soluble (in the correct pH range) nor toxic, is another example of treatment by chemical oxidation or reduction to produce nonobjectionable substances. Reducing agents that have

been found to work well include sulfur dioxide, sodium or potassium bisulfite, or metabisulfite, and sodium or potassium bisulfite plus hydrazine. The correct range of pH, usually in the acid range, must be maintained for each of these chemical reduction processes to proceed successfully.

Table 8-7 presents additional examples of treatment of industrial wastewater by oxidation or reduction of an objectionable substance to produce one or more nonobjectionable substances.

Oxidation of (soluble) Ferrous Ions to (insoluble) Ferric Ions by Oxygen

Iron is soluble in water in the +2 (ferrous) valence state. Ferrous ions are very easily oxidized to the +3 (ferric) valence state, soluble only in strongly acidic aqueous solutions. The oxygen content of air is a sufficiently strong oxidizing agent to effect this oxidation.

Aeration, followed by sedimentation, has been used successfully to remove iron from industrial and other wastewaters, including landfill leachate. The aeration step accomplishes conversion of the dissolved ferrous ions to the insoluble ferric state. The ferric ions quickly and readily precipitate from solution as ferric oxide (Fe_2O_3), which forms a crystal lattice that builds to particle sizes that settle well under the influence of gravity. Coagulants and/or coagulant aids are often used to assist the coagulation and flocculation process, and thus, produce a higher-quality effluent.

A benefit that often results from removing iron by oxidation followed by sedimentation is that other metal ions, all of which are inherently hydrophobic, “automatically” adsorb to the particles of ferric oxide as they are forming via precipitation. They are thus removed from solution along with the iron. This process, known as “co-precipitation,” is sometimes augmented by actually adding more ferrous ions to

Table 8-7 Examples of the use of chemical oxidation or reduction to produce non-objectionable substances

1.	Alkaline chlorination of cyanide to produce carbon dioxide, nitrogen gas, and chloride ion.
2.	Chemical reduction of hexavalent chromium (toxic) to produce insoluble, less-toxic trivalent chromium.
3.	Oxidation of (soluble) ferrous ions to the insoluble ferric state by exposure to oxygen (air).
4.	Destruction of organic materials such as toxic substances (solvents and pesticides, for example) and malodorous substances (methyl mercaptan and dimethyl sulfide, for instance) by oxidation by free radicals.
a.	Hydrogen peroxide + Ultraviolet light
b.	Fenton's reagent (H_2O_2 + Ferrous ions)
c.	Ozone + Hydrogen peroxide
d.	Ozone + Ultraviolet light
5.	Oxidation of organics with ozone, which may or may not involve free radicals.
6.	Oxidation of organics with hydrogen peroxide, which may or may not involve free radicals.
7.	Destruction of toxic organics by oxidation with heat, acid, and either dichromate or permanganate. Products are carbon dioxide, water, and some nonobjectionable refractory compounds. Just about any organic compound can be destroyed by this method.
8.	Wet air oxidation of various organics such as phenols, organic sulfur, sulfide sulfur, and certain pesticides. This process takes place under pressure, with oxygen supplied as the oxidizing agent by compressed air.
9.	Chlorination of hydrogen sulfide to produce elemental sulfur. Subsequent neutralization is usually required.

the wastewater in the form of ferrous sulfate or other ferrous salt in an amount sufficient to co-precipitate other metals.

Oxidative Destruction of Organics by Free Radicals

Free radicals are powerful oxidizers that can convert many organics all the way to carbon dioxide, water, and fully oxidized states of other atoms that were part of the original organic pollutants, including sulfates and nitrates. Free radicals can be generated in a controlled manner to destroy a host of objectionable organic substances, including pesticides, herbicides, solvents, and chelating agents. As discussed previously, chelating agents interfere with the mechanisms employed to remove metals (by precipitation, for instance).

A free radical is an atom, or group of atoms, possessing an odd (unpaired) electron (has no partner of opposite spin). A free radical has such a powerful tendency to obtain an electron of opposite spin, and thus attain thermodynamic stability that it will easily extract one from an organic molecule. When this happens, the organic molecule, or a portion of it, becomes a free radical itself, goes after another molecule, organic or otherwise, forming another free radical, and so on. A chain reaction is thus set up and, if managed properly, can be induced to continue until nearly all of the target substance has been removed.

Management of the chain reaction consists of maintaining the pH of the system within a range favorable for the reaction and supplying enough of the free radical-generating substance (discussed as follows) to keep the process going. Side reactions (with reducing agents) "kill" free radicals. If the rate of "killing" free radicals exceeds the rate of generation of free radicals for a long enough time, the treatment process terminates.

A free radical, then, has one unpaired electron and has the same number of electrons as protons. A negatively charged ion, in contrast, has an even number of electrons, each paired with another electron of opposite spin, and has more electrons than protons.

Free radicals can be generated by the following methods:

1. Adding hydrogen peroxide.
2. Adding hydrogen peroxide to a solution that contains ferrous ions, either present in the wastewater or added along with the hydrogen peroxide (Fenton's reagent).
3. Adding hydrogen peroxide, then irradiating with ultraviolet light.
4. Adding ozone and hydrogen peroxide.
5. Adding ozone and irradiating with ultra violet light.


Oxidation with Hydrogen Peroxide

Hydrogen peroxide has the chemical formula H_2O_2 and is an oxidizing agent that is similar to oxygen in effect but is significantly stronger. The oxidizing activity of hydrogen peroxide results from the presence of the extra oxygen atom compared to the structure of water. This extra oxygen atom is described as a "peroxidic oxygen" and is otherwise known as "active oxygen."

Hydrogen peroxide has the ability to oxidize some compounds directly; for instance, alkenes, as shown following. Peroxidic oxygen adds to the double bond, producing a hydroperoxide as shown in equation 8-19:

The hydroperoxide then autooxidizes to alcohols and ketones.

Hydrogen peroxide consists of two hydrogen atoms and two oxygen atoms, bonded by shared electron pairs as shown in Figure 8-16.








Figure 8-16 Structure of hydrogen peroxide.


The oxygen — oxygen single bond is relatively weak and is subject to break-up to yield $\bullet\text{OH}$ free radicals:






or,



The two $\bullet\text{OH}$ free radicals sometimes simply react with each other to produce an undesirable result; however, the radical can attack a molecule of organic matter, and in so doing, produce another free radical. This is called a chain-initiating step:




As previously discussed, in free radical oxidation of organics, this process continues in such a way that the organics are broken down all the way to carbon dioxide and water.




Hydrogen Peroxide Plus Ferrous Ion (Fenton's Reagent)

Hydrogen peroxide will react with ferrous ions to produce ferric ions, hydroxide ions, and hydroxyl free radicals, as shown in equation 8-20:



The hydrogen peroxide thus dissociates into one hydroxide ion (nine protons and ten electrons [OH^-]) and one hydroxyl free radical (nine protons and nine electrons [$\bullet\text{OH}$]), as shown in equation 8-21:



In this case, there is only one $\bullet\text{OH}$ free radical, as opposed to two $\bullet\text{OH}$ free radicals, when hydrogen peroxide breaks down in the absence of ferrous ions as discussed previously. The single $\bullet\text{OH}$ then attacks a molecule of organic material, also previously discussed, initiating a chain reaction (chain-initiating step) with the result that the organic material is eventually oxidized all the way to carbon dioxide and water.

Hydrogen Peroxide Plus UV Light

When hydrogen peroxide is added to an aqueous solution, which is simultaneously irradiated with ultraviolet light (UV), the result is that the hydrogen peroxide breaks down more readily into $\bullet\text{OH}$ free radicals than when the UV is not present, as illustrated in equation 8-22:




There are, therefore, significantly more hydroxyl free radicals to enter into chain-initiating steps, as discussed previously, than is the case without UV.

Ultraviolet light greatly increases the oxidative power of hydrogen peroxide, in a manner similar to that of metal activation (Fenton's reagent). Although it has not been made clear how the reaction proceeds, it seems likely that the ultraviolet energy enables hydrogen peroxide to either separate into two hydroxyl free radicals, each having nine protons and nine electrons, as suggested by equation 8-23:



or to obtain an electron from some source, probably the target organic compounds, and thus dissociate into one hydroxide ion (nine protons and ten electrons (OH^-)) and one hydroxyl free radical (nine protons and nine electrons ($\bullet OH$)), as shown in equation 8-24:



The hydroxyl free radicals then go on to enter or perpetuate a chain reaction, as shown previously.


Oxidation with Ozone

Ozone, having the chemical formula, O_3 , is a gas at ambient temperatures. Ozone has physical characteristics similar to oxygen but is a far stronger oxidizing agent. Ozone reacts with organic compounds in a manner similar to that of oxygen, adding across double bonds and oxidizing alcohols, aldehydes, and ketones to acids. Ozone requires less assistance than does oxygen, as from heat, catalysts, enzymes, or direct microbial action.



Ozone Plus Hydrogen Peroxide

Addition of both ozone and hydrogen peroxide has the effect of oxidizing to destruction

many organics much more strongly and effectively than by adding either ozone or hydrogen peroxide alone. When both ozone and hydrogen peroxide are present in water containing organics, $\bullet OH$ free radicals are formed through a complex set of reactions. The result of the complex reactions is that two $\bullet OH$ radicals are formed from one hydrogen peroxide and two ozone molecules:




The $\bullet OH$ radicals then react with organics to form harmless carbon dioxide, water, and other smaller molecules. As an example, $\bullet OH$ radicals react with trichloroethylene and pentachlorophenol. The products in both cases are carbon dioxide, water, and hydrochloric acid:





The ozone plus hydrogen peroxide system has the advantage, compared to, say, Fenton's reagent, that ozone itself will react in a first-order reaction with organics, resulting in further reduction of pollutants.

In addition to the formation of $\bullet OH$ radicals, as shown by equation 8-26, there may also be formation of oxygen free radicals, as follows:




Oxygen free radicals may then enter into chain reactions to break up organics in equations 8-29 and 8-30:



This chain reaction may continue to destroy many organics in addition to those destroyed by ozone and the $\bullet\text{OH}$ radicals.

Ozone Plus UV Light


Ozone can be used in combination with ultraviolet light to, in some cases, produce more rapid and more complete oxidation of undesirable organic matter than with either ozone or ultraviolet light alone. Equation 8-31 illustrates this alternative process:



Here, again, free radicals may or may not be involved.

Chlorination of Hydrogen Sulfide to Produce Elemental Sulfur

Hydrogen sulfide is objectionable for several reasons, including its contribution to crown corrosion in sewers and its malodorous character. Hydrogen sulfide can be oxidized to elemental sulfur as shown in equation 8-32:



It may then be necessary to neutralize the hydrochloric acid by one of the usual methods.

Additional methods of oxidizing hydrogen sulfide to either sulfate ion or elemental sulfur (both odor free) include the following:

1. Raising the level of dissolved oxygen (beyond the level of saturation at atmospheric pressure) by adding oxygen under pressure.
2. Adding hydrogen peroxide.
3. Adding potassium permanganate.

In the cases of oxygen under pressure or hydrogen peroxide, oxygen oxidizes (takes electrons away from) sulfur atoms. Normally, if the pH is in the alkaline range, the sulfur atoms will be oxidized to elemental sulfur, and 1 gram of hydrogen sulfide will require about 2.4 grams of H_2O_2 , depending on side reactions. If the pH is in the acid range, the sulfur will be oxidized all the way to sulfate ion, and

each gram of hydrogen sulfide will require four times more, or about 9.6 grams of hydrogen peroxide as the pure chemical. In contrast, each gram of hydrogen sulfide will require about 4.2 grams of chlorine (as Cl_2) or 11.8 grams of potassium permanganate (KMnO_4) to oxidize the sulfur to elemental sulfur.

Co-Precipitation

Although technically a physical treatment method because adsorption is the mechanism, co-precipitation is discussed here because it is often brought about as a result of chemical treatment to produce an insoluble substance of another target pollutant. For instance, both arsenic and cadmium are effectively co-precipitated with aluminum or iron. If there is dissolved iron (the soluble form is the ferrous, or +2 state) and arsenic and/or cadmium in an industrial wastewater, oxygen can be added to form insoluble ferric oxide, which then builds a rather loose crystal lattice structure. This precipitate exists in the wastewater medium as a suspension of particulate matter. As these particles are building, arsenic and/or cadmium ions, which are relatively hydrophobic, adsorb to them, effectively removing them from solution. As the particles settle to the bottom of the reaction vessel, and the resulting "sludge" is removed, the treatment process is completed; however, the removed sludge must now be dealt with. As discussed in the section entitled Physical Treatment Methods, the usual procedure is to separate the water from the particles, using vacuum filtration, sludge pressing, or another physical separation process, followed by evaporation. The resulting dry mixed metals can be subjected to metal recovery processes, stored for later metals recovery, or properly disposed of.

Table 8-8 presents an enumeration of successful applications of co-precipitation for industrial wastewater treatment.

Solvent Extraction

Solvent extraction operates on the principle of differential solubilities. When a substance (solute) is dissolved in one solvent and a solvent

Table 8-8 Applications of Co-precipitation of Metals as a Wastewater Treatment Method

1.	In wastewaters containing iron plus other metals, the wastewater can be aerated to oxidize soluble ferrous ions to insoluble ferric ions. As the ferric ions precipitate from solution, dissolved species of other metals will adsorb to the growing crystalline precipitates and will thus be removed from solution.
2.	In wastewaters of low pH that contain aluminum ions, adjusting the pH to 6.3 or so will cause the aluminum to precipitate. The aluminum precipitate particles, which include oxides and hydroxides, act as effective adsorption sites for other metals.
3.	One of the most effective methods for removing arsenic from wastewaters is to oxidize all of the arsenic to arsenate, then add a source of ferrous ion, such as ferrous sulfate. Then, by maintaining the pH in the neutral range, and allowing oxygen to react with ferrous ions and precipitate as Fe_2O_3 crystals, the arsenate will adsorb to the growing crystals, become entrapped, and be effectively removed.


in which that substance is more soluble than it is in the first solvent is added, and the two solvents that are not miscible with each other (not soluble in one another) are mixed vigorously together, the dissolved substance will pass from the first solvent into the second. The driving force is the second law of thermodynamics, as explained in Chapter 2. The stronger bond energies that result when the substance is dissolved in the second solvent result in a lower level of free energy than was the case with the first solvent.

Thermal Oxidation

Certain highly toxic organics, such as PCBs and dioxin, are best destroyed by thermal oxidation. Dow Chemical Co., as well as others, constructed incinerators in the 1940s to safely dispose of wastes from the manufacture of many different chemicals.

PCBs, which are resistant to biodegradation (meaning that they are biodegraded very slowly), are destroyed completely by incineration, but temperatures of 2300°F or more are required. Other organics are destroyed at lower temperatures, and each application must be tested and proven.


Thermal oxidation has often been used to remediate contaminated soil. The mechanism and products of thermal oxidation are the same as for chemical oxidation with oxygen. The mechanism is electrophillic attack, and the products are carbon dioxide, water, and oxidized ions and molecules such as sulfate, sulfur oxides, and nitrogen oxides. Equation 8-33 represents the thermal oxidation process.



When thermal oxidation is required, as opposed to chemical oxidation, it is because the energy of activation required for the reactants shown in equation 8-33 is too great for the reaction to proceed without heat, which supplies the energy of activation needed.

Catalytic Oxidation

When the energy of activation required for oxygen, or another oxidizing agent, to react with a certain organic substance is too great for the reaction to proceed under normal conditions, two ways to overcome this deficiency are (1) to add heat to supply the energy of activation, and (2) to add a catalyst, which reduces the energy of activation. When heat is added, the process is called thermal oxidation. When a catalyst is added, the process is called catalytic oxidation. The principal products are the same, namely, carbon dioxide and water (when the oxidation process is allowed to go to completion), and the mechanism of oxidation is basically the same, except for the effect of the catalyst in reducing the activation energy. In many cases, the catalyst is not consumed in the process, as illustrated in equation 8-34:



Biological Methods of Wastewater Treatment

Biological treatment of industrial wastewater is a process whereby organic substances are used as food by bacteria and other microorganisms. Almost any organic substance can be used as food by one or more species of bacteria, fungi, ciliates, rotifers, or other microorganism. In being so used, complex organic molecules are systematically broken down, or “disassembled,” then reassembled as new cell protoplasm. Oxygen is required in either the dissolved molecular form or in the form of anions such as sulfate and nitrate. The end result is a decrease in the quantity of organic pollutants, and an increase in the quantity of microorganisms, carbon dioxide, water, and other by-products of microbial metabolism.

The following relationship describes the biological treatment process (equation 8-35) where:

Organic matter

1. Is regarded as pollution before the treatment process.
2. Is used as food by the microorganisms.
3. Might have been formed by a natural process, by a living plant or animal, or synthetically by a chemical manufacturing process.
4. Is composed of the elements carbon, hydrogen, oxygen, nitrogen, phosphorus, and many additional elements in much smaller amounts. These elements are connected by chemical bonds, each of which is characterized by a certain quantity of energy called “bond energy.” As the microorganisms disassemble the organic matter, they are able to capture much of this energy and use it to make new chemical bonds, in the synthesis of new protoplasm; however, the process is less than 100% efficient. Fewer chemical bonds can be assembled in the process of

cell synthesis than were disassembled during the microbial degradation process. Because of this, the microorganisms need a way to get rid of carbon, hydrogen, and other atoms that result from the process of degradation but for which there is not sufficient energy to form carbon-carbon and other high-energy bonds required in the cell synthesis process. Because relatively low-energy bonds can be formed with oxygen, the microorganisms expel excess carbon atoms as CO_2 and excess hydrogen atoms as H_2O . Other elements, if in excess, can be combined with oxygen as well and passed off into solution as the oxide. Nitrate and sulfate are examples.

Microorganisms

1. Include bacteria, fungi, protozoa, nematodes, and worms.
2. Exist in a hierarchical food chain within which bacteria and fungi feed directly on the organic matter (pollutants), and the higher life forms (protozoa, nematodes, etc.) feed on the bacteria.


Oxygen

Is referred to as:

- a. a hydrogen acceptor
- b. an electron acceptor

More microorganisms

1. Are the result of growth of the microorganisms originally present.
2. Must be handled and disposed of as waste sludge.
3. Typically amount, in mass, to one-third to one-half the amount of organic matter (pollutants) originally present in the untreated wastewater, when the organic material is measured as BOD and the microorganisms are measured as dried solids.



C₀₂

1. Is a waste product, in that it is a method used by the microorganisms to expel carbon atoms that have resulted from degradation of the organic pollutants, but for which there is not sufficient energy to make carbon-carbon and other higher-energy bonds needed to make new cell material in the cell growth process.
2. Microorganisms do not disassemble organic molecules for the fun of it. They do it because they have a compulsion to grow (i.e., increase in numbers).

H₂O

1. Is a waste product.
2. Is the mechanism used by microorganisms to expel excess hydrogen atoms, derived during the process of disassembling organic matter.

With respect to oxidized organic matter:

1. The degradation of organic matter by the microorganisms is not 100% complete.
2. The organic matter in the untreated wastewater may contain some organic molecules that the microorganisms are unable to degrade.

All biological treatment processes—aerobic, anaerobic, suspended growth, and fixed growth (also referred to as “fixed film”)—are accurately represented by this relationship. The differences in the various configurations of processes are in the speed of reaction, form of oxygen used, relative amounts of “more microorganisms” and “oxidized organic matter” produced, and in the types of tankage and equipment and amount of land required.

The overall process depicted by equation 8-31 involves diffusion of the molecules of organic matter through the aqueous medium (the wastewater itself), and adsorption (or other type of attachment) of these organic molecules onto the surface of the microorganisms. Then, the microorganisms to which the molecules, or particles, of organic matter are attached must manufacture enzymes capable of breaking the

organic molecules or particles down into elementary segments that can pass through the microorganism’s cell membranes. Then, the cells’ metabolic machinery “metabolizes” the elementary segments of organic material, rearranging molecular structures and building more cell protoplasm in order to grow by binary fission, and “wasting” a certain amount of the food as carbon dioxide, water, and some low-molecular-weight organics (oxidized organic material).

Bacteria and fungi are the primary converters of whatever organic materials are in the wastewater to new cell protoplasm and waste materials; however, these single-celled microorganisms make up only a portion of the multitudinous diverse life forms that populate a biological treatment system. In a mature treatment system, a food chain hierarchy becomes established that ranges from the single-celled primary converters through several species of protozoa, rotifers, worms, and, in some cases, algae, and many other types of microscopic life forms. The rotifers and successively higher life forms graze on one or more of the lower life forms (the primary converters), and the trick to managing a well-operating biological treatment system is to manipulate the “feeding” of the microorganisms and removal of certain quantities of the microorganisms on a periodic basis (wasting), in order to maintain optimum relative numbers of the various life forms. In activated sludge systems, this is best done by controlling sludge age to within a range that works best for each individual system.

Development of Design Equations for Biological Treatment of Industrial Wastes

Two equations are used to mathematically describe the fundamental kinetics of the “treatment” that takes place as a result of microorganisms converting organic material to new cell mass, carbon dioxide, water, and residual material, referred to as “oxidized organic material,” “other low-molecular-weight compounds,” or “refractory organics.”

These equations are empirical, are applicable to the treatment of wastes in all environmental media (as examples, activated sludge treatment of wastewater containing organics, biofiltration of air streams containing hydrogen sulfide, and biodegradation of organics in landfilled sludge), and are stated as follows:

$$\frac{dX}{dt} = Y \frac{dF}{dt} - k_d X \quad (8-36)$$

$$\frac{dF}{dt} = \frac{k X S_e}{K_s + S_e} \quad (8-37)$$

where:

X = Mass of microorganisms (grams or pounds).

F = Mass of organic matter used as food by the microorganisms (normally expressed as BOD) (milligrams or pounds).

Y = Constant. Represents the proportion of organic matter that gets converted to new microorganism cell material (dimensionless).

k_d = Constant. Represents the proportion of the total mass of microorganisms that self-degrade (endogenous respiration) per unit time (inverse days).

K = Maximum rate at which the microorganisms represented by the symbol X are able to degrade the organic matter, no matter how much organic matter is present.

S_e = Mass of F at the conclusion of the degradative process. Equivalent to mass of BOD in the treated effluent.

K_s = Mass of organic matter, F, that induces the microorganisms, X, to degrade that organic matter at a rate equal to one-half the maximum possible rate, k.

Two additional parameters are defined as follows:

$$\begin{aligned} \Theta_c &= \frac{X}{\Delta X / \text{day}} & (8-38) \\ &= \text{mean cell residence time} \\ &= \text{sludge age} \end{aligned}$$

where:

Θ_c = the average amount of time a component of the microbial population spends in the reactor before exiting as effluent solids or being removed as daily wasting in order to maintain a constant amount of microorganisms in the reactor.

$$U = \frac{dF/dt}{X} \quad (8-39)$$

Figure 8-17 illustrates the parameters k and K_s . As shown, when the concentration of food, or substrate (designated by F, S, BOD, etc.), is very low, it is therefore limiting, and an increase in concentration of food results in a proportionate (described by the slope of the line that extends from the origin in a straight manner) increase in utilization (eating) rate. When the concentration of substrate reaches a certain level ($S_{\max}$), and from that concentration on, food is not limiting, and the microorganisms utilize the food at their maximum rate, k. At the concentration of substrate equal to one-half $S_{\max}$, the rate of substrate utilization is equal to K_s . The numerical value of k, as described previously, is specific for a given population of microorganisms feeding on a given type, or mixture, of organic substances. As will be shown later, the value of k that is chosen by a design engineer has a direct effect on the size of treatment system, and therefore the cost, not to mention performance. The




Figure 8-17 Specific utilization vs. substrate concentration.

appropriate value of k for given treatment systems has been the subject of heated debate and even lawsuits. More appropriately, however, it has been the subject of considerable research. Values of k have been reported throughout the environmental engineering literature and have ranged from 0.01 to 5.0, a difference of a factor of 5,000! It is always necessary to understand the conditions under which a value of k was determined before using that value for any kind of size calculation for a treatment facility.

In the case of a mixture of substances such as is typical of industrial wastewater, a k rate is applicable to each individual substance. Moreover, when a mixture of substances is utilized by a population of microbes, those substances that are most readily utilized—glucose, for instance—exhibit the highest value of k . As each of the more easily utilized substances in the original mixture is depleted, the apparent value of k decreases. Figure 8-18 illustrates how the apparent value of k changes with time, as a mixture of substances is utilized.

As shown in Figure 8-18, as a population of microorganisms begins utilizing a mixture of substances, the apparent value of k for the mixture is relatively high. As the most easily utilized substance becomes scarce, the microorganisms begin utilizing, successively, those substances that are more difficult to utilize, and the apparent value of k decreases. For the mixture as a whole, then, the most appropriate value for k is an approximate “average” value, or one that is observed over a lengthy period.

In fact, all of the rate constants in the previous equations are specific for the particular population, or “mix,” of the microbes present at any given time, as well as for the type or mixture of types of organic matter. These equations were developed using completely soluble substrate (food) and pure cultures of bacteria. Monod, who developed equation 8-37, used pure cultures of *E. Coli* and *B. Subtilis* in broths of glucose and mannose.

Dividing dF/dt by X normalizes the rate of substrate removal to a unit weight of microorganisms, enabling comparison of performance among systems having different food-to-microorganism mass loading parameters. The result




Figure 8-18 Apparent value of k vs. time for a mixture of substances.

of this mathematical operation is U , the specific substrate utilization rate, as shown in equation 8-39. The parameter U_b would be equal to the food-to-microorganism ratio, F/M , if 100% treatment were taking place.

The fundamental relationships given earlier can be rearranged to develop equations, which can be used for design purposes. Table 8-9 presents several versions of design equations derived from one or more of the basic relationships shown previously. The parameters X , X_0 , t , F , and S_e are measured directly. Θ_c can be calculated, and the parameters Y , k_d , k , and K_s can be determined from the results of either bench scale pilot plant data or data from full-scale treatment systems, as shown following.

Development of Biological Treatment Kinetics in the Laboratory

Bench scale pilot treatment systems can be used to generate values for the kinetic coefficients and constants needed in design equations as follows; four or more treatment systems are operated for several days at steady state and are identical in all respects except for food-to-microorganism ratio (F/M), and those parameters that F/M affects. Those parameters include mixed liquor volatile suspended solids concentration (MLVSS), which is directly related to the value of X . As the

four or more laboratory bench scale pilot units are run simultaneously, the parameters X , X_e , t , F , and S_e are determined each day for several consecutive days. Alternatively, a single, larger-sized pilot unit, or a full-scale treatment plant, can be used. In this case, the system must be operated under conditions of one value of F/M at a time. After four periods of steady state operation at four or more values of constant but different F/M values, the analysis can be carried out. Each time the F/M value is changed, the treatment unit must be operated at that F/M value for a time

period equal to at least three sludge-age periods before it can be assured that “steady state” has been achieved.

The analysis consists of, first, plotting values of the inverse of Θ_c vs. U , as in Figure 8-19. The value of Y is the slope of the straight line of best fit for the plotted data points, as shown in Figure 8-18, and the value of k_d is that of the vertical intercept.

Next, the inverse of the values of U for each of the four or more treatment systems is plotted against the inverse of the corresponding values of S_e , as shown in Figure 8-20.

Table 8-9 Design Equations for Biological Treatment Systems

Characteristics	Complete Mix		
	No Recycle	With Recycle	Plug Flow with Recycle
Hydraulic Residence Time	$\Theta = \frac{V}{Q}$	$\Theta = \frac{V/Q}{1+R}$	$\Theta = \frac{V/Q}{1+R}$
Concentration of BOD ₅ in effluent	$S_e = \frac{K_s(1+K_d\Theta)}{\Theta(k-k_d)-1}$	$S_e = \frac{K_s(1+K_d\Theta_c)}{\Theta_c(k-k_d)-1}$	
Active Biomass Concentration	$X = \frac{[X_0 + (S_0 - S_e)Y]}{1 + k_d\Theta}$	$X = \frac{Y(S_0 - S_e)}{1 + k_d\Theta_c} \times \frac{\Theta_c}{\Theta}$	$X = \frac{Y(S_0 - S_e)}{1 + k_d\Theta_c} \times \frac{\Theta_c}{\Theta}$
Sludge Age	$\Theta_c = \Theta$	$\Theta_c = \frac{K_s + S_e}{S_e(k - k_d) - k_d K_s} \Theta_c^{-1} = (k - k_d) - \left(-\frac{KY(1+R)}{\Theta X} \ln \frac{(S/S_e) + R}{1+R} \right)$	




Figure 8-19 Plot of $1/\Theta_c$ vs. $1/U$




Figure 8-20 Plot of $1/U$ versus $1/S_e$

The vertical intercept in Figure 8-20 is the value of k , and the slope of the line of best fit (Figure 8-20) is equal to K_s/k . Having thus determined values for all of the parameters that appear in the design equations presented in Table 8-9, the design of a new or modified microbiological treatment system, or troubleshooting an existing treatment system, can proceed.

Example 8-5:

Design an aeration tank to reduce the BOD_5 of an industrial wastewater to below 50 mg/L. The BOD_5 of the raw wastewater averages 1,714 mg/L. Primary treatment is expected to remove 30% of the BOD_5 . The average rate of flow is 250,000 gallons per day.

Solution:

Use complete mix with recycle.

The first step is to determine design values for the appropriate kinetic constants:

$$k = 0.51 \text{ hr}^{-1}$$

$$K_s = 325 \text{ mg/L BOD}$$

$$Y = 0.57$$

$$kd = 2.4 \times 10^{-3} \text{ hr}^{-1}$$

$$\Theta = 12 \text{ hrs.} = \text{HRT}$$

$$\Theta_c = 10 \text{ days} = \text{Sludge Age}$$

$$a = 1.5 \text{ mg COD/mg MLVSS}$$

$$b = \text{COD/BOD} = 1.4$$

1. Estimate the soluble BOD of the treated effluent using the following relationship

$$\begin{aligned} S &= \frac{K_s(1 + kd\Theta_c)}{\Theta_c(k_0 - kd) - 1} \\ &= \frac{325(1 + 2.4 \times 10^{-3} \times 10 \times 24)}{10 \times 24(0.51 - 2.4 \times 10^{-3}) - 1} \\ &= 4.24 \text{ mg/L} \end{aligned}$$

Note that this is soluble BOD, which should always be 10 mg/L or less if biological treatment is reasonably complete. It would not be uncommon that the total 5-day BOD would be in the range of 30 to 50 mg/L for a wastewater having a BOD as high as 1,714 mg/L.

2. Reactor Volume:

$$\begin{aligned} V &= Q \times \Theta \\ &= 250,000 \text{ gal/day} \times 1 \text{ ft}^3/7.48 \text{ gal} \times 12/24 \\ &= 16,700 \text{ ft}^3 \end{aligned}$$

3. Required MLVSS concentration:

$$\begin{aligned} X &= \frac{Y(S_0 - S_e)}{1 + kd\Theta_c} \times \frac{\Theta_c}{\Theta} \\ &= \frac{0.57(1200 - 4.24)}{1 + 2.4 \times 10^{-3} \times 10 \times 24} \times \frac{10 \times 24}{12} \end{aligned}$$

$$= 8,655 \text{ mg/LMLVSS}$$

$$\therefore \text{MLSS} = 8,655 \div 0.92 = 9,400 \text{ mg/L}$$

4. Calculate the recycle ratio if the concentration of solids in the recycle is 20,000 mg/L:

$$R = \frac{1 - \frac{\Theta}{\Theta_c}}{\frac{X_r}{\bar{X}} - 1} = \frac{1 - \frac{12}{10 \times 24}}{\frac{20,000}{9,400} - 1} = 0.84$$

$$\therefore \text{Recycle } Q = 0.84 \times \text{influent } Q$$

$$Q_r = 0.84Q$$

5. Calculate the solids generation rate:

$$X_w = \frac{VX}{\Theta_c}$$

$$= \frac{16,700 \text{ ft}^3 \times 8,655 \text{ mg/L} \times \frac{1 \text{ lb}}{454 \times 10^3} \times \frac{3.78 \text{ L}}{\text{gal}} \times \frac{7.48 \text{ gal}}{\text{ft}^3}}{10 \text{ days}}$$

$$= 900 \text{ lb/day}$$

6. Calculate the oxygen consumption rate:

$$\frac{\text{OXYGEN DEMAND}}{\text{VOLUME} \cdot \text{TIME}}$$

$$= \frac{S_0 - S_e}{\Theta} (1 - ay) + 0.9a \cdot kd \cdot X$$

$$= \frac{1.4(1200 - 4.24)}{12} \left(1 - 1.5(0.57) \times \frac{0.92}{1.4} \right)$$

$$+ 0.9 \cdot 1.5 \times 2.4 \times 10^{-3} \times 8,655$$

$$= 182 \text{ mg O}_2/\text{L/hr}$$

Because the volume of the reactor is 16,700 ft³:

$$16,700 \text{ ft}^3 \times \frac{7.48 \text{ gal}}{\text{ft}^3} \times \frac{3.78 \text{ L}}{\text{gal}} \times \frac{0.182 \text{ g}}{\text{L} \cdot \text{hr}} \times \frac{1 \text{ lb}}{454 \text{ g}}$$

$$= 190 \text{ lb Oxygen per day}$$

The Role of Oxygen in Wastewater Treatment



All forms of biological metabolism involve the disassembly of organic compounds (the food) and reassembly into new cell protoplasm (growth) and waste products. Not all of the food can be converted to new cell protoplasm, however. It takes a certain amount of energy, in the form of chemical bond energy, to assemble

new protoplasm; that is, to complete the chemical bonds that hold the carbon, hydrogen, and other elemental units together. The source of that energy is the relatively high-energy bonds in the molecules of the organic matter that is used as food. For instance, when a molecule of glucose is disassembled to obtain energy to build protoplasm material, carbon-carbon bonds are broken, with the consequent release of 60 to 110 kcal/mole of bond energy, depending on what atoms are bonded to the carbon atom being worked on.

Having obtained the energy from the carbon-carbon bond (and other bonds the carbon atoms were involved in), the organism has no further use for the carbon atoms. These “waste” carbon atoms cannot simply be discharged to the environment by themselves, however. They must be attached to other atoms and discharged to the environment as simple compounds. Because this process also requires energy, the “waste” compounds must be of lower bond energy than those of the food that was disassembled. The balance is then available for constructing new cell protoplasm.

The atoms to which the “waste” atoms are bonded are known as “ultimate electron acceptors.” This name arises from the fact that the electrons associated with the waste carbon atoms are paired with electrons of the “ultimate electron acceptor” in constructing the molecule of waste substance.

The function of oxygen in cell metabolism (any cell—animal, plant, or bacterial) is that of ultimate electron acceptor. If the source of oxygen is molecular O₂ dissolved in water, the process is termed “aerobic,” and is depicted in equation 8-40:



(bacterial growth not shown here)

Notice that equation 8-40 shows that unwanted hydrogen atoms from the “food” are

wasted by attaching them to oxygen and discharging them to the environment as water (H_2O).

If the source of oxygen is one or more dissolved anions, such as nitrate (NO_3), or sulfate (SO_4) and if there is no (or very little) dissolved molecular oxygen present, the process is termed "anoxic," and is depicted in equation 8-41: (microbiological growth not shown here)

If there is no oxygen present, either in the molecular O_2 form or in the form of anions, the condition is said to be "anaerobic." Under anaerobic conditions, cell metabolism takes place as a result of substances other than oxygen functioning as the ultimate electron acceptor. Equation 8-42 depicts this type of microbiological treatment.


The microorganisms involved in the process depicted by equation 8-42 are extremely useful in certain industrial waste treatment applications; for instance, treatment of sugar refinery wastes and fruit-processing wastes, which characteristically contain very low quantities of nitrogen and phosphorus compared to the amount of BOD. In a properly designed and operated facultative lagoon, in which there is enough mixing to maintain movement of essentially all the liquid (to enhance contact between dissolved organics and to reduce short-circuiting), but not enough aeration is applied to maintain more than the upper 2 or 3 feet of the lagoon in an aerobic state, incoming dissolved BOD is rapidly "sorbed" onto microbial cells, which eventually settle to the lagoon bottom. Then, within the sludge layers

at the lagoon bottom, anaerobic degradation takes place, whereby the sorbed organics are metabolized, and new (anaerobic) bacterial cells are produced as a result of bacterial "growth." The production rate of new cells, in terms of pounds of new cells produced per pound of organic matter treated (measured as BOD) is significantly less than is the normal case for aerobic treatment. The advantageous result is significantly less waste sludge requiring disposal.


As indicated in the parenthetical notes, equations 8-35, 8-40, and 8-41 show only the process of wasting excess carbon, hydrogen, and, in the case of equation 8-41, sulfur atoms, and do not include the growth process whereby some of the carbon, hydrogen, sulfur, nitrogen, and other atoms are reassembled to produce new cell protoplasm. These equations show only that the energy recovered from some of the disassembly process must be used to create bonds for waste products, such as carbon dioxide, water, and other compounds or anions.

Biological Treatment Technologies

Figure 8-21 presents an enumeration of the principal variations of biological methods of wastewater treatment. As seen in Figure 8-21, it is convenient to classify biological treatment processes as either aerobic or anaerobic (notice that, as used in this sense, the term, "anaerobic" includes both anoxic and anaerobic). Within each of those two major categories, there are two principal types of systems:



organic matter + sulfate anions $\rightarrow$ carbon dioxide + hydrogen sulfide + methane






Figure 8-21 Aerobic and anaerobic methods of wastewater treatment.

suspended growth and attached growth. The suspended growth systems all have diverse populations of microbes suspended in a mixture of liquid that includes the wastewater being treated. When the concentration of microbes is relatively high, as in the case of activated sludge, the mixture of suspended microbes, wastewater being treated, and other substances, both dissolved and suspended, is referred to as "mixed liquor suspended solids" (MLSS). The term "MLVSS" is used to designate that portion of the MLSS that is active microbes. The V in this term stands for "volatile." That the MLVSS concentration is only an approximate indicator of the actual concentration of active microbes in a mixture of activated sludge is discussed in Chapter 6.

Attached growth systems all have masses of microbes attached to a medium. Wastewater to be treated flows in contact with this medium and, especially, the attached microorganisms. The microbes are able to access the organic matter in the wastewater as a result of the wastewater flowing over, around, and through the media to which the microbes are attached. The

trickling filter and the rotating biological contactor are familiar examples of fixed growth systems.

As explained earlier, aerobic wastewater treatment systems require that dissolved molecular oxygen, as the molecule O_2 , be present and available to the microbes as they disassemble organic pollutant molecules. It is convenient to categorize aerobic wastewater treatment systems according to their relative "intensity of treatment." A treatment system of high intensity is one in which the concentrations of both pollutants and microorganisms are high. Oxygen must be added in high quantity to maintain aerobic conditions, and the system is said to be relatively highly stressed. Aerobic biological treatment systems range in intensity from high-rate activated sludge, having MLVSS concentrations as high as 10,000 mg/L and hydraulic retention times as low as a few hours, to very low-stressed aerobic or facultative nonaerated lagoons having MLVSS concentrations of less than 100 mg/L and hydraulic retention times of more than 100 days. Figure 8-22 presents an ordering of




Figure 8-22 Distribution of various types of activated sludge treatment systems, based on treatment intensity, in terms of mass loading of BOD (lbs/BOD/ft³/day).

aerobic, suspended growth wastewater treatment systems ranging from stabilization ponds to high-rate activated sludge. Fixed growth systems also vary in treatment intensity but normally over a smaller range than suspended growth systems.

Development of the most cost-effective suspended growth system is usually a matter of tradeoff between capital cost and operation and maintenance (O&M) costs. The present value of the total capital cost spread over the useful life of the facility and the O&M costs, also expressed as present value in order to allow direct comparison, often change in inverse proportion to each other. Low-intensity systems require larger tankage and more land area but fewer O&M costs in terms of electrical power for aeration and labor costs for operators. High-intensity systems require more skilled operators and significantly more oxygen supplied by mechanical means but smaller tankage and land area.

Treatment of Industrial Wastewaters Using Aerobic Technologies

Suspended Growth Systems: Activated Sludge

An activated sludge wastewater treatment system has at least four components, as shown in Figure 8-23; an aeration tank and a settling tank (clarifier), a return sludge pump, and a means of introducing oxygen into the aeration tank. Wastewater, sometimes pretreated and sometimes not, enters the aeration tank (and is, therefore, the “influent”) and is mixed with a

suspension of microbes in the presence of oxygen. This mixture is referred to as “mixed liquor.” The microbes “metabolize” the organic pollutants in the wastewater, converting them to more microbes, carbon dioxide, water, and some low-molecular-weight organics, as depicted in equation 8-35. After spending, on average, an amount of time equal to the hydraulic residence time (θ) in the aeration tank, the mixed liquor flows into the clarifier, where the solids (MLSS) separate from the bulk liquid by settling to the bottom. The clarified “effluent” then exits the system. The settled solids are harvested from the clarifier bottom and are either returned to the aeration tank or are “wasted.” Those MLVSS solids that are returned to the aeration tank are microbes in a starved condition, having been separated from untreated wastewater for an extended period, and are thus referred to as “activated.” This process of returning microbes from the clarifier to the aeration tank enables buildup of their concentrations to high levels (1,800 to 10,000 mg/L), and that, indeed, characterizes the activated sludge process itself.

Those MLSS that are taken out of the system, and are therefore referred to as “wasted,” represent the main means of controlling the “mean cell residence time,” or “sludge age.” Sludge age is an extremely important parameter in the successful operation of an activated sludge treatment system. Activated sludge systems that are maintained at a very low sludge age, on the order of two days or so, contain what is known as a very young population, which is typically highly active and mobile and




Figure 8-23 Basic components of an activated sludge system.

difficult to induce to settle well in the clarifier. Activated sludges having somewhat longer sludge ages, between 7 and 15 days, have many more microorganisms per unit of organic "food." They are, therefore, in a much more starved condition than a sludge of young sludge age and tend to predation and cannibalism. When food becomes very scarce, the microorganisms themselves become food. The live bacteria and fungi are food for higher life forms, and those that die, break apart, and spew their cell contents into the fluid medium are food for other bacteria and fungi.

In order to defend themselves against predation and cannibalism, some microbial species are able to exude and surround themselves with a protective mass of a polysaccharide material. In addition to affording protection, this gelatinous material helps to flocculate the microbes that make up the MLVSS, enabling better settling characteristics in the clarifier.

When the sludge age increases to more than 20 days or so, the microbes become so advanced in predatory behavior that they develop the ability to manufacture enzymes that can break down the polysaccharide protective material. The sludge thus loses its excellent flocculent nature and, consequently, its good settling characteristics.

The best settling activated sludge and, therefore, the system that produces the clearest effluent, is that system in which the gelatinous polysaccharide protective material is maintained in optimum amounts.

In terms of treated effluent quality, the effluent from activated sludge systems having very low sludge ages is typically high in suspended solids; those having sludge ages of around 10 days have low suspended solids, and those having a very high sludge age are often very high in suspended solids.

An excellent tool for use in maintaining an optimum activated sludge culture, in terms of treatment performance, settleability, and low concentration of solids in the effluent, is the microscope. The usefulness of microscopic examination of activated sludge as an aid for process control can be explained as follows.

Consider a container of fresh, biodegradable wastewater, inoculated with a "seed" of activated sludge from a well-operating treatment system. The container is aerated, well-mixed, and receives a steady supply of biodegradable organics, but at a rate that is slower than the growth rate of the microbial population that develops. Figure 8-24 depicts such a system. Initially, there is a very high concentration of "food" compared to the numbers of microorganisms. Under this condition, bacteria multiply at their maximum rate. Each individual bacterial cell "grows," and by the process of binary fission, becomes two cells within a time period corresponding to the maximum attainable growth rate of that particular species, which can be as short a time as 20 minutes. A logarithmic increase in numbers of the fastest-growing bacteria that can readily metabolize the organics in the wastewater takes place, and those bacteria dominate the population during the first few hours. Examination of a sample of the contents of the container, using a microscope, shows this to be the case.

Figure 8-24 depicts the relative numbers of several of the major types of microbes, as they increase and decrease, with time, under the conditions described in the preceding paragraph. As shown in Figure 8-24, during the initial hours, there is not much growth of anything, while the microbes with which the container was "seeded" become adjusted to the new environment. They need to manufacture the appropriate enzymes for the particular molecules of food available. This period is referred to as the "lag phase of growth."

As the first individual bacteria develop these enzymes and begin to grow, the phase of increasing growth rate occurs, and, eventually, full logarithmic growth takes place and continues as long as food is unlimited and predation does not occur. Figure 8-25 shows the so-called growth curve that applies to each individual species of microbe within the container. This figure shows that, sooner or later, within any biological system that can be described by the preceding paragraphs, food becomes limited and the rate of growth declines. Some individual microbes grow and some die. Normally,




Figure 8-24 Progressive growths and deaths of microorganisms in activated sludge.




Figure 8-25 Typical growth curve.

there is a period when the growth rate equals the death rate, and the population is stable. Finally, as the food supply runs out, and/or predation exceeds growth, the population declines.

Returning to Figure 8-24, and considering the microbial population within the container as a whole, as the bacteria that first begin growing reach high numbers, microbes that prey on them begin to grow. Then, in succession, higher forms of microorganisms that can feed on the microorganisms that grow earlier (and are thus said to be higher on the food chain) go through their own growth curve process. In a biological treatment system, that succession is typically flagellated bacteria (bacteria equipped with a "tail" that propels them), free-swimming ciliates, stalked ciliates, rotifers, and finally, worms. Microscopic examination of a sample of the microbial population from a given treatment system, then, can reveal the current stage of development of the system, in terms of "young sludge" or "old sludge."

Experience has shown that, usually, optimum operation of activated sludge occurs when the relative proportions of amoeboids, flagellated bacteria, free-swimming ciliates, stalked ciliates, and rotifers are as shown in Figure 8-26. Figure 8-26 shows that, when activated sludge is in a young condition, the relative numbers of flagellated bacteria and free-swimming bacteria are high, and there are almost no stalked ciliates. The effluent from the secondary clarifier is high in suspended solids, and many of those solids consist of long, thin bits and pieces of ill-formed activated sludge, referred to as "stragglers." The cure for this condition is to decrease the food-to-microorganism ratio by wasting less sludge and allowing the concentration of MLVSS in the aeration tank to increase.

Figure 8-26 shows further that when the relative proportions of rotifers, stalked ciliates, and nematodes becomes high, compared to the flagellated bacteria and free-swimming ciliates, there will again be high solids in the effluent from the secondary clarifier. In this case, the solids appear as tiny, more or less spherical bits and pieces of activated sludge,

referred to as "pin floc." The cure for this condition is to increase the rate of sludge wasting, thus increasing the food-to-microorganism ratio.


Unfortunately, it is not always the case that adjusting the rate of sludge wasting cures problems of high suspended solids in the treatment system effluent. Conditions other than sludge age that can affect effluent quality are concentration of dissolved oxygen in the aeration tank, degree of mixing, the changing nature of the influent to the aeration tank, temperature, and the presence of toxic materials. High numbers of filamentous organisms within the activated sludge community, as explained in the section titled Selectors, is a common cause of poor effluent quality.

Selectors. Among the most common problems associated with activated sludge treatment systems is the poor settling of the activated sludge itself, referred to as "bulking sludge," caused by the presence of so-called filamentous microorganisms. Filamentous microorganisms, sometimes called "filaments," are characterized by long strands of "hairlike filaments." A small amount of these microbes is good to have because they help to produce clarity in the effluent, but too many lead to an unacceptably slow settling rate.

There are three principal causes for the development of excess numbers of filamentous microbes within an activated sludge system: (1) low concentrations of nutrients, especially nitrogen and/or phosphorus; (2) low levels of dissolved oxygen, either throughout the aeration tank or in pockets within the aeration tank (resulting from inadequate mixing); and (3) low levels of organic loading (low F/M ratio). So-called selectors have been very effective in preventing the development of dominant populations of filamentous microorganisms from occurring.

A selector is a device that counteracts the third of these causes. It is basically a chamber in which the activated sludge experiences high F/M conditions for a period that is short compared to the time spent in the aeration tank.

Figure 8-26 Relative predominance of microorganisms versus F/M and SRT.



Under the high F/M conditions, the “good” microbes outcompete the bad (filamentous) microbes, preventing their growth. In the high F/M environment, the nonfilamentous microbes adsorb most of the dissolved organics, leaving insufficient food for the filamentous organisms in the more dilute environment of the aeration tank.


The most common type of selector is a tank of 10 to 30 minutes hydraulic retention time, completely mixed, in which return sludge and untreated wastewater are commingled before proceeding to the aeration tank. This tank can be separate from the aeration tank, or it can be a compartment within the aeration tank. Often, the latter can be done at lower construction cost. Figure 8-27 shows two general variations of construction of selectors.

Selectors can be aerobic, anoxic, or anaerobic but must always be well mixed. Therefore, a selector should be equipped with both mechanical mixing and aeration, in order to provide the flexibility to operate aerobically or otherwise, as experience indicates which produces the best results.

VARIATIONS OF THE ACTIVATED SLUDGE PROCESS. Activated sludge is essentially a biological wastewater treatment process in which microorganisms feed on waste organic matter in an aeration tank, grow in numbers as a result, are separated from the treated wastewater in a clarifier that follows, hydraulically, the aeration

basin, and are then returned to the aeration basin in a starved condition in order to greatly increase the numbers of microorganisms in the aeration tank. The basic process is extremely flexible and capable of many different configurations. Table 8-10 lists eight alternative configurations and presents comments regarding the characteristics and appropriate use of each.

CONVENTIONAL PLUG FLOW. If there is a standard of reference for the activated sludge wastewater treatment process, it is the conventional plug flow system; however, conventional plug flow is by no means the most common variation of biological treatment system used for industrial wastes. Figure 8-23 presents a schematic of conventional plug flow. Table 8-10 notes several important features or characteristics that distinguish this system from other variations of the activated sludge process. As shown in Figure 8-28, and noted in Table 8-10, the most outstanding characteristic of plug flow is the long, narrow pathway the wastewater must traverse in flowing from the inlet to the outlet of the aeration tank. The reason for this is to ensure that the microbes, having entered the aeration tank as return sludge at the tank inlet, have sufficient time to be in contact with the organic matter contained in the volume of wastewater they originally mixed with, in order that as little mixed liquor as possible gets through the tank in a period



(a) Tank of 10-30 min. hydraulic retention time, located within aeration tank




(b) Tank of 10-30 min. hydraulic retention time, located outside aeration tank

Figure 8-27 Variations in selector configuration.

TABLE 8-10 Variations of the Activated Sludge Process

<i>Process Variation</i>	<i>Comment</i>
Conventional plug flow	Aeration tanks are long and narrow to minimize short-circuiting. Operational parameters range as follows: HDT; 4-6 hrs, F/M; 0.3-0.6, MCRT; 7-14 days, F/M is high at head of tank, low at effluent end.
Conventional complete mix	Aeration tanks square or circular, conc. of substances everywhere equal to conc. in effluent, shock effects minimized, operational parameters as for conventional plug flow.
PACT process	Aeration tanks either plug flow or complete mix. Powdered act. carbon added to aeration tank to remove nonbiodegradable organics. Operational parameters as for other variations.
Extended aeration	Aeration tanks as for either plug flow or complete mix, sludge wasting rate low, MCRT 20 days or more, MLVSS 1,600-2,200 mg/L, F/M 0.05-0.1. Hydraulic retention time 20 hours or more.
High rate aeration	Aeration tanks as for complete mix, F/M; 0.8-1.2, MLVSS; 5,000-10,000 mg/L, aeration rate very high, HRT; 3-6 hrs, MCRT; 15-25 days.
Contact stabilization	Aeration tank as for plug flow or complete mix, contact tank precedes clarifier, sludge flows to aeration tank, MLSS in aeration tank (called stabilization tank) 3,000-6,000 mg/L, HRT; contact tank 30 min or so, HRT; stab. tank 3-8 hrs.
Sequencing batch reactor	Aeration tank as for complete mix, operational parameters as for conventional, aeration tank and clarifier are one and the same.
Pasveer ditch	Aeration tank unique configuration, see description below. Operational parameters similar to conventional plug flow.
Deep shaft	Aeration tank unique configuration, see description below. Operational parameters similar to conventional plug flow.

**Figure 8-28** Basic flow pattern of the conventional plug flow variation of the activated sludge process.

shorter than the theoretical detention time. An important design objective, then, is to minimize short-circuiting.

Several different approaches have been used to create a long, narrow flow path through the aeration tank. The most common approach has been to make use of baffles in a rectangular tank as shown in Figures 8-29 (a) and (b); however, research has shown that baffles create dead volumes, as depicted in Figure 8-30. Figure 8-30 shows that, as the

mixed liquor flows from the inlet to the outlet, dead volumes exist in the regions of corners and wherever flow proceeds around the end of a baffle. The undesirable effects of the dead volumes are (1) reduction of the working volume of the aeration tank, with consequent reduction of actual HRT, and (2) development of anaerobic conditions in the dead volumes with consequent bad odors and development of filamentous bacterial populations.



Figure 8-29 Baffle arrangements in a flow-through tank.




Figure 8-30 "Dead volume" in a baffled, flow-through tank.

CONVENTIONAL COMPLETE MIX. The “complete mix” variation of the activated sludge process is modeled after the familiar completely mixed continuous flow reactor, which is used in many manufacturing processes. The mathematical relationships that were developed many years ago and published in the chemical engineering literature can be used for design as well as for operation. For instance, the “standard” equation that relates the change in concentration of a given substance entering a completely mixed reactor to the concentration leaving the reactor as influenced by the theoretical hydraulic retention time and the reaction rate is given by:

$$C_{ei} = \frac{C_{oi}}{1 + k_t} \quad (8-43)$$

where:

C_{oi} = Concentration of substance i entering the reactor.

C_{ei} = Concentration of substance i exiting the reactor.

k = Rate of reaction of substance i in the reactor.

t = Amount of time, on the average, molecules or other elemental quantity of substance i spend in the reactor.

Stated in terms of kinetic parameters, as developed earlier in this chapter, the concentration of BOD_5 (for instance) in the effluent from

a completely mixed activated sludge system is given by:

$$S = \frac{K_s(1 + k_d\Theta_c)}{\Theta_c(k - k_d) - 1} \quad (8-44)$$

where:

S = Concentration of substrate (i.e., BOD_5) in the effluent.

K_s = Mass of organic matter that induces the microorganisms to degrade that organic matter at a rate equal to one-half the maximum possible rate, k .

k_d = Constant. Represents the proportion of the total mass of microorganisms that self-degrade (endogenous respiration) per unit time (inverse days).

k = Maximum rate at which the microorganisms represented by the symbol X are able to degrade the organic matter, no matter how much organic matter is present.

Figure 8-31 is a diagrammatical representation of a wastewater treatment plant designed to operate in the completely mixed mode.

One of the major differences between the conventional plug flow system and the complete mix system is in regards to short-circuiting. In the plug flow variation, the objective of both design and operation is to keep short-circuiting to an absolute minimum. As little as




Figure 8-31 Schematic diagram of a complete-mix activated sludge system.

possible of the incoming pollutants should reach the effluent in amounts of time shorter than the theoretical hydraulic retention time, calculated by dividing the volume of the tank by the flow rate. In the case of the complete mix system, the objective is to manage short-circuiting, recognizing that a certain quantity of the pollutants will reach the effluent almost immediately after entering the aeration tank.

Figure 8-31 illustrates that when an elemental volume of flow enters the reactor, it is immediately dispersed throughout the reactor. The effluent, at any instant in time, is simply an instantaneous sample of the completely mixed contents of the reactor. Therefore, the concentration of any given substance in the effluent is the same as its concentration in the reactor, and the effluent necessarily contains a small amount of unreacted substance.

The primary advantages, then, of the complete mix variation of the activated sludge process, are:

1. Slug doses of any given constituent are quickly diluted to the maximum extent afforded by the aeration tank.
2. The amount of short-circuiting and, therefore, the amount of unreacted pollutant can be controlled in a direct manner, by manipulation of the flow rate (for a given volume of aeration tank), and determined by calculation.

The complete mix variation of the activated sludge process is often favored for application to industrial wastewaters, largely because of its ability to dilute slug doses of substances and to withstand periodic changes in wastewater characteristics because of changes in activity within the manufacturing plant. Either diffused or mechanical aeration can be used, and, in some cases, when the concentration of substances to be treated is low (relatively, volume of aeration tank is high), a combination of mechanical mixing devices plus diffused or mechanical aeration is the least costly system.

THE PACT MODIFICATION OF ACTIVATED SLUDGE. The powdered activated carbon technology (PACT) modification of the activated sludge

process is a proprietary process that was developed during the mid-1970s to solve problems that related to the nonbiodegradability of certain synthetic organics. The PACT process is essentially one of the familiar variations of the activated sludge process with the additional feature that powdered activated carbon is added to the aeration tank. The activated carbon is incorporated into the MLSS to adsorb organics that are dissolved in the wastewater. The activated carbon adsorbs almost any organic, whether biodegradable or not, but the adsorbed biodegradable organics tend to be removed by microbial action, whereas the nonbiodegradable organics do not. The result is that the activated carbon becomes saturated with nonbiodegradable organics and eventually must be removed from the system. Figure 8-32 shows, diagrammatically, the PACT modification of activated sludge in the complete mix mode.

Because the powdered activated carbon is incorporated into the MLSS within the activated sludge system, it is removed as a consequence of normal sludge wasting that is done to control the mean cell residence time (sludge age). The wasted sludge can then be incinerated to reduce the volume of excess biological solids and, at the same time, regenerate the activated carbon. Experience has shown that about 20% of the adsorptive capacity of the activated carbon is lost with each regeneration; therefore, continual makeup with new activated carbon is required.

The appropriate quantity of powdered activated carbon must be determined, first, by laboratory experimentation, then by operating experience. To prevent discharge of excessive nonbiodegradable organics during start-up and during the first few weeks of operation of a PACT system, an excessive quantity of activated carbon should be added, then the concentration reduced gradually until one or more of the target substances begins to be detected.

PREDICTIVE MATHEMATICAL MODEL OF THE PACT PROCESS. A predictive mathematical model that can be used to analyze laboratory scale pilot




Figure 8-32 PACT modification of the activated sludge process, complete-mix configuration.

data to develop design parameters for a full-scale PACT system is presented as follows.

The parameters needed to design the biological portion of the PACT process are the same as for ordinary activated sludge; namely, the coefficients Y , k_d , k , and K_s , as explained previously. Furthermore, the laboratory procedures to use to develop values for these parameters are the same as presented earlier; namely, the use of "block aerators," and the daily monitoring of food in, food out, sludge growth, and oxygen utilized. In the case of the PACT process, however, it is necessary to determine, and then subtract, the influences of organic matter removed and daily sludge increase, in order to determine those values that were caused by biological activity.

EXTENDED AERATION ACTIVATED SLUDGE. The extended aeration modification of activated sludge has the design objective of lower costs for waste sludge handling and disposal, at a sacrifice of higher capital costs because of larger tankage and more land area per unit of BOD loading. There may be a savings in O&M costs resulting from a lower level of intensity required from the operators, but there is an increase in the amount of oxygen required per pound of BOD in the influent because of the increased amount of autooxidation (there is some increase in aeration via the surface of the aeration tank because of the larger surface area). The reduction in amount of wasted sludge to be disposed of per pound of BOD removed results from the increase in autooxidation (use of the contents of the cells of dead microbes for food) because of a longer sludge age. Table 8-10 shows the range of values for F/M loading, hydraulic detention time, sludge age, and MLVSS concentrations appropriate to the extended aeration modification of the activated sludge process.

HIGH-RATE MODIFICATION OF ACTIVATED SLUDGE. The high-rate modification of the activated sludge process is simply one of the previously described modifications (plug flow, complete mix, or other) in which the MLVSS concentration is maintained at a significantly higher concentration than is normal for

conventional processes, and hydraulic retention time is significantly shorter than "normal." The high-rate process can be used to treat readily biodegradable wastes such as fruit-processing wastewaters, but effective equalization is required to prevent short-term changes in waste characteristics.

Advantages of the high-rate process are that it is effective in overcoming the problem of the tendency toward bulking caused by dominance of filamentous organisms in complete mix systems, as well as lower construction costs because of smaller tankage. Disadvantages include relatively intense operational control requirements, as well as relatively large quantities of waste sludge because of less autooxidation.

CONTACT STABILIZATION MODIFICATION OF ACTIVATED SLUDGE. The contact stabilization modification differs from the conventional process in that the activities that normally take place in the aeration tank—adsorption of substances onto the microorganisms, then metabolism, or conversion of these substances to more microorganisms plus waste products—are separated. As shown in Figure 8-33, the untreated wastewater is mixed with return sludge in a relatively small "contact tank." The rapid process of adsorption of pollutants takes place here. The mixture then moves on to an aeration tank, or "stabilization tank," where microbial metabolism takes place. The aeration tank is also relatively small, compared to conventional activated sludge, because only the sludge, after separating from the bulk liquid in the clarifier, proceeds to the aeration tank. The bulk liquid is either discharged from the clarifier as final effluent or is subjected to further treatment, such as disinfection, sand filtration, or another process. Because only the sludge (with its load of adsorbed organic material) proceeds to the aeration tank, energy requirements for mixing are lower.

The principal advantage of contact stabilization is the lower capital cost because of smaller tankage; however, this modification is useful on only wastes that are rapidly adsorbed. In general, those wastes are characterized by a high proportion of dissolved, relatively simple organics.




Figure 8-33 Schematic of contact stabilization modification of activated sludge.

SEQUENCING BATCH REACTOR MODIFICATION OF THE ACTIVATED SLUDGE PROCESS. The sequencing batch reactor (SBR) process is a modification of complete mix activated sludge. As diagrammed in Figure 8-34, the two principal sequential processes of activated sludge— aeration and settling—take place in the same tank. Settling occurs, after sufficient aeration time for treatment has taken place, after turning off all aeration and mixing. Then, clarified supernatant is decanted, the reactor is refilled with fresh, untreated wastewater, and the cycle is repeated. Waste sludge is withdrawn immediately after the react phase has been completed.

An SBR is normally operated in six sequential stages, or phases, as follows:

1. Fill phase. The reactor is filled until the desired F/M ratio has been reached.
2. React phase. The reactor is mixed and aerated. Treatment takes place.
3. Sludge wasting phase. A quantity of mixed liquor that corresponds to the quantity of

solids, on a dry basis, is withdrawn from the completely mixed contents of the reactor. For instance, if a 10-day sludge age is desired, one-tenth of the volume of the reactor is withdrawn each day.

4. Settle phase. Aeration and mixing are terminated, and the reactor functions as a clarifier.
5. Decant phase. Clarified, treated wastewater is withdrawn from the top one-quarter to one-third of the reactor.
6. Idle phase. The system can be mixed and aerated at a low rate for a few days at a time needed between periods of waste generation.

There are several modifications to the basic procedure outlined previously. For instance, it has been found advantageous in some cases to either mix, aerate, or both, while filling is taking place. In these cases, the first one or two stages are referred to as the “mixed fill phase,” followed by the “react fill phase” (stages 1 and 2), or just “the react fill phase” (phase 1). Also,




Figure 8-34 Schematic of sequencing batch reactor process.

some operators have found it acceptable to waste sludge from the bottom of the reactor after settling has taken place. Although this practice results in handling less water with the waste sludge, it does not ensure the removal of the same fraction of the active microbial solids each day, as does the practice of wasting a certain fraction of the mixed reactor contents each day.

Among the several important advantages of the SBR process is its capability of having the react phase extended for as long as is necessary to achieve the desired degree of treatment. In this respect, it is good design practice to have at least two parallel SBR units, each of at least half the design capacity. In the absence of a parallel unit, a collection tank, designed and operated as an equalization basin, can receive and store wastewater until the SBR unit is able to receive more wastewater.

With two parallel SBR units, the following troubleshooting procedures are available to the operator:

1. If one of the units receives a large slug dose, the second unit can be used to perform double duty while the first unit is allowed to continue to react until the supernatant is suitable for discharge.

2. If one of the SBR units becomes upset because of toxicity, or another reason, the second unit can be placed in "double-duty mode," then the contents of the upset unit can be bled into the operating unit at as slow a rate as is necessary for complete treatment and recovery of the upset unit to take place. During extended periods of low waste generation, such as for yearly maintenance shutdown of the processing plant, all of the MLSS can be placed in one of the SBR units. It can then be "fed" a small amount of synthetic waste to maintain viability of the microbes.
3. As is the case for duplicate systems of any unit process, one can be used for treatment while the other is emptied for maintenance.

In short, the operator has more flexibility and control with SBR technology than with flow-through technology. Any or all of the cycle stages can be lengthened or shortened to achieve desired treatment. The "idle phase" allows taking up the slack between the total lengths of time of the other five phases and the 24-hour day.

SBR technology has successfully, and very cost effectively, been used for removal of nitrogen (by the nitrification-denitrification process).

It has also, but less frequently, been used to remove phosphorus.

The nitrification-denitrification process can be incorporated into the operation of an SBR system as follows:

1. Allow nitrification to take place during the react phase by:
 - a. maintaining dissolved oxygen (DO) level above 2 mg/L
 - b. maintaining the temperature within the reactor higher than 17° C
 - c. maintaining sufficient react time

If these conditions are maintained, and if no substances in the wastewater are toxic to the nitrosomonas species, nitrification of the ammonia released from the organic matter in “treating” the BOD will take place. Then, denitrification (conversion of the nitrate ions to nitrogen gas) can be induced by:

2. Discontinue aeration, but maintain mixing after the react phase.

During this period, the contents of the reactor become anoxic. Facultative bacteria (nitro-bacter) continue to oxidize organic matter (BOD) and use the oxygen atoms from the nitrate ions for an electron acceptor.

There are “tricks” to achieving successful nitrification-denitrification as well as desired BOD removal using SBR technology. One trick is to maintain the proper amounts of time for each phase. Another is to manage the amount of BOD remaining after the react cycle (by addition of methanol, if necessary) so there is enough to support the denitrification process, but not enough to cause noncompliance.

SBR technology can be used to achieve a lower quantity of phosphorus in the industrial waste discharge, but only with the successful application of more operator skill than for ordinary operation. Some phosphorus will always be removed with the waste sludge because all animal and plant cells contain phosphorus. The microbial cells of the activated sludge can be induced to take up more than the normal amount of phosphorus (referred to as “luxury uptake of phosphorus”). If this is done successfully, more

phosphorus than normal is included with each pound of waste sludge. The procedure for inducing luxury uptake of phosphorus in an SBR system is as follows:

3. Allow anaerobic conditions to develop within the contents of the reactor by the absence of aeration during the fill cycle. As soon as the small amount of nitrate that is contained in the MLSS at this point has been used up for its oxygen (electron acceptor) content, the microbes that are capable will turn to phosphate ions. The microbes will absorb and/or adsorb phosphate ions at this point, effectively removing them from the bulk liquid.
4. Allow sufficient time during and possibly after the fill phase for the “luxury uptake” of phosphorus to take place to the maximum. Experimentation that is carefully controlled and with observations recorded is required.
5. Conduct the sludge-wasting phase at this point, before the react phase.
6. Begin aeration and, consequently, the react phase.

The contents of the reactor should be well mixed, in order to maintain contact between the microbes and the dissolved phosphate ions, throughout steps 1 through 4.

PROCEDURE FOR DESIGN OF AN SBR SYSTEM. The following procedure can be used to design an SBR wastewater treatment system. In all instances where the word, “select” appears, the design engineer must have available either extensive experience with the wastewater in question, or the results of extensive laboratory and/or pilot treatability studies.

1. Select a hydraulic retention time.
2. Select an F/M loading.
3. Obtain the kinetic coefficients.
4. Select a value for the concentration of settled sludge.
5. Select a value for the specific gravity of the settled sludge.

6. Determine how much of the reactor will be decanted during the decant phase.
7. Select a depth of liquid (working depth).
8. Determine nutrient requirements.
9. Estimate, using the following calculation, the concentration of soluble BOD in the effluent:

$$S_e = \frac{K_s(1 + k_d\Theta_c)}{\Theta_c(k - k_d) - 1} \quad (8-45)$$

The result of performing several trials to balance a desired value for θ_c and the resulting value of S_e will produce the design value for θ_c .

10. Compute the mass of MLVSS required

$$X = \frac{Y(S_o - S_e)}{1 + k_d\Theta_c} \times \frac{(\Theta_c)}{\Theta} \quad (8-46)$$

11. Select a desired range for MLVSS concentration.
12. Calculate the size of the reactor, balancing the required volume for the desired HRT, the required volume to achieve the desired MLVSS concentration taking into consideration the calculated MLVSS mass required, and the volume needed to decant the desired volume each day.

PASVEER OXIDATION DITCH AND VARIATIONS. During the 1930s, Pasveer invented the “brush aerator” that consisted of a cylindrical street brush immersed to about 20% of its diameter in the mixed liquor of an activated sludge aeration tank. Figure 8-35 illustrates how, when the brush was rotated, it would throw droplets of the mixed liquor into the air, thus accomplishing aeration as oxygen molecules from the air dissolved in the water droplets. As with other mechanical aeration devices, the very large surface-to-volume ratio of the very large number of water droplets provided for effective dissolution of oxygen into the water. This inexpensive aerator was combined with an innovative aeration basin to produce a cost-effective extended aeration activated sludge treatment system. Figure 8-36 shows that the aeration basin was built in the shape of an oval, similar in

appearance to a race track. One or more brush aerators were placed to accomplish both aeration, by throwing droplets of mixed liquor (MLSS plus the bulk liquid) into the air, and mixing, by causing the mixed liquor to flow around and around the oval basin. In addition, a high degree of dissolution of oxygen into the mixed liquor through the liquid surface was accomplished. The movement of the mixed liquor, induced by the brush aerator, kept the mixed liquor mixed and continually renewed the surface with unaerated mixed liquor. Because the aeration basin was simply an oval ditch, construction cost was small, and because the surface-to-volume ratio of the mass of mixed liquor was high, surface aeration accounted for a large fraction of the total, thus, the cost for aeration was low. The system came to be known as the “Dutch Ditch,” acknowledging Pasveer’s nationality as well as the materials of construction of the aeration basin.

Since Pasveer’s time, several variations to his basic ideas have been developed. In some cases, the earthen basin has been replaced with other materials of construction, including concrete, asphalt, plastic membrane, and steel. Several devices have been used in place of the brush aerator. All such systems, however, have in common the high surface-to-volume ratio afforded by the shallow, oval-type aeration tank configuration, enabling relatively low cost for aeration and mixing.

DEEP SHAFT AERATION. Two perplexing problems with activated sludge treatment systems in general, and extended aeration systems in particular are (1) the characteristically low efficiency of transfer of oxygen from the air supplied, to actual use by the microorganisms (typically 2% to 15%), and (2) the relatively large land area required. In the case of conventional extended aeration systems, which attempt to reduce operation costs by autooxidation of sludge rather than by having to dispose of it by landfilling, the more extended the aeration, the more land area is required. The deep shaft aeration system was developed to solve, or significantly diminish, these two problems.




Figure 8-35 Pasveer's "brush aerator."




Figure 8-36 Schematic of Pasveer oxidation ditch.

With respect to low efficiency of oxygen transfer, one of the basic causes is the low driving force for dissolution of oxygen, which, as explained earlier, is simply the difference between the saturation concentration in the mixed liquor and the concentration that actually exists. This driving force can be increased in direct proportion to the value of the saturation concentration for any given value of the actual concentration. The saturation concentration can be increased in direct proportion to the pressure of oxygen in the gas volume that is in contact with the mixed liquor, and this pressure can be increased in direct proportion to the depth beneath the surface of the aeration basin

at which bubbles of gas containing oxygen exist. These facts led to the realization that if an aeration basin were configured as a very long U-tube of small diameter, and if this U-tube-shaped basin were oriented vertically to attain very high hydraulic pressure at the bottom, because of the very deep column of liquid above it, the saturation concentration of oxygen would be many times higher than usually experienced with activated sludge. The result would be a driving force many times greater, and transfer efficiency would increase accordingly. Thus, the deep shaft aeration system, shown diagrammatically in Figure 8-37, was developed.




Figure 8-37 Schematic of a deep shaft treatment system.

Figure 8-37 shows a deep shaft aeration system consisting of a 20-foot diameter boring into the earth, similar to a mine shaft. A partition separates the shaft into two compartments. Raw or, in some cases, pretreated, wastewater enters the compartment on the left and is drawn down toward the bottom of the shaft by a small difference in hydrostatic head between the two sides. Air bubbles are blown into the compartment containing “fresh” wastewater, only a few feet below the surface. Thus, the pressure against which the blowers work to force air into the mixed liquor is small. These air bubbles are carried down to the bottom of the shaft with the mixed liquor because the velocity of the fluid toward the bottom of the shaft is greater than

the rise rate of the bubbles. As the bubbles are carried deeper into the shaft, the hydrostatic pressure becomes greater, thus the pressure within the bubbles becomes greater. The greater pressure in the bubbles causes the saturation concentration of oxygen in the mixed liquor to increase proportionately; thus, the driving force for dissolving oxygen into water increases.

Pressure does not influence microbial activity; therefore, the bacteria and other microbes throughout the full depth of the shaft can utilize the oxygen within the air bubbles that were introduced into the mixed liquor under low-pressure conditions. The result is a profound increase in the efficiency of the transfer of oxygen.

Design and Operational Characteristics of Activated Sludge Systems. Table 8-11 presents important design and operational characteristics of five alternative configurations of the activated sludge method of wastewater treatment.

The parameters presented in Table 8-11 are “average” values, applicable to wastewaters that have concentrations of BOD, TSS, FOG, and other common parameters that are not far outside the normal ranges found in municipal wastewater. In cases of activated sludge treatment systems for industrial wastewaters having concentrations of BOD or other characteristics that are significantly outside these ranges, laboratory and/or pilot studies must be conducted. There is no reliable way to transpose, or interpolate, performance characteristics of one of these biological treatment processes as achieved with one type of wastewater on another, unless the fundamental characteristics of the pollutants in the wastewater are similar.

Aeration Systems for Activated Sludge. Air must be supplied to activated sludge systems

for mixing and to provide oxygen for microbial respiration. There is a wide range of alternative air supply systems available, and there can be as much as a 150% difference in total annual costs from one system to another. Figure 8-38(a)–(p) presents an enumeration of the major types of aeration devices available.

As shown in Figure 8-38, the two principal types of aeration device are mechanical and diffuser. The basic difference between the two is that the mechanical aerators cause small droplets of the mixed liquor to be thrown up out of the aeration tank, through the air above the tank, and back down into the tank. These mechanical devices also mix the contents of the aeration tank, with the objectives of (1) there being no “dead zones,” and (2) each portion of the liquid mass in the aeration tank being thrown into the air every few minutes. Oxygen transfer takes place through the surface of each droplet. For this reason, the more efficient mechanical aerators are those that create the largest surface-to-volume ratio of the activated sludge mass per unit of energy expended per unit of time, explained as follows.

Table 8-11 Design and Operational Characteristics of Activated Sludge Systems

<i>Parameter System Type</i>	<i>HRT</i>	<i>Sludge Age</i>	<i>MLVSS mg/L</i>
Conventional	6–8 hrs	7–12 days	2,000–3,000
Extended	20 hrs	20 days	1,200–2,500
High Rate	3–4 hrs	6–10 days	2,500–4,000
Contact Stabilization	0.5 hrs	7–12 days	2,000–3,000
Sequencing Batch Reactor	6–8 hrs	7–12 days	2,000–3,000



Figure 8-38(a) Alternative device for diffusion: Aeration panel. (Photo courtesy of Parkson Corporation.)



Figure 8-38(b) Alternative device for diffusion: Flexible membrane diffuser. (Photo courtesy of Parkson Corporation.)




Figure 8-38(c) Alternative device for diffusion: Dome diffuser. (Photo courtesy of Parkson Corporation.)



Figure 8-38(d) Alternative device for diffusion: Coarse-bubble. (Photo courtesy of Parkson Corporation.)




Figure 8-38(e) Alternative device for diffusion: Fine-bubble membrane diffuser. (Photo courtesy of Eimco Process Equipment, a Baker Hughes Company.)



Figure 8-38(f) Alternative device for diffusion: Disk diffuser. (Photo courtesy of U.S. Filter/Envirex.)




Figure 8-38(g) Alternative device for aeration: Submerged static aerator. (Photo courtesy of IDI/Infilco Degremont, Inc.)

The driving force for oxygen transfer in the case of mechanical aerators is the gradient between the oxygen concentration in the air and the concentration of dissolved oxygen within a given droplet. As illustrated in Figure 8-39, the transfer of oxygen from the air into a droplet is a five-step process. First, oxygen diffuses through the bulk air medium to the surface of the droplet. Next, each oxygen molecule must diffuse through the double-layered “skin” of the droplet, which consists of a layer of nitrogen and oxygen molecules covering a layer of water molecules. This diffusion through the two layers can be considered one step and is thought to be the rate-limiting step for the process as a whole. The final two steps are diffusion of oxygen into the bulk liquid of the droplet, followed by diffusion into the bulk liquid contents of the aeration tank, once the droplet returns to the tank.

The reason that diffusion through the double “membrane” at the surface of the droplet is the rate-limiting step is illustrated in Figure 8-40. Within either the bulk air or the bulk liquid,

each molecule of the medium is attracted to other molecules equally in all directions. At the interface between liquid and air, however, each molecule of gas or liquid, as the case may be, is attracted to other like molecules in only the directions that are either parallel to, or away from, the other medium. Therefore, because the total attractive force is the same as in the bulk medium, but the force is distributed over only half the space, the effective attraction is essentially doubled. This causes the molecules of both gas and liquid to be more dense and, therefore, less permeable to the passage of other molecules.

Air diffusers introduce bubbles of air into the bulk liquid within the aeration tank, as illustrated in Figure 8-41. In this case, as opposed to the case for mechanical aerators, the oxygen transfer process is from a more or less spherical “container” of air directly to the bulk liquid. Again, the driving force for oxygen transfer is the difference in concentration between oxygen molecules in the air bubble and the concentration in the bulk liquid. There




Figure 8-38(h) Alternative device for aeration. (Photo and drawing courtesy of IDI/Infilco Degremont, Inc.)

is still the process of diffusion of oxygen molecules through, first, the air, except that here the air is contained in a small “package,” which is the bubble. Next, the oxygen molecules must diffuse through the double “membrane” of gas, then through liquid molecules that surround the bubble, then into the bulk liquid. Here, the process has four steps rather than five, and the rate-limiting step is still considered to be the rate of diffusion through the double-layered membrane.

Air diffusers manufactured to supply air to activated sludge wastewater treatment systems are divided into two categories; coarse bubble diffusers and fine bubble diffusers, also called “fine pore diffusers.” In general, coarse bubble diffusers require less maintenance than fine bubble diffusers, require somewhat less air pressure to pass a given flow rate of air (therefore less power per unit of air supplied), but achieve a lower degree of oxygen transfer efficiency (OTE). Fine bubble diffusers characteristically provide higher OTE values than coarse bubble diffusers because of the

significantly higher surface-to-volume ratio of the smaller air bubbles. Because the rate-limiting step of the oxygen transfer process is diffusion through the double-layered “membrane” surrounding each air bubble, and because the flux of oxygen, in terms of pounds of oxygen per unit area of bubble surface, is the same regardless of bubble size, increasing the bubble surface area directly increases the transfer of oxygen.

Fine bubble diffusers have been shown to have significant disadvantages compared to coarse bubble diffusers or mechanical aerators in certain specific instances because of a higher tendency to cause foaming and because of a tendency to clog or otherwise become fouled. If foaming occurs and anti-foam agents are added, the anti-foam agents act to cause the fine bubbles to coalesce and become large bubbles. The tendency for fine pores to clog or become otherwise fouled results in the necessity for periodic cleaning or replacement. In addition, the lower air supply rate needed by fine bubble diffusers for the required oxygen

transfer results in less air for mixing, which is an important component of aeration. The addition of one or more alternatives to satisfy mixing requirements—for instance, by supplying more air than is required for oxygen transfer, or by making use of mechanical mixers along with the fine bubble aerators—sometimes results in the long-term economics favoring coarse bubble diffusers.

Some industrial wastes have chemical or physical characteristics that result in their being bad candidates for fine bubble diffusers. Sometimes, the reason is obvious. Treatment systems for potato starch processing wastewater, which foams copiously because of the types of proteins present, and treatment of pulp mill wastewaters, which contain chemical components (possibly including sulfonated remnants of lignin) that cause small bubbles to coalesce, are examples.

Basics of Oxygen Transfer. The basic relationship that describes the oxygen transfer process is as follows:

$$\frac{dC}{dt} = K_L a (C_{inf}^* - C) \quad (8-47)$$

where:

dC = Change in concentration of oxygen with time dt .

$K_L a$ = Overall mass transfer coefficient. Made up of the coefficients K_L , the liquid film coefficient, and a , the unit interfacial area.

C_{inf}^* = The saturation concentration for oxygen in water. It is the concentration to which oxygen would become dissolved in water if a gas containing oxygen is in contact with water for an infinite period. Its value is proportional to the mole fraction of oxygen in the gas that is in contact with water.

C = Concentration of dissolved oxygen at time t .

The value of $K_L a$ in this equation is normally determined by experiment. C_{inf}^* and C are measured directly, and $K_L a$ is determined by performing a regression analysis of oxygen uptake data obtained by conducting experiments during which oxygen concentration is measured at progressive times after aeration of




Figure 8-38(i) Alternative device for aeration: Typical deep basin flow pattern. (Drawing courtesy of IDI/Infilco Degremont, Inc.)




Figure 8-38(j) Alternative device for aeration. (Courtesy of IDI/Infilco Degremont, Inc.)



Figure 8-38(k) Alternative device for aeration: Pontoon-mounted, aspirating aerators. (Photo courtesy of Eimco Process Equipment, a Baker Hughes company.)



Figure 8-38(l) Alternative device for aeration: Fixed-mounted, aspirating aerators. (Photo courtesy of Eimco Process Equipment, a Baker Hughes Company.)




Figure 8-38(m) Alternative device for aeration. (Drawing courtesy of Eimco Process Equipment, a Baker Hughes Company.)

a test liquid has begun, starting with a concentration of approximately zero. Figure 8-42 presents a typical graph of the concentration of dissolved oxygen in an aqueous solution after the aeration process has begun at time equal to zero, starting with a dissolved oxygen concentration of about zero. As shown in Figure 8-42, the concentration of dissolved oxygen increases at a decreasing rate (first-order kinetics) until either the saturation concentration (C_{inf}^*) is reached, or an equilibrium is reached at which the rate of dissolution of

oxygen is equal to the rate at which dissolved oxygen is consumed, by either microbiological respiration or chemical reaction.

Extensive experimentation has shown that the value of $K_L a$, the overall mass transfer coefficient, depends on several characteristics and factors. In fact, within a given aeration basin in which oxygen is being dissolved into a given industrial wastewater, the value of $K_L a$ is different in different locations within that basin. Some of the characteristics and factors include:




Figure 8-38(n) Alternative device for aeration: Submerged turbine aerator. (Photo courtesy of IDI/Infilco Degremont, Inc.)



Figure 8-38(o) Alternative device for aeration: Sequencing batch reactor (SBR). (Photo courtesy of Paques ADI Systems, Inc.)



Figure 8-38(p) Alternative device for aeration: Fixed submerged aerator. (Photo courtesy of ABS, a company in the Cardo Group.)




Figure 8-39 Illustration of the mass transfer of oxygen molecules from air into a droplet of water.




Figure 8-40 Illustration of the rate-limiting step for oxygen transfer.




Figure 8-41 Diffusion of oxygen from inside air bubble to bulk liquid.




Figure 8-42 Determination of the value of $K_L a$.

- Temperature
- Chemical makeup of the wastewater as it changes from one location to another within the basin. The principal reason for this change is the treatment process itself.
- Liquid depth
- Barometric pressure
- Relative humidity
- Intensity of mixing or turbulence
- Variation in physical characteristics of the aeration devices at different locations within the basin (If there is, indeed, a variation. Usually, significant variation is caused by different degrees of clogging and other wear and tear effects of service).

It is not possible, therefore, to compare the effectiveness of one aeration device with another, unless all of the influencing characteristics are equal except the aerators themselves,

or unless procedures are applied to account for the differences. Such procedures have been developed and are described in "*Standard Guidelines for In-Process Oxygen Transfer Testing*," published by the American Society of Civil Engineers (ASCE) publication No. ASCE-18-96. Two approaches are described in this publication. The first is referred to as the "nonsteady state method." The second is called the "off-gas method." A summary of these procedures is as follows.

NON-STEADY STATE METHOD. This method determines the average oxygen transfer coefficient ($K_L a$) under actual process conditions by measuring the change in dissolved oxygen (DO) concentration over time after producing a sudden change in the prevailing steady state conditions. DO concentrations are then taken at successive time intervals, at one or more locations within the operating aeration basin. The

DO concentration versus time characteristics, as the contents of the basin progress toward a new equilibrium condition, are thus determined. The following assumptions accompany this procedure:

- The system is completely mixed.
- The oxygen uptake rate and $K_L a$ values remain constant during the test.
- DO probes are located so that each detects a DO concentration that is representative of equal basin volumes.

One of two methods is used to produce the sudden change in (departure from) steady state conditions. The first is to (as suddenly as possible) change the level of power supplied to the aerators. The second is to quickly pour a volume of hydrogen peroxide (H_2O_2) into the operating basin. When the level of power is increased, the value of $K_L a$ is determined by analysis of the increase in DO concentration as it approaches the new equilibrium value. When the hydrogen peroxide method is used, the excess DO is stripped out in a manner equivalent to the manner in which it would increase. $K_L a$ is thus determined by use of a curve that mirrors the expected characteristics of increase to the equilibrium value. A nonlinear regression (NLR) technique is used to determine the values of $K_L a$.

It is important to maintain constant load and oxygen uptake conditions throughout the test. This can be managed by either diverting some of the load or by conducting the test during periods when the load is expected to be constant.

OFF-GAS METHOD. This method employs a tentlike hood to capture and measure gas-phase oxygen emerging from the surface of an operating aeration basin. The mole fraction of oxygen in the off-gas is then compared to the mole fraction of oxygen in the air supplied to the basin. A gas-phase mass balance is then used to directly determine the oxygen transfer efficiency of the diffused air aeration devices in service at the

time the test was conducted. Devices for measuring the oxygen content of air and the flow rate of air are used to determine the mass of oxygen that enters the aeration basin over a defined period. Equivalent devices are used to measure the mass of oxygen exiting the basin through the surface of the liquid over the same period. This ratio is used to calculate the mass rate of oxygen input to the aeration basin. Typically, the performance curves supplied with the air blower equipment (mass of air per horsepower-hour, for instance) are used to determine (or to check, if a flow meter is used) the mass of air supplied to the aeration basin.

The tentlike device, or, hood, is equipped with pressure-sensing devices, as well as oxygen concentration-sensing equipment, and gas flow rate measurement capability. The oxygen concentration-sensing equipment is used to determine the mole fraction of oxygen in the gas that is exiting the aeration basin via the surface of the mixed liquor. The pressure-sensing devices are used to determine when the flow of gas into the hood is equal to the flow exiting the hood. This flow equilibrium is shown to be the case when the pressure within the hood remains constant over a period. (It is recommended that the hood be maintained under a slight positive pressure, with respect to the atmosphere outside the hood; i.e., + 1.27 to 2.54 mm [0.05 to 0.10 in.] water gauge.)

The area of the base of the hood, expressed as a ratio of the total area of the aeration basin, is used to calculate the total mass rate of oxygen exiting the aeration basin. The difference between the quantity of oxygen entering the aeration basin in a unit time and the quantity exiting the basin in the same unit of time is then used to determine the oxygen transfer characteristics of the particular aeration system (blowers, air delivery system, and diffusers) used for that test.

A gas-phase mass balance of oxygen over the liquid volume is written as:

$$\begin{array}{l} \text{Oxygen removed from gas stream} \\ \text{oxygen dissolved into the liquid} \end{array} =$$

or,

$$\rho(q_i Y_i - q_e Y_e) = K_L a (C^*_{inf} - C)V \quad (8-48)$$

where,

- ρ = Density of oxygen at temperature and pressure at which gas flow is taking place.
- q_i, q_e = Volumetric rate of gas flow into and out of the volume of liquid, respectively.
- Y_i, Y_e = Mole fraction of oxygen in gas (air) flow into and out of the liquid, respectively.
- C = Concentration of dissolved oxygen in the liquid (aqueous solution).
- V = Volume of basin.

as illustrated in Figure 8-43.

The value of $K_L a$, then, is calculated directly by rearrangement of equation 8-48:

$$K_L a = \frac{\rho(q_i Y_i - q_e Y_e)}{(C^*_{inf} - C)V} \quad (8-49)$$

As was the case with the nonsteady state method described previously, the resulting estimates of the value of $K_L a$, oxygen transfer efficiency, and other characteristics are applicable, strictly speaking, to only those particular conditions of temperature, atmospheric pressure, chemical characteristics of the mixed liquor, and all other variables that existed when the test was conducted. The standard oxygen transfer rate (SOTR) equation has been developed to provide a method to enable comparison, on a best estimate basis, of the performances of different aeration devices by adjusting, mathematically, the value of $K_L a$ to account for nonstandard conditions when actual tests were conducted.

The standard oxygen transfer rate (SOTR) is defined as:

$$SOTR = K_L a (C^*_{inf}) \quad (8-50)$$

Standard conditions are considered to be as follows in the United States:

- Temperature = 20°C
- Barometric pressure = 760 mm Hg
- Tap water




Figure 8-43 Gas phase mass balance.

In Europe, standard conditions are considered to be as follows:

- Temperature = 10°C
- Barometric pressure = 760 mm Hg
- Tap water

In the United Kingdom, a surfactant (commercial detergent) is added to the tap water.

Three factors, α , β , and θ , are used to mathematically adjust the value of $K_L a$ to account for the effects of differences in wastewater characteristics (chemical content, etc.), differences in the saturation value of dissolved oxygen, and the effects of temperature, respectively. The alpha factor (α) is used to compare the oxygen transfer effectiveness in a given wastewater to its effectiveness in clean water:

$$\alpha = K_L a_{ww} / K_L a_{cw} \quad (8-51)$$

where:

$K_L a_{ww}$ = The value of $K_L a$, the overall mass transfer coefficient, in the wastewater that is under consideration.

$K_L a_{cw}$ = The value of $K_L a$ in clean water, under the same conditions of temperature, barometric pressure, and

relative humidity that prevailed for the determination of $K_L a$.

In other words, then, the value of alpha (α) is the ratio of the rate of oxygen transfer in the wastewater under consideration to the rate of oxygen transfer in clean water, when all other physical and environmental characteristics are equal.

Usually, the value of alpha is less than one, meaning that there are few substances normally found in wastewater that enhance the dissolution of oxygen. If one aeration device is able, somehow, to "produce" an alpha value that is higher than that "produced" by another (several have been reported in the literature), and if the difference in the values of $K_L a$ does not negate this effect, the aerator producing the higher alpha value is shown to be the better performer.

The beta (β) factor, used to account for the difference in the saturation value of dissolved oxygen in a given wastewater as opposed to the saturation value in clean water, is expressed as:

$$\beta = C_{inf\,ww}^* / C_{inf\,TP}^* \quad (8-52)$$

The saturation concentration of the wastewater in question in contact with air can be determined by testing the wastewater in the laboratory. Published tables are used to obtain the appropriate value for the saturation concentration of oxygen in tap water that is in contact with air.

A reasonably accurate correction for differences in temperature is as follows:

$$K_L a_{(T)} = K_L a_{(20)} (\Theta^{T-20}) \quad (8-53)$$

where:

$K_L a_{(T)}$ = Value of $K_L a$ at temperature T

T = Temperature, °C

Θ = 1.024

"Standard" correction factors for differences in barometric pressure and relative humidity are presented in *Guidelines for Quality Assurance of Installed Fine Pore Aeration Equipment* (ASCE, 1998).

The standard oxygen transfer rate (SOTR) is used to estimate the actual oxygen transfer rate (OTR) under actual (as opposed to standard) conditions by use of equation 8-54:

$$OTR = \alpha \left(\frac{\beta C_{walt}^* - C_L}{C_{inf20}^*} \right) \theta^{T-20} SOTR \quad (8-54)$$

where

C_{walt}^* = The saturation concentration of oxygen (from ambient air) in tap water, corrected for the increased saturation concentration at the depth of operation of the aeration devices; i.e., $C_{walt}^* = C_{TP}^* \times f_d$.

where:

C_{TP}^* = The saturation concentration of oxygen (from air) in water at the prevailing temperature and atmospheric pressure.

f_d = Factor accounting for increased saturation concentration at depth.

$$f_d = \frac{C_{inf20}^*}{C_{20}}$$

C_{20} = Saturation concentration at the surface, under standard conditions.

C_L = The target value of dissolved oxygen under normal operating conditions.

Progressing one step further, it is convenient to determine air flow requirements for any given wastewater treatment process by use of equation 8-55:

$$Q = \frac{SOTR}{SOTE \times \rho_a \times f_a \times 60} (100) \quad (8-55)$$

Where:

SOTR = Oxygen transfer rate under standard conditions, lb O_2 /hr.

SOTE = Oxygen transfer efficiency under standard conditions, %.

Q = Rate of flow of air under standard conditions, SCFM.

- ρ_a = Density of air at standard conditions = 0.075 lb/ft³.
 f_a = Weight fraction of oxygen in air, decimal (0.231).
 60 = Minutes per hour.
 100 = Conversion from percent to decimal.

Under standard conditions, then,

$$Q = \frac{96.62 \times SOTR}{SOTE} \quad (8-56)$$

SHOP TESTS. An alternative method for estimating the value of K_{La} , as well as other parameters and characteristics of oxygen transfer effectiveness by various aeration devices, is the so-called shop test.

A given vessel is filled with a given liquid (water or an industrial wastewater). The aerator being evaluated is activated, with the dissolved oxygen concentration equal to zero. Measurements of dissolved oxygen concentration are made at periodic time intervals, and a plot of the data as shown in Figure 8-42 enables determination of the value of K_{La} at the temperature, barometric pressure, and relative humidity that prevailed at the time of the testing. The aeration device that produces the highest value of K_{La} is shown to be the most effective, as far as oxygen transfer is concerned, of those evaluated under the specific, identical conditions.

As another alternative, a slight modification of the shop test, is to make use of a cylinder, 2 feet or so in inside diameter, mounted alongside the aeration basin, on site. The aeration device(s) to be evaluated is installed at the bottom of the cylinder; the cylinder is fitted with air flow rate, gas phase oxygen, and dissolved oxygen-sensing equipment; and the cylinder is filled with mixed liquor from the aeration basin. Tests as described previously are run to determine values of both alpha and K_{La} . The primary advantages of this system are that the tests can be run on fresh MLVSS and wastewater, as opposed to having to transport these substances to the shop, and the close control over chemical and physical conditions, as opposed to the lack of control that attends the off-gas method described earlier.

Aerated Lagoons. Aerated lagoons usually consist of earthen basins equipped with mechanical or diffused aeration equipment. There is no secondary clarifier except for a quiescent zone at the outlet. There is no controlled sludge return from the bottom of this quiescent zone.

As an alternative to the quiescent zone, a separate pond is sometimes used, in which case the pond is referred to as a polishing pond. In other cases, a mechanical clarifier can be used. A considerable number of pulp and paper mills, in fact, have installed mechanical clarifiers as part of aerated lagoon systems. These alternatives are desirable if the design of the lagoon makes use of complete mix conditions as a method to avoid short-circuiting.

There are two distinct types of aerated lagoon systems: (1) aerobic and (2) partially mixed, facultative.

An aerobic lagoon must have sufficient mixing to suspend all of the solids and must have enough aeration capacity to satisfy all of the BOD removal aerobically.

A partially mixed, facultative lagoon requires only enough mixing to keep all of the liquid in motion. A significant portion of the biological and other solids resides at the lagoon bottom and undergoes anoxic and anaerobic degradation. Enough aeration is applied to maintain aerobic conditions in only the upper 2 to 3 feet of liquid in a partially mixed, facultative lagoon.

The advantage of a partially mixed, facultative lagoon over an aerobic lagoon is significantly lower operating cost. In a properly operated partially mixed, facultative lagoon, much of the dissolved BOD in the raw wastewater is "sorbed" (via adsorption and absorption) onto and into the microbial cells, which then settle to the bottom and undergo anoxic and anaerobic degradation. There is no requirement to supply oxygen for this degradation process. Furthermore, anoxic and anaerobic metabolisms result in the generation of far less sludge, in the form of growth of new microbial cells, per unit of BOD degraded, than is the case with aerobic metabolism.

The advantage of an aerobic lagoon over a partially mixed, facultative lagoon is in the process control. There is no positive control over how much sludge settles and how much stays in suspension in a partially mixed lagoon. Because there is no settling out of sludge solids in a properly operated aerobic lagoon, there is no lack of control. There is, however, a significant price to pay for the extra aeration capacity required for an aerobic lagoon over that required for a partially mixed, facultative lagoon.

The anoxic and anaerobic microbial activity that takes place at the bottom of a properly operated partially mixed, facultative lagoon converts organic solids within the sludge to soluble organic acids, which diffuse into the upper strata of the lagoon. These compounds are volatile and highly odorous, and constitute a potential odor problem; however, if there is sufficient aerobic microbial activity in the upper strata of the lagoon, the organic acids will be converted to carbon dioxide, water, and microbial cell protoplasm. Properly designed and operated partially mixed, facultative lagoon systems do not emit noticeable odors.

Aerated lagoons require relatively little operator attention because there is no wasting or returning of sludge to manage sludge age. Technically, sludge age is infinite, and autooxidation is at the maximum. Therefore, the effluent TSS concentration is typically high (relatively, compared to activated sludge). Aerated lagoons eventually collect sufficient inert solids that sludge removal is required.

The frequency of sludge removal can vary from yearly to once every 10 or so years. The high cost (relatively) aspects of lagoon systems include large land area as well as the cost of constructing a liner system to protect the groundwater, including the (substantial) cost of geotechnical and hydrogeologic investigations of alternative sites. These investigations and collected data are necessary to determine whether on-site soils can be re-compacted as an earthen liner. If a synthetic liner is needed, determine whether embankment toe drains are required. Among other considerations are permissible slopes, define embankment and

earthen liner construction details, permissible lift height and compaction requirements.

In the case of partially mixed, facultative lagoons, periodic losses of solids (via the effluent) that had previously settled to the bottom, plus periodic episodes of algae blooms within the lagoon, combine to make them unreliable in complying with effluent TSS restrictions. Some facultative lagoon installations have incorporated additional facilities that are used only when needed, such as a sand filter, or a final, settling lagoon, to ensure compliance with discharge permits. Here, again, a well-developed life-cycle cost analysis is needed to determine the wisdom of selecting any of the various lagoon alternative configurations.

Nonaerated Facultative Lagoons. Nonaerated facultative lagoons are designed and constructed similarly to aerated lagoons, but there is no aeration other than that which diffuses naturally through the surface. These systems are termed “facultative” because, properly operated, the upper one-third, or so, of the depth is aerobic, the lower one-third, or so, is anoxic to anaerobic, and the middle one-third phases in and out of the aerobic and anoxic states and is therefore facultative. In order to achieve aerobic conditions throughout a significant portion of the depth (one-third, or so), the organic loading must be sufficiently low that the rate of diffusion of oxygen from the air above the lagoon is as high or higher than the rate of oxygen utilization by the aerobic microbial population. As with other types of lagoons, anoxic and anaerobic degradation take place within the sludge at the bottom. Organic solids are converted to dissolved organic acids, which diffuse into the aerobic region near the surface, presenting a potential odor problem. In a properly designed and operated system, however, these volatile organic acids are converted to carbon dioxide, water, and microbial cell protoplasm by the aerobic microbial population in the aerobic zone. Well-functioning facultative lagoon systems, aerated or not, do not give off significant objectionable odors.

Again, there is a cost trade-off between aerated and nonaerated facultative lagoons. Aerated lagoons require substantial cost for power to operate the aeration system. Nonaerated lagoons require substantially more land area and therefore, higher cost for liner systems, including geotechnical and hydrogeologic investigations for several alternative sites.

Oxidation Ponds. Oxidation ponds are designed and constructed similarly to facultative lagoons, in that they are usually earthen basins of very long hydraulic detention time. The design objective is different from that of facultative lagoons, however. Oxidation ponds must be sufficiently shallow and have sufficiently low organic loading that aerobic conditions are maintained everywhere. In this respect, “everywhere” means the liquid contents of the lagoon and not the sludge volume that accumulates at the bottom. For this condition to hold, the rate of production of oxygen by algae, plus the rate of diffusion of oxygen through the surface and from there to the bottom of the pond, must always be greater than the rate of utilization of oxygen by the microbes within the system as they metabolize the organic pollutants.

Because of their shallow construction, oxidation ponds are useful only in warm climates. Also, because algae are usually a principle source of oxygen, sunlight intensity is an important design consideration. The requirement for liner systems to protect the groundwater is a major cost consideration because oxidation ponds typically have the highest area-to-volume ratio of the commonly used biological treatment systems.

DESIGN OF LAGOON SYSTEMS. The foregoing discussions have shown that, in general, there is a tradeoff between detention time and aeration capacity in the design of aerobic biological treatment systems. The question, then, is, “What combination of detention time and aeration capacity produces the desired quality of effluent for the lowest life-cycle cost?” Factors on which the answer bears include wastewater strength, characteristics relating to biodegradability of the organics in the wastewater, cost for land, soil type as it relates to construction costs, and temperature, as well as others.

Whereas activated sludge systems for treatment of industrial wastes are best designed using the procedures presented previously, lagoon systems have been most successfully designed using one of the empirical approaches presented and discussed briefly in Table 8-12.

Table 8-12 Alternate Approaches to Design of Lagoon Systems

<i>Approach</i>	<i>Comment</i>
Areal loading	Lagoon system size is determined by simply applying an area loading rate of, for instance, 15 lb BOD/ac/d, with no more than 40 lb/ac/d in any one of several lagoons in series. Depth is a separate design parameter, which increases with colder climates. Depth is first determined to provide required detention time, then is increased to accommodate anticipated ice thickness, sludge storage, and accommodation of direct rainfall, if significant. Experience is the principal design guide.
Plug flow	Useful when long, narrow ponds can be constructed. Construction cost is relatively high because of the high perimeter-to-volume ratio. If baffles are used to create a long, narrow flow path, considerable dead space results and must be taken into consideration regarding hydraulic detention time.
Complete mix	Complete mix operation is useful for controlling short-circuiting. Best treatment results when three or more ponds are operated in series. Successful design depends on selecting the correct reaction rate constant, k . Value of k decreases with consequent increase in lagoon system size with decreasing operating temperature.
Marais and Shaw	A variation of the complete mix method approach. Design considerations are identical to complete mix approach.
Gloyna method	Applicable to warm climates with high solar radiation. Assumes solar energy for photosynthesis is above saturation.
Wehner-Wilhelm	Requires knowledge of hydrodynamic equation characteristics of each pond as well as reaction rate.

In general:

- Temperature affects both the rate of microbial respiration and the rate at which oxygen dissolves in the bulk liquid in the lagoon.
- Algae affect the quality of the effluent from a lagoon by:
 1. Adding to the TSS of the lagoon effluent.
 2. Adding oxygen to the bulk liquid of the lagoon during the daylight hours.
 3. Depleting the oxygen in the bulk liquid of the lagoon during the nondaylight hours.

Experience has shown that the amount of algae present in lagoon systems increases from aerobic to partially mixed facultative to nonaerated facultative to those highest in algae mass, oxidation ponds. In all but complete mix aerobic systems, algae are integral parts of the treatment system and must be expected. Furthermore, lightly loaded (relative to design) systems are likely to have significantly more algae. The U.S. EPA has recognized that compliance with typical secondary permit limits for total suspended solids (TSS) may be impossible for certain lagoon systems, and have provided for "equivalent to secondary" alternative TSS limits on a case-by-case basis.

In the course of the normal daily operation of a lagoon system over the full calendar year, solids, including those that were contained in the raw wastewater and the microbial solids that result from the microbial purification action of the lagoon system, and algae settle to the bottom of the lagoon to form a sludge deposit, referred to as the benthic deposit, or benthos. Anoxic/anaerobic conditions develop in the benthos, and anoxic/anaerobic bacterial action reduces the volume of the benthos and releases volatile acids to the overlying bulk liquid. This adds to the BOD load to be treated by the lagoon system. During the spring months, lagoons located in cold climates experience an overturn when the benthos rises into the bulk liquid. This is known as a "benthic release." The BOD of the bulk liquid increases significantly during these periods, typically

causing nearly complete depletion of the dissolved oxygen supply. When this happens, aerobic biological treatment is limited to what can be supported by the immediate dissolution of oxygen by the aerators and by diffusion through the surface. In some locations, a similar benthic release occurs during the autumn months. Very often, under these conditions, concentrations of both BOD and TSS in the lagoon effluent rise to exceed permit limitations. It is extremely important to include the effects of benthic release in the design of a lagoon system as well as in the plan of operation.

One solution is to design and build a three-lagoon system. Treat with two lagoons and use the third lagoon to store effluent not suitable for release (have a high and a low discharge pipe). The stored wastewater can be routed through the two treatment lagoons during periods of low wastewater flow.

LOW-ENERGY COMPLETE MIX APPROACH. Experience has shown that the most significant cause of failure of lagoon systems to perform as intended has been short-circuiting. Many techniques have been used to solve short-circuiting problems, including use of baffles and strategic placement of inlet and outlet devices. However, perhaps the most positive approach has been to employ a low-energy, complete mix technique. In this approach, the shape of the individual ponds that make up the lagoon system, combined with the type of aeration device, has enabled complete mix hydrodynamics, as evaluated using chemical tracer studies.

BOD TEST CONSIDERATIONS When aerobic treatment systems, especially lagoons, are operated in an underloaded (relative to design) condition, there is a potential problem with use of the standard 5-day biological oxygen demand (BOD₅) test for determining plant performance as well as compliance with permit limits. When the carbonaceous BOD (CBOD) has been removed, the microorganisms within the treatment system (lagoon), under certain conditions, begin oxidizing ammonia that has been

liberated from proteins and other substances. This “extra treatment” leads to the development of a robust population of nitrifying bacteria (nitrosomonas and nitrobacter), which are present in the treated effluent. Consequently, when samples of the treated effluent are placed in BOD bottles, nitrification of ammonia (including that introduced with the dilution water) takes place during the 5-day BOD test. The result is that the BOD₅ test will include both CBOD from the treated wastewater and an amount of nitrogenous oxygen demand (NBOD) (about 4.6 mg of oxygen are required to oxidize one mg of ammonia). Experience shows that a treated effluent having a CBOD of less than 10 mg/L can exhibit a BOD₅ of more than 50 mg/L using the standard 5-day BOD test. For this reason, an alternative BOD test has been developed in which nitrification inhibitors are added to the BOD bottle in the standard 5-day BOD test. This test is referred to as the CBOD test and is authorized to be used instead of the standard BOD₅ test, on a

case-by-case basis, by the U.S. EPA as well as essentially all state environmental agencies. In fact, some state agencies have authorized the CBOD test to be used at the choice of the analyst.

Attached Growth Systems

Attached growth wastewater treatment processes are characterized by a microbiological slime mass attached to a solid surface. As the wastewater flows over the slime mass, organic substances and other nutrients diffuse into it, providing food for growth of the microbes. In the case of aerobic systems, oxygen also diffuses into the slime mass. Typically, the microbes grow, increasing the mass (referred to as the “slime layer”), and the slime layer develops as shown in Figure 8-44.

As depicted in Figure 8-44, organics, other nutrients, and oxygen diffuse from wastewater, which is moving over the surface of the slime layer. As the slime layer grows, it becomes so




Figure 8-44 Characteristics of attached growth slime layer.

thick that oxygen becomes consumed before it can diffuse more than a few millimeters into the slime layer. An anaerobic zone thus becomes established, even though the process, as a whole, is said to be aerobic. The anaerobic zone is usually a fortuitous development, however, because the anoxic and anaerobic activity act to consume microbes that have grown in the aerobic zone, as well as some of the organics that have diffused in from the wastewater. This activity reduces the quantity of waste sludge that must be handled and disposed of. There is almost always some sloughing off of excess slime layer, however, and therefore a clarifier is usually included in the attached growth treatment system.

Three aerobic attached growth wastewater treatment processes that are in common use, as shown in Figures 8-45(a)–(c), are the trickling filter, the rotating biological contactor (RBC), and the fluidized bed.

Trickling Filters. Trickling filters make use of solid “media,” usually contained in a steel or concrete tank, round, square, rectangular, or other shape, with a perforated bottom. Wastewater is applied to the top of the media by distribution devices, and, under the influence of gravity, trickles down over the surfaces of the media. Air flows from the bottom, up through the media to supply oxygen. Air blowers can be used for this purpose, but normally, sufficient air flows by gravity because the biological activity in the filter gives off enough heat to cause the air to expand, thus becoming lighter and buoyant compared to the ambient air.

The earliest trickling filters (from the early 1900s through the 1950s) made use of stones of 1 to 4 inches in size for the medium over which the wastewater was caused to flow, or “trickle.” Stone, or in some cases slag or coal, is still used, but many trickling filter systems use media manufactured from plastic. Also, some



Figure 8-45(a) Aerobic fixed film systems; trickling filter. (Photo courtesy of NSW Corporation.)



Figure 8-45(b) Aerobic fixed film systems; rotating biological contactor (RBC). (Photo courtesy of U.S. Filter/Envirex.)



Figure 8-45(c) Aerobic fixed film systems; fluidized bed. (Photo courtesy of NSW Corporation.)

trickling filter systems employ horizontal flow, referred to as "cross flow." Figures 8-46(a)–(c) show photographs of stone media as well as representative types of plastic media. The plastic media are often referred to as "packing." Filters making use of stone media are normally 3 to 8 feet in depth. Plastic media trickling filters have been built as shallow as 6 feet and as deep as 40 feet.

The system used to distribute wastewater over the top of the media can be either movable or stationary. A grid of stationary nozzles supplied with wastewater by pumps is common in the case of plastic media filters. So-called rotary distributors, shown in Figure 8-47, are normally used with stone media filters as well as with plastic media. The rotary distributor is fed from the center of the circular filter. The action of the wastewater issuing from one side of the distributor arm supplies what is needed to turn the distributor, thus spreading an even application of wastewater over the top of the bed of media.

RECIRCULATION. It is important to manage the operation of a trickling filter to control the thickness of the slime layer. If the slime layer is too thin, there will be insufficient microorganisms to accomplish the desired degree of treatment. Also, a slime layer that is too thin allows the applied wastewater to flow too quickly through the filter and thus receive insufficient treatment. If the slime layer becomes too thick, the flow of air becomes impeded because of insufficient open space between adjacent surfaces of the filter media. Successful operational performance of a trickling filter results when the organic loading rate and the hydraulic loading rate are in proper balance. The ability to recycle wastewater that has already passed through the trickling filter is the operator's best means to control this balance, as illustrated in Figure 8-47.

Figure 8-47 shows a trickling filter followed by a clarifier. A recycle pump is included so that varying rates of flow of effluent from the clarifier can be recycled back to the influent to the trickling filter, thus affording the operator a means of controlling the

hydraulic loading rate to the trickling filter-clarifier system. The hydraulic loading rate is the sum of the influent plus the recycled flow rates. As this flow rate increases, increased quantity of water flushing through the filter increases. This increase has the effect of physically shearing the slime layer, reducing its thickness.

During normal operation, trickling filters are not significant sources of odors, even though, as described previously, significant anoxic and anaerobic activity takes place within the slime layer. Normally, the aerobic microbiological activity within the few millimeters closest to the surface of the slime layer oxidizes the odorous and other products of anoxic and anaerobic metabolism. However, if the organic loading rate is too high with respect to the hydraulic loading rate, the slime layer grows too thick, the rate of flow of air becomes insufficient to supply enough oxygen to accomplish the needed aerobic oxidization, and an odor problem develops. Often, treatment performance becomes insufficient, as well. The problem can be corrected by increasing the recycle rate and causing hydraulic shearing of the slime layer, reducing its thickness.

DESIGN. Several different approaches are in current use for designing trickling filter systems. If at all possible, it is best to take advantage of what has been learned by operating an existing system on a wastewater with as close to identical characteristics as possible. Although this may be feasible for municipal wastewaters, it is often impossible in the case of an industrial wastewater. Here, again, there is no substitute for a well-designed and executed laboratory study, followed by a pilot scale program. Several manufacturers of trickling filter systems have pilot scale treatment units that can be moved to an industrial site on a flatbed trailer and operated for periods of up to several months to obtain realistic design criteria and other valuable information. As a preliminary step in the case of design of a trickling filter system for an industrial application, the following methods can be used:




Figure 8-46(a) Various types of trickling filter media. (Photo courtesy of NSW Corporation.)




Figure 8-46(b) Various types of trickling filter media. (Courtesy of Marley Cooling Tower, a United Dominion Industries Company.)




Figure 8-46(c) Various types of trickling filter media. (Courtesy of Marley Cooling Tower, a United Dominion Industries Company.)



Figure 8-47 Photograph of rotary distributor for trickling filter. (Courtesy of U.S. Filter/General Filter.)

1. NRC equations

An empirical approach to design of trickling filters was developed in the 1940s by analyzing records from several military installations. This approach is, therefore, more applicable to domestic wastewater, but some industrial wastes, such as certain food-processing wastewaters, might be sufficiently similar in characteristics to warrant its use. It behooves the design engineer to give careful and thorough consideration to such similarities and possible differences before proceeding very far. The benefit of the NRC equation approach, of course, is the quickness and low cost of developing an initial estimate of cost for a trickling filter treatment system.

The BOD removal efficiency can be estimated by:

$$E = \frac{100}{\sqrt{\frac{W}{1 + 0.0561VF}}} \quad (8-57)$$

where:

- E = BOD removal efficiency (%)
- W = Organic loading rate (lb BOD/day)
- V = Volume of filter media, thousands of ft³
- F = Recirculation factor (dimensionless)

The recirculation factor is determined by:

$$F = 1 + R \left(1 + \frac{R}{10}\right)^2 \quad (8-58)$$

where:

- R = Recirculation ratio (Q_r/Q)
- Q_r = Rate of recycle flow (GPM)
- Q = Rate of flow of wastewater to filter (GPM)

Usually, the organic loading rate can be determined by a wastewater characterization study, as described in Chapter 6. In the case of an industrial plant yet to be built, the organic loading rate can be estimated using information obtained from an existing facility, where it is reasonable to expect that wastewater characteristics would be similar. Caution is warranted, however. The NRC equations have been shown to yield reasonably good estimates when applied to municipal wastewater having a temperature close to 20°C. If the wastewater to be treated is expected to be of a significantly lower temperature, then the expected treatment efficiency would be significantly less for a given organic loading rate.

Eckenfelder's equations. Eckenfelder has published an approach to the design of trickling filters that was developed by analyzing laboratory, pilot scale, and full-scale trickling filters having various types of plastic media and treating various industrial wastes. As is the case for use of the equations presented earlier for design of activated sludge treatment systems, it is necessary to obtain a microbiological reaction rate, K , to use this approach:

$$\frac{S_e}{S_i} = \exp[-KS_a^m D(Q_v)^{-n}] \quad (8-59)$$

Where:

- S_e = BOD₅ of effluent from filter, after clarifier (mg/L)
- S_i = BOD₅ of wastewater applied to trickling filter (mg/L)
- K = Reaction-rate constant (see following)
- m = empirical constant (see following)
- n = empirical constant (see following)
- S_a = Specific surface area of trickling filter
- D = Depth of trickling filter (ft)
- Q_v = hydraulic loading rate (ft³/day/ft²)

Where:

$$S_a = \frac{\text{Surface area of trickling filter (ft}^2\text{)}}{\text{volume of trickling filter (ft}^3\text{)}} \quad (8-60)$$

The reaction-rate constant, K , is specific for a given depth of trickling filter. The reason for this is that, as wastewater trickles down through progressive depths of the filter, the more easily assimilated organic compounds are removed first. Therefore, the "localized" rate of removal, or "treatment," decreases with increasing depth of trickling filter, and, consequently, the "localized" value of K decreases with increasing depth. However, the value of K for the trickling filter as a whole increases with increasing depth because the more BOD₅ is removed, the deeper the trickling filter. The rate of increase in the value of K decreases with increasing depth.

This decreasing rate of increase in overall reaction-rate is impossible to predict without laboratory and pilot scale data. Therefore, values of K that are calculated from data taken at an operating, full-scale trickling filter are applicable for only the depth of that filter.

Similarly, values for the empirical constants m and n are specific for the conditions, including temperature, depth of trickling filter, wastewater, and filter media, that existed when the data from which the values were calculated were obtained. Published values of these constants, including values for the reaction-rate constant, K , are useful as indicators of the relative treatability of some wastewaters, taking into account comparable filter depths and temperatures, but are not useful for design of new systems, or retrofit of existing systems, unless all of the physical and operating conditions are substantially the same. Once again, in the case of industrial wastewaters, as opposed to municipal wastewaters, there is no substitute for a well-designed and executed laboratory, followed by pilot scale, study to generate values of design parameters for a trickling filter wastewater treatment system.

Roughing Filters. There are many instances where trickling filters have been used to reduce, or "knock down," the BOD₅ of industrial wastewaters before a principle, or main, treatment system. Trickling filters are useful for this purpose because they are robust processes, are relatively resilient, and require relatively little operator attention. In short, roughing filters often present a cost-effective alternative for significant BOD removal when reliable additional treatment facilities follow.

Roughing filters are typically operated at high hydraulic loading rates, in part to prevent them from becoming anaerobic and thus sources of odor nuisance, as explained previously. Usually, high recycle rates are used for this purpose.

Roughing filters have been successfully used to "absorb" shock loads caused by daily clean-up or occasional spills. In this role, the roughing filter protects the main treatment system

and, thus, provides effective protection against noncompliance episodes.

Two very important effects of roughing filters on the overall wastewater treatment system are: (1) The roughing filter removes the most easily assimilated organic material. The effect on the reaction-rate constant of downstream treatment facilities must be considered in the design and operation of the main treatment system. (2) Because of the high hydraulic loading rates and the high microbiological growth rates (because of the easily assimilated organics), sloughing from roughing filters is typically relatively high. This must also be considered in the design of the main treatment system.

Usually, plastic filter media are used. Depths of roughing filters can range up to 40 feet. The potential for roughing filters to become an odor nuisance is often present. The most effective means the operator has to solve an odor nuisance problem is the recycle rate.

Rotating Biological Contactors. Rotating biological contactors (RBC) are attached growth processes consisting of a series of parallel discs made of highly resilient plastic. The discs rotate about a metal rod whose ends are attached to the ends of a basin that contains the wastewater to be treated. As the discs rotate, only a portion of the disc assembly is emersed in the wastewater. While the discs are emersed, microbes that have attached themselves to the discs adsorb and absorb organic material and other nutrients from the wastewater. As each portion of each disc rotates out of the wastewater, it comes into contact with air, thus supplying oxygen for microbial assimilation of the organic substances. The depth of emersion determines the relative amounts of time the discs with their attached growth are in contact with wastewater and air. The speed of rotation determines the actual amounts of time. Usually, the depth of emersion is both a design and an operation parameter, whereas the speed of rotation is only a design parameter. The operator can vary the depth of emersion by adjustment of overflow weirs on the basin but seldom has the capability to vary the speed of rotation.

RBC systems can consist of a single basin containing one or more rotating disc assemblies, or can be arranged such that two or more basins, each containing one or more rotating disc assemblies, are in series. When two or more basins are in series, each is called a "stage." Because the stages are separate, and because the most easily assimilated organics are removed in the first stage, and so on through the final stage, a different population of microbes is established on each one. Also, reaction kinetics are successively slower from the first stage to the last. This characteristic of RBC systems has been used advantageously in treatment systems where nitrification must take place. The final stage(s) can be managed to maintain an optimum environment for nitrosomonas organisms.

As an additional note, one or more RBC stages can be operated in the anoxic mode, following the nitrification stage, by completely immersing the rotating disc assembly in a basin of effluent from the nitrification stage. The denitrification stage, of course, should be covered. The denitrification stage can be prevented from becoming anaerobic, and thus an odor nuisance, by controlling the hydraulic residence time by use of recycle. As odors are noticed, the recycle rate can be increased, preventing anoxic respiration from going to completion.

Two problems that RBC systems have experienced, and that can be prevented by appropriate design and operation, are (1) physical failure of the shaft and/or the drive assembly that turns the shaft and (2) odor nuisance.

Experience with many RBC systems has resulted in knowledge of what is required with respect to materials of construction and appropriate equipment sizing to prevent shaft failure. The treatment process design engineer must aggressively ensure that the equipment supplier is well aware of past shaft failure problems and has specifically designed the equipment to withstand all conceivable stresses. Written guarantees are no conciliation for the devastating disruptiveness of having to replace a rotating disc assembly.

Experience has shown that addressing the root cause of the problem can prevent odor nuisance problems, which have plagued some RBC systems. In some cases, severe odor problems have resulted from excess growth of the microbiological slime layer. The slime layer becomes so thick that it bridges across the space between the discs, preventing air from flowing in these spaces. The consequent absence of oxygen results in anoxic and anaerobic conditions and the production of volatile acids, hydrogen sulfide, and other reduced sulfur compounds, all of which are strongly malodorous. At the lowered pH caused by the volatile acids, the hydrogen sulfide becomes insoluble and passes into the atmosphere. Hydrogen sulfide can be smelled by humans in the low parts per billion ranges and can quickly cause an intolerable odor problem. This problem can be prevented by keeping the slime layer from bridging across the space between the discs. Techniques that have been successfully applied include installing a coarse bubble air diffuser (holes drilled in a pipe) at the low point of the emersion of the discs so that the bubbles travel up through the wastewater between the discs. This technique also acts to supply additional oxygen to the microbes within the slime layer.

A second technique that has been helpful in solving odor nuisance problems associated with RBC wastewater treatment systems addresses the fact that free molecular oxygen is poisonous to the microorganisms that produce the odorous substances. Adding a small quantity of hydrogen peroxide to the influent to an RBC stage that appears to be developing an odor nuisance problem has worked well. This technique can be used while a permanent solution is being developed and implemented.

DESIGN. In practice, the design of an RBC wastewater treatment facility is carried out by selecting one or more proprietary systems and working through the design procedures supplied by vendors of those systems. Typically, the design engineer will work with a representative of the manufacturer of the proprietary system to first establish the necessary

characteristics of the wastewater. In the case of an existing facility, it will probably be necessary to carry out a full-scale wastewater characterization study, as presented in Chapter 4, making sure to include the pollution prevention phases. In the case of a new industrial production facility, it will be necessary to estimate the wastewater characteristics, making maximum use of data from existing plants reasonably expected to be similar.

After design values of wastewater characteristics have been selected, the design parameters for the treatment system are determined. These parameters include the following:

1. Organic loading rate (lb BOD₅ per 1000 ft² of disc surface per day)
2. Hydraulic loading rate (gal per ft² of disc surface per day)
3. Number of stages
4. Number of shafts per stage
5. Diameter of discs
6. Number of discs per shaft
7. Depth of submergence of each rotating disc assembly
8. Rate of rotation of each shaft
9. Hydraulic retention time for each stage

The organic and hydraulic loading rates usually follow the recommendations of the manufacturer, but the design engineer, who assumes ultimate responsibility for the successful operation of the system, must be aware of the reasonableness of the manufacturer's recommendations. The best way to do this is to become familiar with existing installations and the degrees of success and the problems those systems have had.

The number of stages is determined by making an estimate, using all of the available information, including the experience of other design engineers, of the efficiency of removal (% removal of BOD₅) in each successive stage. The first stage, of course, removes the most easily assimilated organics and requires the most oxygen. The succeeding stages are characterized by successively slower treatment kinetics, and the hydraulic residence times, depths of submergence, and disc rotation rates should be appropriate.

Fluidized Bed. Attached growth fluidized bed systems for treatment of industrial wastewater consist of a bed of granular material in a tank equipped with a hydraulic distribution system at the bottom and a treated effluent collection device at the top, very similar to an upflow sand filter. (In fact, upflow sand filters function as fluidized bed treatment systems when their operation results in an attached growth of microorganisms [slime layer] on the sand media.) Wastewater to be treated is caused to flow up through the media, usually with a pump. As the wastewater flows up through the bed, its velocity and consequent drag force overcome gravity and lift the granules of media. The higher the velocity, the greater the lift.

A slime layer consisting of microorganisms capable of assimilating the organics in the wastewater becomes attached to the granules of media. Oxygen is made available to these microorganisms by adding air, air enriched in oxygen, pure oxygen, or another source of oxygen to the influent flow.

Because wastewater generation within a manufacturing or other industrial facility is never steady throughout the calendar year, it is necessary to use an effluent recycle system to maintain a constant velocity of flow. A clarifier follows the fluidized bed to separate biological material that has sloughed off from the media, as well as particles of the media itself that gets carried over the effluent weir.

DESIGN. Design of an attached growth fluidized bed wastewater treatment system is necessarily based on laboratory and pilot scale studies.

The choice of media should take into account surface-to-volume ratio, potential reactivity with substances in the wastewater, and specific weight. Heavier media require more pump energy to attain fluidization.

Treatment of Industrial Wastewaters Using Anaerobic Technologies

Anaerobic wastewater treatment, accomplished through microbiological degradation of organic substances in the absence of dissolved

molecular oxygen, has undergone a complete change in role since the mid-1980s. Used for decades as a slow-rate process requiring long retention times and elevated temperatures, it was considered economically viable for only wastes of high organic strength. Its principal role in wastewater treatment was for stabilization of waste biosolids from aerobic treatment processes, or as a treatment step preceding aerobic treatment in which large, complex molecules were broken down to more readily biodegradable substances. It is now used routinely, at ambient temperatures, on industrial wastewaters having organic strengths as low as 2,000-5,000 mg/L COD. In fact, there is certainly the potential to turn the wastewater treatment world upside down because of the economic attractiveness of treating wastewaters using anaerobic technology first, then polishing with one of the aerobic technologies.

More recent developments have enabled use of anaerobic treatment at cold temperatures for wastewaters having COD values as low as 100 to 200 mg/L. Research conducted since the mid-1970s has shown that, by addressing the fundamental reasons for the apparently slow treatment capability of anaerobic systems, modifications could be developed to overcome them. The result has been the development of anaerobic technologies that are capable of treatment performance comparable to aerobic systems, at significantly lower overall cost. Additionally, anaerobic systems are capable of treating some substances that are not readily treated by aerobic systems, such as cellulosic materials, certain aromatic compounds, and certain chlorinated solvents.

In this chapter, all microbiological mechanisms carried out in the absence of dissolved molecular oxygen (O_2), whether anoxic or truly anaerobic, are referred to as anaerobic. In this sense, then, the term "anaerobic" simply means "in the absence of free, molecular oxygen."

Although it can be argued that conclusive proof has yet to be produced, it is useful, in interpreting the performance of modern anaerobic treatment technologies, to assume that the fundamental reason for the apparently slow

kinetics of anaerobic treatment is just that—it is a slow microbiological process. On an individual microorganism-to-organic molecule basis, anaerobic degradation is slower than aerobic degradation. The method by which anaerobic treatment was made capable of competing with aerobic treatment was to greatly increase the numbers of anaerobic organisms per unit of organic matter to be treated. For instance, if aerobic metabolism is 10 times faster than anaerobic metabolism, then the time required for complete treatment by either process can be made nearly equal by increasing the number of active anaerobic organisms to 10 times the number of aerobic organisms, for a given volume of wastewater.

Figure 8-48 illustrates the means by which anaerobic treatment was successfully transformed from a slow process, compared to aerobic treatment, to one that has a required hydraulic retention time that is essentially the same as what is considered normal for aerobic treatment. Figure 8-48(a) illustrates the “old” type of suspended anaerobic culture, characterized by large clumps of biological solids. The active microorganisms can be found within only a limited thickness of active biofilm on the surface. Because the surface-to-volume ratio is small, the total number of active anaerobic microorganisms is small for a given volume of reactor.

Figure 8-48(b) illustrates two of the newer types of suspended microbiological cultures.

Anaerobic microorganisms are induced to grow on the surfaces of particles that are very small compared to the clumps of biosolids shown in Figure 8-48(a), or are induced to develop small beads rather than large clumps. The surface-to-volume ratios in the (b) illustrations are orders of magnitude greater than in the (a) illustration. The result is that there are several orders of magnitude more active microbes in a given volume of reactor in the newer anaerobic treatment systems.

The question arises, then, as to whether this same strategy could be used to make aerobic treatment even faster. The answer is that for aerobic treatment, the rate-limiting step becomes oxygen transfer, or getting oxygen from the outside air, or in some cases, from a source of pure oxygen, to the inside of each microbe. There is no such limitation in the case of anaerobic treatment. For anaerobic treatment, the sources of oxygen are nitrate, sulfate, and other anions already present in the wastewater, and water itself.

The principle cost-saving characteristics of the newer anaerobic treatment technologies, compared to aerobic technologies such as activated sludge, are (1) the absence of need for aeration, which represents the largest portion of O&M costs for aerobic systems and (2) the fact that the amount of waste biosolids (sludge) that must be handled, dewatered, and disposed of is less than that for aerobic systems by approximately a factor of ten. Added to these




Figure 8-48 Illustration of the increase in active biomass with decreased size of film support media.

advantages is the cost-recovery capability represented by methane. Methane recovered from anaerobic treatment processes has routinely been used as a source of energy to operate motors for pumps, or for space heating, either at the treatment plant itself, or in another location. As a general rule, about 5.62 ft³ of methane can be harvested as a result of anaerobic degradation of 1 pound of COD.

The reason for the smaller quantity of waste biosolids is that anaerobic metabolism is much less efficient, in terms of units of cell growth per unit of organic matter metabolized, than is aerobic metabolism. Consequently, more of the organic matter being treated is used for energy, and correspondingly less is used for cell growth. For the same reason, correspondingly less nitrogen, phosphorus, and other nutrients are needed per unit of organic matter removed, for treatment to take place. For most anaerobic treatment applications, approximately 80% to 90% of the COD removed is converted to methane and carbon dioxide. Five percent or less becomes incorporated into new cell protoplasm, and the balance is lost as heat or refractory organic "junk."

A corollary to the characteristics of low rate of conversion of organic material to new cells and low rate of excess biosolids production is the characteristic of very long mean cell residence times, compared to aerobic treatment systems. In many anaerobic treatment systems, mean cell residence times, otherwise known as "sludge age," are on the order of 100 to 200 days or more.

Two important characteristics of industrial wastewaters regarding their suitability as candidates for treatment by one of the anaerobic technologies are alkalinity and sulfur content. As explained following, the anaerobic degradation of organic substances in industrial wastewaters includes conversion of complex materials to organic acids. If the alkalinity within the treatment system is insufficient, the pH will decrease to the point of toxicity to the system's microbial population. Similarly, if the sulfate content of an industrial wastewater is more than about 200 mg/L, the concentration of hydrogen sulfide, which is a by-product of

the anaerobic degradation process, will increase to the range of toxicity to the system's microbial population.

Development of Anaerobic Technologies

The development of anaerobic wastewater treatment, from a very slow process to a very fast treatment process, is illustrated in Figure 8-49. Hydraulic retention time is used as the indication of treatment speed. The earliest anaerobic reactors were open tanks or open earthen ponds. There was no attempt to control anything. The contents of the reactors was simply allowed to react at its own speed, at whatever temperature resulted, and to develop its own characteristics of biosolids, gas production, and inert solids buildup. Eventually, the organic material would become stabilized, witness the absence of massive accumulations of organics after many years.

Taking advantage of the fact that, in general, all biochemical reactions double in rate, approximately, for every 10°C increase in temperature, the next generation of anaerobic reactors were managed to attain faster treatment performance by heating. Usually, a degree of mixing was accomplished, either as a separate objective or as a fortuitous consequence of the heating process, which also added to the increase in treatment efficiency by increasing the effectiveness of contact between the microbes and the organic material.

Mechanisms of Anaerobic Metabolism

Anaerobic treatment of organic wastes can be described as a progression of events that starts with hydrolysis, proceeds through acidogenesis, and ends with methanogenesis. These processes are symbiotic, in the sense that none can proceed for very long without one or more of the others, explained as follows.

As illustrated in Figure 8-50, complex organics, such as lipids (fats), proteins, polysaccharides, polynucleotides, and aromatics, are first broken down to their elemental building blocks. Hydrolysis is the principal mechanism for this process, and there is no reduction of COD. Exoenzymes secreted by a

variety of anaerobes carry out this hydrolysis. The basic building blocks include fatty acids in the case of lipids, amino acids in the case of proteins, simple sugars for polysaccharides, nucleic acids for nucleotides, and benzene derivatives for aromatic compounds. These basic building materials are further broken

down, again by hydrolysis, to alcohols, and then to fatty acids of relatively small molecular size. Acetic acid, plus smaller amounts of propionic, butyric, and valeric acids are the products of this process, which is known as “acidogenesis.” Molecular hydrogen is also produced during this process.




Figure 8-49 Development of anaerobic technologies.





Figure 8-50 The groups of bacteria and the principal transformations performed in converting organic particulates to methane and carbon dioxide during anaerobic digestion. (After Mosey and McInerny and Bryant. Each rectangle represents a bacterial group).

The final steps include conversion of the products of hydrolysis and acidogenesis to methane and carbon dioxide. This process is known as "methanogenesis."


The portion of organic matter that is converted to new microbial cells is not necessarily represented in Figure 8-50. Some of the intermediate and some of the final products of

hydrolysis and acidogenesis are diverted to various metabolic pathways of cell material construction. Probably, most of the new cell material is made via the two-carbon precursor of acetate, which is ethanol, being carried into the cells, then acted on by the cell's construction machinery, which includes the RNA, the DNA, and the mitochondria.


The primary product of the hydrolytic breakdown of complex organic substances is ethanol. At this point, very little, if any, COD has been removed from the wastewater, and very little, if any, energy has been captured by the anaerobes for use in reassembling some of the organic breakdown products into new cell protoplasm. The method used by most anaerobes to liberate this needed energy is to convert the ethanol to methane and carbon dioxide, a process that, overall, releases almost 21 kcal per mole of ethanol converted. The anaerobes cannot convert ethanol directly to methane and carbon dioxide, however, but must first convert ethanol to acetic acid, with the consequent release of molecular hydrogen:





The acetic acid is converted to methane and carbon dioxide:



The energy made available by this transformation, 6.77 kcal/mole of acetate converted (minus losses because of inefficiencies), is used by the anaerobes to make new chemical bonds in the assembly of new cell protoplasm. There are many products of hydrolysis and acidogenesis other than acetic acid, however, including ethyl alcohol, propyl alcohol, propionic acid, butyl alcohol, and others. Many of these substances cannot be converted directly to methane and carbon dioxide. Current thinking is that at least three species of anaerobic organisms are involved in a three or more step process, at least one of which is an energy-consuming process. The three-step process for conversion of ethanol is shown in equations 8-63 through 8-65. Equation 8-63 shows that first, ethanol is converted to acetate and molecular hydrogen, a process that consumes 1.42 kcal of energy per mole of ethanol converted:



Then, both the acetate and the hydrogen are converted to methane and carbon dioxide, each by a different species of anaerobe:




As shown, 6.77 kcal of energy per mole of acetate converted is made available (minus losses because of inefficiencies) from the conversion of acetate to methane and carbon dioxide. Two and a half times more than that, 15.63 kcal/mole, are made available by the conversion of hydrogen and carbon dioxide to methane and water.

As is the case with many microbiological metabolic processes, one of the products of metabolism, as shown in equation 8-63, is highly toxic to the species that carries out the process. In the case shown by equation 8-63, the substance that is toxic to the species that carries out that reaction is molecular hydrogen. Consequently, in order for the process to continue in an anaerobic reactor, the hydrogen must be removed by the species responsible for the reaction, represented by equation 8-65, almost as soon as it is formed. The two anaerobic species are thus symbiotic because one depends on the other for food (molecular hydrogen) and the other depends on the first to remove the hydrogen, which is toxic to it. In addition, the two species are symbiotic in that, by a means that is not fully understood at this time, some of the energy released by the reaction shown in equation 8-65 is made available and used by the species that carries out the reaction shown in equation 8-63.

In a manner similar to that shown in equations 8-64 and 8-65, propionic, butyric, and other alcohols and acids are converted to methane and carbon dioxide with the release of energy that can be used for cell synthesis. As an example, equation 8-66 illustrates the breakdown of propionate to acetate and hydrogen,

which are then converted to methane and carbon dioxide as shown in equations 8-64 and 8-65.



Here, again, molecular hydrogen is highly toxic to the species that carries out the reaction shown in equation 8-66. Success of the overall process depends on a symbiotic relationship between two anaerobic species, as described previously.

Variations of Anaerobic Treatment Systems

There are two types of anaerobic wastewater treatment systems: suspended growth and attached growth, as is the case with aerobic wastewater treatment systems. Attached growth systems are commonly referred to as fixed film (FF) systems.

Suspended growth systems are those in which anaerobic microorganisms feed on the organic content of wastewater in a vessel or lagoon that contains no managed support medium to which the microorganisms attach. As microbial growth takes place, it is retained in the reactor by settling before the treated effluent is decanted. The microbes form particles that grow to a size that is dictated by the solids management characteristics of that particular system. In general, the solids management capability and characteristics differentiate between the several types of anaerobic treatment systems in common use.

Attached growth systems, otherwise known as fixed film systems, have a support medium, often called "packing," to which the anaerobic microorganisms attach as they grow. The media

can be stationary or not. Stationary media include rocks, coal, plastic or metal discs, and plastic packing. Sand is an example of media that is not stationary.

Suspended Growth Systems. UPFLOW

ANAEROBIC SLUDGE BLANKET (UASB). Figure 8-51 presents a diagrammatic sketch of the UASB system, which is one of the more technologically advanced high-rate anaerobic wastewater treatment systems. These systems are capable of removing 80% to 90% of COD from wastewaters having influent COD concentrations as low as 2,000 mg/L with hydraulic retention times of 8 to 10 hours.

The distinguishing characteristic of the UASB system is the granular bead, 1 to 2 millimeters in diameter, that contains the anaerobic microbes. These active beads are developed within the anaerobic reactor by the most basic process that is characteristic of life itself, natural selection. As wastewater is induced to flow up through the anaerobic sludge blanket, hydrodynamic drag causes the blanket to be fluidized, or expanded. Because the food is there, under anaerobic conditions, anaerobic microbes of all types utilize it and grow. Those species that tend, for whatever reason, to form into solid beadlike structures become incorporated into solids that are too heavy to be carried up and over the effluent weir. Those that do not tend to form into relatively heavy solids are carried up, over the weir, and out of the system. Eventually, those microbes that tend to form into rather dense, beadlike solids, come to predominate the biological growth and become, themselves, the sludge blanket.




Figure 8-51 Upflow anaerobic sludge blanket system (UASB). (Drawing courtesy of Biothane Corporation.)

If the velocity of upflow through the sludge blanket is managed, by use of effluent recycle when wastewater flow rate decreases, the beadlike microbial solids that make up the sludge blanket rub against one another and continually roll and abrade each other's surfaces. This action keeps the sizes of the individual beads to within the desired range and maintains the desired high value of "active microorganism-to-organic substance," which accounts for the high performance of the system.

As illustrated in Figure 8-51, the principle components and operational characteristics of the UASB system are:

- An influent distribution system
- A sludge "blanket" consisting of beads of active anaerobic (and/or anoxic) microorganisms, formed as described previously
- A gas collection system
- An effluent collection and discharge system that excludes air from the interior of the reactor

As influent wastewater enters the reactor via the influent distribution system, it flows up through the sludge blanket. Depending on the rate of flow, the velocity of the rising influent causes a certain amount of expansion of the sludge. Furthermore, depending on the cross-sectional area of the sludge blanket, there is a

certain variability in the distribution of the influent wastewater. There is a choice to be made here. For a given volume of sludge blanket (i.e., quantity of active microorganisms), the smaller the ratio of the cross-sectional area of sludge blanket to its depth, the more uniform the distribution of influent, but the greater the head against which the influent wastewater pump(s) must pump. Recently, design practice has favored deeper sludge blankets of relatively small cross-section.

MIXED, HEATED ANAEROBIC DIGESTER The mixed, heated anaerobic digester, usually arranged in two stages as illustrated in Figure 8-52, is what could be called "the typical 'high-rate' sludge digester." It represents an advanced version of the "old" anaerobic treatment technology, in which only mixing and temperature elevation were used to reduce required hydraulic retention time. The principal objective of mixing was to improve contact between active microbes and organic material, often in solid form. The objective of heating was simply to take advantage of the fact that almost all microbial metabolism doubles in rate for each 10°C rise in temperature. As an attending benefit, some organics, more soluble at the elevated temperature, are more readily metabolized because of their more direct availability to the microorganisms.




Figure 8-52 Mixed heated anaerobic digester.

Methane harvested from the treatment process itself is normally used to heat the digester contents. This accounts for the fact that the process is simply not economically feasible if the organic content is less than that represented by 8,000 to 10,000 mg/L COD.

As shown in Figure 8-52, the first stage of a mixed, heated anaerobic digester is the reactor. Nearly all of the anaerobic degradation of organics takes place in the first stage. The second stage is not mixed. This stage normally has a floating cover, and gas produced in the first stage is piped to this vessel. The functions of the second stage are solids separation by sedimentation, sludge storage, and gas storage. Clarified supernatant is decanted and, normally, returned to the head of the treatment system, possibly representing a significant organic and TSS load. Gas and stabilized solids are periodically transferred to processing and final use or disposal.

ANAEROBIC CONTACT REACTOR. The anaerobic contact reactor is a technologically advanced variation of the “old” mixed, heated anaerobic digester. It is technologically advanced in that it attempts to maintain a high ratio of active microbes-to-organic matter, by providing sufficient mixing energy to keep the sizes of biological solids small by shearing action, and by returning “seed” organisms to the reactor from the clarifier. Hydraulic retention times of less

than a day have been reported, with treatment performance approaching 90% removal of COD.

As shown in Figure 8-53, the mixed, heated anaerobic reactor is followed by a clarifier. If a plain sedimentation clarifier is used, it is normally preceded by a degasifier. Otherwise, a vacuum flotation solids separation device may be used. The raw or pretreated wastewater enters the anaerobic reactor, which is normally operated in the completely mixed mode (CMR). Active anaerobes are continually recycled back from the clarifier, maintaining high-rate treatment kinetics.

Anaerobic contact reactors have proven to be of significant value as a first stage for removing COD from high-strength wastewaters, such as those from meat packing and rendering plants. Subsequent stages have usually been aerobic. The impressive cost effectiveness of the anaerobic first stage is because of (1) the rapid hydrolysis of complex organics to simple, easy-to-treat compounds with very little energy input (equation 8-60), (2) the small quantity of excess biosolids that results, and (3) the advantageous use that is made of the heat that accompanies some industrial wastewaters. This heat would be detrimental to the aerobic technologies because the saturation concentration of oxygen, and thus the driving force to dissolve oxygen into the mixed liquor, is significantly lowered.




Figure 8-53 Anaerobic contact reactor.

Fixed Film Systems.

EXPANDED BED REACTOR. The expanded bed system is among the most technologically advanced anaerobic wastewater treatment options. This technology, illustrated in Figure 8-54, was developed with the objectives of (1) achieving the maximum possible active microbe-to-organic matter ratio, (2) optimizing the effectiveness of contact between organic substances and microbes, and (3) at the same time, minimizing the energy requirement to expand, or “fluidize,” the bed as well as to pump wastewater through the system.

As illustrated in Figure 8-54, the objective of maximizing the F/M ratio has been achieved through use of a “packing medium” that has a surface-to-volume ratio that is as large as possible. The objective of maximizing the efficiency

of contact between microbes and organic matter was achieved by utilizing the upflow (fluidized bed) configuration. The objective of minimizing the energy needed to fluidize the bed (expand the bed, in this case) was achieved by utilizing material of low specific weight (specific gravity only slightly greater than one) as the packing medium.

Referring again to Figure 8-54, raw or pre-treated wastewater, blended with recycled effluent, is pumped into the bottom of the reactor. A distribution system distributes this mixture as uniformly as possible across the full cross-section of the reactor. The wastewater then flows up through the packing medium, which is coated with a thin film of active anaerobic microbes. As mentioned earlier, the velocity of upflow of wastewater being treated has several purposes, and its value is critical to the




Figure 8-54 Anaerobic attached film expanded bed reactor (AAFEB).

success of the system. The first purpose is to expand the bed and cause the organic molecules in the wastewater to follow a tortuous path, contacting many coated grains of the medium. The second purpose is to carry biological and other solids that become knocked off the grains of medium up through the bed. The third purpose is to cause the grains of medium to abrade against one another, rubbing off excess biological and other solids and, thus, maintaining the active microbes on the medium in as thin a film as possible.

The velocity of upflow through the expanded bed system, coupled with the recycle rate, also determines the hydraulic retention time (HRT). The rate at which microbial solids are produced, removed from the grains of medium by the abrasive action of the expanded bed, and carried up through and out of the bed determines the mean cell residence time, or sludge age.

As the biological and other solids emerge from the top of the bed, the upflow velocity of flow decreases as a result of the absence of solid particles of the medium from the cross-section of the flow. Here, the solids are not carried upward, but "settle." Solids thus accumulate in the settling zone above the expanded bed and must be removed at a rate

that precludes them from being swept over the outlet weir at the top of the reactor.

Methane and carbon dioxide gases are continually produced within the microbial films surrounding the particles of bed medium. These gases result in bubbles that grow until their buoyancy carries them up and out of the bed. They then rise more slowly through the solids settling zone and are collected by a device located above the settling zone.

FLUIDIZED BED REACTOR. The fluidized bed reactor resembles the expanded bed system in physical appearance, but differs principally in three respects: (1) the media used are typically much heavier (sand rather than diatomaceous earth), (2) the velocity of wastewater upflow is significantly higher (needed to fluidize the heavier media), and (3) the amount of expansion is significantly greater (20% rather than 5%).

Figure 8-55 shows a diagram of an anaerobic fluidized bed wastewater treatment system. As shown in Figure 8-55, raw or pretreated wastewater, combined with recycled effluent, is pumped through a distribution system at the bottom of the reactor and up through the




Figure 8-55 Anaerobic fluidized bed reactor.

media, which might be sand. The upflow velocity expands the bed, which allows any given molecule of water or organic material to take a tortuous path through the bed, contacting many grains of medium and, consequently, the microbial film attached thereto. The upflow velocity of the wastewater also causes the grains of the medium to constantly rub against each other, and the abrasive action keeps the microbial film from growing too thick and from bridging between grains to form blockages to flow. Biological and other solids that are knocked loose from the media are carried up through the media by the relatively high velocity of the upflowing wastewater.

As the wastewater emerges from the top of the bed of sand (or other medium), the effective cross-sectional area for the flow increases greatly as a result of the absence of solid medium. Consequently, the upflow velocity decreases, so that it no longer can carry solids upward. The solids thus “settle” in the zone just above the bed.

As methane and carbon dioxide gases are produced within the microbial films on the surfaces of the media, bubbles form and grow until their buoyancy carries them up through

and out of the bed. These gas bubbles then rise through the solids settling zone and are collected at the top of the reactor. The type of gas collection device is one of the characteristics that distinguishes among different proprietary fluidized bed systems.

PACKED BED REACTOR. An anaerobic packed bed reactor consists of a vessel (round steel tank, rectangular concrete basin, earthen lagoon, etc.) that is filled with a stationary solid medium to which microbes can attach and through which wastewater flows and comes into contact with the microbes. An anaerobic packed bed reactor can be operated in either the upflow or downflow mode, and effluent recycle can be used to even out variations in raw wastewater flow rate. Many different types of packing can be used, but the most common are stones and plastic devices of various shapes. The design objectives of the plastic media include high surface-to-volume ratio, structural strength, and to be nonreactive with any chemical that might be in the wastewater. Figure 8-56 shows a diagram of a packed bed reactor.




Figure 8-56 Anaerobic packed bed reactor.

ANAEROBIC LAGOONS. Anaerobic lagoons are subjected to such a high organic loading that anoxic or anaerobic conditions prevail throughout the entire volume. The biological treatment processes that take place are the same as those that take place in anaerobic digesters; however, there is no mixing, no heating, and no attempt to control or manage either the size or location of the “clumps” of biological solids that develop. Consequently, the progress of treatment is relatively slow, although highly cost effective in many applications.

Basically, the typical anaerobic lagoon is an earthen basin having an inlet, outlet, low surface-to-volume ratio, and is relatively deep. If the basin is not excavated from soil of very low permeability, it must be lined to protect the groundwater below. Because of the ever-present potential for problems caused by odors, it is usually necessary to cover anaerobic lagoons. Covers have been manufactured from synthetic membranes and Styrofoam. In some cases, the layer of solids that forms on the surface of the lagoon as a result of floating greases, oils, and the products of microbial metabolism (scum layer) has successfully prevented intolerable odor problems.

Organic loading rates reported for anaerobic lagoons have varied from 54 to 3,000 pounds of BOD₅ per acre per day. BOD₅ removal performance has varied from 50% to 90%. Lagoon depths have varied from 3.5 to 7 feet, and hydraulic detention times have varied from 4 to 250 days. More typical organic loadings have been in the range of 1,000 pounds of BOD₅ per acre per day, with BOD₅ removals in the range of 70% to 80%. Depths have been typically in the range of 5 to 7 feet. More typical hydraulic detention times have been in the range of 30 to 50 days, and have varied with climate, being longer in colder climates.

Physical Methods of Wastewater Treatment

Physical methods of wastewater treatment remove substances by use of naturally occurring forces such as gravity, electrical attraction,

and van der Waalls forces, as well as by use of physical barriers. In general, the mechanisms involved in physical treatment do not result in changes in chemical structure of the target substances. In some cases, physical state is changed, as in vaporization, and often, dispersed substances are caused to agglomerate, as happens during filtration.

Physical methods of wastewater treatment include sedimentation, flotation, and adsorption, as well as the use of physical barriers such as bar racks, screens, deep bed filters, and membranes.

Separation Using Physical Barriers

Many separation processes make use of a physical barrier through which the target pollutants cannot pass, simply because of their size. These physical barriers are classified according to the size of the passageways through which all but the target pollutants (and larger) can pass, and they range from bar racks to reverse osmosis. Bar racks, screens, and sieves are considered to be either part of the headworks or part of primary treatment, whereas filters, microscreens, dialysis processes, and reverse osmosis are normally considered either secondary or tertiary treatment, depending on specific use.

In the cases of the physical barriers with smaller pores (filters and microscreens, for instance), particles are often caught on the barrier bridge across the openings and form a filter themselves. For some substances, this surface filter is very effective with respect to degree of suspended solids removal and builds to appreciable thickness. Often, this process contributes to longer filter or screening runs. Some substances, however, are prone to clogging the surface of the filter or screen and are thus not appropriate candidates for filtration or screening.

Racks and Screens

Screening is a physical treatment method that uses a physical barrier as the removal mechanism. Screening ranges from coarse bar racks,

used to remove objects of 1 inch or more in size, to microscreening, used to remove particles as small as macromolecules (10 or so millimicrons in size).

The success of screening as a treatment method depends on the appropriateness of the mesh size of the screening device, compared to the sizes of the target substances, the clogging characteristics of the material removed on the screen, and the self-cleaning, or nonclogging, characteristics of the screening device. Bar racks can be either equipped with mechanical self-cleaners or must be periodically cleaned by hand. Smaller screens, including microscreens, are more difficult to clean, and the clogging characteristics of the wastewater must always be taken into account.

Screening is not to be confused with filtration in regards to mechanism of removal. Screening employs the mechanism of physical barrier as the primary removal method. Filtration employs adsorption, sedimentation, and coagulation, in conjunction with the physical barrier.

All screening devices that have mesh sizes smaller than $\frac{1}{2}$ inch must be pilot tested before design. The objectives of the pilot test program should include the clogging characteristics of both the screen and the materials in the wastewater, the buildup of head loss over time, and the potential for damage to the screen.

Bar Racks

Bar racks, often the first treatment devices to be encountered by wastewaters en route to renovation, protect pumps and other equipment from damage. These devices remove objects such as pieces of product or raw material, broken or dropped items of maintenance equipment, gloves, plastic wrapper material, or other foreign objects that inadvertently gain access to the industry's system of drains and sewers. A self-cleaning feature is considered well worth the extra cost because organic and other materials that are objectionable in many ways, including production of odors, tend to accumulate on these types of equipment. Materials of construction, as they relate to corrosiveness of

both the wastewater and the atmospheric environment in which the equipment must operate, are vitally important design considerations.

Two types of bar racks in general use include racks with stationary bars equipped with a moving automatic mechanical cleaning system and so-called filter screens, which have a slotted conveyor that passes all but the target objects. These objects are conveyed away from the wastewater by a moving slotted conveyor. Figures 8-57 and 8-58 show examples of a bar rack with an automatic moving mechanical cleaning system and a filter screen, respectively. Filter screens have been used with exemplary success at fish-processing plants, tanneries, woolen mills, and sugar refineries, to name a few.

Vibrating Screens

An example of a vibrating screen, used widely and successfully at vegetable-processing plants, metal-milling shops, and poultry-processing plants, is the so-called Sweco screen, pictured in Figure 8-59. This screen operates by receiving a wastewater stream at its center. The vibrating action of the screen causes particles or objects larger than the mesh size of the screen to migrate to the periphery, while everything else goes through the screen. Alternative types of vibrating screens include inclined vibrating screens and drum-type vibrating screens.

Tangential Screens

Tangential screens, also known as "sidehill screens," have the advantage of having no moving parts. Various devices have been used to clean these screens while in use, including water sprays, steam blasts, and air blasts.

The tangential screen shown in Figure 8-60 operates in the following manner: Wastewater enters the reservoir at the back of the screen, and after filling the reservoir, overflows over the top of the screen and flows down over the inclined face of the screen. Water and solids smaller than the mesh size of the screen proceed through the screen to the collection




Figure 8-57 Bar rack with automatic moving mechanical cleaning system. (Photo courtesy of U.S. Filter.)

device, and are then conveyed to the next treatment step. All other solids slide down the incline to be collected at the bottom. The name derives from the fact that the wastewater actually approaches the screen tangentially, as it overflows the reservoir at the top of the screen and down the incline until it proceeds through the screen.

Rotating Cylindrical Screens

Rotating cylindrical screens are designed to continuously clean themselves, using the flushing action of the screened water itself. Figure 8-61 shows a photograph of a typical rotating cylindrical screen. Figure 8-62 illustrates how the self-flushing action cleans the rotating screen on a continuous basis. As shown in Figure 8-62, wastewater enters the reservoir on one side of the rotating screen. Water and solids that are smaller than the mesh size of the screen flow through the screen, while larger solids are carried on the surface of the rotating screen, over the top, down the side, and are removed by the doctor blade located on the side of the screen cylinder opposite the raw

wastewater reservoir. Small solids that are caught in the spaces between the wedge-shaped bars that make up the screen are knocked loose and reenter the wastewater (downstream of the screen itself) via the wastewater that has just gone through the screen, as shown in Figure 8-62. The wedge-shaped bars of the screen and the action of the screened wastewater flushing back through the screen in the direction opposite to that of the screening action accomplish the continuous cleaning as the screen operates.

Microscreening

Microscreening, often called microstraining, is a physical treatment process that closely resembles the rotating screen, described previously. The major differences are in the size of the screen mesh openings and in the flow path taken by the wastewater being screened. Screen mesh openings used by microscreens are in the range of 20 to 35 μm . The filter medium is usually a fabric made of synthetic fiber.

As shown in Figure 8-63(a) and (b), the microscreen is a rotating drum having filter fabric around its periphery. The drum is mounted




Figure 8-58 Filter screen. (Photo courtesy of U.S. Filter.)



Figure 8-59 Vibrating screen. (Courtesy of SWECO.)

into one wall of a reservoir of wastewater, which enters the drum through that end. The wastewater then flows through the filter fabric from the inside to the outside of the drum. Solids that are too large to pass through the filter fabric are removed from the fabric by a mechanism at the highest part of the rotating drum. These collected solids flow via a trough to a collection tank. The screened wastewater flows over a weir, which, as illustrated in Figure 8-63(a) and (b), maintains a certain degree of submergence of the microscreen. Because of this submergence, a certain amount of screened wastewater flows back through the filter fabric (from the outside to the inside), dislodging particles that have been wedged into the mesh. In addition to this filter fabric cleaning action, a system of spray nozzles usually cleans the fabric. In total, the fabric-cleaning process consumes from 2% to 5% of the wastewater flow that has already been screened.

Microscreens have been used to remove algae and other solids from oxidation pond effluents as well as other types of wastewater treatment lagoons. Reported removal performance has usually been in the range of 50%. Hydraulic loading rates have been in the range of 75 to 150 gallons per square foot of filter medium per minute ($\text{gal}/\text{ft}^2/\text{min.}$).

Plate and Frame Filters

Plate and frame filter presses, normally thought of in the context of waste treatment as sludge dewatering devices, have been used with excellent results as separation processes for precipitated metals and other substances, immediately following flocculation. A plate and frame filter can also be used sometimes with and sometimes without precoat and/or body feed, as shown in Figure 8-64.

Figure 8-64 presents an illustration of a plate and frame filter press. The feed slurry, which may contain diatomaceous earth or another "body feed" such as "pearlite," enters the center of each framed cavity. The liquid is forced by pressure created by the feed pump to proceed through the filter medium, which can consist of fabric made of natural, synthetic, or

metal fibers. The target particles that, by virtue of their size, cannot go through the filter media (fabric plus body feed, if any) accumulate within the framed cavities until the cavities are full, or until the resistance to flow equals, or nearly equals, the pressure created by the pump. At this point, the filter run is stopped, and the plates are opened to discharge the accumulated cake.

A principle advantage of using a plate and frame filter press immediately following flocculation of a precipitated or coagulated substance is that the product is in an easily handled form. It is also a noteworthy advantage that no gravity settling device is used, thus eliminating the expense and labor needed to operate and maintain that unit process.

Membrane Separation

Membrane separation processes include microfiltration (MF), ultrafiltration (UF), nanofiltration (NF), reverse osmosis (RO), dialysis, and electrodialysis. They use one or more membranes, which can be thought of as physical barriers between phases, through which only limited components of the phases can pass. These processes are used to separate molecular or ionic species from waste streams. The properties of pollutants to be removed that bear on the appropriateness of these processes, or, indeed, that influence the selection of one of these processes over the others, are particle size, diffusivity, and/or ionic charge. Each of these membrane processes functions by way of something in the wastewater stream passing through one or more membranes and being concentrated in a stream known as the "reject." The treated effluent is less concentrated in the target pollutants than the influent by an amount that is proportional to the driving force as well as to the length of time over which the treatment takes place.

The rejection (removal) capability of a given membrane is rated on the basis of its nominal pore size or molecular weight cutoff (MWCO). MF, UF, and NF membranes typically have pore sizes that allow them to effectively remove micron-sized (10^{-6} m) substances from water. UF membranes remove substances that are 10^{-9} m and larger.

Nanofilters are usually rated by the smallest molecular weight substance that is effectively removed. These substances include organic molecules. Molecular shape and polarity are influential, as well as molecular size, in determining removal effectiveness.

Reverse osmosis, also referred to as “hyperfiltration,” effectively removes ion-sized substances such as sodium, calcium, sulfate, chloride, and nonpolar organic molecules.

Membrane materials are made from organic polymers, such as cellulose acetate, polysulfone,



Figure 8-60 Tangential screen. (Courtesy of Hycor.)



Figure 8-61 Rotating cylindrical screen. (Courtesy of Hycor.)




Figure 8-62 Self-flushing action of a typical rotating cylindrical screen.



Figure 8-63(a) Microscreening process. (Courtesy of U.S. Filter/Envirex Products.)

polycarbonate, and polyamide, and inorganics, including aluminum oxide (ceramic) and porous carbon. The preparation of a given polymer can be varied to produce membranes of different porosity or MWCO. These membranes can be configured in stacks of plates,

spiral-wound modules, or bundles of hollow fibers. Figures 8-65(a)–(d) show several different configurations in which commercial membranes can be obtained.

Probably the greatest deterrent to more widespread use of membrane processes is the

tendency of the membranes to become fouled, or blocked, by colloidal and other substances in wastewater. This phenomenon, which is sometimes referred to as concentration polarization, leads to flux inhibition, or reduction in throughput. Various techniques have been, and are being, developed to combat this problem, including flow perturbations such as back flushing and pulsing.

Another problem with the use of membrane processes for wastewater treatment is

biological fouling. Various microorganisms can become deposited on membrane surfaces, where they can flourish as a result of fresh nutrients constantly being transported to them by action of the treatment process itself. Sometimes, this problem can be controlled by disinfection of the wastewater, chlorination, ultraviolet, or other treatment, upstream of the membrane system. Care must be taken to avoid damage to the membrane by the disinfection activity.




Figure 8-63(b) Microscreening process. (Courtesy of U.S. Filter/Envirex Products.)




Figure 8-64 Plate and frame filter press. (Courtesy of U.S. Filter/JWI.)

There has been significant research and development recently to produce membranes that resist fouling of any type. This development has enabled potential use of membrane technologies to be used as waste treatment at the source, as part of an overall waste minimization (pollution prevention) program. In some cases, it may also be feasible to replace clarifiers within wastewater treatment systems with one or more membrane technology systems, thus greatly simplifying solids separation. The product water may be suitable for reuse in one or more processes (including wash-down water), and the solids may be suitable for reclamation.



Figure 8-65(a) Commercial membrane configurations. (Courtesy of U.S. Filter/Memcore.)



Figure 8-65(b) Commercial membrane configurations. (Courtesy of U.S. Filter/Memcore.)

Removal Mechanisms

As explained earlier, microfiltration, ultrafiltration, and nanofiltration are membrane separation processes that differ principally in the size range of the target substances. These filtration processes involve physical filtration of wastewater by forcing, by use of pressure, water molecules through a membrane that is not permeable to the target substances. These target substances can vary in size from small particles to molecules. Although this description can be applied equally well to reverse osmosis, the two processes differ with respect to the types of membranes used. There is only very small osmotic pressure to overcome in the case of ultrafiltration, for instance.

The membranes used for ultrafiltration are not of the “semipermeable” types that are associated with osmosis. Therefore, although pressure is the principal driving force for both reverse osmosis (RO) and ultrafiltration (UF), the required pressure is significantly less, and the cost for power is less for UF. Typical operating pressures for ultrafiltration systems vary from 5 to 100 psig, compared to 300 to 1,500 psig for RO systems. Whereas RO has the ability to remove dissolved ions such as sodium



Figure 8-65(c) Commercial membrane configurations. (Courtesy of IDI/Infilco Degremont, Inc.)




Figure 8-65(d) Commercial membrane configurations. (Courtesy of IDI/Infilco Degremont, Inc.)

and chloride, as well as organic molecules and undissolved solids, these filtration processes do not remove low-molecular-weight ions and molecules. Ultrafiltration and nanofiltration are useful for removing higher-molecular-weight organic and inorganic molecules as well as undissolved solids.

Ultrafiltration has been used in “direct filtration” of precipitated metal ions. This process involves the addition of a precipitating agent, such as sodium hydroxide, or sodium sulfide, followed directly by ultrafiltration. The coagulation and sedimentation steps are eliminated. Ultrafiltration has also been used to clarify dilute colloidal clay suspensions, as well as to remove microorganisms.

As with all other applications of treatment devices applied to industrial wastewater, an extensive pilot program must be conducted before final design.

Reverse Osmosis

Reverse osmosis operates by allowing water molecules to pass through a membrane that will not pass the molecules or ions regarded as pollutants. In any system in which two volumes

of water are separated by a membrane that is pervious to water molecules but not to the particular molecules or ions that are dissolved in the water, and if the concentration of those molecules or ions is greater on one side of the membrane than it is on the other side, water molecules will pass through the membrane from the less concentrated volume to the more concentrated volume, in an attempt to equalize the concentration on each side of the membrane, in conformance with the second law of thermodynamics. This movement of water from one side of the membrane to the other causes the depth of water to increase on one side and decrease on the other, resulting in a differential head, thus, differential pressure, on one side of the membrane with respect to the other. The differential pressure counteracts the tendency of water to move across the membrane, until the point is reached that the differential pressure-resisting movement of water through the membrane equals the “pressure” caused by the desire of the system to equalize the concentration of all dissolved substances on each side of the membrane. At that point, equilibrium is reached, and the net movement of

water across the membrane is zero. The differential pressure at equilibrium equals the “osmotic pressure” and is directly proportional to the difference in concentration of dissolved substances in the two water volumes.

This process is “osmosis” and takes place whenever volumes of water of different concentrations in one or more dissolved substances are separated by a membrane (known as a “semipermeable membrane”) that is permeable to water but not to the dissolved substances. If the water on one side of a semipermeable membrane is very low in dissolved solids, and wastewater is placed on the opposite side, a relatively strong osmotic pressure tends to drive water molecules from the clean water side to the dirty water side. Now, if pressure greater than the osmotic pressure is imposed on the dirty water side, the osmotic pressure is overcome. Because the membrane is permeable to water molecules, the pressure forces water through the membrane, from the wastewater into the clean water compartment, against the osmotic pressure, which increases in proportion to the increasing dissolved solids concentration differential. The result is concentration of the wastewater and production of clean water.

The membrane’s ability to pass water molecules but not other ions and molecules accounts for the wastewater treatment mechanism. The osmotic pressure that must be overcome, added to additional pressure required to force water molecules through the membrane, accounts for the relatively high cost of energy to operate an RO wastewater treatment system. Typical operating pressures for RO systems range from 300 to 1,500 psig.

Reverse osmosis systems have been successfully applied to removing fats, oils, and greases (FOG), as well as salts and other dissolved substances, from wastewaters in order to comply with discharge limitations. In several cases, the substances removed by RO have been successfully recycled and reused, substantially reducing the real cost for this treatment step. In fact, because RO is more widely used as a manufacturing process than for wastewater treatment, it

should always be considered as part of a wastes reduction or pollution prevention program.

Electrodialysis

The mechanism of separation of pollutants from wastewater using electrodialysis is that of electrical attraction of ions and consequent movement through a solution toward an electrode, of opposite charge, combined with selective transport of ionic species through membranes. The driving force is electrical attraction, and the selectivity of the membranes makes the separation of target pollutants from wastewater possible. Figure 8-66 presents a diagrammatic representation of an electrodialysis cell. Electrodes of opposite charge are on either end of the cell. Within the cell are placed, alternately, cation permeable and anion permeable membranes. When the cell is filled with wastewater, and the electrodes are charged, cations migrate toward the cathode, and anions migrate toward the anode. In cell 2, cations migrate toward cell 1 and are admitted into cell 1 because the membrane between the two is cation permeable. Anions migrate from cell 2 toward cell 3, drawn by the anode, and are admitted to cell 3 through the anion permeable membrane. At the same time, anions migrate in cell 1 toward cell 2, drawn by the anode, but are not admitted to cell 2 because the membrane between cells 1 and 2 is not anion permeable. Likewise, in cell 3, cations migrate toward cell 2, drawn by the cathode, but are not admitted to cell 2 because the membrane separating cells 2 and 3 is anion permeable, not cation permeable. As this process continues, cells 2, 4, 6, and so on, lose nearly all ions, whereas cells 1, 3, 5, and so on, gain the ions lost by the even-numbered cells. The effluent from the even-numbered cells is called the product water, and the effluent from the odd-numbered cells is called the concentrate. The concentrate may be considered to be waste, and may be either disposed of directly or processed further, or it may be considered to be source of valuable substances to be recycled or otherwise made use of.




Figure 8-66 Schematic diagram of an electro dialysis cell.

The potential to reduce real costs for treatment by realizing value from pollution prevention should always be given full consideration. As with reverse osmosis and ultrafiltration, electro dialysis may have its greatest potential usefulness in purifying isolated waste streams for reuse of substances that were previously considered pollutants, and/or for simple reuse in the manufacturing process from which it came.

Electro dialysis is applicable to removing only low-molecular-weight ions from wastewater. Electro dialysis may be used in combination with ultrafiltration where dissolved ions would be removed by electro dialysis and organic molecules would be removed by ultrafiltration.

Filtration Using Granular Media

Three principle types of granular filters used for industrial wastewater treatment include deep bed granular filters, precoat filters, and slow sand filters. Filters are physical treatment devices, and the mechanisms of removal include one or more of physical entrapment, adsorption, gravity settling, impaction, straining, interception, and flocculation. Whereas slow sand filtration accomplishes removal within only the first few millimeters of depth from the surface of the sand, both deep bed granular filters and precoat filters (when body feed is used) make use of much more of the filter medium.

There are two distinct operations that characterize any granular filter: the filtering phase and the cleaning phase. With respect to these two phases, operation may be continuous or semicontinuous. In continuous operation, the

filtering of wastewater and the cleaning of the filter medium or media take place at the same time. In semicontinuous operation, these steps take place in sequence.

Deep Bed Granular Filters

The intended operational process of a deep bed granular filter is that solid particles in the suspending medium are caused to follow a torturous path through the void spaces between the filter granules until one or more removal mechanisms result in the particle being retained somewhere within the depth of the filter. Deep bed granular filters can be (1) of the downflow type, in which a considerable portion of removal takes place on the surface of the filter medium as well as in the initial few inches, or (2) in the upflow mode, in which the filter bed is expanded, or fluidized, and the initial few inches of filter medium is not as significant to overall removal. In fact, the primary removal mechanism involved in an upflow filter application is likely quite different from that involved in a filter operated in the downflow mode.

Deep bed granular filters use one, two, or more types of media, including sand, anthracite coal, and garnet. Figure 8-67 presents a sketch of a multimedia deep bed granular filter in which granular anthracite overlays silica sand, which overlays granular garnet. The specific weights of these three materials increase in the same order, so that during the backwashing part of the filter's operational cycle (cleaning phase), a natural separation of the three materials takes place.

Upflow Granular Filters

Figure 8-68 illustrates one of the primary mechanisms by which solid particles are removed by deep bed granular filters operated in the upflow mode. As illustrated in Figure 8-67, the upflow velocity of the wastewater being treated creates a buoyant force on the granules of filter medium, causing the bed to expand in proportion to that upward velocity. Target particles within the wastewater are carried up into the expanded filter bed, wherein there are velocity gradients. The velocities of liquid flow within the expanded bed are greatest near the middle portions of the spaces between filter medium granules, and are nearly zero in close proximity to the granules. Immediately above each filter medium granule there is a space in which the liquid velocity is either zero, or is in a downward direction. The target particles are carried (up) into the “depths” of the filter by the upflow velocity gradients between particles, then become trapped in the regions adjacent to and on top of, the individual

granules of filter medium. Once the particles come into contact with the granules, adsorption takes place, and the particles are removed from the wastewater. Also, as the particles are brought into contact with one another, coagulation and flocculation take place, and the resultant larger, denser flocs settle under the influence of gravity in the regions of stagnant velocity above each of the granules. The target particles are thus removed from the bulk liquid by a combination of coagulation, flocculation, gravity settling, and adsorption.

There is no widely accepted mathematical model for use in designing an upflow deep bed granular filter described previously. Experience has shown that filter performance is a function of the filtration rate, the concentration and characteristics of the particles to be removed, and the size, surface characteristics, density, and other characteristics of the filter media. An extensive pilot program is always required to develop reliable design parameters.




Figure 8-67 Illustration of a multimedia, deep bed, granular filter, shown in backwash mode. (Courtesy of IDI/Infilco Degremont, Inc.)




Figure 8-68 Illustration of removal mechanism of an upflow granular filter.

Within the limits allowed by the size and numbers of filter units available, and the quantity of wastewater to be treated, the operator has most control over effluent quality by controlling the filtration rate. If the filtration rate is too high, excess solids will be swept up and out of the filter. If the filtration rate is too low, there will not be adequate bed fluidization, and the removal mechanisms described earlier will not be able to manifest themselves. The most desirable filtration rate is that which results in the greatest quantity of satisfactory filtrate, on a long-term basis, per unit time of filter use.

Downflow Granular Filters

Deep bed granular filters operated in the downflow mode remove solid particles by mechanisms that are quite different from those that take place in the upflow mode. In the downflow mode, particles that are smaller than the sizes of the pores and passageways between filter medium granules are carried down into the depths of the filter until they contact, and are adsorbed onto, one of the granules of filter medium. Figure 8-69 illustrates the currently

accepted model of filtration mechanisms within downflow granular filters.

Figure 8-69 illustrates that particles are transported to the vicinity of filter granules (collectors), more or less along the paths of fluid streamlines, where attachment, and sometimes detachment, occur. Figure 8-69 shows that several transport mechanisms are operative, including hydrodynamics, diffusion, gravity settling, inertia, and interception.

As a deep bed granular filter is operated in the downflow mode, many of the larger particles are intercepted and removed by sieve action at the surface of the filter bed. Also, to some extent, these particles bridge across each other and form their own filter, which further filters out new particles brought to the filter surface. This is the primary removal mechanism in the case of slow sand filters, precoat-body feed filters, and other "surface-type" filters. In the case of deep bed granular filters, however, the filtration rate must be sufficiently high that hydrodynamic forces carry most of the particles past the media surface and into the depths of the filter where the mechanisms of diffusion, sedimentation, interception, and so on, illustrated in Figure 8-69, lead to attachment, and thus, removal.

In the case of precoat-body feed filters, described in more detail following, the filter bed continually builds in depth as the filter run progresses, and there is a continually renewed "surface" on which particles are collected by sieving action.

Filtration rate, then, is a critical operational parameter in downflow filters and upflow filters. In the case of downflow filters, too low a filtration rate results in too much removal of solids in the upper layers of the filter. The head loss becomes too high for further operation before the deeper portions of the filter are made use of. Too high a filtration rate, on the other hand, results in flushing too many solids through the filter, causing the filtrate to be unacceptable.

Headloss is a major operational factor in the case of downflow granular filters because hydraulic head, or pressure, is what causes flow through the filter. As particles are




Figure 8-69 Illustration of removal mechanism of a downflow granular filter.

removed on and within the filter, resistance to flow through the filter increases. This resistance to flow manifests itself in hydraulic headloss. Eventually, headloss builds to the point where the rate of flow through the filter is unacceptable, and the particles must be removed by backwashing. Usually, previously filtered water is used for backwashing. The backwash water is pumped through a manifold and distribution system at the bottom of the filter. The backwashing rate of flow is sufficient to expand the bed so that the scouring action of hydrodynamic forces and the filter medium granules bumping and rubbing against each other dislodge the particles removed during filtration. The upflowing backwash then carries the removed solids up and out of the filter

media, and into a trough or other collection device above the expanded filter bed.

Auxiliary scouring is sometimes necessary and is normally provided by one or a combination of high-pressure sprays onto the surface layers of the filter medium, mechanical stirring or racking within the filter bed, and/or the introduction of air bubbles at the bottom of the filter.

Downflow deep bed granular filters are operated either as constant head with declining rate of flow, or as constant rate of flow with either increasing head or constant headloss. Constant headloss is achieved by use of an artificial headloss device, such as a valve on the outlet, that gradually decreases its effect to maintain a constant total headloss across both the filter

and the valve during the filter run. Constant rate of flow with increasing head is achieved by either gradually increasing the depth of water over the filter throughout the filter run, or by applying pressure with air or a pump to an enclosed filter influent chamber. It is common practice to attach a manifold that applies water at a constant head to each of several parallel filters that then operate in the declining rate of flow mode. As the headloss in one filter increases, more flow proceeds to the other filters until the flow rate through the entire group of filters becomes unacceptable, either because of inadequate total filtration rate or because of unacceptable filtrate quality. At this point, backwashing takes place.

Often, filter performance can be significantly improved by use of chemical coagulants. It is critically important to provide adequate and appropriate chemical feed and rapid mixing, but it is not necessary to provide slow mixing because flocculation takes place very effectively within the filter, in either the upflow or downflow mode. This mode of operation, referred to as direct filtration, can be used when the load to the filter is not such that it

would be less expensive, long term, to provide a solids removal step consisting of chemical feed, rapid mix, slow mix (flocculation), and gravity settling before filtration. One technique for removing phosphorus, as explained in the section on chemical methods of wastewater treatment, is to add alum before the filter.

Deep bed granular filters, both upflow and downflow, can be operated in configurations where the filtration media are continuously washed. Sometimes referred to as “moving bed filters,” these systems have worked well in certain applications. Usually, a reasonably constant solids loading is desirable for successful continuous washing applications.

Figures 8-70(a)–(d) show four types of deep bed granular filters.

Pressure and Vacuum Filtration

Pressure filters and vacuum filters operate by means of exactly the same mechanisms as described for deep bed granular filters operated in the downflow mode. The difference is with respect to the values of the absolute pressures on each side of the barrier. These values are




Figure 8-70(a) Granular filter for industrial waste. (Courtesy of IDI/Infilco Degremont, Inc.)




Figure 8-70(b) Granular filter for industrial waste. (Courtesy of Parkson Corporation.)




Figure 8-70(c) Granular filter for industrial waste. (Courtesy of IDI/Inflico Degremont, Inc.)




Figure 8-70(d) Granular filter for industrial waste. (Courtesy of IDI/Infilco Degremont, Inc.)

normally atmospheric on the low-pressure side of a pressure filter, and greater than atmospheric on the high-pressure, or feed side. In the case of the vacuum filter, the pressure on the feed side of the barrier is normally atmospheric, whereas the pressure on the low-pressure side of the barrier is less than atmospheric. The principal differences between the equipment, then, are that a liquid pump and air-tight conveying devices are used on the feed side of pressure filters, whereas an air pump (vacuum pump) and air-tight piping and duct work are used on the low-pressure side of the barrier in the case of a vacuum filter. The physical barrier can consist of sand or another granular material, or fabric made of natural or synthetic fibers. The fabric can be coated with diatomaceous earth, or another fine granular material, or used without a granular coating material.

Precoat

If the fabric is coated with diatomaceous earth, perlite, or another granular material of low specific gravity, just before each use, the

filter is said to be “precoated.” This “precoat” is applied by simply mixing a predetermined quantity of the precoat material in clean water, then passing the slurry through the filter just as in a normal filter run. The precoat material, which is the diatomaceous earth, perlite, or other granular material, will collect in a uniform layer on the fabric to form a thin granular filter bed. A valve is then activated, and the precoat slurry is replaced with wastewater. It is important that the hydraulic pressure used for precoating be maintained continuously from the start of the precoat process to the end of the filter run, to maintain the integrity of the precoat.

Body Feed

After the precoat has been applied, and the process of filtering the wastewater through the precoat has commenced, a prescribed concentration of the same material as used for precoat (diatomaceous earth, perlite, or other granular material) is added to the wastewater. Figures 8-71(a) and (b) illustrate two methods for accomplishing this procedure. Figure 8-71(a)

shows that a slurry of filter media can be metered into the stream of wastewater as it is being pumped to the filter. Figure 8-71(b) shows that, alternatively, a predetermined amount of the filter medium can be mixed into

the wastewater that is to be filtered by use of a mixing tank. The mixing tank can be of a size that holds one day's contribution of wastewater, one filter run, or another convenient or cost-effective size.



Figure 8-71(a) Body feed added to precoat filter.



Figure 8-71(b) Body feed added in mixing tank.




Figure 8-72 Body feed increases filter depth.

Figure 8-72 illustrates the way in which the granules of body feed add to the thickness of the precoat to develop a filter of increasing depth as the filtration process proceeds in time. As shown in Figure 8-72, the granules of body feed, which are evenly dispersed throughout the wastewater, collect on the outside of the precoated filter support surface as the wastewater is forced through. These granules thus build a filter of ever-increasing thickness, preventing the original precoat from blinding over with suspended solids from the wastewater. Rather, the suspended solids, which are the target pollutants intended to be removed by the filter, are removed in the ever-increasing depth of the body feed filter as it builds.

Pressure or vacuum filters are routinely used to remove solids from dilute industrial wastewaters, usually with chemical conditioning, as well as to dewater sludges. One common use of pressure or vacuum filters is to dewater precipitated metals.

Figures 8-73(a)–(f) show six pressure or vacuum filters that can be used in industrial wastewater treatment.

Swimming Pool Filters


In some cases of short-term need, an off-the-shelf, packaged, automated deep bed granular or septum-type filter assembly, intended for swimming pool use, is a cost-effective alternative to achieve treatment by filtration. These items are inexpensive and are designed and constructed to provide reliable, automated service for a few years assuming an unaggressive water mixture.

Packaged Water Treatment Systems


Many packaged treatment systems were designed and manufactured to treat potable water. Many of these systems can be used to treat many different industrial wastewaters, with little or no modification. Some wastewaters that are candidates for these systems




Figures 8-73(a) Pressure and vacuum filters. (Courtesy of IDI/Infilco Degremont, Inc.)



Figures 8-73(b) Pressure and vacuum filters. (Courtesy of IDI/Infilco Degremont, Inc.)



Figures 8-73(c) Pressure and vacuum filters. (Courtesy of IDI/Infilco Degremont, Inc.)



Figures 8-73(d) Pressure and vacuum filters. (Courtesy of Eimco Process Equipment, a Baker Hughes Company.)



Figures 8-73(e) Pressure and vacuum filters. (Courtesy of EIMCO Process Equipment, a Baker Hughes Company.)


include dilute, small-volume process wastes, stormwater runoff, contaminated groundwater, and cooling water.

Several issues must be thoroughly addressed during the concept or preliminary design phase of such a project, including corrosivity, effects of any hazardous materials, or other properties, such as heat, intermittent flow, color,

susceptibility to weather, and variability of wastewater characteristics.

Slow Sand Filter

Slow sand filters are characterized by a loading rate that is significantly lower than the more conventional (sometimes referred to as “rapid



Figures 8-73(f) Pressure and vacuum filters. (Courtesy of Waterlink Separators, Inc.)

sand filters”) filter described earlier. In general, slow sand filters are useful for polishing small quantities of treated wastewater, water that has been used for scrubbing gases and is to be either discharged or renovated for another use, or simply as a final “emergency” barrier before discharge of water that is normally very clean.

Slow sand filters are loaded at rates between 2 and 4 gallons per day per square foot of filter surface area. Bed depths are typically 2 to 4 feet.

The mechanisms of removal in slow sand filtration include entrapment, adsorption, biological flocculation, and biological degradation. In fact, one of the reasons for the very low hydraulic loading rate of slow sand filters is to allow aerobic conditions within the first inch or two of the sand filter surface. The aerobic conditions allow for aerobic and, thus, relatively complete, biological removal of the organic portion of the material removed from the waste stream. Sand filters are cleaned periodically by removal of the top one-half to two inches of sand from the surface.

Plain Sedimentation

Plain sedimentation can be described as the separation of particulate materials from wastewater as a result of the influence of gravity. The more quiescent (nonmoving) the hydraulic regime, the more effective is this removal process; therefore, a principal objective of plain sedimentation equipment is to produce “quiescent conditions.” The process of plain sedimentation is often referred to as “clarification,” and the devices used to accomplish plain sedimentation are called “clarifiers” or “settling tanks.”

There are three modes by which particles undergo the plain sedimentation process: discrete settling, flocculent settling, and zone settling. Discrete settling is that process by which individual particles proceed at a steady velocity, governed principally by the specific gravity of the particle and the viscosity of the wastewater, toward the bottom of the settling device. The settling of sand in water is an example of discrete settling. Flocculent settling is undergone by particles, often organic,

that agglomerate to larger, faster settling particles as the settling process takes place over time. The settling of activated sludge in the upper several feet of a secondary clarifier (clarifier that follows, hydraulically, an activated sludge aeration tank or a fixed growth treatment process) is an example of flocculent settling. Zone settling is typically undergone by a suspension of relatively concentrated solid particles (sludge) as it concentrates even more. The vertical distance that an individual particle moves decreases with increasing depth in the sludge mass itself.

The overall objective of any physical wastewater treatment device, including clarifiers, is to remove as much solid material as possible, as inexpensively as possible, with a resulting sludge that has as low a water content as possible. The final residuals of the treatment processes must undergo final disposal, and the cost of final residuals disposal is usually proportional to some degree to the water content.

Discrete Settling

Under the influence of gravity, a particle immersed in a body of fluid accelerates downward until the forces relating to viscosity that resist its downward motion equal the force caused by gravity. At this point, the particle is said to have reached terminal velocity, described by equation 8-67:

$$V_s = \left[\frac{4g(\rho_s - \rho_1)D}{3C_{D\rho_1}} \right]^{\frac{1}{2}} \quad (8-67)$$

where:

- v_s = velocity of sedimentation (ft/sec)
- g = acceleration due to gravity (ft/sec²)
- ρ_s = density of the particle (lb/ft³)
- ρ_1 = density of the fluid (lb/ft³)
- D = diameter of particle (ft)
- C_D = coefficient of drag

The coefficient of drag, C_D , depends on several factors, including the diameter of the particle, if hydraulic turbulence is significant within the settling device. For the small size of

particles usually encountered in clarification of industrial wastewater, and the relatively low turbulence encountered in a well-operating clarifier, the relationship presented in equation 8-68 is considered to hold:

$$C_D = \frac{24}{N_R} \quad (8-68)$$

where: N_R = Reynolds number

Because Reynolds number increases with increasing turbulence of the fluid, the settling velocity, which is analogous to the rate of clarification, increases with decreasing turbulence.

There are interesting relationships, as shown by Hazen and Camp, between particle settling velocity, the surface loading of a clarifier, and the theoretical effect of depth of the clarifier on particle removal efficiency. These relationships are based on the conditions of a uniform distribution of particles throughout the entire clarifier at its influent end, and of whether a particle can be considered to be removed as soon as it reaches the bottom of the clarifier. If the rate of settling, expressed as vertical distance settled per unit of horizontal distance of forward flow in (ft/ft) of a particle in a clarifier is multiplied, top and bottom (numerator and denominator), by the rate of wastewater flow, in cubic feet per day, the units of gallons per day can be developed in the numerator, and the units of area, or square feet, can be developed in the denominator.

Therefore, equation 8-69 can be written:

$$V_s(\text{ft/ft}) = \text{surface loading rate (GPD/ft}^2\text{)} \quad (8-69)$$

which states that particle settling velocity, in ft/ft, is numerically equivalent to a term called "surface loading rate," having the units, gallons (of wastewater) per square foot (of clarifier surface area) per day, indicating that only clarifier surface area, to the exclusion of clarifier depth, is of significance to the performance of a clarifier.

Figure 8-74 illustrates that the major effect of increasing clarifier depth is simply to increase the time it takes to remove a given

particle, rather than to have any effect on removal effectiveness or efficiency.

Figure 8-74 illustrates that all particles having settling velocities equal to or greater than v_s will be completely removed. All particles having settling velocities less than v_s will be removed as described by the ratio v/v_s .

Flocculent Settling

Many solid particles found in wastewaters tend to agglomerate as they settle under quiescent hydraulic conditions, and because they become denser as they coagulate and agglomerate, their terminal velocities increase over time. The paths followed by solid particles undergoing flocculent settling, then, are illustrated in Figure 8-75.

Often, a given industrial wastewater contains a mixture of solids, some of which settle as discrete particles, and others that undergo flocculent settling. When sufficient particles reach the lower portion of the clarifier, the accumulated mass (sludge blanket) undergoes zone settling. Normally, either discrete or flocculent settling predominates in the upper portion of the clarifier and, therefore, becomes the basis for design. Those gravity clarification devices that combine the processes of primary sedimentation and sludge thickening are called "clarifier-thickeners." For these devices, the thickening characteristics of the settled sludge are also a basis for design.

Sludge Thickening

Once solids have settled under the influence of gravity, they must be removed from the bottom of the clarifier and ultimately disposed of. In order to reduce the cost of handling this material, it is desirable to reduce the moisture content, and thereby the volume, to a minimum as soon as practicable. To this end, "gravity thickeners" are often designed and built as integral components of wastewater treatment systems. Some clarifiers incorporate a thickening capability into the sludge zone, and are thus called "clarifier-thickeners."

Kynch, Talmage and Fitch, Behn and Liebman, and Edde and Eckenfelder have developed various methods for predicting performance of thickeners based on results of laboratory bench scale tests. These thickening tests have the common procedure of using standard 2-liter graduated cylinders that are filled with primary clarifier sludge, then the rate of downward progress (under the influence of gravity) of the sludge-water interface is determined. The aforementioned researchers have published different methods for analyzing the data collected using the 2-liter graduated cylinders.

Kynch's method uses the assumption that the settling velocity of a particle is a function of only the concentration of particles around that particle. A conclusion that resulted from this analysis was that waves of constant concentration move upward from the bottom of a settling solids concentration, each wave moving at a constant velocity. Talmage and Fitch used this analysis to show that the area of a gravity thickener is a function of the "solids handling capacity" of a given zone of constant concentration. The unit area (U.A.) required to pass a unit weight of solids through a given concentration (C_i) can be expressed as:

$$\text{U.A.} = \frac{1}{V_i} \left(\frac{1}{C_i} - \frac{1}{C_u} \right) \quad (8-70)$$

where:

V_i = settling velocity of the particles at concentration C_i

C_u = underflow solids concentration

The "underflow solids concentration" is the suspended solids concentration of the sludge as it is withdrawn from the bottom of the clarifier.

Behn and Liebman developed a relationship for the depth of the sludge compression zone as a function of the initial sludge concentration, rate of elimination of water from the mass of compressing sludge, dilution ratio, specific gravities of the solids and water, underflow concentration, and thickener area.




Figure 8-74 Illustration of the effect of increasing clarifier depth.




Figure 8-75 Illustration of settling paths taken by particles undergoing flocculent settling.

Edde and Eckenfelder developed a procedure for scale-up from bench scale results to design parameters for prototype thickeners. Thickener design is based on the following mathematical model relating thickener mass loading (ML) to underflow concentration (C_u), as follows:

$$(C_u/C_o) - 1 = D/(ML)^n \quad (8-71)$$

The depth of sludge in a batch test (D_b) is related to depth of sludge in the prototype (D_t) based on conditions observed in the field.

The design procedure presented as follows uses a “settling column” (for discrete and/or

flocculant settling) and a 2-liter graduated cylinder (for sludge thickening) to obtain laboratory data for use in design of an industrial wastewater clarifier-thickener.

Design Procedure

Figure 8-76 shows a standard laboratory settling column used to generate data for use in designing a clarifier. Figure 8-77 shows a photograph of a settling column. Usually, two or more 6-inch-diameter transparent plastic pipe

sections are clamped together to make up a column that is 12 to 16 feet long. The column is fitted with sampling ports at each foot of depth, when the pipe is standing on end. A plate seals the bottom, and a clean-out port is located as close to the bottom as possible.

The settling column is filled with mixed, raw wastewater and allowed to achieve quiescent conditions. At intervals of 5 to 15 minutes, samples are withdrawn from each of the sample ports for suspended solids analysis.




Figure 8-76 Settling column.



Figure 8-77 Settling column.

Figure 8-78 presents a plot of the results of suspended solids analyses obtained at progressive time intervals from each of the sampling ports in the settling column. Lines that connect the data points from each sampling port represent given fractions of TSS removal and describe the approximate path that would be taken by particles settling in an ideal settling tank (no physical or other influences on the settling particles other than gravity and viscous resistance to motion). The data plotted as shown in Figure 8-78 are analyzed, and criteria for design of a clarifier are developed, as shown in the following example.

Example 8-6: Development of design criteria for a clarifier-thickener

By Kurt Marston

Using a standard settling column, and the procedures described by Eckenfelder and Ford,

develop design criteria for the settling portion of a combination clarifier-thickener to remove and concentrate suspended solids from wastewater from a paper mill. Using standard 2-liter graduated cylinders, develop design criteria for the sludge thickening portion of the combination clarifier-thickener.

Solution: Clarifier portion of clarifier-thickener

Raw wastewater was collected from the paper mill effluent at an integrated Kraft pulp and paper mill. The standard settling column shown in Figure 8-76 was filled with the (well-mixed) wastewater, and quiescent conditions were allowed to develop. Then, samples were withdrawn from each of the ports simultaneously at various time intervals. Each sample was analyzed for suspended solids concentration. The BOD_5 was determined on samples from the

port located 3 feet below the top of the column. Two of these procedures were carried out, one at a temperature of 3.5°C and another at 18.5°C.

The data thus developed were plotted as shown in Figures 8-79 and 8-80. Figure 8-79 presents the results of data from the procedure performed at the temperature of 3.5°C. Figure 8-80 presents the results of data taken at 18.5°C. Comparison of these results shows that higher settling rates were obtained at the higher temperature, a result to be expected because of the higher viscosity, thus greater drag, and thus slower settling of particles through the more viscous medium at the lower temperature.

Figure 8-81 presents suspended solids removal versus detention time for the wastewater at 3.5°C and at 18.5°C. The corresponding overflow rates are presented in Figure 8-82. BOD₅ removal as a function of suspended solids removal is presented in Figure 8-83. These results, as expected, show that BOD₅ removal increased with increasing suspended solids removal, but at a decreasing rate, as the limit of BOD₅ contributed by suspended solids (as opposed to dissolved organics).

These three figures, then, are the principal product of the settling column analysis procedure. These results, along with appropriate scale-up factors (obtained from manufacturers) can be used to determine the cost for the different sizes of clarifier, as determined by overflow rate and the desired percent removal of suspended solids and/or BOD₅.

Thickener Portion of Clarifier-Thickener

Samples of primary clarifier sludge were collected at a paper mill that was very similar in type of manufacturing process to the mill for which the column settling analyses presented previously were being performed. The samples of sludge were diluted (with primary effluent) to the desired initial suspended solids concentration, then placed in the 2-liter graduated cylinders. The initial suspended solids concentration, temperature, and specific weight of the water were determined

for each cylinder. The liquid-solids interface level was recorded at regular intervals until a constant level was reached. The results of these data are presented in Figure 8-84, which presents plots of solids-liquid interface height versus time for four initial sludge concentrations.

Using the mathematical models presented by Talmage and Fitch and Behn and Liebman, the solids concentration, C_i , at the interface at time, t_i , and the settling velocity, V_i , of the particles at concentration C_i can be determined.

Figure 8-85 presents solids concentration, C_i , versus time relationships for the four sludge slurries examined, and Figure 8-86 presents the concentration-velocity relationships.

The next step is to determine the unit area (ft.²/lb/day) required for given values of sludge-liquid interface settling velocities for three or more different values of initial sludge concentrations. These results are presented in Figure 8-87, which shows that for given values of initial sludge concentration there is a maximum unit area (high point on each curve). As discussed by Behn and Liebman and Talmage and Fitch, the maximum unit area for a given underflow (initial sludge) concentration is the theoretical cross-sectional area required for a sludge thickener.

Figure 8-88 is then constructed in order to determine the depth required for thickeners for given values of underflow (initial sludge) concentration. As discussed by Behn and Liebman, the depth of a thickener is a fraction of the volume represented by a given "dilution" of the solids, or "dilution factor". Figures 8-88(a) – (d) present plots of dilution factors versus time for the appropriate values of sludge underflow concentration. The slopes of the appropriate lines are equal to the values of k in equation 8-72:

$$Depth = H = \frac{Q_o C_o (t_u - t_c) \left(\frac{1}{\rho_s} + \frac{D_\infty}{\rho_w} \right)}{A - \frac{(D_c - D_u)(Q_o C_o)}{\rho_w (k H_0)}} \quad (8-72)$$




Figure 8-78 Plot of percent removal of TSS at given depths vs. time. Settling column analysis.




Figure 8-79 Solids removal for depth vs. time (3.5°C).




Figure 8-80 Solids removal for depth vs. time (18.5°C).




Figure 8-81 Suspended solids removal vs. time.




Figure 8-82 Suspended solids removal vs. overflow rate.




Figure 8-83 BOD₅ removal vs. suspended solids removal.




Figure 8-84 Liquid-solids interface height vs. time.

Figure 8-89 can be constructed to illustrate the analysis of data described by Edde and Eckenfelder. In this analysis, the results of sludge-liquid interface height versus time and unit area versus settling velocity are plotted as presented in Figures 8-84 and 8-87.

Then, the values of maximum unit area for different feed and underflow concentrations are constructed as shown in Figure 8-89. The next step is to construct the semi-log plot of the depth in the batch test versus original solids concentration, as presented in Figure 8-90. Figures 8-89 and 8-90 can be interpolated to obtain values needed for design calculations, which are not identical to those used in the laboratory analysis.

Design Calculations

By Kurt Marston

Having constructed the curves as presented in Figures 8-79 through 8-90, the appropriate size of clarifier-thickener for wastewaters of

given solids settling characteristics can be determined, as illustrated in the following demonstrative calculations.

Example 8-7:

Design a clarifier-thickener for the pulp and paper wastewater using the testing data described in Figures 8-79 through 8-90 to accommodate an influent design flow of 10 million gallons per day (MGD) and to achieve 60% suspended solids removal at 3.5°C with an underflow concentration of 10,000 mg/L. Influent suspended solids (the raw wastewater) were measured at approximately 300 mg/L.

Clarifier requirements can be derived from Figures 8-81 and 8-82. Based upon the data curves for wastewater at 3.5°C, Figure 8-81 shows a minimum detention time of approximately 20 minutes and Figure 8-82 shows a minimum overflow rate of approximately 2500 gpd/ft² required to achieve 60% suspended solids removal.

Minimum area for clarification = $(10,000,000 \text{ gpd}) / (2500 \text{ gpd/ft}^2) = 4,000 \text{ ft}^2$




Figure 8-85 Sludge concentration vs. time.




Figure 8-86 Sludge concentration vs. settling velocity.




Figure 8-87 Unit area vs. velocity.

Minimum depth for clarification = (Flow)(detention time)/Clarifier area = 4.6 ft

These values represent results obtained under ideal (laboratory) settling conditions. It is necessary to apply scale-up factors appropriate to each type of clarifier. Scale-up factors are normally selected based upon experience reported

in the literature and through discussions with manufacturers. Typical scale-up factors are in the range of 1.5 to 2.0.

Thickener requirements calculated using the Behn and Liebman Methods:

C_u = Underflow Concentration = 10,000 mg/L = 0.624 lbs/ft³




Figure 8-88(a) Dilution factor vs. time.




Figure 8-88(b) Dilution factor vs. time.




Figure 8-88(c) Dilution factor vs. time.




Figure 8-88(d) Dilution factor vs. time.




Figure 8-89 Ratio of underflow to feed solids concentration vs. mass loading.

From Figure 8-85 the maximum time for reaching a concentration of 10,000 mg/L (t_u) is for the data curve for the 6,600 mg/L test sample with a value of approximately 440 minutes.

Figure 8-87 shows a maximum Unit Area of approximately 0.28 ft²/lb/day for the family of curves for the 6,600 mg/L test sample.

Solids loading to the thickener would be 60% of the 300 mg/L entering the clarifier = 180 mg/L in 10 MGD = 15,200 lbs/day.

Minimum area for thickening = (15,200 lbs/day) (0.28 ft²/lb/day) = 4260 ft²

Sludge Depth (H) required for thickening is calculated using equation 8-72.

From Figure 8-88(b), the value for k is the slope of the lower curve or 7.76×10^{-3} , and,

using the upper curve, $D_u = 85$ for $t_u = 440$ minutes, $D_c = 118$ for $t_c = 120$

$$H = \frac{\frac{15,200}{1440}(440 - 120)\left(\frac{1}{(1.35)62.4} + \frac{81.2}{61.91}\right)}{4260 - \frac{(118 - 85)\left(\frac{15,200}{1440}\right)}{61.91(1.33)7.76(10^{-3})}}$$

$$= 1.2 \text{ feet}$$

Plate, Lamella, and Tube Settlers

Examination of Figure 8-74 reveals that a particle settling at terminal velocity, v_s , in an ideal settling tank of hydraulic retention time, Q/V (where Q is the flow rate and V is the tank




Figure 8-90 Depth vs. concentration.

volume), will not become “removed,” until it reaches the end of the tank, if it starts at the surface. Furthermore, the deeper the tank, the longer the required HRT to remove the particle. There is a temptation, then, to imagine a very shallow tank, in which particles would reach the bottom very quickly, thus being removed in a very short amount of time and with relatively little cost (because of the small size of the clarifier). Common sense reveals, however, that turbulence resulting from such a shallow flow path would prevent effective settling (the clarifiers would not be able to attain quiescent conditions). The theoretical implication still remains, however, that the shallower the settling tank, the quicker the removal.

What, then, is the optimum depth for a clarifier, given that, on the one hand, surface loading is the only parameter that affects removal in an ideal clarifier and, on the other hand, that hydraulic turbulence affects removal in a negative way in a “real” clarifier?

Looking again at Figure 8-74, it can be seen that, no matter what the depth of the ideal settling tank, removal (by virtue of having reached the “bottom”) of solids having settling velocities much slower than v_s could theoretically be achieved if a series of false bottoms were placed within the tank, similar to a stack of trays. Figure 8-91 illustrates such a concept.

Although the theoretical validity of the concept illustrated in Figure 8-91 is indisputable, the actual occurrence of hydraulic turbulence imposes limits on application. Several devices have been developed and are in wide-spread

use that are based on the theoretical advantage illustrated in Figure 8-91. The device illustrated in Figure 8-91, known as a “plate settler” or a “lamella separator,” is an example.

Figure 8-92 shows a tank that contains a stack of flat plates that nearly fills the tank. The plates are inclined at an angle of 60° . The influent end of the tank is equipped with a device to distribute incoming flow uniformly across the tank, so that, to the extent possible, equal amounts of raw wastewater are caused to proceed through the spaces between each of the plates.

It is a fundamental principle of hydraulic flow, in both theory and fact, that fluids flowing in contact with a solid surface establish a velocity gradient. The velocity of flow is very small close to the solid surfaces and increases with distance from solid surfaces. Within the spaces between the plates shown in Figure 8-92, then, the velocity of flow from the influent end of the tank to the effluent end is greatest near the midpoints between the plates and is very small close to the plates. Therefore, if the velocity of flow of wastewater flowing through the “plate settler” shown in Figure 8-92 is less than the settling velocity of some of the solid particles contained in the wastewater, these particles will “settle.” As these particles settle, they quickly approach one of the plate surfaces, where the flow velocity steadily decreases. Eventually, the solid particles become very close to the plates, where the velocity of flow is almost zero. These settled particles then slide down the plates and into the sludge hopper, as illustrated in Figure 8-92.




Figure 8-91 Illustration of conceptual increase in removal efficiency by adding a series of false bottoms to an open, ideal settling tank.




Figure 8-92 Plate or Lamella separator. (Courtesy of Parkson Corporation.)

It is seen, then, that the treatment effectiveness of the simple, open clarifier can be improved dramatically by adding a series of “false bottoms” that have the effect of greatly decreasing the distance through which solid particles must settle before they are “removed” from the bulk liquid. Practical problems such as clogging of the spaces between the plates, the need for periodic cleaning before resuspension of organic solids by the action of denitrification or other phenomena, distribution of the flow at the influent end of the tank, collection of clarified flow at the effluent end, and the

cost of the plate system become the factors that influence design. These practical considerations also influence the selection procedure between alternative types of false bottom systems, or, indeed, whether it is more desirable to use a simple, open clarifier.

A great deal of experience has shown that, in general, plate settlers, or similar alternatives, are the clarifiers of choice for inorganic solids such as those associated with metals precipitation. Plate settlers have not been shown to be advantageous, however, for organic solids such as activated sludge. For

metals precipitation, for instance, it has been shown that the required HRT for satisfactory removal can be less for plate-type settlers than for open clarifiers by factors of six to eight.

Centrifugation

Centrifuges, which are devices that amplify the forces at work in gravity separation, are of several different types. Centrifuges are used for separation of grit and other relatively heavy solids at the head end of wastewater treatment facilities, as well as for sludge thickening and/or dewatering at the “other end” of such facilities.

So-called swirl separators, an example of which is illustrated in Figures 8-93(a)–(b), are devices that are used to separate grit that employ relatively low centrifugal force. The source of energy for these devices is normally a pump. The pump causes wastewater to flow through the swirl separator at a velocity sufficient to cause grit, or another high-specific-gravity material, to be thrown to the outside of the circular path within the separator (by centrifugal force). The solids are then collected at the outside of the separator, while the degritted liquid is collected at, or near, the center.

There are three basic types of centrifuges used for concentration of sludges: the solid bowl type, the basket type, and the disk-stack type. The essential differences are in the method by which separated solids are harvested. Figures 8-94(a)–(c) present illustrations of the three types of sludge-concentrating centrifuges.

Centrifuges have also been used to a limited extent for separation of lighter-than-water substances such as oil. In these cases, the aqueous discharge is collected at the opposite outlet from that where solids having a specific gravity greater than one are the target substances for separation.

A solid bowl-type centrifuge is diagrammed in Figure 8-95. The horizontal cylindrical-conical bowl rotates to cause solid particles to be thrown against its wall as they enter the bowl with the liquid to be dewatered at the center of the cylinder. A helical scroll within the bowl rotates at a slightly slower rate than the bowl itself and operates in a manner similar to a

screw conveyor to scrape the solids along the wall of the bowl to the solids discharge area. Centrate (the liquid from which solids have been removed) is discharged at the opposite end of the bowl.

The effectiveness of solids concentration is somewhat proportional to the speed of rotation of the bowl and inversely proportional, to a certain degree, to the feed rate. In some instances, chemical conditioning of the feed enhances operational effectiveness. Various polymers, as well as lime, ferric chloride, and other chemical conditioning agents, have proven to be cost-effective performance enhancers in various applications. Variations in operating parameters of the solid bowl centrifuge can also affect performance, such as scroll rotation rate and pool volume.



Figure 8-93(a) Swirl separator. (Courtesy of Smith & Loveless.)




Figure 8-93(b) Swirl separator. (Courtesy of Smith & Loveless.)



Figure 8-94(a) Photo of a solid bowl centrifuge. (Courtesy of Alfa Laval, Inc.)



Figure 8-94(b) Basket-type centrifuge. (Courtesy of Alfa Laval, Inc.)



Figure 8-94(c) Disc-stack centrifuge. (Courtesy of Alfa Laval, Inc.)




Figure 8-95 Diagram of a solid bowl centrifuge. (Courtesy of Alfa Laval, Inc.)

Figure 8-96 shows a diagram of a basket-type centrifuge. Here, feed (liquid plus the solids to be removed) enters the basket at the bottom. The basket rotates about its vertical axis, and solid particles are caused by centrifugal force to be thrown against the sides of the basket. The basket gradually fills up with solids, as liquid spills out over the top of the basket. When the basket becomes sufficiently full of solids, the feed is stopped, and a set of knives removes the solids from the basket. Machine variables that affect performance include basket spin rate, solids discharge interval, and skimmer nozzle dwell time and travel rate. Performance is normally inversely proportional, to some degree, to feed rate, and conditioning chemicals often are not used.

The disc-stack centrifuge, diagrammed in Figure 8-97, is composed of a series of conical disks and channels between the cones, which rotate about a vertical axis. Feed enters the top, and solid particles are forced by centrifugal force against the cones. Centrate is discharged

as shown in the diagram, and solids exit the bottoms of the conical discs to a compaction zone. A small fraction of the wastewater is used to flush out the compacted solids. The moisture content of the dewatered solids is proportional to the feed rate. Normally, conditioning chemicals are used to enhance operational performance.

Flotation

Gravity Flotation

Gravity flotation is used, sometimes in combination with sedimentation and sometimes alone, to remove oils, greases, and other floatables such as solids that have a low specific weight. Various types of “skimmers” have been developed to harvest floated materials, and the collection device to which the skimmers transport these materials must be properly designed. Figures 8-98(a)–(f) are photographs of different types of gravity flotation and harvesting equipment.




Figure 8-96 Diagram of a basket-type centrifuge. (After EPA 625/1-74-006.)



Figure 8-97 Disc-stack-type centrifuge. (Courtesy of Alfa Laval, Inc.)

Dissolved Air Flotation

Dissolved air flotation (DAF) is a solids separation process, similar to plain sedimentation. The force that drives DAF is gravity, and the force that retards the process is hydrodynamic drag. Dissolved air flotation involves the use of pressure to dissolve more air into wastewater than can be dissolved under normal atmospheric pressure, then releasing the pressure. The “dissolved” air, now in a super-saturated state, comes out of solution, or “precipitates,” in the form of tiny bubbles. As these tiny bubbles form, they become attached to solid particles within the wastewater, driven by their hydrophobic nature. When sufficient air bubbles attach to a particle to make the conglomerate (particle plus air bubbles) lighter than water (specific gravity less than one), the particle is carried to the water surface.

A familiar example of this phenomenon is a straw in a freshly opened bottle of a carbonated beverage. Before the bottle is opened, its contents are under pressure, having been pressurized with carbon dioxide gas at the time of bottling. When the cap is taken off, the pressure is released, and carbon dioxide precipitates from solution in the form of small bubbles. The bubbles attach to any solid surface, including a straw, if one has been placed in the bottle. Soon, the straw rises up in the bottle.

In a manner similar to the straw, solids having a specific gravity greater than one can be caused to rise to the surface of a volume of wastewater. Solids having a specific gravity less than one can also be caused to rise to the surface at a faster rate by using DAF than without it. Often, chemical coagulation of the solids can significantly enhance the process, and in some cases, dissolved solids can be precipitated, chemically, then separated from the bulk solution by DAF.

“Dissolution” of Air in Water

Examination of the molecular structures of both oxygen and nitrogen reveals that neither would be expected to be polar, therefore, neither would be expected to be soluble in water.



Molecular oxygen Molecular nitrogen

The question arises, then, as to how nonpolar gases like oxygen and nitrogen can be dissolved in water. The answer, of course, is that they cannot. Nonpolar gases are “driven” into a given volume of water by the mechanism of diffusion. Molecules of nitrogen and oxygen in the gaseous state create pressure as a result of constant motion of the molecules. The generalized gas law:

$$pV = nRT \quad (8-73)$$

where:

p = Pressure, psi

V = Volume, in³

n = Number of moles of gas in a given volume of gas

R = Universal gas constant 0.082 liter atmospheres/mole/° Kelvin

T = Temperature, ° Kelvin

rewritten as

$$p = \frac{nRT}{V} \quad (8-74)$$

states that the pressure exerted by a given number of molecules of a gas is directly proportional to the temperature and inversely proportional to the size of the volume in which those molecules are confined.

Dalton’s law of partial pressures states further that, in a mixture of gases, each gas exerts pressure independently of the others, and the pressure exerted by each individual gas, referred to as its “partial pressure,” is the same as it would be if it were the only gas in the entire volume. The pressure exerted by the mixture, therefore, is the sum of all the partial pressures. Conversely, the partial pressure of any individual gas in a mixture, such as air, is equal to the pressure of the mixture multiplied by the fraction, by volume, of that gas in the mixture.




Figure 8-98(a) Gravity flotation and harvesting equipment. (Courtesy of U.S. Filter/Envirex.)




Figure 8-98(b) Gravity flotation and harvesting equipment. (Courtesy of IDI/Infilco Degremont, Inc.)




Figure 8-98(c) Gravity flotation and harvesting equipment. (Courtesy of KWI.)




Figure 8-98(d) Gravity flotation and harvesting equipment. (Courtesy of Oil Skimmers, Inc.)

Henry's law, which describes, mathematically, the "solubility," in terms of weight per unit volume, of a gas in water, is written as:

$$C = Hp \quad (8-75)$$

where:

C = Concentration of gas "dissolved" in water (mg/L)

H = Henry's constant, dimensionless, specific for a given gas

The consequence of this equation is that, by way of the process of diffusion, molecules of any gas, in contact with a given volume of

water, will diffuse into that volume to an extent that is described by Henry's Law, as long as the quantity of dissolved gas is relatively small. For higher concentrations, Henry's constant changes somewhat. This principle holds for any substance in the gaseous state, including volatilized organics. The molecules that are forced into the water by this diffusion process exhibit properties that are essentially identical to those that are truly dissolved. In conformance with the second law of thermodynamics, they distribute themselves uniformly throughout the liquid volume (maximum disorganization), and they

law, if they are depleted by way of reaction with other substances, or by biological metabolism. The difference between a substance existing in water solution as the result of diffusion and one that is truly dissolved can be illustrated by the following example.




Diagram illustrating the components and dimensions of a dissolved air flotation (DAF) tank:

- ADJUSTABLE OVERFLOW WEIR PLATE
- SKIMMER FLIGHTS (QUANTITY VARIES)
- SKIMMER FLIGHT SUPPORTS
- 12" STATIC FREEBOARD
- INLET MIXING CHAMBER
- RADIAL HEADER
- INFLUENT DISTRIBUTION BAFFLE
- UNDERFLOW SCUM BAFFLE
- SCUM COLLECTION TROUGH
- 3" NPT SCUM OUTLET COLLECTION
- Dimensions: 6", 45", 6", 2 1/8"

Figure 8-98(f) Gravity flotation and harvesting equipment.

Consider a beaker of water in a closed space—a small, airtight room, for instance. An amount of sodium chloride is dissolved in the water, and the water is saturated with oxygen; that is, it is in equilibrium with the air in the closed space. Now, a container of sodium chloride is opened, and at the same time, a pressurized cylinder of oxygen is released. The concentration of sodium chloride will not change, but, because the quantity of oxygen in the air within the closed space increases (partial pressure of oxygen increases), the concentration of dissolved oxygen in the water increases. The oxygen molecules are not truly dissolved; that is, they are not held in solution by the forces of solvation, or hydrogen bonding by the water molecules. Rather, they are forced into the volume of water by diffusion, which is to say, by the second law of thermodynamics. The molecules of gas are constantly passing through the water-air interface in both directions. Those that are in the water are constantly breaking through the surface to return to the gas phase, and they are continually being replaced by diffusion from the air into the water. An equilibrium concentration becomes established, described by Henry's law. All species of gas that happen to exist in the "air" participate in this process: nitrogen, oxygen, water vapor, volatilized organics, or whatever other gases are included in the given volume of air.

The concentration, in terms of mass of any particular gas that will be forced into the water phase until equilibrium becomes established, depends on the temperature and the concentration of dissolved substances such as salts and the "partial pressure" of the gas in the gas phase. As the temperature of the water increases, the random vibration activity, "Brownian motion," of the water increases. This results in less room between water molecules for the molecules of gas to "fit into." The result is that the equilibrium concentration of the gas decreases. This is opposite to the effect of temperature on dissolution of truly soluble substances in water, or other liquids, where increasing temperature results in increasing solubility.

Some gasses are truly soluble in water because their molecules are polar, and these gases exhibit behavior of both solubility and diffusivity. Carbon dioxide and hydrogen sulfide are examples. As the temperature of water increases, solubility increases, but diffusivity decreases. Also, because each of these two gases exists in equilibrium with hydrogen ion when in water solution, the pH of the water medium has a dominant effect on their solubility, or rather, their equilibrium concentration, in water.

In the previous example, where a beaker of water is in a closed space, if a flame burning in the closed space depletes the oxygen in the air, oxygen will come out of the water solution. If all of the oxygen is removed from the air, the concentration of "dissolved oxygen" in the beaker of water will eventually go to zero (or close to it), and the time of this occurrence will coincide with the flame extinguishing because of lack of oxygen in the air.

Dissolved Air Flotation Equipment

The dissolved air flotation (DAF) process takes advantage of the principles described earlier. Figure 8-99 presents a diagram of a DAF system, complete with chemical coagulation and sludge handling equipment. As shown in Figure 8-99, raw (or pretreated) wastewater receives a dose of a chemical coagulant (metal salt, for instance), then proceeds to a coagulation-flocculation tank. After coagulation of the target substances, the mixture is conveyed to the flotation tank, where it is released in the presence of recycled effluent that has just been saturated with air under several atmospheres of pressure in the pressurization system shown. An anionic polymer (coagulant aid) is injected into the coagulated wastewater just as it enters the flotation tank.

The recycled effluent is saturated with air under pressure as follows: A suitable centrifugal pump forces a portion of the treated effluent into a pressure-holding tank. A valve at the outlet from the pressure-holding tank regulates the pressure in the tank, the flow rate through the tank, and the retention time in the

tank, simultaneously. An air compressor maintains an appropriate flow of air into the pressure-holding tank. Under the pressure in the tank, air from the compressor is diffused into the water to a concentration higher than its saturation value under normal atmospheric pressure. In other words, about 23 ppm of "air" (nitrogen plus oxygen) can be "dissolved" in water under normal atmospheric pressure (14.7 psig). At a pressure of six atmospheres, for instance, ($6 \times 14.7 =$ about 90 psig), Henry's law would predict that about 6×23 , or about 130 ppm, of air can be diffused into the water. In practice, dissolution of air into the water in the pressurized holding tank is less than 100% efficient, and a correction factor, f , which varies between 0.5 and 0.8, is used to calculate the actual concentration.

After being held in the pressure-holding tank in the presence of pressurized air, the recycled effluent is released at the bottom of the flotation tank, in close proximity to where the coagulated wastewater is being released. The pressure to which the recycled effluent is subjected has now been reduced to one atmosphere, plus the pressure caused by the depth of water in the flotation tank. Here, the "solubility" of the air is less, by a factor of slightly less than the number of atmospheres of pressure in

the pressurization system, but the quantity of water available for the air to diffuse into has increased by a factor equal to the inverse of the recycle ratio.

Practically, however, the wastewater will already be saturated with respect to nitrogen but may have no oxygen because of biological activity. Therefore, the "solubility" of air at the bottom of the flotation tank is about 25 ppm, and the excess air from the pressurized, recycled effluent precipitates from "solution." As this air precipitates in the form of tiny, almost microscopic, bubbles, the bubbles attach to the coagulated solids. The presence of the anionic polymer (coagulant aid), plus the continued action of the coagulant, causes the building of larger solid conglomerates, entrapping many of the adsorbed air bubbles. The net effect is that the solids are floated to the surface of the flotation tank, where they can be collected by some means, thus removed from the wastewater.

Some DAF systems do not have a pressurized recycle system, but rather, the entire forward flow on its way to the flotation tank is pressurized. This type of DAF is referred to as "direct pressurization" and is not widely used for treating industrial wastewaters because of undesirable shearing of chemical flocs by the pump and valve.



Figure 8-99 Dissolved air flotation system.

Air-to-Solids Ratio

One of the principle design parameters for a DAF wastewater treatment system is the so-called air-to-solids ratio (A/S). The mass of air that must be supplied per day by the compressor and air delivery system is calculated by multiplying the mass of solids to be removed each day by the numerical value of the A/S. If the A/S is too low, there will not be sufficient flotation action within the treatment system. If, on the other hand, the A/S value is too high, there will be many more air bubbles than can attach to the solids. Many of the unattached fine bubbles will coalesce; large bubbles will result, causing turbulence in the flotation tank. Experience has shown that A/S values in the range 0.02 to 0.06 result in optimal flotation treatment.

Calculations of Recycle Ratio and Quantity of Air

The quantity of air needed for a given industrial waste treatment application can be calculated directly from the A/S ratio, once its value has been determined by laboratory and pilot experimentation:

$$\begin{aligned} & \text{Weight of air, lbs/day} \\ &= (\text{lbs solids/ day}) \times A/S \end{aligned} \quad (8-76)$$

Optimum Pressure for the Air-Dissolving System

The optimum pressure for the air-dissolving system is determined by balancing the cost for operating the water-pressurizing pump and the compressor against the capital costs for the individual components of the system, which include the pressurization tank. Generally, the higher the pressure, the greater the cost for power, but the smaller the recycle flow and, therefore, the smaller the size of the components. However, as shown by the equation for pump horsepower:

$$H.P. = \frac{Q\Gamma H}{550} \times \text{pump efficiency} \quad (8-77)$$

where:

- H.P. = Horsepower required to operate pump
- Q = Rate of flow being pumped (cfs)
- Γ = Specific weight of water (lb/ft³)
- H = Pressure, or "head" against which the pump is pumping. In this case, H equals the pressure of the pressurization tank, ft (of water).

The horsepower required for the pressurization pump increases directly with increasing pressure, and decreases with decreasing rate of flow. Therefore, there is a compensating tradeoff. As the pressure is increased to dissolve more air in a given flow rate of water, or to dissolve a given quantity of air in a smaller flow rate of water, power requirement increases. Power requirement decreases, however, as the rate of flow decreases as a result of less water needed by the higher pressure. The fact that higher pressure results in the need for more heavy-duty equipment, coupled with the fact that higher pressure requires more power consumption by the air compressor (the air requirement is governed by the solids load, which is not related to the pressure), results in increased costs for increasing pressure.

Because of these counteracting effects on costs, it is not a simple matter to select an operating pressure that minimizes overall costs. In most applications, operating pressures between 60 and 120 psig have been used.

Design of the air-dissolving portion of a DAF treatment system includes the following:

1. Determination of the size, i.e., air flow rate, working pressure, and, consequently, the motor horsepower of the compressor.
2. Determination of the water flow rate, total dynamic head, and, consequently, the motor horsepower of the recycle pump.
3. Determination of the size and pressure rating of the pressure-holding tank.
4. Selection of the appropriate valve for control of flow rate from the pressure-holding tank as well as the pressure to be maintained.
5. Selection of the appropriate sizes of piping and materials of construction.

Competing considerations that concern the working pressure for the pressurization air-dissolving system are that the higher the pressure, the more air can be dissolved, but the higher the horsepower required, and, therefore, the higher the operating costs for the recycle pump motor and the compressor motor.

Adsorption

Adsorption can be defined as the accumulation of one substance on the surface of another. The substance undergoing accumulation, and thus being adsorbed, is called the adsorbate, and the substance on which the accumulation is taking place is called the adsorbent. The adsorbate can be dissolved, in which case it is called the solute, or it can be of the nature of suspended solids as in a colloidal suspension. Colloidal suspensions of liquids or gases can also be adsorbed. The discussion presented here addresses substances such as ions or organic compounds dissolved in water adsorbing onto solid adsorbents. However, the principles hold for solid, liquid, or gaseous adsorbates adsorbing onto solid, liquid, or gaseous adsorbents.

The mechanism of adsorption can be one or a combination of several phenomena, including chemical complex formation at the surface of the adsorbent, electrical attraction (a phenomenon involved in almost all chemical mechanisms, including complex formation), and exclusion of the adsorbate from the bulk solution, resulting from stronger intermolecular bonding between molecules of solvent (hydrogen bonding in the case of water) than existed between molecules of solvent (water) and the solute. As is almost always the case, the driving force is explained by the second law of thermodynamics. The sum total energy of all bonds is greater after adsorption has taken place than before.

As a wastewater treatment process, adsorption is of greatest use when the substance to be removed is only sparingly soluble in water. Many organic substances have groups that ionize weakly, or have very few ionizable groups per unit mass of substance. These groups form hydrogen bonds with water molecules that are

of sufficient strength to hold the organic molecules in solution, but a good adsorbent reverses the solvation process because, as stated previously, the sum total of all chemical bonds is greater after adsorption than before.

The Adsorbent

Activated carbon is the most common adsorbent in use for industrial wastewater treatment. Other adsorbents include synthetic resins, activated alumina, silica gel, fly ash, shredded tires, molecular sieves, and sphagnum peat. Because adsorption is a surface phenomenon, a desirable characteristic of an adsorbent is a high surface-to-volume ratio. Surface-to-volume ratios are increased in two ways, by decreasing the size of particles of adsorbent and by creating a network of pores or "tunnels" within the particles of adsorbent.

Activated carbon is manufactured by pyrolyzing organic materials such as bones, coconut shells, or coal, then oxidizing residual hydrocarbons using air or steam. A granular material that has an intricate, interconnected network of pores ranging in size from a few angstroms to several thousand angstroms in diameter results. The pores that are 10 to 1,000 angstroms in diameter are referred to as micropores and are responsible for most of the adsorptive capability of the material. The larger pores are relatively unimportant in adsorptive treatment capability, but are important passageways through which ions and dissolved organics can diffuse to reach the innermost adsorptive surfaces.

Most adsorbents have weak negative charges on their surfaces; therefore, the pH of the wastewater being treated has an influence on the adsorptive process because hydrogen ions repress the negative surface charges at lower pH values. Also, at low pH conditions, dissolved or suspended substances that tend to have a negative surface charge increase in adsorption.

Adsorption Equilibria

When wastewater is successfully treated by adsorption, the substances being removed

adsorb onto, and thus “coat” the adsorbent until equilibrium is established between the molecules of substance adsorbed and those still in solution. Depending on the characteristics of both the adsorbate and the adsorbent, equilibrium is reached when either a complete monolayer of molecules coats the adsorbent or when the adsorbent is coated with layers of adsorbate several molecules thick.

A standard laboratory procedure that is used to determine the effectiveness with which a given wastewater can be treated with a given adsorbent is described as follows: Several flasks containing samples of the wastewater (containing the adsorbate) are dosed with different quantities of adsorbent, which is in either granular form or has been ground in a ball mill to powder form. The flasks are shaken using a device that shakes all the flasks together, and the temperature is held constant. Shaking continues until the contents of all flasks have reached equilibrium, as determined by the concentration of adsorbate remaining constant with time. The adsorbate may be a specific chemical compound such as trichloroethylene, or a group of compounds (measured as COD, for instance). Then, a plot is constructed showing the relationship between the concentration of adsorbate in solution after equilibrium has been reached and the quantity of adsorbate adsorbed per unit mass of adsorbent. Such a plot is called an isotherm because of the conditions of constant temperature held throughout the test.

Several standardized isotherm models have been developed to provide the ability to calculate estimates of adsorbent efficiency and costs after generating a relatively small amount of laboratory data. The model developed by Langmuir is one of the most widely used, and is stated as follows:

$$q = \frac{q_m K_a C}{1 + K_a C} \quad (8-78)$$

where:

q = Mass of adsorbate adsorbed/mass of adsorbent

q_m = Mass of adsorbate adsorbed/mass of adsorbent if a complete layer, one molecule thick were adsorbed

K_a = Constant (related to enthalpy of adsorption)

C = Concentration of adsorbate present in solution at equilibrium.

Langmuir's model is based on (1) the assumption that only a single layer of molecules of adsorbate will adsorb to the adsorbent, (2) the immobility of the adsorbate after being adsorbed, and (3) equal enthalpy of adsorption for all molecules of adsorbate. It has long been accepted as a good, generalized model for making estimates based on very little data. It is most useful when linearized as follows:

$$\frac{C}{q} = \frac{1}{K_a q_m} + \frac{C}{q_m} \quad (8-79)$$

or

$$\frac{1}{q} = \frac{1}{q_m} + \frac{1}{K_a q_m} \times \frac{1}{C} \quad (8-80)$$

Laboratory data can be plotted as shown in Figures 8-100 and 8-101.

Values for the constants K_a and q_m can then be determined from the slopes and intercepts. These constants can then be used in the original Langmuir equation (equation 8-78) to estimate quantities of adsorbent needed (inverse of q) for known quantities of adsorbate to be removed.




Figure 8-100 Plot of laboratory data for Langmuir isotherms.

If adsorption is known or suspected to take place in multiple layers, a more appropriate model is given by the Brunauer-Emmett-Teller (BET) equation, equation 8-81:

$$q = \frac{q_m K_b C}{(C_s - C)[1 + (K_b - 1)(C/C_s)]} \quad (8-81)$$

where:

C_s = Concentration of adsorbate in the wastewater when all layers of adsorbate on the adsorbent are saturated

K_b = Constant related to energy of adsorption

Figure 8-102 shows the approximate relationship between the concentration of adsorbate in the wastewater after adsorption has taken place to the point of equilibrium and the amount adsorbed.

As shown in Figure 8-102, this relationship is not linear; however, the BET model can be rearranged to the following linear form:

$$\frac{C}{(C_s - C)q} = \frac{1}{K_b q_m} + \frac{K_b - 1}{K_b q_m} \left\{ \frac{C}{C_s} \right\} \quad (8-82)$$

and the plot of laboratory data shown in Figure 8-103 can be used to determine the mathematical value of the constant K_b .

Perhaps the most widely used model for estimating adsorbent efficiency and costs is an empirical model developed by Freundlich, stated as follows:

$$q = \frac{1/n}{K_f C} \quad (8-83)$$

where:

K_f = Constant

n = Empirical constant greater than one

Freundlich's model requires no assumptions concerning the number of layers of adsorbed molecules, heats of adsorption, or other conditions. It is strictly a curve-fitting model and works very well for many industrial wastewater applications.

Freundlich's model is made linear by taking the logarithm of both sides:

$$\log q = \log K_f + (1/n) \times \log C \quad (8-84)$$

Plotting q versus C on log-log paper yields a straight line, the slope of which is the inverse of n , and the vertical intercept is the value of K_f , as shown in Figure 8-104.

In practice, candidate adsorbent materials (different types of activated carbon, for instance) are evaluated for effectiveness in treating a given industrial wastewater by constructing the Freundlich, Langmuir, or BET isotherms after obtaining the appropriate laboratory data. The isotherms provide a clear indication as to which candidate adsorbent would be most efficient in terms of pounds of adsorbent required per pound of adsorbate removed, as well as provides an indication of the quality of effluent achievable. Example 8-8 illustrates this procedure.

Example 8-8:

Wastewater from a poultry-processing plant was treated to the extent of greater than 99% removal of COD and TSS using chemical coagulation, dissolved air flotation, and sand filtration. The question then arose about the economic feasibility of using activated carbon to further treat the water for (re)use in the plant as cooling water or for initial washdown during daily plant clean-up. Table 8-13 presents the data that were obtained from the isotherm tests using the adsorbate designated Carbon A.

The data shown in Table 8-13 were plotted on a log-log scale as shown in Figure 8-105.

Figure 8-105 shows that the slope of the isotherm was about 0.899, and the vertical intercept was about 0.007. Therefore, the value for the constant, n , in the Freundlich model is calculated as:

$$1/n = 0.899; n = 1.112 \quad (8-85)$$

and the value for the constant K_f is calculated as:

$$\text{intercept} = \log K_f = \log 0.007; K_f = 0.007 \quad (8-86)$$

It is now possible to use the Freundlich model to calculate the quantity of Carbon A required to produce treated effluent of whatever quality is deemed appropriate, balancing cost against effluent quality:




Figure 8-101 Plot of laboratory data for Langmuir isotherms.




Figure 8-102 Concentration of adsorbate in bulk liquid vs. amount adsorbed.




Figure 8-103 Plot of laboratory data for BET isotherms.




Figure 8-104 Log-log plot of q vs. C (Freundlich isotherm).

For a desired effluent quality of TOC
 $= 10 \text{ mg/L} = C$:

$$\begin{aligned}\frac{1}{n} &= \frac{1}{1.112} \\ q &= K_f C \\ q &= 0.007(10) \\ &= 0.06 \text{ mgTOC} \\ &\text{adsorbed/mg adsorbent}\end{aligned}\quad (8-87)$$

or, $1/0.06 = 18$ pounds carbon adsorbent required for each pound of TOC removed from the sand filter effluent.

Evaluating Relative Effectiveness Among Different Carbon Products

Two characteristics of activated carbon can be evaluated from the Freundlich isotherms. One is the relative capability for removing impurities from the wastewater to a sufficiently low level to satisfy requirements for reuse or for discharge. The second characteristic is the relative efficiency of several different carbon products; that is, the quantity of activated carbon required to remove a given quantity of pollutants, as illustrated in Figure 8-106.

Figure 8-106 shows Freundlich isotherms for three different activated carbon products plotted on the same graph. In such a composite graph, the further to the right the isotherm, the less efficient the activated carbon product, in terms of pounds of the carbon

product required to remove 1 pound of TOC. Figure 8-106 further shows that if a TOC concentration of no more than 10 mg/L (for instance) can be tolerated, Carbons A and C have potential use, whereas Carbon B need not be considered further.

As additional notes, it has been found that, in general, high-molecular-weight (greater than 45) organics that are not readily biodegradable tend to be good candidates for removal by adsorption on activated carbon or other adsorbates. Also, certain inorganics that are not highly soluble in water (some heavy metals, reduced sulfur gases, and chlorine, are examples) are good candidates for removal by adsorption.

Activated carbon can be very effective in removing metal ions from wastewater by first, chelating the metal ions with an organic chelant such as citric acid or EDTA. When the chelated mixture is treated using activated carbon, the organic chelant adsorbs to the carbon, removing the chelated metals along with it.

Ion Exchange

Ion exchange is a physical treatment process in which ions dissolved in a liquid or gas interchange with ions on a solid medium. The ions on the solid medium are associated with functional groups that are attached to the solid medium, which is immersed in the liquid or gas.

Table 8-13 Data Obtained From Isotherm Tests — Carbon A

Flask No.	Carbon dose (grams)	TOC of effluent at equilibrium (mg/L)	TOC on carbon (mg/mg Carbon)
1	3.2	2.2	18
2	1.8	7.6	0.028
3	1.3	20.1	0.038
4	0.92	22.3	0.052
5	0.55	28.1	0.076
6	0.41	30.2	0.096




Figure 8-105 Log-log plot of data from poultry processing wastewater.




Figure 8-106 Composite plot of isotherms of three different carbon products.

Typically, ions in dilute concentrations replace ions of like charge that are of lower valence state, but ions in high concentration replace all other ions of like charge. For instance, calcium ions or ferric ions in dilute concentrations in water or wastewater replace hydrogen or sodium ions on the ion exchange medium. The divalent or trivalent ions move from the bulk solution to the surface of the ion exchange medium, where they replace ions of lesser valence state, which, in turn, pass into the bulk solution. The ion exchange material can be solid or liquid, and the bulk solution can be a liquid or a gas.

However, if a bulk solution has a high concentration of ions of low valence state, and is brought into contact with an ion exchange material having ions of higher valence state, the higher valence ions will be replaced by the lower valence state ions. For instance, if a strong solution of sodium chloride is brought into contact with an anion exchange material that has nitrate ions associated with its functional groups, the chloride ions will replace the nitrate ions.

In these examples, the ions that exchange are referred to as mobile, and the functional groups are referred to as fixed. Ion exchange materials occur extensively in nature; ion exchange materials of high capacity can be manufactured. Clays are examples of naturally occurring ion exchange materials. Approximately one-tenth of a pound of calcium (expressed as

calcium carbonate), for instance, per cubic foot of clay is a typical cation exchange capacity for a naturally occurring clay. So-called zeolites are naturally occurring materials of much higher exchange capacity. About 1 pound of calcium per cubic foot of zeolite is a good average value for this material. Synthetic ion exchange materials are produced that have capacities of more than 10 pounds calcium per cubic foot of exchange material.

Naturally occurring materials that have ion exchange capability include soils, lignin, humus, wool, and cellulose. The ion exchange capacity of soils is used by land treatment systems. Synthetic ion exchange resins of high capacity are manufactured, typically, as illustrated in Figure 8-107.

As shown in Figure 8-107, a "good" ion exchange material consists of a foundation of an insoluble, organic, or inorganic three-dimensional matrix, having many attached functional groups. In the example shown in Figure 8-107, the three-dimensional matrix is formed by polymerization, in three dimensions, of styrene and divinylbenzene molecules. The functional groups are soluble ions that are able to attract ions of opposite charge and are attached by reacting various chemicals with the basic matrix material. In the example shown in Figure 8-107, the soluble ions are sulfonate ions, attached to the three-dimensional matrix by reacting the matrix with sulfuric acid. The term "resin" is used for the foundation matrix material.




Figure 8-107 Typical process for manufacturing ion exchange resins.

Materials that exchange cations have acidic functional groups such as the sulfonic group, R-SO_3^- ; carboxylic, R-COO^- ; phenolic, R-O^- ; or the phosphonic group, $\text{R-PO}_3\text{H}^-$. In each case the R represents the foundation matrix. Materials that exchange anions have the primary amine group, R-NH^+ ; the secondary amine group, $\text{R-R}'\text{N}^+$; or the quaternary amine group, $\text{R-R}'\text{N}^+$. The tertiary amine group can also be used. Cation exchange resins having a high degree of ionization are referred to as “strongly acidic,” and those having a low degree of ionization are called “weakly acidic exchangers.” Strongly basic and weakly basic anion exchangers are named in the same way.

Strongly acidic or strongly basic ion exchangers normally have greater attraction for the target ions and are, therefore, more efficient in terms of effluent quality for a given wastewater loading rate, than are weakly acidic or weakly basic ion exchangers. The strongly acidic or basic exchangers, however, require more regenerant than do the weakly ionized exchangers. In all cases, exchange capacity, in terms of mass of ions exchanged per mass of exchange material, is determined by the number of functional groups per unit mass of the material.

Higher numbers of functional groups per unit mass of material are made possible by higher surface-to-volume ratios for the matrix material. As with all sorption materials, higher surface-to-volume ratios result from the existence of pores throughout the basic material. However, when compared to simple exchange at the outer surface of a bead of ion exchange material, the ion exchange process is slowed somewhat when ions must diffuse into and out of pores.

The density of cross-linking within the lattice-work, or matrix, of the exchange material, is what governs the number and size of pores, and, consequently, has a strong influence on exchange capacity. Greater cross-linking produces a stronger, more resilient resin; however, if the degree of cross-linking is too high, pores will be too small. Larger ions will be physically blocked from entering or moving through them.

Mechanisms of Ion Exchange

The ion exchange process takes place as illustrated in Figures 8-108(a)–(b).

Figure 8-109(a) shows a cross section of a bead of ion exchange material immersed in wastewater containing zinc ions. The functional groups (sulfonic groups) are associated with hydrogen ions at the start of the exchange process. There is a strong gradient of concentration of zinc ions between the bulk solution and the interior of the pores, which are filled with water. There is also a strong gradient of concentration of hydrogen ions between the surface of the exchange resin throughout its porous structure and the water within the pores. Because of this, hydrogen ions have a strong tendency to leave the functional groups and diffuse throughout the pores, but the stronger tendency to maintain electrical neutrality prevents this from taking place. However, as the zinc ions are driven into the interior of the pores by molecular diffusion, because of their concentration gradient (Figure 8-109(b)), they are available to interchange with the hydrogen ions (Figure 8-109(c)). Thus, the force tending to distribute hydrogen and zinc ions uniformly throughout the aqueous system (entropy) is satisfied, and the tendency to maintain electrical neutrality is also satisfied (Figure 8-109(d)). The tendency to maintain electrical neutrality results in stoichiometric exchange (i.e., one divalent ion exchanges with two monovalent ions, etc.).

Kinetics of Ion Exchange

Although the description given earlier of the example illustrated in Figures 8-109(a) – (d) is useful, there is more to the overall ion exchange process. In general, the rate-controlling process is either the rate of diffusion of ions through the film (the region of water molecules surrounding the ion exchange resin material), or it is the rate of diffusion of the interchanging ions within the pores. The first of these processes is called film diffusion, and the second is termed pore diffusion. If the exchange treatment process is of the batch type, then higher rates of stirring minimize the


retarding effects of film diffusion. In a continuous flow column system, higher flow rates minimize these effects. Larger pores can minimize the retarding effects of pore diffusion.

Ion Selectivity


Ion exchange materials that are selective for specific ions exist. For instance, Gottlieb has reported on resins that have a high selectivity for nitrate ions. However, for most ion exchange materials, a common selectivity sequence is based on fundamental chemical properties and/or characteristics.

In general, the smaller the mobile ion for a given charge (valence state), the more strongly attracted, and thus selective, it is toward a given ion exchange material. Also, in general, the lower the atomic weight of an ion, the smaller its size; however, ions are dissolved in water as a result of water molecules surrounding the ion, attracted by electrolytic forces, and held by hydrogen bonding, as described in Chapter 2. The “solvated” ion (ion plus attached layers of water molecules) constitutes the mobile unit. Because ions of higher atomic weight hold solvated water layers more tightly than do ions of lower atomic weight, the heavier ions make up mobile units that are of smaller radius than ions of lower atomic weight. The end result is that,


in general, the higher the molecular weight for a given ionic charge, the more highly selective most ion exchange materials are for that ion. Monovalent cations, consequently, exhibit selectivity as follows:



For divalent cations, the order of selectivity is:



and for monovalent anions the order of selectivity is:



Application of Ion Exchange to Industrial Wastewater Treatment

Ion exchange can be used to remove undesirable ions from industrial wastewaters as a final, or tertiary, treatment step, as treatment for isolated process streams as part of a waste minimization program, or as a polishing step before recycle and reuse of process water or wastewater. Ion exchange can also be used to recover valuable metals or other exchangeable substances.




Figure 8-108 Schematic diagrams of a cation exchange resin framework with fixed exchange sites before and after an exchange reaction. (a) Initial state before exchange reaction with cation, B⁺; (b) equilibrium state after exchange reaction with cation, B⁺.




Figure 8-109 Ion exchange process.

As a process, ion exchange can be operated in either the batch mode or the continuous flow mode. In the batch mode, a container of fluid to be treated is dosed, then mixed with an appropriate quantity of ion exchange “beads.” Beads of 2–4 mm diameter are the physical form in which ion exchange resins are normally used. After the desired amount of exchange of ions has taken place, the beads of resin are separated from the treated fluid by sedimentation, filtration, or another solids separation process. The exchange resin is then rinsed and “recharged” with an appropriate solution of acid, base, or salt.

Far more widely used than the batch process is the continuous flow ion exchange process, illustrated in Figure 8-110.

As shown in Figure 8-110, continuous flow ion exchange is carried out by passing the fluid to be treated through one or more cylindrical containers (referred to as “columns”) packed with exchange resin beads, 2 to 8 feet, or more, in depth. The resin is first “charged” with an appropriate solution (as an example, 5% to 20% sulfuric acid could be used to charge a strong acid cation exchange resin). When essentially all of the functional groups have charging ions associated with them, the charging cycle is stopped, and the material is rinsed with water of very low ion content. Then, the removal cycle is initiated by passing 2 to 5 gpm/ft³ (gpm of wastewater per ft³ of ion exchange resin) through the bed. During this cycle, the target ions diffuse into the pores of

the beads of resin and replace the charging ions on the functional groups. The replaced charging ions diffuse out through the pores and into the bulk solution, then exit the column, as a waste in its own right that must be managed.

As wastewater passes through the column, most of the exchange activity takes place in a zone referred to as an “active front,” or “zone of active exchange.” As resin within the front becomes saturated with target ions, the front progresses from the top to the bottom of the bed. This active front characterizes the continuous flow exchange process. Because the resin ahead of the active front is fully charged, there is always a concentration gradient in terms of the target ions, enabling maximum removal. Batch treatment, on the other hand, is limited by the equilibrium phenomena between the exchange resin and the bulk solution.

It is important to note that maximum removal is not necessarily synonymous with complete removal. In practice, complete removal of target ions usually occurs during the initial portion of the treatment phase. How long this complete removal lasts depends on the hydraulic loading rate of the exchange columns as well as on the strength of attraction between the exchange sites and the target ions. Sooner or later, target ions begin to bleed through and appear in the effluent (referred to as “break-through”) until, at some point, the effluent becomes unacceptable. At this point, the treatment run is stopped, and the exchange resin is backwashed with water, to remove debris and to regrade the resin.

If both cations and anions are to be removed, the treatment train is set up as shown in Figure 8-111, with the cation exchangers preceding the anion exchangers. Otherwise, metal cations that might appear during incomplete removal would precipitate with hydroxide ions within the anion exchanger and cause fouling.

A familiar example of cation-anion removal is the so-called demineralization of water. In this process, the cation exchanger is charged with hydrogen ions and is said to be on the acid cycle, or on the hydrogen cycle. The anion exchanger is charged by passing sodium or potassium hydroxide solution through it, and is

said to be on the hydroxide cycle. Cations (metals, calcium, etc.) are exchanged for hydrogen ions, which then react with hydroxide ions exchanged for anions (sulfate, chloride, etc.) to form water, the only intended substance in the effluent from the anion exchanger.

In many cases, a mixed bed process, in which the cation and anion exchange resins are mixed and packed into a single column is advantageous. The two resins must be separated, however, before recharging, then mixed again for the next ion exchange cycle.

Often, ions that have just been exchanged are soon replaced by ions for which the exchange material is more highly selective. This process results in the less strongly selected ions being pushed along at the front of the zone of active exchange. When breakthrough occurs, the effluent is enriched in the less strongly selected ions.

Practical limitations of the ion exchange process include the following:

1. The fluid to be treated must be reasonably free of undissolved solids. The economics of ion exchange are such that it is cost effective to install and operate solids removal facilities before the process, rather than lose capacity because of fouling.
2. Corrosion-resistant materials of construction are required for the column containers, pumps, and piping.
3. Disposal of spent regenerant (which contains the target ions that have been removed) and rinse waters may pose an expensive problem, if they cannot be discharged to the municipal sewer or to the industry's main wastewater treatment system.

Significant advantages of ion exchange as a process, compared to chemical precipitation, include the following:

1. No significant sludge disposal problem.
2. No chemical feeders, mixers, etc., other than what is required to make up and feed regenerant.
3. The systems are simple to operate and do not require much attention.




Figure 8-110 Schematic of the continuous flow ion exchange process.




Figure 8-111 Treatment train for removal of both cations and anions.

Design Criteria

Design criteria, including brand and type of exchange resins, volumes of resins, treatment train configuration, charging substances, and hydraulic loading rates, are normally generated in the laboratory. The laboratory bench scale set-up shown in Figure 1-3(b) is typical of those used. Also, it is sometimes cost effective to perform a series of batch studies, wherein varying quantities of a fully charged exchange resin are placed into Erlenmeyer flasks containing the liquid to be treated, then mixed in a standardized manner. Plots are then made in the same manner as they are made for carbon adsorption isotherms. Although these plots may not be able to be used exactly as adsorption isotherms are used, they show important trends needed in the design process.

Removal of Specific Organic Substances

In general, ion exchange is useful for removing inorganic substances, but not organic substances, and the reverse is normally the case for activated carbon. However, activated carbon

can be very effective in removing metal ions from wastewater, by simply chelating the metals with an organic chelant, such as EDTA, and certain organics can be removed by ion-exchange-type resins manufactured for that specific purpose. So-called macroreticular resins are available for use in removing specific nonpolar organic materials. Passing a liquid that is a solvent for the target substance regenerates these resins.

Stripping

Stripping is a physical treatment technology, in the sense that no chemical reactions are involved. Stripping is a method of moving one or more chemical substances from one medium, either liquid or gas, to another, also either liquid or gas, but usually the opposite of the first medium. That is, if the first medium is liquid, the second is gas, and vice versa. An example of stripping as a treatment technology is the stripping of acetone from water with air, as described following and illustrated in Figure 8-112.




Figure 8-112 Illustration of stripping as a waste treatment technology. (a) Air bubble stripping molecules of TCE as it rises through the TCE-bearing water. (b) TCE being stripped out of TCE-bearing water cascading over packing.

Acetone is highly soluble in water but can be removed from water solution by bubbling air through an acetone-water mixture, or by causing droplets of the liquid mixture to pass through the air, which takes place during mechanical aeration.

The mechanism of removal is accounted for by a combination of Henry's law of solubility and Dalton's law of partial pressures. Acetone is volatile, compared to water; therefore, molecules of acetone pass from a container of the mixture through the acetone-water surface into the air until the partial pressure of acetone in the air is equal to the vapor pressure of the acetone. If the container is covered, and there is enough acetone in the mixture, equilibrium will be reached, and the concentration of acetone in the mixture will then remain constant. If the vessel is not covered, equilibrium will never be reached. This fact alone will result in all of the acetone eventually being removed from the water mixture, given enough time. However, because of the length of time required, this arrangement hardly qualifies as a wastewater treatment method. The process can be greatly accelerated by greatly increasing the surface area of the acetone-water mixture. This can easily be accomplished by introducing a host of air bubbles to the bulk volume of the acetone-water mixture, or by converting the bulk volume of the mixture to a host of tiny droplets.

Either way, the surface area of the acetone-water mixture will be greatly increased, molecules of acetone will pass from the mixture, through the surface films of either the air bubbles or the liquid droplets, into the air phase, in an attempt to raise the partial pressure of acetone in the air phase to a value equal to the vapor pressure of acetone (at the prevailing temperature). The result will be essentially complete removal of the acetone from the water.


In the case of volatile substances, which are toxic or otherwise objectionable, they must be contained after stripping and subjected to appropriate reuse or final disposal. In many cases, activated carbon has been used to capture organic substances that have been removed

from aqueous solution (polluted groundwater, for instance). In other cases, stripped organics have been disposed of directly, by incineration using a flame in a conduit leading from the enclosed stripping reactor to the atmosphere.


Scrubbing

Scrubbing, like stripping, is a physical treatment technology because no chemical reactions are involved. Also like stripping, its mechanism is accounted for by a combination of Henry's law of gas solubility and Dalton's law of partial pressures. Usually, scrubbing is used to remove one or more target gases from a stream of mixed gases, whereas stripping is used to remove one or more substances that have a higher vapor pressure than water from a wastewater stream.

An example of scrubbing as a treatment method is that of removing hydrogen sulfide from air using chlorine in a water solution of high pH. Figure 8-113 shows a stream of waste air being passed through a "scrubber." The scrubber resembles a discharge stack and operates as follows: A fan draws the air stream through the duct work to the scrubber, forces it up through the scrubbing apparatus, then into the atmosphere. The scrubbing apparatus consists of two parts. The first is a chamber filled with "telerets," known as the "packing," which are solid objects having a high surface-to-volume ratio. The second part is a system for circulating a solution of dissolved chlorine plus dissolved sodium or potassium hydroxide (in water) through the scrubbing chamber by pumping from the reservoir through spray nozzles down onto the telerets. The caustic chlorine solution flows over the surface of the packing, where it contacts the air to be treated. During this contact period, the hydrogen sulfide gas dissolves in the water, where it exists in an equilibrium according to the following:



because the solution is of a high pH, OH^- ions "remove" almost all of the H^+ ions:







Figure 8-113 Illustration of the air “scrubbing” process.

Causing the equilibrium (equation (8-88) to displace to the right. In so doing, essentially all of the hydrogen sulfide that was dissolved out of the stream of contaminated air exists as dissolved sulfide ion, which reacts with dissolved chlorine as follows:



Thus, hydrogen sulfide is “scrubbed” from the air and oxidized to soluble, nonodorous sulfate ion. Of course, it can be reduced back to the sulfide state and come out of solution as hydrogen sulfide under favorable conditions of neutral to low pH. Therefore, it is necessary to dispose of the waste scrubber solution in an appropriate manner. In many applications, the “spent” scrubber solution is simply discharged to the industrial wastewater sewer, after which it is treated in the industry’s wastewater treatment system.

Other Wastewater Treatment Methods

Land Application

There are several versions of land application as a wastewater treatment method, including spray irrigation, wetlands treatment, overland flow, hyponics, and a relatively new, proprietary process called “snowfluent,” in which pretreated wastewater is made into snow by use of the same equipment used at ski areas. In all land application systems, the treatment mechanisms include evaporation, evapotranspiration, microbiological metabolism, adsorption, and direct plant uptake. Land application systems also rely on the groundwater for final disposal of the water, after treatment has taken place. Therefore, land application is appropriate for use with only those wastewaters having all biodegradable organics. Bacteria and other microorganisms living in the soil use the organics as food for energy and reproduction. To this extent, a land treatment site is regenerative and can be used for many years, with appropriate rest periods. To the extent that some substances are removed by adsorption to soil particles, as is the case for phosphorus, a land application site has a limited life.

Land application systems are subject to limitations, some of which are as follows:

1. Land application systems must not be used if it is unacceptable, or even undesirable, for the wastewater, raw or treated, to enter the groundwater. The groundwater is the ultimate disposal destination of all the wastewater that is not evaporated, transpired, or finds its way via overland flow to a surface water body (a form of system failure).
2. The hydraulic application rate must be more than the evapotranspiration rate. Otherwise, salts will be left in the soil rather than washed down into the groundwater. The consequence will be plugged soil, i.e., a failed wastewater treatment system.
3. There are many laws and regulations governing rates of application. Factors that must be considered include:

- a. The hydraulic conductivity of the soil
- b. The rates of evaporation and transpiration in the geographical area
- c. The allowable nitrogen loading in the soil
- d. The type of cover crop used and whether or not it is to be harvested on a regular basis
(subnote: There MUST be a cover crop)
- e. The substances in the wastewater

With respect to allowable application rates, each state has its own regulations. Typically, hydraulic application rates are limited to 5,000 to 10,000 GPD/acre (1/4 to 1/2 inch per day). Nitrogen loading rates are typically limited to 400 lb/acre/yr if the cover crop is harvested, or to 200 lb/acre/yr if the cover crop is not harvested.

Spray Irrigation

Spray irrigation sites are used in rural areas for food-processing wastewaters that are generated on a seasonal basis, as well as for many other industrial wastewaters that contain no nonbiodegradable substances. In arid regions, the wastewater treatment process also supplies the water needs of appropriate crops. In cold regions, sufficient storage must be provided during the nongrowing season.

Design criteria for spray irrigation systems include wastewater application rate, distribution system pipe sizing, and storage facility sizing.

Wastewater Application Rate

The water-balance equation, equation 8-91, is used to determine the acceptable rate of application of wastewater, based on soil hydraulic conductivity considerations. In many cases, one of the substances contained in the wastewater—nitrogen, for instance—might govern the rate of wastewater application. The water balance equation is stated as:

$$L_w(p) = ET - p + W_p \quad (8-91)$$

where:

$L_w(p)$ = Wastewater application rate, in/month

ET = Rate of evapotranspiration, in/month
 p = Rate of precipitation, in/month
 W_p = Rate of percolation into soil, in/month

Notice that if the rate of precipitation exceeds the combined rates of evapotranspiration and percolation, spray cannot take place.

Wetlands Treatment

Wetlands treatment can be described as biological and microbiological treatment of wastewater resulting from the use of pollutants as food for living organisms in a natural or artificial wetlands. Sedimentation in regions of slow flow and eddy currents, adsorption onto the root systems and other parts of plants, as well as photooxidation, direct plant uptake, and photosynthesis are also important mechanisms of pollutant removal. In wetlands treatment, wastewater, usually pretreated to a rather high degree in the case of natural wetlands, is allowed to flow, very slowly, through the wetland system. Bacteria, fungi, and many other types of organisms inhabit the aqueous medium and use pollutants contained in the wastewater for food. Wetlands systems are usually no more than 2 feet deep, in order to enable photosynthesis and diffusion of oxygen from the air to maintain aerobic conditions. Areal loading rates must be managed to avoid the development of anaerobic zones. Flow through them is very slow so that hydraulic retention times are very long because of the lack of input of energy, of the types used with mechanical treatment systems. There is no return of sludge or other attempt to increase the numbers of organisms.

Artificial, or "constructed" wetlands are sometimes used for raw industrial wastewaters or wastewaters having only minimal pretreatment. The organic strength of these wastewaters is typically low. Constructed wetlands are of two types: (1) those having a free water surface (FWS), as with natural wetlands, and (2) subsurface flow systems (SFS), also known as "rock-reed filters" and "root zone filters." These systems have highly porous media, such as sand or rocks, which support the growth of

plants and through which the wastewater flows at a slow rate.

Wetlands treatment uses all of the biological treatment mechanisms that are involved in any of the conventional biological treatment processes and, as such, these systems require nutrients and trace elements. Wintertime operation requires special consideration.

The fact that most natural wetlands occur in areas of groundwater discharge, or are underlain by impermeable material, makes them unlikely sources of future groundwater contamination; however, protection of the groundwater must be positively ensured during the design and construction process. In the case of artificial wetlands, protection of groundwater by installing an appropriate liner is a major design consideration.

Reeds, cattails, sedges, and bullrushes are types of emergent plants that have performed well in wetlands treatment systems. Floating plants, such as water hyacinths and duckweed, are also effective. In particular, the root systems of water hyacinths project a mesh into the flow that effectively adsorbs both dissolved and suspended matter. Microbial degradation, however, is responsible for the bulk of the treatment of dissolved and suspended organic matter. The plant life participates in reaeration. If the plant life is used for nutrient removal—nitrogen and/or phosphorus, for instance—there must be a periodic harvesting of these plants to prevent reintroduction of these nutrients to the water flow when the plants die. The bioaccumulation of trace elements such as cadmium must be considered when selecting final disposal methods for the plants.

Design parameters for wetlands systems include system geometry, hydraulic retention time, type, size and porosity of media, hydraulic loading rate, organic or nutrient loading rate, temperature, and slope.

The area and length-to-width ratio of the basin are determined by either hydraulic retention time or organic or nutrient loading rate, and whether the system is FWS or SFS. Temperature is a very important consideration, closely paralleling lagoons and stabilization ponds in that respect.

Bibliography

- American Society of Civil Engineers, *Standard Guidelines for In-Process Oxygen Transfer Testing*, publication No. ASCE-18-96, 1997.
- American Society of Civil Engineers, *Wastewater Treatment Plant Design*, Water Pollution Control Federation Manual of Practice No. 8, Manuals and Reports on Engineering Practice No. 36, 1977.
- Amirtharajah, *Journal of the American Water Works Association*, December 1988.
- Behn, V.C., and J.C. Liebman, "Analysis of Thickener Operation," *Journal of the Sanitary Engineering Division*, ASC, vol. 89, 1963.
- Burd, R.S., "A Study of Sludge Handling and Disposal," Federal Water Pollution Control Administration, WP-20-4, Washington, D.C., 1968.
- Butler, J.N., *Ionic Equilibrium—A Mathematical Approach*, Addison-Wesley, Reading, Massachusetts, 1964.
- Cummins, M.D., and J.J. Westrick, "Packed Column Air Stripping for Removal of Volatile Compounds," Proceedings of National Conference on Environmental Engineering, American Society of Civil Engineers, Minneapolis, Minnesota, 1982.
- Eckenfelder, W.W., "Trickling Filter Design and Performance," *Trans. ASCE*, 128, Part III, 1963, p. 371.
- Eckenfelder, W.W., and W. Barnhart, "Performance of a High-Rate Trickling Filter Using Selected Media," *Journal of the Water Pollution Control Federation*, 35(12), 1963.
- Eckenfelder, W.W., and D.L. Ford, *Water Pollution Control: Experimental Procedures for Process Design*, Pemberton Press, New York, 1970.
- Edde, H.J., and W.W. Eckenfelder, "Theoretical Concept of Gravity Sludge Thickening; Scaling-up Laboratory Units to Prototype Design," *Journal of the Water Pollution Control Federation*, vol. 40, 1968.
- Fair, G.M., J.C. Geyer, and D.A. Okun, *Elements of Water Supply and Wastewater Disposal*, Wiley, New York, 1971.
- Gailer, W.S., and H.B. Gotaas, "Analysis of Biological Filter Variables," *Journal of the Sanitary Engineering Division*, ASCE, 90(6), 1964.
- Germain, J.E., "Economical Treatment of Domestic Waste by Plastic-Medium Trickling Filters," *Journal of the Water Pollution Control Federation*, 38(2), 1966.
- Great Lakes–Upper Mississippi River Board of State Sanitary Engineers, *Recommended Standards for Sewage Works*, Health Education Service, Inc., Albany, 1978.
- Hawkes, H.A., *Microbial Aspects of Pollution*, Academic, London, 1971.
- Kavanaugh, M.C., and P.R. Trussell, "Design of Aeration Towers to Strip Volatile Contaminants from Drinking Water," *Journal of the American Water Works Association*, vol. 72, no. 12, Denver, Colorado, 1980.
- Kynch, G.J., *A Theory of Sedimentation*, Transactions of the Faraday Society, vol. 48, 1952.
- Lanouette, K.H., "Heavy Removal," *Chemical Engineering Journal*, 84 (10): 73-80, 1977.
- McKinney, R.E., *Microbiology for Sanitary Engineers*, McGraw-Hill, New York, 1962.
- Metcalf & Eddy, Inc., *Wastewater Engineering—Treatment, Disposal, and Reuse*, G. Tchobanoglous and F.L. Burton (eds.), McGraw-Hill, New York, 1991.
- National Fire Protection Association, "Recommended Practice for Fire Protection in Wastewater Treatment and Collection Facilities," NFPA Standard 820, 1992.
- National Research Council, "Sewage Treatment at Military Installations," *Sewage Works Journal*, 18(5), 1946.
- Novotny, V., and A.J. Englande, Jr., "Equalization Design Techniques for Conservative Substances in Wastewater Treatment Systems," *Water Research*, 8(325), 1974.
- Novotny, V., and R.M. Stein, "Equalization of Time Variable Waste Loads," *Journal of the Environmental Engineering Division*, ASCE, 102(613), 1916.
- Paler, S.A.K., M.A. Brenton, T.J. Nunno, F.M. Sullivan, and N.F. Surprenant, *Metal/Cyanide Containing Wastes: Treatment*

- Technologies*, Noyes Data Corporation, Park Bridge, New Jersey, 1988.
- Schulze, K.L., "Load and Efficiency of Trickling Filters," *Journal of the Water Pollution Control Federation*, 32(3), 1960, p. 245.
- Shinsky, F.G., *pH and pION Control*, Wiley, New York, 1973.
- Smith, J.M., *Chemical Engineering Kinetics*, 2nd ed., McGraw-Hill, New York, 1972.
- Smith, R., R.G. Eilers, and E.D. Hall, "Design and Simulation of Equalization Basins," U.S. Environmental Protection Agency, Advanced Waste Treatment Research Laboratory, Cincinnati, Ohio, 1973.
- Stenstrom, M.K., and R.G. Gilbert, "Effects of Alpha, Beta and Theta Factor Upon the Design, Specification and Operation of Aeration Systems," *Water Research*, vol. 15, 1981.
- Sundstrom, D.W., and H.E. Klei, *Wastewater Treatment*, Prentice Hall, Englewood Cliffs, New Jersey, 1979.
- Talmage, W.P., and E.B. Fitch, "Determining Thickener Unit Areas," *Industrial and Engineering Chemistry*, vol. 47, 1955.
- The American Public Health Association, the American Society of Civil Engineers, the American Water Works Association, and the Water Pollution Control Federation, *Glossary, Water and Wastewater Control Engineering*, 1969.
- The Soap and Detergent Association, *Phosphorus and Nitrogen Removal from Municipal Wastewater: Principles and Practice*, 2nd ed., R. Sedlak (ed.), Lewis Publishers, New York, 1991.
- U.S. Congress, Office of Technology Assessment, "Technologies and Management Strategies for Hazardous Waste Control," U.S. Government Printing Office, Washington, D.C., 1983.
- U.S. Environmental Protection Agency, *Chemical Aids Manual for Wastewater Treatment Facilities*, EPA 430/9-79-018, MO-25, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, *Control and Treatment Technology for the Metal Finishing Industry—Sulfide Precipitation*, Industrial Environmental Research Laboratory, EPA 625/8-80/003, Cincinnati, Ohio, 1980.
- U.S. Environmental Protection Agency, *Control and Treatment Technology for the Metal Finishing Industry*, Industrial Environmental Research Laboratory, EPA 625/8-82-008, Cincinnati, Ohio, 1982.
- U.S. Environmental Protection Agency, *Control of Organic Substances in Water and Waste Water*, Office of Research and Development, EPA 600/8-83/011, Cincinnati, Ohio, 1983.
- U.S. Environmental Protection Agency, *Design Manual—Phosphorus Removal*, EPA/621/1-87/001, Washington, D.C., 1987.
- U.S. Environmental Protection Agency, *Disinfection of Wastewater* Task Force Report, EPA 430/9-75-012, Washington, D.C., 1976.
- U.S. Environmental Protection Agency, *Electroplating Industry*, EPA 625/5-79-016, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, *Estimating Costs of Granular Activated Carbon Treatment for Water and Wastewater*, Office of Research and Development, Washington, D.C., 1983.
- U.S. Environmental Protection Agency, *Evaluation of Sludge Management Systems*, EPA 430/9-80-001, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, *Flow Equalization*, Technology Transfer, EPA 625/4-74-006, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Innovative and Alternative Technology Assessment Manual*, Municipal Environmental Research Laboratory, EPA 430/9-78-009, MCD 53, Cincinnati, Ohio, 1978.
- U.S. Environmental Protection Agency, *Lining of Waste Impoundment and Disposal Facilities*, SW-870, Washington, D.C., 1983.
- U.S. Environmental Protection Agency, *Manual for Nitrogen Control*, EPA/625/R-93/010, Washington, D.C.
- U.S. Environmental Protection Agency, *Meeting Hazardous Waste Requirements for Metal Finishers*, EPA 625/4-87/018, Cincinnati, Ohio, 1987.

- U.S. Environmental Protection Agency, *Nitrification and Denitrification Facilities, Wastewater Treatment*, Technology Transfer, Washington, D.C., 1973.
- U.S. Environmental Protection Agency, *Operations Manual for Anaerobic Sludge Digestion*, EPA 430/9-76-001, Washington, D.C., 1976.
- U.S. Environmental Protection Agency, *Oxygen Activated Sludge Wastewater Treatment Systems*, Technology Transfer Seminar Publication, Washington, D.C., 1973.
- U.S. Environmental Protection Agency, *Physical-Chemical Nitrogen Removal, Wastewater Treatment*, Technology Transfer, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Process Control Manual for Aerobic Biological Wastewater Treatment Facilities*, EPA III-A-524-77, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Process Design Manual for Phosphorus Removal*, Technology Transfer, EPA 625/1-76-001a, Washington, D.C., 1976.
- U.S. Environmental Protection Agency, *Process Design Manual for Sludge Treatment and Disposal*, Technology Transfer, EPA 625/1-74/006, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Process Design Manual for Suspended Solids Removal*, Technology Transfer, EPA 625/1-75/003a, Washington, D.C., 1975.
- U.S. Environmental Protection Agency, *Process Design Manual for Upgrading Existing Wastewater Treatment Plants*, Technology Transfer, EPA 625/1-71/004a, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Process Manual for Carbon Adsorption*, Technology Transfer, Washington, D.C., 1971.
- U.S. Environmental Protection Agency, *Research Summary—Industrial Wastewater*, Office of Research and Development, EPA-600/18-80-026, Washington, D.C., June 1980.
- U.S. Environmental Protection Agency, *Ultra-violet Disinfection Technology Assessment*, Office of Wastewater Enforcement and Compliance, EPA 832-R-92-004, Washington, D.C., 1992.
- U.S. Environmental Protection Agency, *Upgrading Trickling Filters*, EPA 430/9-78-004, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Wastewater Filtration, Design Considerations*, Technology Transfer, EPA 625/14-74-007a, Washington, D.C., 1974.
- Velz, C.J., "A Basic Law for the Performance of Biological Filters," *Sewage Works Journal*, 20, 1948, p. 607.
- Wachinski, A.M., and J.E. Etzel, *Environmental Ion Exchange — Principles and Design*, Lewis Publishers, New York, 1997.
- Wallace, A.T., "Analysis of Equalization Basins," *Journal of Sanitary Engineering Division*, ASCE, 94(1161), 1968.
- Water Environment Federation, *Design of Municipal Wastewater Treatment Plants*, WEF Manual of Practice No. 8, Alexandria, Virginia, 1992.
- Water Environment Federation, *Odor Control in Wastewater Treatment Plants*, WEF Manual of Practice No. 22, Alexandria, Virginia, 1995.
- Wei, J., and C.D. Prater, "A New Approach to First Chemical Reaction Systems", *American Institute of Chemical Engineers Journal*, 9(77), 1963.
- Wei, J., and C.D. Prater, *Advances in Catalysis*, vol. 13, Academic Press, New York, 1962.

9 Treatment and Disposal of Solid Wastes from Industry

Solid wastes from industries include all wastes that are discharged to places or facilities other than to the air or to the water, plus the residuals from air and water pollution control systems. They are classified as either industrial wastes, solid wastes, or hazardous wastes, depending on their characteristics. Disposal methods include landfills, incinerators, and composting. In some cases it is advantageous to subject certain of these wastes to treatment before disposal by one of these methods.

Before the Industrial Revolution in the mid-1800s, almost all wastes—industrial, commercial, and domestic—were derived from natural substances and were, therefore, biodegradable. Pollution of any portion of the environment was caused by pathogens from human wastes or was the result of simply overwhelming the ability of the environment to undergo self-purification. Either way, the pollution was temporary, and the self-purification capability of “Mother Earth” would eventually prevail.

The Industrial Revolution was attended by solid waste and other waste disposal activities that could never be self-purified by the natural processes of microbiological degradation, chemical oxidation and reduction, adsorption, absorption, or other natural phenomena. As examples, some open dumps were sites of very large amounts of heavy metals pollution. Other sites where coal gasification took place are still polluted with tarry residuals that are classified as hazardous because of toxic organics.

The problem of soil and groundwater pollution greatly accelerated with the development of synthetic organics, beginning a few years before World War I and greatly increasing during and after World War II. New synthetics that were developed and produced in great quantity during that period included chlorinated

solvents, synthetic rubber, several pesticides and herbicides, polychlorinated biphenyls (PCBs), and plastics such as polyethylene, polyurethane, and a host of others. Many of these substances are classified as hazardous because of toxicity, flammability, reactivity, or corrosivity. Toxicity, of course, has always been synonymous with hazardous. The other three characteristics were deemed “hazardous” as a matter of law by the *Resource Conservation and Recovery Act (RCRA)* in 1986.

Microorganisms did not have the ability to produce enzymes necessary to degrade these synthetic organics because the organics were not present on the earth during the millions of years of development of the microorganisms. Consequently, the earth was unable to undergo self-purification, and these substances were carried by percolating rainwater and other precipitation to the groundwater.

The result, in the context of solid waste handling and disposal, is that extensive and sophisticated safeguards have become standard components of landfills, incinerators, composting facilities, or any alternative solid waste disposal technology. Modern landfills have double liners with leachate collection and treatment and leak detection. Some landfills have triple liners. All landfills must be closed according to strict regulations, on reaching their useful life. Typically, an impermeable cap equipped with gas collection and erosion control means are required.

Incinerators have stack emission controls and are subject to strict regulations regarding handling and disposal of ash and residuals from stack emission controls. Composting facilities have extensive safeguards to protect against groundwater pollution. All three disposal technologies are subject to strict and extensive

regulations regarding what is allowed to be disposed of using their technology. All three technologies are also subject to the requirement of groundwater monitoring at their sites.

Of paramount importance to the area of solid wastes handling and disposal is the mandate for pollution prevention, discussed in Chapter 7. The pollution prevention mandate requires that industries develop, plan for, and provide for handling and disposal of all wastes associated with any product throughout its life cycle, including minimizing the sum total of those wastes. Minimization involves source reduction as well as recycling and reuse.

Among the most desirable methods of waste reduction is the production of a salable substance or material, either by modification of the waste itself or by combining it with another waste material. Chipboard, which is used as a substitute for plywood by the construction industry, was originally developed using wastes from wood-working, for example. Composted food-processing wastes, including wastes from the processing of fish, poultry, meat, and vegetables, have been extensively used for soil conditioning and fertilization. Rendering plants have developed capabilities to process many organic wastes that were formerly disposed of into animal feed supplements. Potato-processing wastes are further processed to produce starch. Many industries have constructed and used facilities to store solid wastes that contain metals or other substances of value, until an improved recovery process is developed, or until market conditions become more favorable. These are more examples of a continuing effort on the part of industry to reduce the quantity of solid wastes that require disposal.

Characterization of Solid Wastes

Each significant solid waste stream should undergo characterization in order to determine the following:

- Opportunities for waste reduction
- Rate of waste generation
- Whether or not the waste is hazardous

- Suitability of the waste for landfilling
- Physical properties as they relate to suitability for landfilling
- Chemical properties as they relate to suitability for landfilling
- Estimation of leachate characteristics
- Suitability of the waste for incineration
- Estimated characteristics of stack emissions
- Estimated requirement for auxiliary fuel
- Estimated characteristics of ash
- Suitability of the waste for composting

Opportunities for Waste Reduction

The first and most important order of business in a solid waste management program is to identify any and all opportunities for reducing the volume, strength, and hazardous nature of wastes, always with the goal of elimination. For instance, the solid wastes manager should constantly be seeking opportunities for given wastes to be used as raw material in another manufacturing process, even if there is a cost. The cost should be compared to the cost of processing and disposing of the waste, and an appropriate amount should be added as insurance against having to deal with the disposed waste in the future for one reason or another. If the waste can be safely incorporated into another product, a permanent solution will have been implemented.

As a very simple example, a certain cardboard manufacturing plant had a daily production capacity of 1,000 tons per day of heavy brown paper. The plant had a wastewater treatment plant that produces about 3 tons (dry basis) of waste biosolids per day. After years of landfilling this sludge, the suggestion was made to simply incorporate the waste biosolids into the brown paper. The relatively tiny amount of biosolids, which had been a sizable solid waste disposal problem, “got lost” in the 1,000 tons of brown paper, forever solving a previously expensive problem.

As another example, during the 1970s, the number of poultry farms and poultry-processing facilities increased dramatically in response

to a growing desire on the part of the American public to reduce intake of cholesterol. Many of the poultry-processing plants made use of dissolved air flotation (DAF) for wastewater treatment. The residual from the DAF process is a sludge that is very difficult and expensive to dispose of. A solution that was developed and used by some of the processing plants was to incorporate the DAF residual into the raw materials that were being used to produce feed for the poultry. Because the DAF residual was essentially all poultry parts and pieces, it was perfect as a feed additive to be fed right back to the chickens. Again, an expensive and problematic solid waste disposal problem was resolved. In this case, the result was a significant savings of money for both waste disposal and feed production.

Rate of Waste Generation

Often, rigorous attention paid to managing production processes to “do it right the first time” and having little or no off-spec product to dispose of can significantly reduce the volume of solid wastes. Also, improved preventive maintenance and improved operation and maintenance (O&M) practices to reduce leaks, spills, and accidents can have the effect of significant reductions in the volumes of solid wastes, as well as wastewater and air pollutants.

Whether the Waste Is Hazardous

Whether or not the waste is hazardous has a major effect on both the cost of solid waste handling and disposal and the risk of future liability. It is *always* a good idea to substitute nonhazardous materials for hazardous materials used in production, if the resulting wastes become nonhazardous. An example is to use hot water and detergent or a hot caustic solution as a degreaser fluid rather than one of the chlorinated organic solvents. In many cases, the hot detergent or caustic solution outperforms the chlorinated solvent. The principal value of this substitution, however, is that the sludge from the hot detergent or caustic process will likely not require disposal as a hazardous substance.

As another example, certain sludges from industrial processes or industrial waste treatment facilities are required to be handled and disposed of as hazardous wastes because, on being subjected to the Toxic Characteristic Leaching Procedure (TCLP) test, the quantity of metals leached is more than is allowed. It has been possible, in some instances, to mix “superphosphate” fertilizer into the sludge with the result that the sludge is then able to “pass” the TCLP test. The treatment mechanism at work here is that the metal ions become tied up as extremely insoluble metal phosphates. The acid solution used for the TCLP test is unable to leach the metal ions from the sludge, and rainwater percolating through the landfilled sludge will certainly not be able to leach the metals and become a groundwater pollution threat.

Suitability of the Waste for Landfilling

Whether or not a particular solid waste is suitable for landfilling depends on its physical characteristics, chemical characteristics, and its probable leachate characteristics (i.e., whether or not there will be hazardous substances in the leachate).

Physical Properties

Physical properties that influence suitability for landfilling include those that influence structural stability. Often, water content is used to determine suitability for landfilling in the case of waste sludges. Another property is physical size. Still another relates to the ability of landfill machinery to handle the waste at the landfill site.

Chemical Properties

Chemical properties that influence suitability for landfilling, in addition to those properties that determine whether a waste is hazardous (i.e., corrosivity, toxicity, ignitability, and reactivity) include foaming agents (methylene blue active substances), iron and manganese, odor and odor, generation potential, for instance, sulfate.

Formal testing procedures for determining whether a waste is hazardous are presented in Chapter 6.

Suitability of the Waste for Incineration

Whether a waste can be destroyed by incineration (often referred to as “combustion”), and the quantity of auxiliary fuel that would be required to maintain a sufficiently high temperature in the combustion chamber to accomplish complete combustion, depends on several characteristics of the waste. Water content and chemical composition are major factors. Water content is important because of the demand that water places on auxiliary fuel usage and, thus, the cost of incineration. Chemical composition influences the following:

- The fraction of the total waste stream that can be converted to carbon dioxide and water
- The characteristics of the stack emissions
- The characteristics of the ash
- The quantity of auxiliary fuel required

Within a total waste stream, the only elements that are converted to carbon dioxide and water are carbon and hydrogen. All other elements are converted to other substances or remain unchanged. Some elements are converted to anions of high oxidation state; for instance, sulfur is converted to sulfur dioxide or sulfur trioxide. Some elements are liberated as the free cation; for instance, mercury that has been incorporated into organic material (methyl mercury) most likely exits the stack as free Hg^+ . Chunks of ferrous metals tend to remain unchanged. Sand and other inerts end up in the ash. Some heavy metals end up in the ash; a portion exit the stack.

It is critically important, then, to be aware of the chemical composition of any waste stream for which treatment by incineration is being contemplated. The word “treatment” is used here, rather than “disposal,” because incineration yields residuals from stack emission treatment (for instance, electrostatic precipitation) as well as ash. These residuals then become the subjects of evaluation of alternatives for disposal method.

Suitability of the Waste for Composting

Certain industrial solid wastes—vegetable processing, for instance—may be excellent candidates for composting. Composting is a method of converting waste material to usable material, and is thus highly desirable. A very large composting facility has been operated for many years in the Midwest of the United States for converting meat-processing wastes to a soil enhancement product.

The Solid Waste Landfill

The Conventional Landfill

Modern landfills are highly secure facilities with sophisticated features to prevent pollution of groundwater or soil. Modern landfills also have safeguards against blowing trash problems, odor problems, rodent and fly problems, fires, and contamination of surface waters.

There are alternatives, but most modern landfills are constructed as follows.

First, the site is cleared and grubbed. Topsoil is removed and stored. Access roads are built, and physical facilities, such as an office building, maintenance and storage building, scales, hot load pit with firefighting equipment, and laboratory facility, are constructed and/or installed.

After excavation to provide a basin in which the solid wastes will be placed has been completed, the liner system is constructed.

Landfill Liner System

Figure 9-1 presents a cross-section of a landfill liner system that was constructed in 1999, and is discussed as a typical modern landfill liner system. The landfill liner system shown in Figure 9-1 can be described as a “double composite with primary and secondary leachate collection.” This particular design can also be described as having leak detection because any leachate collected by the secondary leachate collection is direct and positive evidence of a leak in the primary liner.




Figure 9-1 Double composite landfill liner system.

It is convenient to describe the landfill liner system illustrated in Figure 9-1 by describing how it is constructed. After excavating the landfill "basin" to the subgrade (shown in Figure 9-1), an 18-inch-thick layer of "secondary barrier soil" is placed. This material constitutes a liner in its own right because the hydraulic conductivity (the rate at which water can move through the soil under the influence of gravity) can be no greater than 10^{-7} centimeters per second, equivalent to about 1 foot in 30 years. Federal regulations (Subtitle D) require that a soil liner of not less than 2 feet of soil having a coefficient of permeability ("k") equal to or less than 1×10^{-7} be an integral component of the liner system for all landfills. In the case of the landfill used for this example, the state regulatory agency as well as the U.S. EPA agreed that 18 inches of soil having a "k" value of 1×10^{-7} , plus 12 inches of soil having a "k" value of 1×10^{-5} , plus the geosynthetic clay liner as discussed below, more than satisfied this requirement.

Some states will not accept a substitute for a soil liner, at least 2 feet thick, having a "k" value of 1×10^{-7} or less. One solution for this situation, if enough soil of that low hydraulic conductivity cannot be obtained within a reasonable distance of the landfill site, is to

augment native soil (of higher hydraulic conductivity [larger value of "k"]) with powdered sodium bentonite. Bentonite is a natural clay that exhibits a high degree of swelling on contact with water. In fact, it will swell to 2.5 to 3 times its volume when dry. When relatively small amounts of this material are mixed into soil of higher hydraulic conductivity, the particles of bentonite fit into the void spaces. Then, when a water solution—for instance, leachate—comes into contact with the mixture, the particles of bentonite swell. This swelling action closes off the void spaces in the more highly permeable soil, with the result that the mixture as a whole has a "k" value that satisfies the Subtitle D mandate of 1×10^{-7} or less.

Next, an impermeable membrane is placed over the secondary soil barrier. In the system illustrated in Figure 9-1, that membrane consisted of 80-mil-thick textured high-density polyethylene (HDPE). This barrier is referred to as a "synthetic membrane" and constitutes the secondary liner for the landfill.

Over the top of the synthetic membrane secondary liner is placed a fabric that is referred to as a "geocomposite." This fabric, which is loosely woven using threads of synthetic material, performs two functions. One is to protect the HDPE membrane from being punctured by

anything in the layer of soil above it. The other is to act as a leachate collection and conduit device. Its openly woven texture allows it to perform this function.

Over the top of the geocomposite fabric is placed a 1-foot layer of compacted soil referred to as the “primary soil barrier.” This layer of compacted soil, like the secondary barrier soil, is strictly regulated as to characteristics of aggregate size and uniformity coefficient, and its hydraulic conductivity must be no higher than 10^{-5} centimeters per second.

Over the top surface of the primary barrier soil is placed a sheet of a manufactured material called a “geosynthetic clay liner” (GCL). This material, which is delivered to the site in large rolls and is about one-half inch thick, consists of a matlike fabric that is filled with clay. The clay is used for its impermeability and resistance to chemical attack, which is a possibility in the case of HDPE, although a very remote one. The synthetic fabric has the function of providing the GCL as a whole with structural strength and the capability of constructing a layer of clay that is quite thin.

The next layer, which is placed over the top of the GCL, is the primary liner for the landfill, a sheet of 80-mil-thick textured HDPE. This membrane is constructed by rolling out very large rolls of the HDPE material as it is delivered to the site, and welding sheets edge to edge (actually, the edges overlap) to form a contiguous membrane underlying the entire landfill. The same procedure is used to construct the secondary liner. If everything were as intended throughout time, there would be no passage of leachate through the primary membrane, and everything below it would be superfluous.

The final layer of fabric in the landfill liner system shown in Figure 9-1 consists of a so-called nonwoven geotextile that is placed over the top of the primary synthetic liner. The primary function of this layer of synthetic fabric is to protect the primary liner from being punctured or otherwise breached by the crushed stone, or anything inadvertently put in the crushed stone, above it.

A bed of crushed stone consisting of aggregates of 1- to 1.5-inch diameter is placed on top of the nonwoven geotextile along with the primary leachate collection system. The crushed stone bed has the multiple functions of (1) holding the leachate collection and transport pipe system in place, (2) providing a high degree of hydraulic conductivity to enable leachate to flow to the collection and transport system, and (3) serving as a bed for the solid wastes placed in the landfill.

The primary leachate collection and transport system is a grid of plastic pipe (HDPE in the example illustrated in Figure 9-1), perforated at all locations within the landfill and solid outside the landfill. The layout of the pipe grid, the size and spacing of the laterals and headers, and the material of construction of the pipes themselves are subject to guidelines and regulations issued by each state or solid waste authority. The treatment and disposal of leachate, once collected, is addressed in Chapter 8.

Some landfill liner designs have a layer of groundwater protection in addition to the two that are included in the design illustrated in Figure 9-1. An example is shown in Figure 9-2. The landfill liner system shown in Figure 9-2, which was installed in 1999 in Augusta, Maine, has primary and secondary synthetic membrane liners with primary and secondary leachate collection as shown in Figure 9-2, plus a third synthetic membrane liner below the primary and secondary systems. A system of liquid collection and transport piping is located just above the third liner, which is correctly referred to as “leak detection” because its function is to show evidence of leaks in the “conventional” landfill liner system above it.

Landfill Cover and Cap Systems

Daily and Intermediate Cover

An important feature of any landfill is a practice that began with the earliest landfills in the 1940s, that of daily, intermediate, and final cover. Daily cover consists of soil or other approved material that is placed over




Figure 9-2 Landfill liner with three synthetic membranes and two leachate collection systems.

the deposited wastes as soon as is practical throughout, and without fail at the end of, each day of landfill operation. The purposes of daily cover include control of flies and rodents, fire, odors, volatile organic compound (VOC) emissions, scavenging, and the prevention of items from being blown out of place by wind. A 6 inch depth of soil is mandated by the EPA (Title 40, Subpart C, 258.21) for this purpose; however, because of the high value placed on landfill "air space," the 6 inches taken up by each lift when soil is used for the daily cover has been looked upon as a candidate for replacement by much thinner alternative materials. Although each time a substitute material is used it must be approved on a case-by-case basis, many landfills have been successful in doing so. Alternative materials have included specially constructed membranes (referred to as "tarps"), sludge from primary clarifiers, proprietary fiber slurries, foam-in-place products, and spray-on asphalt membranes.

Intermediate cover is soil that was removed earlier from the landfill excavation and stockpiled. The same is true for daily cover. In some instances, another (approved) material has been used for intermediate cover. An example is

sludge from primary clarifiers at paper mill wastewater treatment plants. The frequency of placement of intermediate cover depends on the characteristics of the material being land-filled but is typically required to be placed on any portion of the landfill if it is to be inactive for 60 or more days. The thickness of intermediate cover is typically required to be no less than 12 inches.

Final Cover and/or Cap

When a landfill, or a discrete segment of a landfill, has reached capacity, it must be "closed" in accordance with applicable regulations. Typically, a constructed "cap" is required, an example of which is illustrated in Figure 9-3. The primary purpose of the cap is to stop the formation of leachate by preventing rainwater or other precipitation from percolating into the landfilled waste. Therefore, the design objective is to provide an impermeable barrier that is able to dissipate methane and other gases into the ambient air, thus preventing an explosion or fire hazard from developing.

As shown in Figure 9-3, it is first necessary to completely cover the (compacted) waste




Figure 9-3 Typical cover section for a landfill.

with soil of approved characteristics. This first layer is the base cover soil. Normally, a minimum thickness of 12 inches is required.

The base cover soil is then overlain with a layer of sand, 9 to 12 inches thick. The primary purpose of this layer is to collect methane and other gases that are generated within the wastes as a result of microbiological or other

activity, and to provide for free flow of the gas to the pipe grid that constitutes the gas collection and relief system. The objective of the combined sand layer and pipe grid is to allow generated gas to pass continuously into the ambient air and not build up beneath the impermeable cap. Therefore, the gas transmission sand must be clean and properly graded

(high uniformity coefficient) to have high gas conductivity.

Above the layer of gas transmission sand is placed a 2-foot layer of so-called barrier soil. The barrier soil is placed in three lifts, the first of 12-inch thickness, the second and third of 6 inches each. This layer of soil is then overlain with a synthetic, impermeable membrane. The primary purpose of the combined barrier soil–synthetic membrane system is to prevent water from any source from percolating down through the landfilled waste. If the cap is successful, leachate formation will cease.

What is placed on top of the impermeable membrane system supports the growth of grass and conducts away rainwater and water from any other source. In order to support the growth of grass, the system that is constructed over the top of the impermeable membrane must be able to allow rainwater to percolate through it, then be collected and carried harmlessly off the site. To this end, the synthetic membrane is overlain with a 12-inch layer of “drainage sand.” The purpose of the drainage sand is to provide an easy flowpath for the percolated water to reach the drainage piping network. The drainage pipes then conduct this water to the stormwater collection and retention system to prevent erosion or other harmful activity.

Above the drainage sand is a geotextile sheet, and above that is a 12- to 18-inch layer of common borrow. The purpose of the geotextile is to prevent percolating water from carrying fines from the common borrow into the drainage sand, thus causing plugging. The purpose of the common borrow is to support the topsoil above it in a way that helps the topsoil retain moisture. If the topsoil were placed directly on the sand, it would quickly dry and not support the growth of grass between periods of rain.

Topsoil is placed in a 6-inch-thick layer over the borrow. Then, it has been found to be good practice to place an erosion control blanket over the topsoil before, or just after, seeding. The erosion control blanket is a fabric of synthetic or natural material that resembles fine netting. It allows ready penetration of water and allows grass to grow up through it.

Gas Venting

The organic material that has been placed in a landfill undergoes anaerobic degradation, with the consequent generation of methane, hydrogen, hydrogen sulfide, and other gases, possibly for many years. Explosions have occurred when one or more of these gases, principally methane, have migrated through the soil and entered a building. To prevent such an occurrence, it is necessary to provide for easy and continuous escape of these gases into the ambient air. Therefore a well-designed and installed gas venting system is a necessary component of a landfill or portion of a landfill that has been closed and provided with final cover or an impermeable cap.

Figure 9-4 presents a drawing of a cross-section of a landfill cap, including a portion of the gas venting system. The standard installation procedure for a gas venting system is as follows: A grid system of trenches is excavated a minimum of 5 feet into the final layer of deposited and compacted solid waste material. Six-inch-diameter perforated plastic pipe is installed in each trench, surrounded by crushed stone. The crushed stone completely fills each trench, except for the plastic pipe. The purpose of the crushed stone is to provide for ready migration of the gas generated in the landfill toward and into the plastic (polyethylene [PE], in the case shown in Figure 9-4) pipe. The purpose of the plastic pipe is to collect the gas and allow it to disperse into the ambient air via the vertical vent pipes shown.

The mechanism of gas collection and dispersion is accounted for by the low specific weight, compared to air, of the mix of gases, which is predominantly methane. When the mixed gas reaches the vertical vent pipe, it rises, under the influence of gravity, thus creating a decrease in pressure (partial vacuum) behind it. This lowered pressure draws gases within the solid waste mass toward and into the vent pipe system. These gases rise up the vent pipe and out the 90° bend, as shown, and the process perpetuates itself.

In general, each state or solid waste authority issues guidelines and regulations regarding the layout of the gas collection grid and the




Figure 9-4 Cross-section of a portion of a landfill cap shows portion of gas venting system.

number and spacing of vertical vents. Also, the characteristics of the industrial solid waste that is landfilled must be taken into account when designing the system regarding how readily gas can move through it to be collected by the venting system.

Stormwater Management

The objectives of stormwater management at a landfill site are to prevent runoff from contacting the landfilled waste material and to prevent erosion. Stormwater management involves the use of berms, grading, catch basins, a storm sewer system, and retention basins. Rip-rap-lined ditches and channels are also used for

stormwater management and erosion control, during active use of the landfill as well as after closure and capping of the landfill. There is always a slope to the cap to prevent standing water, as a minimum, but usually as the result of placing the maximum possible amount of waste in the landfill.

Rip-rap-lined ditches and channels are usually designed as an integral component of the final cover or cap for control of erosion. Detention basins are used to hold collected stormwater for a period to allow solids to settle out before discharge to the receiving water body.

Essentially all solid waste management facilities, including transfer stations, incinerators, compost facilities, and, certainly, landfills

should include a well-designed system of groundwater sampling wells, sometimes referred to as “sentinel wells,” to detect the occurrence of groundwater contamination. There should be at least one up-gradient well to show background, or uncontaminated groundwater quality, and a sufficient number of downgradient wells to detect contamination from any reasonably possible location. The sentinel wells should be monitored, and records should be maintained throughout the life of the facility as well for a reasonable period after closure.

Discharges from Landfills

There are two types of discharges from sanitary landfills: liquid, in the form of leachate, and gaseous (i.e., that which is discharged from the vent system). Both are regulated by federal and state statutes. In the case of leachate, there are strict requirements to contain, collect, and treat it before ultimate discharge to the environment, which would necessarily be either a surface water body or the groundwater.

Leachate

Leachate is contained and collected by the mandated landfill liner and leachate collection system described previously. Regarding

treatment, there are three alternatives: (1) traditional trucking or piping to the industrial facility’s wastewater treatment plant or to a publicly owned treatment works (POTW), (2) treatment using a facility designed specifically for the leachate, and (3) evaporating the leachate in a burner fueled by gas collected from the landfill. Of course, there is also the alternative of combining two or more of these three alternatives. For instance, pretreatment facilities have been used to render leachate from industrial solid waste landfills compatible with either the industrial facility’s wastewater treatment plant or a POTW. Alternative technologies for treating or pretreating landfill leachate are discussed in Chapter 8.

Regarding evaporation by use of a burner fueled by gas from the landfill itself, Figure 9-5 shows an example of a system that was developed for this purpose during the mid-1990s. Landfill gas (LFG), being primarily methane, is fed into the bottom of the combustion chamber shown on the right. Air is fed in very close to the gas inlet nozzle to provide the correct quantity of oxygen for complete combustion of both the landfill gas (including methane and the other gases such as hydrogen sulfide) and the vaporized leachate, which enters this combustion chamber above the flame. A temperature of 1,600°F, achieved in the combustion chamber,




Figure 9-5 Evaporation vessel (From White, et al. 1996).

ensures complete destruction of VOCs or other hazardous substances from either the landfill gas or the leachate.

The leachate is vaporized in the evaporation vessel shown on the left in Figure 9-5. Landfill gas enters the burner at the top of this vessel, and the hot gases from the burning of the LFG are directed down and into the leachate, which enters the evaporation vessel just outside the draft tube within the vessel. Evaporated leachate, plus completely and incompletely oxidized LFG, exit the liquid surface within the draft tube, then proceed to the combustion chamber on the right. Those substances in the leachate that will not evaporate sink to the bottom of the evaporator vessel to form a concentrate, reportedly amounting to less than 5% of the original leachate volume. This concentrate must be dealt with, and options include returning it to the landfill. In order to do this, however, the restrictions and provisions of 40 CFR 264.314 and 265.314 (solid waste regulations) must be complied with.

Landfill Gas

Landfill gas discharges are regulated by Subtitle D (see Chapter 3) and the *Clean Air Act* to attempt to control so-called greenhouse gas emissions. Methane is 21 times more potent in creating climate change than is carbon dioxide, on a carbon-to-carbon basis, according to the U.S. EPA. Moreover, it is the U.S. EPA's estimate that 40% of the methane emitted to the atmosphere on a yearly basis is from active and closed landfills. Consequently, the U.S. EPA has been charged by Congress with enforcing controls on methane emissions from landfills. The result is an ever-increasing requirement for landfill gas collection, with subsequent management to minimize the effect on global climate change.

Gas collected from industrial waste landfills usually requires a certain amount of cleaning before use as fuel in a boiler or other burner. Reasons for cleaning include the following:

- Limiting pollutants released to the atmosphere

- Removing corrosive substances
- Increasing the fuel value, in terms of BTUs per cubic foot

Additionally, to limit emissions of NO_x and carbon monoxide (CO), it may be necessary to use catalytic converters to remove these substances from postcombustion gas, as well as other technologies to address VOCs, sulfur compounds, and silicon-based compounds. The latter have been the source of problems with the catalytic converters used to control emissions of NO_x and CO.

Alternative Landfills

The conventional modern landfill, with leachate containment, collection and treatment, and impermeable cap is referred to, after closing, as a "dry tomb." The combination of impermeable cap, which prevents moisture from reaching the landfilled material via percolating precipitation, and the landfill liner system, which carries away leachate resulting from the period when the landfill was active, ensures that the landfill interior will be dry for a long time. The dry conditions effectively prevent microbial activity. The advantage of this condition is that neither gas nor leachate is produced within the landfill in significant quantity. The disadvantage is that the landfilled material remains "entombed" for those many years. Although this may be a good thing regarding future recycle and reuse of some of the landfilled substances (or for future beings from outer space to examine to reconstruct our civilization), there is a growing sentiment that, on balance, the disadvantages outweigh the advantages.

Probably the greatest disadvantage of the dry tomb approach is that the closed landfill remains a potential threat to the groundwater for as long as it exists. Whenever the integrity of the cap and liner are breached, for whatever reason—earthquakes, tornadoes, accidents, or simply the passage of enough time—water will reach the landfilled wastes and create leachate.

An alternative to the dry tomb approach is to manage the closed landfill to encourage

microbial degradation of the landfilled material (i.e., manage the landfill as a biochemical/chemical reactor). One way to do this is to continually recycle leachate back to the top of the landfilled wastes, and to add water to the leachate to keep the moisture within the landfill at a level that results in maximum generation of gas. Then, the option of collecting the gas for use as fuel is available. The decision to manage an industrial waste landfill as a biochemical/chemical reactor, possibly for the purpose of generating gas for fuel as well as to address the “time bomb” problem where the landfill sits as a threat to groundwater pollution “in perpetuity,” must be based largely on the characteristics of the leachate. If hazardous substances are in hazardous concentrations in the leachate, the cost for proper (including legal) management becomes of overbearing importance.

Solid Waste Incineration

There are many different types of incinerators, and several different conventions are used to classify them. One convention is to classify incinerators as either “mass burn” or “refuse-derived fuel” (RDF). Mass burn technology involves combusting, as completely as possible, all (combustible) substances in a solid waste stream. RDF systems attempt to separate, by volatilization, as much of the organic portion of a solid waste stream as possible, then to clean and otherwise process the resulting mixture of gases to produce a low-, medium-, or even high-grade fuel. The remaining portion of the solid waste stream (char and ash) is then disposed of or further processed, then disposed of.

Another convention used to classify incinerators (or “combustors”—the terms “incinerator” and “combustor” are used synonymously) is based on the equipment technology itself. The following is a list of incinerator technologies in use:

- Fluidized bed
- Rotary kiln
- Hearth-type
- Liquid injection

Another convention is to classify incinerators as either “excess air” or “starved air,” and still another is to classify incineration systems as either “hazardous waste incinerators” or “conventional waste incinerators.”

Under any classification system, all incinerators (combustors) have the following characteristics in common:

- All solid waste substances must be converted to the vapor state before they can be ignited and burned.
- Two types of ash leave the system: fly ash and bottom ash. Both must be managed to prevent them from becoming environmental pollution problems. Incineration is therefore to be regarded as a treatment and volume reduction process, rather than as a disposal process.
- Solid wastes almost always have to be subjected to a conditioning process before entering the combustion chamber. Conditioning may include one or more of grinding, mixing, blending, dewatering, or other treatment.

Fluidized Bed Technology

Fluidized bed technology is considered to have high potential for treating industrial wastes because of the capability of complete combustion and history of relatively low air emissions. Fluidized bed combustion can be combined with recovery of heat; therefore, it has potential as a viable waste-to-energy (WTE) alternative, depending on the overall BTU value and moisture content of the waste.

Fluidized bed incineration systems use a bed of sand or sandlike material that is fluidized (suspended against the force of gravity) by the drag force of air and other gases rising up through the bed, as illustrated in Figures 9-6(a) and (b). The bed is heated to incineration temperature, which can range from 650° to over 1,200°C (1,200° to 2,200°F, or higher), depending on the characteristics of the waste. The heat content of the fluidized bed material, typically sand, is such that it provides a substantial heat reservoir to maintain temperature and combustion as new waste material is injected into the fluidized bed

volume. For instance, the heat content of the bed on a unit volume basis is about three orders of magnitude greater than that of flue gas at the same temperature. Fluidized bed technology is used for hazardous and conventional solid wastes.

A generic fluidized bed combustor system is illustrated in Figure 9-6 (a). The characteristic component of a fluidized bed combustion system is the reaction chamber, which is illustrated in greater detail in Figure 9-6 (b). Figure 9-6 (b) shows that a grate supports the sand or sand-like bed material at the bottom of the primary combustion chamber. A cone-shaped collector-distributor beneath the grate distributes air that is blown into the section below the combustion chamber and collects inerts that are not further combustible and are too heavy to be buoyed up by the rising air column. The inerts are collected and removed from the lower chamber by a conveyor device that locks out air.

The air that is blown into the lower chamber is distributed evenly across the cross-section of the primary combustion chamber by the cone-shaped collector-distributor. This air then rises up through the bed, supplying oxygen for combustion and drag force to fluidize the sand bed. The fluidized bed of sand (or sandlike material) fills most of the primary reaction chamber. Waste materials are fed directly into the primary reaction chamber, along with auxiliary fuel needed to start up the combustion process and to maintain desired temperature, if necessary. Typically, it is not necessary to supply auxiliary fuel to maintain desired temperature while combustion is taking place because the heat value of the organic solid wastes being incinerated is more than enough for this purpose. In fact, it is usually necessary to supply excess air to prevent the temperature from rising too high, causing damage to the system.




Figure 9-6(a) Fluidized bed combustor system. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)




Figure 9-6(b) Typical fluidized bed combustor. (From Pope, 1999.)

As the waste is injected into the lower part of the fluidized bed within the combustion chamber, the heat from the sand grains first gasifies the waste material, then ignites it. Complete combustion of this material follows. The grains of sand are greatly agitated by the column of air passing up through the bed, and this agitation has beneficial effects. The agitation tends to break up the heated particles of solid waste, enhancing the gasification process and resulting in quicker ignition. The agitation also tends to abrade the bed material itself, which tends to keep it clean. Without this self-cleaning action, the particles of bed material would tend to become coated with soot and other products of the combustion of the solid waste material. The agitation also tends to mix and homogenize the injected waste material, promoting faster and more thorough combustion. As the solid waste

material undergoes combustion, liberated heat is transferred back into the bed material (typically sand) to perpetuate the gasification-ignition-combustion process.

The products of combustion rise out of the fluidized bed, toward the top of the reactor. Some systems have a secondary combustion chamber at this point to ensure complete destruction of the waste material. This result is especially important when hazardous materials are being treated.

From the secondary combustion chamber, which may or may not have auxiliary fuel capability, the products of combustion, along with the oxygen-depleted air stream, flow into and through a system that cleans and cools them before discharging to the ambient air. The gas treatment devices included in this system can include cyclones for collecting particulates,

heat exchangers or quenchers to lower the temperature, one or more packed column scrubbers, activated carbon adsorbers, venturi scrubbers, or other devices. Chapter 10 presents discussions regarding the mechanisms and uses of these air pollution control devices.

Fluidized bed reactors are used in some waste-to-energy (WTE) systems. In these systems, typically only gasification takes place in the fluidized bed reactor. The volatilized organic substances from this process are either burned immediately in a boiler or other energy conversion device, or are captured and stored for later use. In some cases, the volatilized product (gases) from the fluidized bed reactor are processed to remove substances that degrade the fuel value; in other cases, other substances of highest fuel value are removed as a valuable by-product. The remaining substances are then burned as a lower-grade fuel.

Advantages

Many years of development and operating experience with fluidized bed combustors have resulted in the following advantages, compared to other combustion systems for treating solid wastes from industries:

- Air emissions are relatively low, compared to other incineration systems.
- Generation of nitrogen oxides (NO_x) tends to be significantly less because of lower excess air and lower temperatures.
- Carbon monoxide (CO) emissions are low because of relatively quick and relatively complete combustion.
- Solids, liquids, and gases can all be burned simultaneously.
- Few moving parts are used.
- Maintenance costs are relatively low.
- Large surface area of bed grains and waste particles enhances the gasification-ignition-combustion process.
- Large heat capacity of bed tolerates fluctuations in solid waste feed rate.
- Size of facility is relatively small.

- High degree of agitation in combustion chamber practically eliminates hot spots and cold spots.

Disadvantages


- Has a low tolerance for items, such as wire, which get stuck in the grate.
- Substances that tend to agglomerate can plug up the sand bed.
- Inerts are difficult to remove from the bed if they are not sufficiently heavy to fall through the grate against the air upflow.

Rotary Kiln Technology

Rotary kilns use an inclined cylinder as the combustion chamber, which rotates slowly to accomplish mixing of the materials and to attempt to expose all surfaces and substances to oxygen within the chamber. Auxiliary fuel, mixed with air, can be injected into either end of the rotating combustion chamber, or at one or more injection nozzles along the side. Rotary kilns have been successfully used to treat hazardous and conventional wastes, solid, semisolid sludges and liquids, either alone or simultaneously, and have been operated at temperatures as high as $1,500^\circ\text{C}$ ($3,000^\circ\text{F}$). Many rotary kiln combustors have been used to incinerate hazardous materials at temperatures in the $1,100^\circ\text{C}$ ($2,000^\circ\text{F}$) degree range.

As with all incinerator technologies, residence time, temperature, and quantity of oxygen made available are important parameters. Among other factors, residence time is influenced by the angle of incline, or slope, of the rotating combustion chamber, and the rate of rotation. The slope typically ranges from 0.02 ft/ft to 0.04 ft/ft. Speed of rotation ranges from 0.5 revolutions per minute (rpm) to 3 rpm. Figures 9-7(a)–(f) illustrate characteristics of the rotating combustion chamber. Figure 9-8 illustrates a typical rotary kiln solid waste incinerator system.


Figures 9-7(a)–(f) show that the conditioned solid waste is fed into the higher end of the



Axial movement through the reactor.

The slope of the kiln produces a slight forward movement toward the discharge end.

Figure 9-7(a) Elements of a rotary kiln incinerator—axial movement through the reactor. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)



$$\text{LOAD FRACTION} = \% \text{ LOADING} = \frac{\text{AREA OF BED}}{\text{TOTAL AREA OF KILN SECTION}}$$

Figure 9-7(b) Elements of a rotary kiln incinerator—the kiln solids flow system—definition of terms. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)




Figure 9-7(c) Elements of a rotary kiln incinerator—ported-kiln concept. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)




Figure 9-7(d) Elements of a rotary kiln incinerator—solids flow in cross section. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)




Figure 9-7(e) Elements of a rotary kiln incinerator—primary-burner concept. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)




Figure 9-7(f) Elements of a rotary kiln incinerator—axial-burner concept. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)

inclined, rotating combustion chamber. Conditioning can include any or all of grinding, mixing, or dewatering. As the kiln rotates, the solid waste tumbles from the up-rotating side back toward the middle of the bottom of the cylinder. As the wastes tumble, they become heated, vaporize (gasify), and mix with oxygen and ignite. They also progress toward the lower end of the rotating combustion chamber. Finally, ash discharges from the lower end.

Figures 9-7(c), (e), and (f) also illustrate that the auxiliary fuel-air mixture can be injected into the combustion chamber at alternative locations, and that exhaust gases exit at either (or both) the higher end or the lower end of the chamber.

Figure 9-8 is an example of a complete rotary kiln incinerator system. As shown, after ignition the gasified solid waste substances burn in the upper portion of the rotating cylinder (i.e., the combustion chamber), and the exhaust gases proceed to a postcombustion chamber, sometimes referred to as the after-burner. The postcombustion chamber is the primary air pollution control device and is

especially important if hazardous materials are contained in either the solid waste stream or the products of combustion, or both. The post-combustion chamber is followed by a heat exchanger, which, in turn, is followed by a particle collector. The cleaned exhaust gas is then discharged.

The heat exchanger is required, on the one hand, to cool the exhaust gases in order to protect the particle collector. It may also be the functional component of a waste-to-energy (WTE) system. In its simplest form, the heat exchanger can be a water spray or radiator that causes heat to be wasted to the ambient air. In its most useful form, it can be a waste heat boiler or other energy conversion device.

The ash must be disposed of in an appropriate manner, and there are alternatives to be evaluated. Landfilling in a secure facility designed and approved for either "special" or "hazardous" solid wastes has been most often used. Other alternatives include solidification with cement before burial, incorporation into asphalt, or solidification with epoxy.




Figure 9-8 Hazardous-waste incinerator system. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)

Advantages

- The technology is proven, having been used for incineration of many different industrial wastes over many years.
- Operation is flexible because the rate of rotation can be varied to suit the needs of a large variety of solid waste characteristics.
- Has been used to incinerate solids, liquids, and gases, in any combination.
- Requires less preparation (conditioning), such as sorting, grinding, and mixing, than certain other technologies.
- Not subject to problems such as plugging of grates, or from substances melting before gasification.
- Adaptable to many alternatives for air emission control, including quenchers, venturi scrubbers, wet gas scrubbers, electrostatic precipitators, and bag houses.
- Provides mixing within the combustion chamber for exposure to heat and oxygen.
- Can receive bulk containers in the feed stream.

Disadvantages

- Subject to formation of hot spots and cold spots.
- High load of particulates on air pollution control devices.
- Relatively high capital cost.
- High amounts of excess air lead to high demand for auxiliary fuel.
- Subject to damage to refractory lining of kiln due to tumbling solids.

Hearth Incinerator Technologies

Hearth incinerators are mass-burn systems in which conditioned solid waste materials are spread out on a (nearly) horizontal surface and burned. Auxiliary fuel is used for start-up and as necessary to maintain desired temperatures. In many cases, excess air is used to maintain

desired temperatures. In these situations, the excess air prevents the burning solid wastes from developing excessively high temperatures that would damage the combustion chamber and downstream equipment.

The most common type of hearth incinerator is the multiple-hearth incinerator, illustrated in Figure 9-9. The multiple-hearth incinerator system shown in Figure 9-9 has five hearths, stacked vertically. New, conditioned solid waste is fed onto the uppermost hearth, where hot gases from materials burning on lower hearths heat the new material, and volatilize water and the most volatile of the organic materials in the solid waste stream. A system of rakes slowly forces the wastes toward the middle of the uppermost hearth and down through a passageway to the next lower hearth. The temperature on this hearth is much higher, and active combustion takes place. The rake system forces burning wastes on this hearth toward the outside, then down onto the next lower hearth, and so on, until the residual ash is raked from the lowest hearth to a collection and transport device that removes the ash from the combustion chamber.

As the solid wastes burn on the middle hearths, the gaseous products of combustion flow up to heat materials on the hearths above. Then they exit the combustion chamber and pass through one or more devices to either finish off combustion, especially of toxic or otherwise hazardous substances, or to clean the exhaust gas stream of other emissions such as particulates, SO_x , malodorous gases, or other substances. In the case of completing the combustion process, a secondary combustion chamber (or postcombustion chamber or afterburner) with its own fans and auxiliary fuel system can be used. In the case of cleaning the exhaust gases before release to the ambient air, alternative processes include a quenching system to cool the exhaust gases to prevent damage to particulate collection devices, the particulate collection devices themselves, electrostatic precipitators, and various types of wet scrubbers.




Figure 9-9 Typical multiple-hearth incinerator. (From Metcalf and Eddy, © 1991. Reprinted by permission of McGraw-Hill, Inc.)

Advantages

- Useful when the water content of the solid waste stream is relatively high.
- Extensive operating history with conventional (nonhazardous) wastes.

Disadvantages

Lack of sufficient control for use with hazardous wastes.

- Subject to formation of cold spots and hot spots.
- Occupies a relatively large area.

Modular Systems

A variety of incinerator systems are available for industrial use and are referred to as

“modular” because they are assembled in sections at the factory for final assembly on site. Some systems are completely mobile after assembly. The principal advantage of modular combustor systems is lower cost because of preassembly under favorable conditions at the factory.

Starved Air Technologies

Starved air technologies, which include pyrolysis technologies, have been used as the first step in a two-step system for processing both hazardous and conventional industrial solid wastes. In this first step, the solid wastes are heated in a low-oxygen atmosphere to accomplish volatilization of all components except

char and ash. Then, the volatilized material is burned as in a conventional incinerator. At some facilities, the volatilized substances are processed to recover one or more components before the rest is incinerated. The volatilization process is carried out at significantly lower temperatures than are used for more conventional incineration technologies, with the advantage that equipment life is prolonged and maintenance costs are lower. More important in the case of hazardous materials, however, is the fact that the incineration step can be carried out under very precisely controlled conditions because only gases are being handled in the combustor phase of the system.

The generally accepted definition of pyrolysis is chemical decomposition by heating in the absence of oxygen. Some of the starved air industrial waste treatment systems do not fit this definition because they are carried out in atmospheres of up to 2% oxygen by volume (compared to 21% in ambient air); however, some systems in operation are called pyrolysis systems, even though "gasification," or simply "starved air," would be more appropriate.

Figure 9-10 is an example of a solid waste starved air system. In Figure 9-10, the conditioned, wet solid wastes enter the dryer, which uses recovered heat from the combustion of waste materials downstream in the same system. The dryer solid wastes are stored for a period (one day, or so), then are fed into the gasification chamber, which is maintained within a temperature range of 425° to 750°C (800° to 1,400°F). Residence times within the gasification chamber depend on the characteristics of the material in the waste stream. For instance, chemical makeup and particle size, as well as bed thickness, all have a significant effect on residence, time. Typical residence times are as short as 2 minutes and as long as 5 hours. The concentration of oxygen in the gasification chamber is maintained near zero. Gasification chambers are maintained under slightly negative pressure to prevent release of fugitive gasses.

After completing the required residence time in the gasification chamber, the nonvolatilized solids (char and ash) are removed and either further processed or landfilled. Further




Figure 9-10 Battell gasification process. (From Niessen, 1996.)

processing can be by high-temperature incineration (to further burn the char), solidification and stabilization using lime, cement, epoxy, asphalt, or another substance, chemical oxidation, or another process. The volatilized material can proceed to incineration in a one- or two-stage combustor, or, preferably, to a cleaning and conditioning process for preparing a fuel of reasonably high value. This fuel can be burned on site or off site in a gas engine, or it can be used in a gas turbine to generate electricity, or burned in a boiler to generate heat or steam to generate electricity. In the case of the system illustrated in Figure 9-10, the heat given off by the combusting volatilized gas stream is recovered and used to dry incoming solid wastes as the first step in the system.

It is also possible to separate by condensation, and thus recover, certain components of the volatilized gas stream. Some of these substances have considerable value, representing a source of cost recovery for the system as a whole.

Another significant advantage of the starved air process is that it results in a char or ash that is concentrated in potentially valuable nonvolatile substances such as metals. For instance, solid waste streams that contain a significant quantity of lead and/or zinc can cause problems in conventional combustors because at normal incinerator temperatures lead and zinc, and certain other substances can volatilize and cause fouling of heat exchangers and spalling of the refractory linings of the combustion chamber.

Advantages

- The volatilized gas stream can be used as fuel for engines, turbines, or for burning.
- Valuable substances such as lead and zinc can be recovered from the char and ash residue.
- The vapor stream can be processed to recover substances of value.
- Lower temperatures lead to longer equipment life and lower maintenance costs.
- Process control is relatively easy because the gasification process is endothermic. There is no danger of self-overheating.

Disadvantages

- One disadvantage of starved air technologies is that the process takes place in a reducing atmosphere, with the result that the products are highly corrosive. Therefore, the materials of construction are relatively expensive.
- In the case of certain solid waste streams, highly toxic, and in some cases carcinogenic, substances are generated. This problem sometimes requires construction and operation of very highly reliable and effective volatilized gas stream incineration.

Design Considerations

There are choices to make regarding the technology to employ for the gasification step as well as the subsequent processing and ultimate disposal of the volatilized gas stream and the solid residuals. The gasification step can be accomplished in any of several furnace types, including:

- Rotary kiln
- Rotary hearth
- Roller hearth
- Car bottom

Rotary Kiln

The rotary kiln reactor for carrying out the gasification step is essentially the same as was discussed previously for the rotary kiln combustor. Differences include provision to exclude oxygen from the gasification furnace, and different materials of construction because of the oxidative environment in the combustor furnace versus the reducing environment in the gasification furnace. Also, auxiliary fuel must always be used in the gasification furnace because of the endothermic nature of the process, whereas provision must be made to supply and control excess air for cooling in the case of the combustor furnace.

Rotary Hearth

A typical rotary hearth reactor, illustrated in Figure 9-11, consists of a doughnut-shaped

hearth that rotates through a stationary heated gasification chamber. Industrial solid wastes, conditioned as needed, are fed onto the continuously rotating hearth ahead of the heated chamber. As the waste enters the heated chamber, the pyrolysis process begins, and continues after the wastes leave the heated chamber. Vaporized organics and other gaseous substances are continuously extracted from the top of the enclosure that covers the entire hearth, and proceed to the next step, which, in the example shown in Figure 9-11, is a reactor that conditions and ultimately uses the fumes for fuel to fire the waste heat boiler.

Roller Hearth

The roller hearth gasification system is used by individual industries and by centralized hazardous waste processors to gasify hazardous wastes that are brought to the facility in containers such as 55-gallon steel drums. The containers are opened at the top, usually by removing the top, and the containers are fed, upright so as not to spill the contents, into the heated chamber. Rollers cover the bottom of the heated chamber and allow the open drums

to be pushed along through the heated chamber from the entrance to the exit. In some cases, the rollers are motorized such that they propel the containers through the heated chamber.

As the containers pass through the heated chamber, the target substances in those containers volatilize, or "gasify," char and ash remaining in the containers. The vapors are collected, processed, and stored, then used as either fuel or as a source of mixed substances, mostly organic, from which to recover certain substances of value. The remainder is either incinerated, or, if possible, used as a (lower grade) fuel.

Car Bottom

Car bottom gasification furnaces are small, two-part systems. One part is a mobile "car," on wheels, on which containerized wastes, often of a hazardous nature, are placed. The car is then rolled into the second part, which is a furnace without a bottom. The car becomes the bottom of the furnace. After the car and the furnace have been joined to form the complete furnace, the furnace is heated, and the gasification process takes place.




Figure 9-11 Rotary-hearth pyrolyzer. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)

As fumes exit the containers, which are often 55-gallon drums, they are collected, then are usually combusted as a means of disposal in a furnace of higher temperature. The char and ash that remain in the bottom of the containers can then be processed to recover certain substances. The remaining char and ash must then be disposed of using appropriate means, which might include incinerating (the char) in a combustor of high temperature, landfilling in an appropriate landfill, or solidification.

Car bottom gasification technology is normally operated on a batch basis. The advantage, as with many other batch technologies, is that the residence time, or time allowed for the gasification process to take place, can be extended for as long as needed for the process to go to completion.

Two incinerator technologies are in wide use in the United States, being used for treatment (volume reduction and characteristic transformation) of two classifications of solid wastes. The two incinerator technologies are hearth incinerators and rotary kiln incinerators. The two classifications of solid wastes are

hazardous and conventional. Of all incinerators in use for all purposes, those that are based on liquid-injection technology account for about half, but they are not of use for incinerating solid wastes.

Generally, incinerators for hazardous materials are required to maintain significantly higher temperatures in the combustion chamber than are incinerators for conventional wastes. For this reason, hazardous waste incinerators are required to be built using more expensive materials and techniques.

The Process of Composting Industrial Wastes

Some industrial solid wastes are amenable to composting as a treatment process to prepare the waste for future use as a soil conditioner. Typically, these solid wastes are close to 100% organic in composition, are readily biodegradable, contain no hazardous materials, contain a moderate amount of moisture, and can be handled with conventional equipment such as front end loaders and belt conveyors. The basic composting process is illustrated schematically in Figure 9-12.




Figure 9-12 Basic composting process.

As illustrated in Figure 9-12, microorganisms use the organic material within a pile of mixed solid wastes for food. Initially, the temperature is close to the temperature of the ambient air, and oxygen is present in the air that occupies the void spaces between the solid waste materials. Also, there must be enough moisture present for the microorganisms to live in. Bacteria can live only in an aqueous environment and can metabolize only substances that are dissolved in water. As the bacteria and other microorganisms metabolize the food that is dissolved in the moisture content of the compost pile, heat is generated. The source of the heat is as follows: As the microorganisms disassemble the proteins, carbohydrates, lipids, and other materials that make up the solid wastes in the compost pile, energy from the breaking of chemical bonds is liberated. The microorganisms use some of this liberated energy to reassemble atomic and molecular parts and pieces into new cell protoplasm and other materials to make new cells (i.e. growth), but the process is less than 100% efficient, and the leftover energy is lost as heat. As heat is generated, the temperature rises. During the increasing temperature phase, a continual natural selection process favors those microorganisms that thrive at higher temperatures, and then, as the temperature rises more, still other microorganisms are favored that thrive at still higher temperatures, and so on, until the range of thermophilic microorganisms is reached, at about 70°C. The composting mass stays at about this temperature because heat is now lost about as fast as it is generated.

Regarding the fact that microorganisms cannot ingest "food" unless it is dissolved in water, the reason composting of solid wastes proceeds successfully is because of the ability of some microorganisms to produce "exoenzymes" (enzymes that are manufactured inside the microorganism, but are then sent outside, into the aqueous environment) that can attack undissolved organic solids and cause them to dissolve into the water, in parts and pieces. This relatively slow process continues until all of the solid substances have been "disassembled and dissolved," with the exception of that

fraction of the original solid waste mass that is resistant to biodegradation, which is called "humus."

All of the foregoing processes can, and will, take place naturally; no management is required. However, if too much moisture evaporates and is lost from the system, the microorganisms are unable to live, and the process is arrested. If there is too much moisture, water fills the void spaces between solid waste materials, the dissolved oxygen in the water is soon depleted by the respiring microorganisms, and the system becomes anoxic or anaerobic. If the system becomes anoxic or anaerobic, the temperature will not rise to the thermophilic range, bad odors will be created, and the microbial degradation process will be very slow. For these reasons and others, a successful process for treating solid wastes from industries by use of the composting process to achieve volume reduction, chemical and biochemical stability, and an end product that can be safely and beneficially "disposed of" requires a high degree of management.

Regarding the temperature within the composting mass, there are two major benefits to achieving and maintaining the thermophilic range (about 70°C). The first is that microbial degradation takes place very fast. In general, the rate of microbial metabolism doubles for each 10°C rise in temperature. The benefit to solid waste treatment, of course, is a shorter time required to reach a stable condition. Organic material that has been biologically stabilized will not undergo further significant biodegradation and will, therefore, not become an odor or other nuisance or health problem. The second major benefit of achieving and maintaining the thermophilic range for a significant period is that pathogenic organisms, including bacteria and viruses, are killed. This is especially important if human wastes, usually in the form of sludge from wastewater treatment facilities, are included in the mix of solid wastes. In the context of treating solid wastes from industries, this ability to kill pathogens may or may not have value. What is always of value, however, is the ability of the composting process to produce a stable, inoffensive, useful

product from a putrescible material that is inherently a disposal problem. Because sludge from industrial wastewater treatment systems is one of the industrial waste candidates for treatment by composting, and because toilet wastes may be treated along with processing wastewaters at a given industrial plant, the ability to kill pathogens obviously has value in some industrial situations.

It is often beneficial to mix fresh solid wastes with a bulking agent, such as wood chips, at the start of the composting process. The bulking agent does not necessarily become involved in the composting process itself; that is, the bulking agent does not necessarily undergo biological degradation. Rather, the bulking agent helps provide spaces for air to reside, and thus provide oxygen for microbial respiration. A bulking agent also provides channels for air to move from outside the composting mass to the inner spaces where oxygen is being depleted. In some cases, fully composted product from the process is used. When an agent other than the compost itself is used for bulking, it may or may not be separated from the finished product for reuse. Sometimes it is left in the composted product to enhance the desirability and value of the product for certain uses. In other cases it is separated from the final product by screening, stored, then used again with new batches of solid wastes.

Because of the continual depletion of oxygen, it is necessary to continually renew the oxygen supply by providing fresh air to the entire composting mass. This is accomplished by either turning and fluffing up the composting mass periodically or by blowing or drawing air through it. Also, if the moisture content becomes too low because of evaporation, it is necessary to add more moisture by spraying or other means.

It is important to maintain the oxygen content in the void spaces within the composting mass between 5% and 15% by volume (compared to about 21% in ambient air). Less than 5% will possibly allow local pockets of anaerobic or anoxic conditions to develop, leading to an odor problem. More than 15% is

indicative of overaeration, with consequent inability of developing temperatures into the thermophilic range.

Moisture content must also be maintained within a favorable range, but that range is waste specific and is best determined through experience. The proper procedure is to first conduct bench scale laboratory tests, followed by a pilot scale program. Once an optimal range of moisture is determined by these studies, the initial compost process is set up, then observed closely and compared to the pilot scale results. The objective is to reach thermophilic temperatures within a few days and to achieve complete composting within 14 to 28 days.

In some cases, it is good practice, and in other cases, it is absolutely necessary, to grind the solid waste material before composting. Grinding has the beneficial effects of greatly increasing the surface area of the organic substances, thus enhancing the composting process, and renders the material more easily mixed with the bulking agent. Grinding also produces more uniform moisture content throughout the solid waste material. Mechanical grinders for this purpose are available from several vendors.

Three general technologies are used in the United States for composting: windrow, static pile, and mechanical. Windrow composting typically uses a very large, specialized mobile machine that straddles a windrow of composting solid wastes and works it over by fluffing and turning the windrow. Static pile technology also typically uses a windrow or other type of pile and uses a blower to either maintain a partial vacuum within the pile to cause air to flow from the ambient air into the pile, or to blow air out through the pile.

Windrow Composting Technology

Solid wastes to be composted by the windrow method are first mixed to produce a reasonably uniform composition so that the time required for complete composting is close to the same throughout the windrow. In some cases, a grinding procedure, using specially made solid waste grinders, either precedes or follows the

mixing procedure. Next, the mixture is processed to adjust the moisture content to the desired range, then, typically, mixed thoroughly with a bulking agent such as wood chips or previously composted material. The next step is to arrange the mixture in a windrow using a front-end loader or other machinery. The windrows are 5 to 7 feet high and are 10 to 20 feet wide at the base. Figure 9-13 is an illustration of typical windrow dimensions. About once per day or, in some cases, more often, the windrow machine travels the length of the windrows and mechanically works over the composting material and, in some cases, blows air into it. The objective of working over, or turning, the composting material is to expose new portions of the mass to the open air, thus renewing the oxygen supply. As explained previously, it is necessary to maintain an average oxygen concentration in the void spaces of 5% to 15% by volume (compared to 21% in ambient air) within the composting mass to prevent odor problems and to enable the composting mass to maintain temperature in the thermophilic range. Figure 9-14 illustrates a windrow machine.

A large compost facility in Puyallup, Washington, has modified the windrow turning

machine to include a 10,000-gallon water tank for adjusting the moisture content of the composting mass. This facility uses grass clippings that are picked up at curbside throughout the city as a bulking agent. Because the grass clippings have a tendency to settle and mat, it is necessary to blow (rather than draw) additional air through the composting mass to reestablish porosity, thus proper oxygenation. The extra air, moved by use of three 50-horsepower centrifugal blowers, removes too much moisture from the composting mass, thus the need for the water tank.

Other problems that are unique to the composting of a given solid waste or use of a given bulking agent or other additive can often be solved by taking advantage of simple concepts. As another example, in Rockland, Maine, a compost facility that was used to convert fish processing wastes to a soil conditioning agent made use of leather buffing dust (similar to sawdust, but of almost zero moisture content, [also a troublesome industrial solid waste]) to adjust from too high a moisture content to the optimum range.

The composting process is normally complete in 14 to 21 days (in some cases, as long as




Figure 9-13 Dimensions of typical windrows (from MSW Management, 1996).



Figure 9-14 Windrow composting machine. (Courtesy of Scarab Manufacturing.)

28 days), after which the finished compost is stirred and allowed to “cure” for several weeks or months. During curing, the microbial population reduces and stabilizes by adjusting itself to a food-poor environment. Normally, minor odor problems that may have existed at the end of the composting process disappear during the curing process because the remaining species of microbes consume whatever is the source of the minor odors.

Static Pile Technology

Static pile technology uses a system that sucks air through the composting mass by drawing a vacuum at the bottom of the pile. This method, which was originally developed in the mid-1970s to treat sludge from sewage treatment plants, is illustrated in Figure 9-15.

As shown in Figure 9-15, a grid of perforated pipes supported on the top surface of a concrete pad is connected to a blower. The solid waste to be composted is piled over the pipe grid after first undergoing conditioning by grinding and mixing with the bulking agent. Then, the pile is covered to insulate it to enable the temperature to build up to the thermophilic range (about 70°C). The composting process begins immediately, because of the presence of both bacteria and food; therefore, air flow should begin immediately to prevent the development of an odor problem. The blower draws air through the composting material from the outside in, to maintain the proper concentration of oxygen within the voids in the composting material, as discussed previously. Standard procedure is to discharge the exhaust air from the blower into a pile of finished compost, to filter out fine particulates and to control minor odors.

Mechanical Composting Technology

Mechanical composting technology involves the use of a container and mechanical stirring equipment. The solid waste is first conditioned by grinding and mixing with a bulking agent as described for the windrow and static pile technologies. Then, the mixture is placed in the container-stirring system, which maintains even




Figure 9-15 Composting with forced aeration. (From Corbitt, © 1999. Reprinted by permission of McGraw-Hill, Inc.)

distribution of oxygen, temperature, and moisture while the composting process is taking place.

Two variations of mechanical composting technology are the rotating drum system and the vertical system. As it is now used, the rotating drum system is a “precomposting” process or, more accurately, a “compost starting” system. The conditioned (ground and mixed with bulking agent) solid waste is placed in one end of an inclined, rotating drum, which may or may not have additional mechanical devices inside to enhance mixing. The rotating of the drum mixes and brings about evenly distributed temperature and moisture. The rotation action also accomplishes aeration of the composting mass, by rolling the composting mass in an atmosphere of ambient air.

After 2 to 5 days, the partially composted material exits the lower end of the rotating drum. The composting process can be finished by use of either windrow technology or static pile technology. The value of the rotating drum process is that it significantly reduces the total time required for completing the composting process.

A second mechanical composting technology is referred to as “vertical process.” This technology uses large silos or bins that are maintained full of composting material, which is continually moving from the top to the bottom. Composted product is harvested from the bottom and is replaced with conditioned (ground and mixed with a bulking agent, and in some instances, carbonaceous material) solid waste at the top. Air is blown through, usually from the bottom to the top, to maintain the correct (5% to 15% by volume) oxygen content within the gas phase in the vertical composter. The oxygen content, as well as temperature and moisture content, is monitored by use of sampling ports in the side of the vertical composter. The principal advantage of this technology, then, is the capability to closely monitor and control the progress of the composting process.

Additional Considerations

Nutrients

Depending on the nitrogen and phosphorus content of the industrial solid waste, and other nutrient levels, the nutrient content of the compost may be of significant benefit as fertilizer in the conventional sense. Some nitrogen is lost during the composting process, however. Conversely, some industrial solid wastes might be suitable candidates for composting as a treatment process, except for lack of adequate nutrient. In these cases, it might be cost effective to add nutrients such as nitrogen and phosphorus, probably in the form of agricultural fertilizer. The cost of the fertilizer, added to the cost of composting, minus the income from sale of the final composted product as a soil conditioner or other use may be less than the cost of disposing of the solid waste by use of an alternate technology.

Odors

One of the primary concerns always expressed when composting is under consideration is the potential odor problem. The simple fact is that almost all composting facilities experience odor problems to one degree or another, and the reason is also simple. It is almost impossible to maintain aerobic conditions throughout the entire composting mass all the time. When pockets of anoxic or anaerobic conditions develop, odors are produced. Whether the odors result in a problem depends on how the potential for odor generation is managed, and how the odors that finally do get generated are managed. The most important management activity is to do everything reasonably practicable to prevent odors from being generated. This means to managing the piles or windrows to maintain optimum oxygen, temperature, and moisture conditions. For those odors that do get generated despite all management efforts, there are, generally, two control strategies: (1) containment and treatment, and (2) “reodorization” (masking) before release.

Containment and treatment have been successfully accomplished by conducting the composting process in an enclosure that is maintained under a negative pressure. The exhaust from the air withdrawal system is treated by use of a scrubber or flare. Figure 9-16 illustrates the containment and treatment approach to odor management.

Reodorization, or “masking,” can be accomplished by use of the same containment facility as is illustrated in Figure 9-16 for containment and treatment. The difference is that a masking agent is added to the exhaust stream when it is needed. Another approach is to add the masking agent to the air stream that is blown into the composting mass if this is the method used to manage the oxygen concentration within the pile. Several masking agents are used for this purpose, most of which are proprietary. Still another approach that has been successful is to use a misting system to dispense a masking agent onto the compost pile. Figure 9-17 illustrates a misting system that has been used

successfully to manage odor problems at compost facilities.

Other candidates for application of composting technology for treating solid wastes from industry include meat-processing wastes, feed lot wastes, vegetable-processing wastes, and fish-processing wastes.

Solidification and Stabilization of Industrial Solid Wastes

Solid wastes from industries, including both fly ash and bottom ash from combustion processes, can sometimes be conveniently, safely, and cost-effectively stabilized by one or more of the processes that are characterized as “solidification and stabilization” (S/S). In this context, “safely” refers to compliance with all laws and regulations, as well as with respect to potential harm to people or the environment. “Stabilized” refers to transformation of a substance from a form in which it is leachable, hazardous, or otherwise objectionable, to a




Figure 9-16 Illustration of containment for odor control.




Figure 9-17 Dispensing system for odor-masking agent.

form in which it cannot be leached, vaporized, or enter into a reaction with another substance.

Solidification and stabilization (S/S) technologies are used to convert the solid waste, with or without the free-flowing liquid associated with it, to a state such that it can be land-filled or otherwise applied to the land without danger of forming unacceptable leachate or gas. Several technologies can be used, depending on the characteristics of the waste material.

It is a problem, regarding S/S methods of solid waste treatment before disposal, that laws and regulations are ever-changing. It can be said that if the S/S product can "pass" all applicable tests, such as the Paint Filter Liquids Test (PFLT) and the Toxic Characteristic Leaching Procedure (TCLP), it is "safe" to be disposed of in an approved landfill; however, the criteria for passing those tests, as well as the procedures of the tests themselves, have been changing over time; thus, the moving target problem. Nevertheless, certain industrial solid wastes, having certain hazardous or otherwise objectionable characteristics, can be treated using certain S/S techniques, which would seem essentially certain to comply with any present or future acceptance testing procedure. For instance, the objectionable characteristic of certain industrial solid wastes that contain formaldehyde is that the formaldehyde, which is toxic, can be leached out by water to represent a threat of groundwater pollution. If the solid waste mass can be treated by mixing it with phenol (another toxic substance) to produce (stoichiometrically) a "phenol-formaldehyde resin," then the resin is extremely insoluble, and that which does dissolve is relatively inert and nontoxic. Whether such a treatment process can be reliably and cost-effectively (in the context of alternatives) carried out largely depends on the characteristics of the solid waste.

A second problem regarding S/S methods for treatment of solid wastes before landfilling is that additional volume is added. As "air space" at approved landfills increases in its already high value, this consideration will increase in importance.

Notwithstanding the moving target problem, several S/S technologies warrant serious consideration, which means a very close examination of the characteristics of the solid waste and the characteristics of the S/S product. The feasibility of using any given S/S technology for treatment before disposal of a given solid waste stream must be closely evaluated using a four-step process:

1. Evaluate the likelihood of successful application of each alternative S/S technology on a theoretical basis (basic chemistry and physics). This evaluation should include a thorough search to determine whether any of the available alternative S/S technologies have been used successfully on a similar waste stream at another location.
2. Perform bench scale tests using those technologies that appear promising. Testing must include all product evaluation tests, such as TCLP and PFLT procedures, where applicable.
3. Perform pilot plant evaluations using those S/S technologies having the most favorable bench scale tests. Include product evaluation tests.
4. Perform a detailed preliminary design of the prototype treatment system(s). A thorough and detailed cost opinion analysis must be included.

There are at least three systems by which S/S technologies are categorized:

1. By process system
2. By binder used
3. By S/S mechanism

S/S Process Systems

There are at least four systems in use to accomplish S/S treatment of industrial waste streams: (1) in the 55-gallon drum in which the waste materials to be treated have been collected; (2) in a specially designed and constructed facility to carry out the S/S process on site; (3) in a mobile facility; or (4) in a sludge pit or lagoon or other collection facility of the solid waste stream.

In the case of the “in-drum” system, treatment chemicals or binders are added directly into the 55-gallon steel drums used to collect the solid wastes. Stirring and reaction are carried out, and the stabilized product is often placed in a landfill or other facility still in the drum.

Specially built S/S plants, similar to incinerators, are operated either on site or at central locations. The process can be batch-type or continuous. These facilities are appropriate for large quantities of solid wastes.

In some cases, the reaction chemicals or binders are added directly into a collection tank, storage tank, or lagoon in which the target solid wastes have collected. In the case of lagoons, it might be feasible, safe, and cost effective to simply close the lagoon, under RCRA or other approved procedures, with the stabilized solid wastes remaining. This type of procedure is referred to as in situ treatment and disposal.

Binders Used for S/S Technologies

Solidification agents that have been successfully used to stabilize industrial solid wastes include both organic and inorganic substances.

Organic binding agents

- Epoxys
- Asphalt
- Urea-formaldehyde
- Polyesters
- Polyolefins

In all of these technologies, appropriate pretreatment of the solid wastes is very important.

Epoxys

Several different epoxy mixes have been used as binders for the S/S treatment of industrial wastes, including proprietary substances and procedures. Epoxys have been successfully used for S/S treatment in 55-gallon drums, as discussed earlier. Epoxys use at least two reactants; therefore, mixing must be rapid and thorough. If executed properly, the hardened epoxy

incorporates the solid waste substances within its polymerized matrix, effectively reducing by orders of magnitude the surface area of the target material that can be contacted by water, or other potential leaching liquid. Epoxys are characteristically nonreactive and are expected to prevent leaching or other reaction of the target substances for extremely long periods.

There are different types of epoxy, using different reactants and producing polymerized matrices having different chemical properties. Some are more resistant to certain organic solvents, strong acids, or caustic substances. Therefore, the most appropriate epoxy for a given application should be the subject of considerable research before a given S/S technology is selected or rejected. The results of bench scale trials should also be evaluated in light of these characteristics.

Asphalt

Many industrial solid wastes have been successfully solidified and stabilized by simply incorporating them into an asphalt mix at a conventional asphalt batch plant. In other cases, special asphalt mixes using specially designed and constructed mixing equipment have been used. Factors that must be considered include reactivity potential between the asphalt binder and any of the components of the solid waste stream, the future effects of heat on the physical integrity of the asphalt, the potential for substances that are solvents for the asphalt coming in contact with the disposed products, and the potential for wearing or abrading of the asphalt product.

Urea-formaldehyde

An epoxylike matrix can be formed by the polymerization that occurs when urea and formaldehyde are mixed in proper proportions. As with the epoxy S/S treatments discussed previously, target substances in solid wastes can be incorporated into this matrix, effectively solidifying and, thus, stabilizing the target substances. The choice between urea-formaldehyde and epoxy as the S/S treatment depends largely on potential reactions between

substances in the solid waste stream and the urea-formaldehyde mixture.

Polyesters

Several polyesters can be used for S/S treatment of certain solid waste target substances. As with epoxy and urea-formaldehyde technologies, the binding effect that polyesters can have on solid waste target substances results from incorporation of the target substances (and other substances present with the target substances) in the inner mass of the matrix that forms when the polymerization process takes place, whereby small organic ester molecules combine to produce a relatively huge monolithic mass. It is not (necessarily) that the target substances become chemically incorporated into the matrix, but rather, that the target substances become entrapped within the matrix. Being so entrapped, it is impossible for water or another dissolving or reacting substance to come in contact with the target substances. Thus, the goal of the S/S technology is accomplished.

Polyolefins

Polyethylene and polyethylene-butadiene are two polyolefins that can be used in the same way as is described for polyesters to solidify and thus stabilize certain solid waste streams. The choice between polyesters and polyolefins is, again, based on the chemical properties of the solid waste substances and the chemical and physical properties and characteristics of the environment of the disposal site. The mechanisms of stabilization are essentially the same. For example, if a solid waste is first conditioned by evaporation to dryness and grinding to a fine granular consistency, it can be mixed together with appropriate proportions of ethylene and butadiene, plus a catalyst. In the presence of the catalyst, ethylene and butadiene polymerize to form a monolithic mass. As the polymerization process takes place, the granules of solid waste material become entrapped within the polymeric mass.

Inorganic Binding Agents

- Portland cement

- Pozzolan substances
- Lime
- Gypsum
- Silicates

Portland Cement

One of the first S/S techniques to be used was to simply mix conditioned solid wastes with Portland cement, sand, and water, then allow the mixture to harden into concrete. In many cases, fly ash has been mixed in. The fly ash contains silica, thus enters into a pozzolan reaction that adds to the structure of the concrete mass. Also, the fly ash may have been a disposal problem in itself. In this case, including fly ash in the mixture with cement and another waste material has solved two hazardous waste disposal problems concurrently.

Solidification with Portland cement achieves stabilization of solid wastes by preventing water from any source—percolating rainwater or groundwater, for instance—from being able to leach substances from the solid waste because the water can no longer come into contact with the waste material. In this case, the waste material has been entrapped within a monolithic block of relatively high strength. Even if cracks eventually develop in the concrete mass, the surface area of the waste material that can be contacted by water are orders of magnitude less than before the solidification process.

At least two stabilization mechanisms are involved when Portland cement is used as the solidification agent:

- Entrapment within a monolithic mass
- Incorporation into the chemical structure of the monolithic substance

Any water that is included in the solid waste stream is taken into the structure of the concrete as the curing process takes place.

Use of Portland cement as the solidification agent, or “binder,” is relatively safe but relatively expensive. The decision to use Portland cement rather than a less expensive solution is usually made to reduce perceived future risk to a minimum.

Pozzolan Substances

Fly ash, from the burning of fossil fuels and other substances, contains fine grains of non-crystalline silica. When fly ash is mixed with lime and water, the calcium in the lime reacts with the silica from the fly ash to produce a low-strength cementlike solid substance. This reaction is referred to as a “pozzolan” reaction. Conditioned solid wastes can be mixed into the lime–fly ash–water mixture, as was described for the Portland cement S/S technology. The result is much the same, in that the target substances in the solid waste stream have become immobilized and protected from the leaching process. The reactants are less expensive, on the one hand, and one of them, the fly ash, is a solid waste in its own right. This technology, then, accomplishes treatment for safe disposal of two, or, at least portions of two, solid waste streams.

As was the case with Portland cement as the binder, at least two stabilization mechanisms are involved when the pozzolan-type solution is used:

- Entrapment within a monolithic mass
- Incorporation into the chemical structure of the monolithic substance

Any water that is included in the solid waste stream is taken into the structure of the monolithic mass as it forms via the “curing process.”

Lime

Some solid waste streams, having certain characteristics of chemical composition and moisture content, can simply be mixed with lime and allowed to dry. On drying, a low-structural-strength solid mass is formed, which has low solubility in water. Many metal ion species that were present in the waste stream will have been precipitated as the highly insoluble hydroxide, except for those metal ion species such as lead and zinc, which have lowest solubilities in the lower pH range. pH, of course, has no meaning in a solid substance; however, a metal that is precipitated as the hydroxide and is then placed in a dry environment will not dissolve into water that eventually comes into contact with

it to a degree higher than its theoretical solubility limit.

If there are significant quantities of lead and/or zinc, or other metal whose hydroxide is more soluble than desired in the solid waste stream (along with those metals that do precipitate best at high pH levels), there are at least two alternatives. One is to add a source of water-soluble sulfide ions to the lime—for instance, sodium sulfide; the second is to add a source of soluble phosphate ions—triple-superphosphate fertilizer, for instance. The sulfide or phosphate ions will precipitate those metal ions that remain in water solution after the pH has been raised to the 12 to 13 range by the solubilized lime.

The security of a lime-treated solid waste mass can be enhanced significantly by encapsulating the final product in an impermeable membrane that is either sprayed onto the surfaces and allowed to cure, or by wrapping the final product in an already formed membrane.

Gypsum

Gypsum is another relatively inexpensive substance, as is lime, that forms a solid mass on drying. Unlike lime, however, gypsum is not an alternative for treating wastes in which metal ions are among the target substances. Whereas the anion associated with lime is hydroxide, the anion associated with gypsum is sulfate. Metal sulfates are soluble in water. Gypsum is, therefore, an alternative substance for treating certain solid waste streams where incorporation into a low-structural-strength solid mass is the principle objective. Importantly, gypsum itself (calcium sulfate) is very sparingly soluble in water; therefore, those substances that were components of the original solid waste stream that are incorporated into the dried monolithic mass product are “sheltered” from contact with water. If disposed of properly, by placing in a suitable burial facility, the problem of future leachate will have been solved.

Silicates

Another category of substances—the silicates—can be mixed as a liquid with properly

conditioned solid wastes, then, on drying, form a monolithic matrix that is:

- Insoluble in water and water repellent
- Relatively inert regarding reaction with most chemical substances
- Stable over time
- Capable of incorporating the target substances into its monolithic mass

An advantage of the silicates compared to pozzolans, lime, and gypsum is that the silicates form a gel that is pliable and, therefore, resistant to cracking if physically deformed. The basic objective of treatment is the same as for pozzolans and gypsum; that is, to make it extremely difficult, if not impossible, for water to produce leachate from the treated solid waste in the future. Treatment using silicates is different, however, from treatment with lime or Portland cement, in that metal ions will not be precipitated as a water-insoluble substance by using silicates. Therefore, silicate technology would likely not be a good choice for treatment before disposal of a solid waste stream in which metal ions are target compounds.

Mechanisms Involved in S/S Treatment Procedures

Some of the mechanisms by which individual S/S technologies accomplish stabilization of target substances in solid waste streams have been discussed in the preceding paragraphs. A more thorough discussion of these and other mechanisms is presented as follows.

To restate the overall objective of S/S treatment, it is to produce a product that can be reliably and safely disposed of, usually in an appropriate landfill, without danger of generating an objectionable leachate in the future. The mechanisms employed by the individual solidification technologies discussed previously, are as follows:

- Incorporation into a monolithic solid mass
- Precipitation of target substances to form non-leaching products

- Adsorption of target substances to form non-leaching products
- Absorption of target substances to form non-leaching products
- Adsorption of water from the solid waste mass
- Absorption of water from the solid waste mass
- Encapsulation

Incorporation into a Monolithic Solid Mass

In order for leachate to form, water must come into contact with a soluble material, dissolve an amount of that material, then continue to flow under the influence of gravity away from the solid waste material. One effective way to prevent leachate formation, then, is to make it impossible for water from outside a mass of solid waste material to contact target substances. One way this objective can be accomplished is to incorporate the target substances within a monolithic mass of an insoluble solid. Any water approaching this solid mass will be forced to flow around it, thus, never achieving contact with the target substances.

The mechanism is simple, but the objective is not. The most difficult problem has to do with all of the counterobjective activities that take place over a very long period. Destruction of the structural integrity of the monolithic solid mass, either slowly over time, or as a result of physical damage, must be prevented. The long-term effects of "natural" phenomena, such as acid rain, must be carefully considered and designed into the overall technological solution.

There are basically two ways by which target substances can be incorporated into a formed monolithic mass: (1) by chemical reaction and actual incorporation into the lattice structure of the monolithic solid as it is forming, for instance, by polymerization, and (2) by entrapment within the physical structure of the monolithic solid as it is being formed.

Precipitation of Target Substances to Form Nonleaching Products

Several alternative technologies use precipitation of target substances. As discussed earlier, using lime as a binder is one of them. Other alternatives include mixing with soluble carbonate, sulfide, or phosphate compounds, usually combined with a substance to form a monolithic solid mass.

Adsorption of Target Substances to Form Nonleaching Products

Certain adsorbents, such as activated carbon, can be mixed into a slurry of solid waste materials with the result that water is not able to desorb the target substances over time. Before this technology can be deemed appropriate for a given waste stream, however, extensive testing must be carried out to determine the degree of adsorption as well as resistance to desorption. Moreover, the optimum adsorbent is seldom selected early in the evaluation procedure. There are many different activated carbons as well as alternatives to activated carbon. There are also many different chemical characteristics regarding the potential leaching solution that must be evaluated; for instance, different values of pH, acidity, alkalinity, oxidation-reduction potential (ORP), and TDS content, to name a few.

Absorption of Target Substances to Form Nonleaching Products

Regarding S/S technologies, certain materials can absorb and hold target substances in a solid waste stream in the manner that a sponge absorbs and holds water. This technology type has potential application when the target substances within a solid waste stream are part of the liquid portion of the stream.

Adsorption of Water From the Solid Waste Mass

In some cases, activated carbon, or another adsorbent, has been used to adsorb water from a solid waste mass to change its physical characteristics to a more manageable state.

Substances that are dissolved in the water are often incorporated into the bulk activated carbon (or other adsorbent) product, and must be dealt with appropriately. One alternative for this requirement is incineration to destroy the adsorbed target substances and to reactivate and recover the activated carbon for extended use.

Absorption of Water from the Solid Waste Mass

Materials that are capable of absorbing water from a solid waste stream have been used for two purposes: (1) to prepare the solid waste for further treatment in a less wet state, and (2) to isolate target substances that are dissolved in the water phase of the solid waste stream. Once absorbed into the absorbing material, that material can be further processed by treating the material, the water, and the dissolved target substances as a whole, or by physically removing the absorbed water phase, then treating that liquid for recovery (for reuse), fixation, or destruction of the target pollutants.

Encapsulation

Encapsulation prevents contact between water and target substances by forming a physical impermeable barrier around a volume of solid waste, or a volume of solid waste that has been treated using one of the technologies discussed earlier. Alternative methods for encapsulation include wrapping a volume of the treated or "raw" solid waste in a membrane of high-density polyethylene (HDPE) or other material; spraying one of the commercially available products that then polymerizes to form a seamless, impermeable coat; or dipping a volume of treated or "raw" solid waste in a solution that will then polymerize to form a seamless, impermeable coating.

Bibliography

Archinger, W.C., and L.E. Daniels, "An Evaluation of Seven Incinerators," Proceedings of National Incinerator Conference, American Society of Mechanical Engineers, New York, 1970.

- ASHRAE *Handbook and Product Directory*, American Society of Heating, Refrigerating and Air Conditioning Engineers, New York, 1977.
- Baron, J.L., et al., *Landfill Methane Utilization Technology Workbook*, CPE-8 101, U.S. Department of Energy, Washington, D.C., 1981.
- Baumeister, T. (ed.), *Marks Standard Handbook for Mechanical Engineers*, 8th Ed., McGraw-Hill, New York, 1978.
- Brunner, D.R., and D.J. Keller, "Sanitary Landfill Design and Operation," U.S. Environmental Protection Agency, Report No. SW65ts, Washington, D.C., 1972.
- Campbell, J.A., "Waste Fuel Densification: Review of the Technology and Application," *Proceedings of the International Conference on Prepared Fuels and Resource Recovery Technology*, Argonne National Laboratory, ANL/CNSV-TM-60, Argonne, Illinois, 1981.
- Canter, L.W., and R.C. Knox, *Groundwater Pollution Control*, Lewis Publishers, Chelsea, Michigan, 1985.
- Corbitt, R.A., *Standard Handbook of Environmental Engineering*, 2nd Ed. McGraw-Hill, New York, 1999.
- Freeman, H.M. (ed.), *Standard Handbook of Hazardous Waste Treatment and Disposal*, McGraw-Hill, New York, 1989.
- General Electric, *Solid Waste Management: Technology Assessment*, Schenectady, New York, 1975.
- Hasselriis, F., et al., "Eco-Fuel II: The Third Generation," *Proceedings of the International Conference on Prepared Fuels and Resource Recovery Technology*, Argonne National Laboratory, ANL/CNSV-TM-60, Argonne, Illinois, 1981.
- Hasselriis, F., *Refuse Derived Fuel Processing*, Butterworth-Heinemann, Woburn, Massachusetts, 1984.
- Hollander, H.I., and W.A. Sanders II, "Biomass: An Unlimited Resource," *Consulting Engineer*, vol. 55, Barrington, Illinois, 1980.
- Keitz, E., "Profile of Existing Hazardous Waste Incineration Facilities and Manufacturers in the United States," U.S. Environmental Protection Agency, EPA 600/2-84/052, Cincinnati, Ohio, 1984.
- Landfill Leachate Clogging of Geotextile (and Soil) Filters*, Risk Reduction Engineering Laboratory, EPA/600/2-91/025, Cincinnati, Ohio, 1991.
- Lawrence Berkeley Laboratory, *Characterization of Solid Waste Conversion and Cogeneration Systems*, U.S. Department of Energy, DOE/EV-0105, Washington, D.C., 1980.
- Metcalf and Eddy, Inc., revised by G. Tchobanoglous and F.L. Burton, *Wastewater Engineering: Treatment, Disposal, and Reuse*, 3rd Ed., McGraw-Hill, New York, 1991.
- Mitchel, G., et al., *Small-Scale and Low-Technology Resource Recovery Study*, U.S. Environmental Protection Agency, Washington, D.C., 1979.
- MSW Management*, p. 44, March/April 1996.
- National Academy of Sciences of the National Research Council, *The Recovery of Energy and Materials from Solid Waste*, National Academy Press, Washington, D.C., 1981.
- National Center for Resource Recovery, *Waste-to-Energy Compendium*, DOE/CE/20167-05, U.S. Department of Energy, Washington, D.C., 1981.
- Niessen, W.R., "Evaluating Gasification and Advanced Thermal Technologies for Processing MSW," *Solid Waste Technologies*, September/October, 1996.
- Niessen, W.R., and S.H. Chansky, "The Nature of Refuse," *Proceedings of National Incinerator Conference*, American Society of Mechanical Engineers, New York, 1970.
- Pope, K., "Europe's Landfill Alternative," *Solid Waste Technologies*, June 1999.
- Reilly, T.C., and D.L. Powers, "Resource Recovery Systems, Part 2: Environmental, Energy and Economic Factors," *Solid Wastes Management*, New York, June 1980.
- Schroeder, P.R., A.C. Gibson, J.M. Morgan, and T.M. Walski, "The Hydrologic Evaluation of Landfill Performance (HELP) Model, Volume 1—Users Guide for Version I (EPA/530-SW-84-009), and Volume II—Documentation for Version I (EPA/530-SW-84-010),"

- U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi, 1984.
- Schroeder, P.R., et al., "The Hydrologic Evaluation of Landfill Performance (HELP) Model," U.S. Environmental Protection Agency, U.S. Army Engineer Waterways Experiment Station, Vicksburg, Mississippi, 1988.
- Schroeder, R.L., et al., "Raytheon Service Company Experience and Programs in Resource Recovery," Proceedings of the International Conference on Prepared Fuels and Resource Recovery Technology, Argonne National Laboratory, ANL/CNSW-TM-60, Argonne, Illinois, 1981.
- Shepherd, K.R., "RDF Fuels in a Waste-To-Energy System—The Teledyne National Experience," Proceedings of the International Conference on Prepared Fuels and Resource Recovery Technology, Argonne National Laboratory, ANL/CNSV-TM-60, Argonne, Illinois, 1981.
- Sommerlad, R.E., "Considerations Affecting Dedicated Boiler Design for Refuse Derived Fuels (RDF)," Proceedings of the International Conference on Prepared Fuels and Resource Recovery Technology, Argonne National Laboratory, ANL/CNSV-TM-60, Argonne, Illinois, 1981.
- Tchobanoglous, G., H. Theisen, and R. Eliasen, *Solid Wastes: Engineering Principles and Management Issues*, McGraw-Hill, New York, 1977.
- Theodore, L., and J. Reynolds, *Introduction to Hazardous Waste Incineration*, Wiley-Interscience, New York, 1987.
- Tittlebaum, M.E., "Organic Carbon Content Stabilization Through Landfill Leachate Recirculation," *Journal of the Water Pollution Control Federation*, vol. 54, no. 5, Washington, D.C., 1982.
- U.S. Environmental Protection Agency, *Design and Construction of RCRA/CERCLA Final Covers*, Office of Research and Development, EPA 625/4-91/025, Washington, D.C., 1991.
- U.S. Environmental Protection Agency, *Design, Construction and Evaluation of Clay Liners for Waste Management Facilities*, Office of Solid Waste and Emergency Response, EPA 530/SW-88/007F, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, *Development Document for Proposed Effluent Limitations Guidelines and Standards for the Landfills Category*, EPA 821-R-97-022, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, *Economic and Cost-Effectiveness Analysis for Proposed Effluent Limitations Guidelines and Standards for the Landfills Category*, EPA 821-B-97-005, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, *Environmental Assessment for Proposed Effluent Limitations Guidelines and Standards for the Landfills Category*, EPA 821-B-97-007, Washington, D.C., 1997.
- U.S. Environmental Protection Agency, *Guide to Technical Resources for the Design of Land Disposal Facilities*, Risk Reduction Engineering Laboratory, Center for Environmental Research Information, EPA 625/6-88/018, Cincinnati, Ohio, 1988.
- U.S. Environmental Protection Agency, *Guide to the Disposal of Chemically Stabilized and Solidified Waste*, SW-872, Cincinnati, Ohio, 1980.
- U.S. Environmental Protection Agency, *Handbook—Remedial Action at Waste Disposal Sites* (revised), EPA 625/6-85/006, Washington, D.C., January, 1987.
- U.S. Environmental Protection Agency, *Interim Standards for Owners and Operators of New Hazardous Waste Land Disposal Facilities*, Code of Federal Regulations, Title 40, Part 267, U.S. Governmental Printing Office, Washington, D.C., 1981.
- U.S. Environmental Protection Agency, *Management of Hazardous Waste Leachate*, Municipal Environmental Research Laboratory, SW-871, Cincinnati, Ohio, 1980.
- U.S. Environmental Protection Agency, *Procedures Manual for Groundwater Monitoring at Solid Waste Disposal Facilities*, EPA 530/SW-611, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Process Design Manual for Sludge Treatment and Disposal*, EPA 625/1-74/006, Washington, D.C., 1974.

- U.S. Environmental Protection Agency, *Protecting Health and Safety at Hazardous Waste Sites: An Overview*, Technology Transfer, EPA 625/9-85/006, Cincinnati, Ohio, 1985.
- U.S. Environmental Protection Agency, *Protection of Public Water Supplies from Ground-Water Contamination*, Center for Environmental Research Information, EPA 625/4-85/016, Cincinnati, Ohio, 1985.
- U.S. Environmental Protection Agency, *Refuse-Fired Energy Systems in Europe: An Evaluation of Design Practices, An Executive Summary*, Publication SW 771, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, *Requirements for Hazardous Waste Landfill Design, Construction and Closure*, Center for Environmental Research Information, Office of Research and Development, EPA/625/4-89/022, Cincinnati, Ohio, 1989.
- U.S. Environmental Protection Agency, *Technical Guidance Document: Final Covers on Hazardous Waste Landfills and Surface Impoundments*, Office of Solid Waste and Emergency Response, EPA 530-SW-89 047F, Washington, D.C., 1999.
- U.S. Environmental Protection Agency, *Statistical Support Document for Proposed Effluent Limitations Guidelines and Standards for the Landfills Category*, EPA 821-B-97-006, Washington, D.C., 1997.
- Velzy, C.O., "Energy from Waste Plants—An Overview of Environmental Issues," Presented at the Third U.S. Conference of Mayors/National Resource Recovery Association Conference, Washington, D.C., 1984.
- Velzy, C.O., "State of the Art of Emissions Control," Presented at New York Academy of Sciences, New York, 1984.
- Velzy, C.O., "The Enigma of Incinerator Design," *Incinerator and Solid Waste Technology*, ASME, New York, 1975.
- Velzy, C.R., and C.O. Velzy, "Incineration," Sec. 7, *Marks' Standard Handbook for Mechanical Engineers*, 8th ed., McGraw-Hill, New York, 1978.
- Vence, T.D., and D.L. Powers, "Resource Recovery Systems, Part 1: Technological Comparison," *Solid Wastes Management*, New York, 1980.
- Vesiland, P.A., and A.E. Rimer, *Unit Operations in Resource Recovery Engineering*, Prentice-Hall, Englewood Cliffs, New Jersey, 1981.
- White, T.M., V.M. Grace, and W.A. Freivald, "Leachate Evaporation Using Landfill Gas," *Solid Waste Technologies*, May/June, 1996.
- Wilson, E.M., et al., *Engineering and Economic Analysis of Waste to Energy Systems*. U.S. Environmental Protection Agency, EPA-600/7-78-086, Washington, D.C., 1978.

10 Methods for Treating Air Discharges from Industry

Control of the discharges of air pollutants from industries can be organized into three categories:

1. Reduction at the source
2. Containment
3. Removal by use of one or more treatment technologies

Reduction at the Source

Reduction at the source, as an integral part of a pollution prevention program, is the preferred control method. Reduction at the source can be accomplished by the following:

- Identifying each and every source within the entire industrial facility. This must include the full range of air pollutant generation activities, from the boilers used for hot water and space heating, to each separate manufacturing process step, to dust blowing around the parking lot.
- Substituting nonpolluting process materials for those that are hazardous or otherwise objectionable.
- Maintaining vigorous maintenance and preventive maintenance programs to ensure that all process equipment is generating a minimum of pollutants, that all containment facilities are performing as designed to minimize fugitive emissions, and that all treatment equipment is operating at top efficiency in terms of pollutant removal.
- Ensuring that accident and spill prevention procedures and facilities are up to date, well known to those that should know them, and reviewed and revised at regular intervals.
- Ensuring that emergency response facilities and procedures are up to date and well known.

- Maintaining a rigorous program of analyzing past spills and emergencies with the objective of determining: (1) how to prevent each and every spill event from ever happening again, and (2) how to improve responses to emergency events over past responses.

A formal Air Pollution Management Plan (APMP) is a necessity. The APMP must be a living, active document that is used often and reviewed and revised frequently. The APMP is truly the key to minimizing the cost for air pollution control.

Containment

After reduction at the source, containment is the most cost-effective method of air pollution control. Containment refers to the absence of leaks, or of any type of breach in structural integrity in buildings, ductwork, storage tanks (i.e., any location or facility from which air pollutants could enter the environment without such entrance resulting from the express intention of the environmental managers). Such unwanted discharges are called “fugitive emissions” and are the primary target of a pollutant containment program.

One of the most effective methods of containment, to prevent release of fugitive emissions, is to maintain a “negative pressure” inside buildings; that is, to maintain the atmospheric pressure inside the building at a lower value than the atmospheric pressure outside the building. This can be accomplished by, for example, use of one or more wet scrubbers installed so that air from any location within the plant must go through one of the scrubbers before reaching the outside. Induced air fans continually evacuate air from the building and

force this air to pass through the scrubbers. If the fans and scrubber systems are sized properly, occasional opening of pass doors as well as truck doors can take place without significant release of air pollutants.

Hoods and Isolation Chambers

Appropriate and effective use of hoods is important to the objective of cost minimization. Hoods and isolation chambers can prevent air pollutants from contaminating large volumes of air. It is always less expensive to treat a smaller volume of more highly concentrated pollutant than to remove the same mass of pollutant from a larger volume of air or other gas.

Fans and Ductwork

Properly designed, operated, and maintained fans and ductwork are key to successful containment of air pollutants. Fans of too low capacity allow air pollutants to drift out of the containment system at the source. Fans of too high capacity dilute the target pollutants excessively, leading to increased cost of treatment.

Treatment

Properly considered the last resort, but nonetheless the most expensive and important in terms of compliance with the law, removal of pollutants from gas streams before discharge to the air is the major subject of this chapter.

Treatment Systems for Control of Particulates

There are five methods in general use for controlling particulate emissions:

- Gravity separators
- Inertial separators
- Electrostatic precipitators
- Fabric filters
- Wet scrubbers

Gravity and inertial separators, including so-called cyclones, are dry, "no moving parts" devices. They take advantage of the relatively high specific gravity of certain types of particulate matter, including fly ash, dust, cement particles, and organic solids. Electrostatic precipitators take advantage of the electrostatic charge on the surface of particles, either present from natural phenomena or induced. Fabric filters use physical blocking and adsorption, and wet scrubbers use a liquid to entrap particulates, thus removing them from a gas stream.

Gravity Separators

Gravity separators are devices that provide quiescent conditions, thus counteracting the tendency of a particulate-laden gas stream to sweep the particulates along with it as a result of aerodynamic drag. Most gravity separators are simple, open chambers, sometimes with a mechanism at the bottom to remove collected material. As is the case with other, rather passive particulate removal devices, gravity separators are normally used as pretreatment devices, upstream of more sophisticated equipment. The greatest value of gravity separators is to prolong the life of the more sophisticated equipment. Figure 10-1 shows an example of a gravity settling device for removal of particulates as an element in an air pollution control system.

Inertial Separators

Inertial separators use the differential specific gravity between particulates and the gas that contains them. Inertial separators cause the stream of flowing gas to change directions. The inertia of the particulates, being directly proportional to the weight of each particle, causes them to resist the change in direction, thus they are propelled out of the stream. Cyclones of various designs are the most common examples of inertial separators. Some dry, venturi devices use the inertia of particulates moving along in a gas stream to effect removal. Figure 10-2 shows a drawing of a typical inertial separator.




Figure 10-1 An example of a gravity settling device for removal of particulates as an element in an air pollution control system.




Figure 10-2 Cyclone separator: example of an inertial separator. (From Buonicore and Davis, © 1992. Reprinted by permission of John Wiley and Sons, Inc.)

Electrostatic Precipitators

Electrostatic precipitators (ESPs) are more active (as opposed to passive) than gravity separators but still have no moving parts. There is, however, a constant input of energy. ESPs consist of a series of elements having an electrostatic polarity that attracts particulates because of an electrostatic charge of opposite polarity on the surfaces of the particulates. Figures 10-3(a)–(c) show, schematically, the principle of operation of ESPs.

Even though there is a naturally occurring surface charge on essentially all particles in

nature, the corona that is generated in the chambers of ESPs induces an even greater surface charge.

There are five types of ESPs in general use:

- Plate-wire precipitator
- Flat-plate precipitator
- Two-stage precipitator
- Tubular precipitator
- Wet precipitator

The wet precipitator is a variation of any of the other four types.




Figure 10-3(a) Electrostatic precipitator components. (From Buonicore and Davis, © 1992 by Van Nostrand-Reinhold. Courtesy of the Institute of Clean Air Companies and reprinted by permission of John Wiley and Sons, Inc.)




Figure 10-3(b) Electrostatic precipitator components. (From Buonicore and Davis, © 1992 by Van Nostrand-Reinhold. Courtesy of the Institute of Clean Air Companies and reprinted by permission of John Wiley and Sons, Inc.)




Figure 10-3(c) Electrostatic precipitator components. (From Buonicore and Davis, © 1992 by Van Nostrand-Reinhold. Courtesy of McGill Clean Air Corporation. Reprinted by permission of John Wiley and Sons, Inc.)

The Plate-Wire Precipitator

The plate-wire precipitator is shown schematically in Figure 10-3(b). This device consists of parallel metal plates and wire electrodes of high voltage. Voltages range between 20,000 and 100,000 volts, as required. As the particulate-laden gas flows between the parallel plates, the particulates are attracted to, and adhere to, the plates. The plates must be cleaned periodically, usually by “rapping,” and in some cases by water spray, and the wires must be cleaned of collected dust as well. The plate-wire precipitator is the most commonly used ESP by industry.

The Flat-Plate Precipitator

The flat-plate precipitator is shown schematically in Figure 10-3(c). The flat-plate ESP consists of a series of parallel flat plates in which some of the plates serve as the

high-voltage electrodes. Corona, needed to increase the surface charge on the particles to be removed, are generated in chambers preceding the ESP itself. As with wire-plate ESPs, the plates have to be cleaned periodically.

The Two-Stage Precipitator

In the two-stage precipitator, the high-voltage electrodes precede the collector electrodes, as opposed to their being arranged in parallel, as is the case with the wire-plate ESP and the flat-plate ESP. The plates are normally cleaned by spraying with water. In some instances, detergents are added to the water.

The Tubular Precipitator

The tubular precipitator is named for its shape and has its high-voltage wire coinciding with the axis of the tube. Tubular ESPs can fit into the stack because their shape is similar to

that of the stack. Tubular ESPs are cleaned with a water spray.

The Wet Precipitator

If an ESP—wire-plate, flat-plate, two-stage, or tubular—is operated with wet walls, it is properly referred to as a wet precipitator. Wet walls are used when the increase in particulate removal efficiency warrants the added cost for capital, operation, and maintenance.

Fabric Filters

Fabric filters use the mechanism referred to as “physical barrier,” aided by a degree of adsorption. Fabric woven from a wide variety of materials collects particulates from a gas that is forced through it. As a coating of filtered-out particles builds up on the surface of the filter fabric, this layer becomes an additional filter, which is usually more effective than the fabric alone. This is referred to as developing the filter (Figure 10-4). Eventually, the layer becomes so thick that the filter as a whole is too restrictive to pass the desired flow rate of gas undergoing treatment. At this point, the filter must be taken off line and either cleaned or disposed of and replaced.




Figure 10-4 Illustrates the process of “developing the filter.”

Fabric filters can be obtained in many different configurations. Figure 10-5 shows a “bag house,” which is a type of fabric filter that is used for many industrial applications.

Wet Scrubbers

Wet scrubbers, used for removal of gases and other chemicals as well as particulates, are the most common type of air pollution control in use by industries. They are also the most extensive, in terms of complexity of equipment, moving parts, requirement for controls, and operation and maintenance requirements. Wet scrubbers can be designed for a single target pollutant—for instance, particulates—but while in operation they will remove, to some degree, any other pollutant that will react with, or dissolve in, the scrubber fluid. Wet scrubbers can also be designed for multipurpose removal. For instance, a scrubber can be designed to remove both particulate matter and sulfuric acid fumes by using a caustic solution as the scrubbing fluid in a system also configured to remove particulates.

Wet scrubbers that are intended for different target pollutants have several design and construction features in common. Figure 10-6 presents a schematic drawing of a basic wet “scrubbing tower,” which has physical features that are common to wet scrubbers used for many different target pollutants.

As diagrammed in Figure 10-6, the components of a basic scrubber include a vessel, some type of packing (of which there are many different types), a fan, or blower, a reservoir for the scrubber fluid, and a pump for the fluid. There are many options for additional features and many optional configurations for the system as a whole.

Venturi Scrubbers

Venturi scrubbers are intended for removal of only particulates. Figure 10-7 shows a diagram of a venturi scrubber, which consists of a restriction in the air transport ductwork and spray nozzles located either in the restricted zone, referred to as the “throat” of the venturi, or just upstream of the throat. The throat is




Figure 10-5 Bag house air filter installation. (From Cooper and Alley, *Air Pollution Control: A Design Approach*, 2nd Edition, 1986. Reprinted by permission of Waveland Press, Inc., Prospect Heights, Illinois.)

preceded by a “converging section” and is followed by a “diverging section.” These two sections constitute the venturi.

The mechanism for removing particulates from the air stream with a venturi scrubber is as follows: As the stream of gas approaches the throat of the venturi, its velocity increases dramatically. The kinetic energy imparted by the high velocity shears the fluid sprayed into the gas stream into tiny droplets. Particulates and other substances in the gas stream become adsorbed onto the extremely large surface area of the fluid droplets. Then, as the gas stream slows down to its original velocity in the diverging section and beyond, the droplets coalesce, become too heavy to be propelled along with the gas stream, and consequently, settle out of the stream under the influence of gravity.

Venturi scrubbers have the advantage of being relatively inexpensive in terms of both first cost and costs for operation and have few, if any, moving parts other than the blower. On the other hand, venturi scrubbers are relatively low-efficiency treatment devices. They are most often used as pretreatment devices, upstream from devices with higher removal efficiency, such as packed wet scrubbers.

Tray Scrubbers

Tray scrubbers, a diagram of which is shown in Figure 10-8, are somewhat more extensive than venturi scrubbers. Tray scrubbers may be used for pretreatment or as the only treatment for certain air streams.




Figure 10-6 Schematic of a basic wet scrubber.

As shown in Figure 10-8, the basic components of a tray scrubber include a set of orifices, or nozzles, a set of trays that may be perforated, in addition to the basic components illustrated in Figure 10-8. The mechanism by which tray scrubbers remove particulates from gas streams is as follows: The orifices or nozzles direct the gas stream onto the trays, which are covered with the scrubber fluid. As the stream of gas proceeds through the orifices, the velocity of the gas increases rather suddenly. The particulates are carried by inertia into the

scrubber fluid and are thus removed from the air stream. The high velocity of the gas as it strikes the fluid-covered plates serves a second purpose, which is to cause the fluid to become frothy, greatly increasing the fluid surface area and thus particle capture efficiency.

Treatment Systems for Control of Gaseous Pollutants

Five methods are in general use for removing gaseous pollutants from gas streams:




Figure 10-7 Diagram of a venturi scrubber.

- Adsorption
- Absorption
- Condensation
- Incineration
- Biofiltration

Activated carbon is the technology in most general use for treating gas streams by the

mechanism of adsorption. Those that employ the mechanism of absorption or condensation, or both, often use wet scrubbers as the basic equipment. Incineration is normally accomplished in a chamber of more sophisticated design than either carbon columns or scrubbers, and normally requires a high degree of safety assurance technology.




Figure 10-8 Schematic drawing of a tray scrubber. (Courtesy of Sly Manufacturing Company.)

Adsorption

Removal of air pollutants by adsorption onto granules of activated carbon is an extremely effective technology for volatile organic compounds (VOCs) and other organic pollutants. It is not effective for removing most inorganic substances, however. Activated carbon is a nonreactive material with an extremely high surface-to-volume ratio. Activated carbon is normally manufactured in a two-step process: The first is to char the raw material (bituminous coal and coconut shells are examples) to eliminate hydrocarbons; the second is to heat the charred material to 750° to 950°C in the presence of steam and the absence of oxygen. The result is a very highly porous residual. Many activated carbon products have surface areas of 1,000 to

1,500 m²/gram. The highly developed system of pores accounts for the extremely large surface area, and the large surface area accounts for the highly effective adsorptive characteristic of activated carbon.

The mechanism by which adsorption works as a treatment process is explained in detail in Chapter 2. In being removed from a gas stream by adsorption, the pollutant moves from a gas phase to a solid phase, and must now be managed as a solid waste. An advantage of activated carbon is that the spent carbon can be reheated so that the adsorbed pollutants are incinerated (converted to carbon dioxide, water [vapor], and ash), and the activated carbon regenerated for reuse. With each regeneration cycle, however, a certain amount of adsorptive capacity is lost. There is always the

requirement for makeup with some portion of new activated carbon.

Activated carbon treatment systems for treating gas streams are usually configured as illustrated in Figure 10-9. Cylindrical containers referred to as “carbon columns” are filled (“packed”) with beds of activated carbon granules through which the gas stream to be treated is forced to flow by use of a blower. Very often, several containers are connected in series. The multiple container arrangement allows for a factor of safety, as well as provides a means to remove one or more columns for maintenance or bed replacement without stopping the flow of gas for longer than the time required to shunt out the column to be removed.

As the contaminated gas stream travels through the bed, adsorption of the pollutants takes place. The purified effluent gas exits the last column in the series. The portion of the bed that is closest to the inlet receives a continuous dose of concentrated pollutants and is thus driven to the point of saturation by the highest possible driving force (the

concentration gradient). Portions of the bed that are downstream of the inlet receive progressively less concentrated amounts of the pollutants. As the portions of the bed closest to the inlet become progressively saturated, a “front of saturation” moves steadily toward the outlet end. In this manner, a “concentration profile” develops and progressively moves toward the outlet end of the system, as illustrated in Figure 10-10.

Eventually, dilute concentrations of pollutants appear in the effluent. When these concentrations increase to the point of unacceptability, “break-through” is said to have occurred, and it is necessary to remove the columns from service.

One strategy for operating a gas stream treatment system as described previously is to remove the most upstream column from the series system at the occurrence of break-through, and, at the same time, to install a fresh column at the most downstream column. The carbon from the spent column can then be regenerated, or disposed of and replaced with virgin activated carbon.




Figure 10-9 Activated carbon adsorption system for removal of gaseous pollutants and other chemicals from gas streams. (From Buonicor and Davis, © 1992. Reprinted by permission of John Wiley and Sons, Inc.)




Figure 10-10 Concentration profile along adsorption column.

Adsorbents Other Than Activated Carbon

Certainly, activated carbon is the most commonly used adsorbent for treatment of gas streams for removal of gaseous pollutants. Other adsorbents that have been successfully used include a variety of resins, activated alumina, silica gel, and so-called molecular sieves. One of the primary characteristics of a good adsorbent is a high surface area per unit weight. Although no commercially available products compare to activated carbon in this respect, other characteristics in combination with reasonably high surface area per unit weight make some adsorbents useful for certain applications.

Resins

Resins are produced by inducing controlled cross-linking between certain organic

substances. Resins with a surface area of 100 to about 700 m² per gram can be produced to exhibit a high selectivity for certain substances. For instance, phenolic resins have been successfully used to remove odorous substances from air streams.

Resins can be produced in granular form such that they resemble activated carbon in physical size and shape. Resins can, therefore, be used in a packed bed configuration, using the same vessels and equipment as are used for activated carbon.

Activated Alumina

Activated alumina is produced by a specialized heat treatment of aluminum trihydrate, a primary ingredient of bauxite as it is mined. It can be obtained in granular form similar in size

and shape to activated carbon granules. Therefore, it can be directly substituted for activated carbon to use the same physical set-up and equipment. Although activated alumina is most often used to remove moisture from air, it has been used, and has potential use, for removal of certain air pollutants from gas streams that are either being discharged to the air or are being recycled. A potential use is in series with another adsorbent. Surface areas of activated alumina products are in the range of 300 m² per gram.

Silica Gel

Silica gel has been used to remove sulfur compounds from a gas stream, and to remove water from gas. It is produced by neutralizing, washing, drying, and roasting sodium silicate. It can be obtained in granular form, and as is the case with resins and activated alumina, it can be used in the same physical set-up as activated carbon. Silica gel products have surface areas of about 700 to 800 m² per gram.

Molecular Sieves

Molecular sieves have been effectively used for removing odorous chemical substances, such as hydrogen sulfide, and methyl and ethyl mercaptans from gas streams. They are crystalline substances manufactured from aluminosilicate and can be obtained in granular form and used as a substitute for activated carbon, using the same equipment in the same configuration. Molecular sieves have surface areas comparable to activated carbon. Typically, the surface area of molecular sieve products averages about 1,200 m² per gram.

Absorption

The chemical mechanism of absorption is that of dissolution. In a gas stream treatment system that employs absorption as the treatment technology, the stream of gas to be discharged to the air or recycled for reuse is brought into intimate contact with a liquid. Substances dissolve into the liquid and are thus removed from the gas stream. In some cases, the removed

substance changes in character, but in other cases it does not. Either way, the removed substance has been converted from an air pollutant to a potential water pollutant and must be dealt with further. Absorption systems, then, are not complete as treatment systems in themselves but are components of treatment systems.

The primary purpose of absorption equipment is to first, contain the pollutants, and then to maximize the opportunity for pollutants to move from the gas phase to the liquid phase. This is accomplished by maximizing the surface area of the liquid absorbent and causing the gas stream to move past as much of the liquid surface as possible. Time of contact, of course, is a major parameter.

Where the target pollutants are highly soluble in water, the liquid absorbent can be water. However, a chemical substance is usually present in the liquid absorbent that readily reacts with the target pollutant to form a product that is either highly soluble in the liquid absorbent or that forms a precipitate. For instance, sulfur dioxide, a gas at ambient temperatures, can be removed from a stream of air by contacting it with a solution of sodium hydroxide. Soluble sodium sulfate will quickly form and remain in the liquid. As another example, a stream of air containing silver sulfate in aerosol form can be contacted with an aqueous solution of sodium chloride. Insoluble silver chloride will form and remain suspended in the liquid until it is removed by an additional treatment step.

The "packed tower," an air pollution treatment system that resembles the wet scrubber system used for removal of particulates and discussed earlier, is the most common technology used for removal of gaseous (and aerosol) pollutants. The basic components of packed tower technology are illustrated in Figure 10-11.

The packed tower system, also called a "packed column," consists of the following elements:

- A vessel (tower), usually cylindrical, usually constructed of steel and coated as needed to prevent corrosion or other forms of destruction.




Figure 10-11 Schematic drawing of a packed tower absorber. (From Alley, © 1998. Reprinted by permission of McGraw-Hill, Inc.)

- Packing to promote intimate contact between molecules of target pollutants and the liquid absorbent.
- A spray distribution system to apply the liquid absorbent evenly over the entire top surface of the packing.
- A reservoir, usually at the bottom of the tower, to serve as a wet well for the pump.
- A pump to transfer liquid absorbent from the reservoir to the spray system.
- A blower to force the gas stream from its source to the packed tower and up through the packing.
- A support floor, highly perforated, to hold the packing above the reservoir to provide

a space for incoming gas (influent) to distribute itself evenly across the cross-section of the tower. It also serves as an inlet device to promote even application of the influent gas to the bottom of the column of packing. It must also allow the liquid absorbent to readily drain away from the packing.

Additional elements that are often included as components of a packed tower absorption system are the following:

- A packing restrainer to prevent the individual units of packing material from being carried up by the gas as it passes through the packing.

- A demister to prevent droplets of liquid from exiting the tower with the exiting treated gas stream.
- An overflow device to maintain the proper depth of liquid absorbent in the reservoir.
- A liquid redistributor located within the depth of the packing to collect liquid absorbent after it has flowed through a portion of the packing and redistribute it over the top surface of the next portion of packing.

A description of the operation of the packed tower is as follows: The liquid absorbent is pumped continuously from the reservoir to the spray distribution system. After being applied evenly over the top surface of the packing material, the liquid absorbent flows slowly down over the surfaces of the packing. As the gas stream, which has entered the tower in the space between the reservoir and the bottom of the packing, flows up through the packing, substances that can dissolve in the liquid do so. These substances have thus been removed from the gas stream, which continues its upward flow and exits the tower at the top. Excess moisture in the form of aerosol-size droplets or larger are trapped by the demister as the gas stream passes through.

Design parameters for a packed tower system include quantity of packing material and the flow rate capacity of the blower. These parameters, in addition to the flow rate capacity of the liquid absorbent pump, determine the time of contact between the gas stream and the absorbent. The physical characteristics of the packing material have a great effect on the mass transfer efficiency because the more thin the film of liquid absorbent as it flows down over the packing, and the more turbulent the flow of this thin film, the greater is the opportunity for each molecule of target pollutant to contact nonsaturated absorbent in which it can dissolve or otherwise interact. In the same manner, the physical characteristics of the packing material influence the characteristics of flow of the gas stream up through it. The more torturous the flow paths and turbulent the flow of the gas, the greater the opportunity is for individual molecules of target pollutant to

actually physically contact the liquid absorbent. The greater contact leads to higher removal efficiency, all other influences being equal.

Condensation

Gases can be changed to liquids by decreasing temperature, increasing pressure, or both. Thus, the mechanism by which condensation technology accomplishes air pollutant removal is based on the generalized gas law, stated as:

$$PV = nRT \quad (10-1)$$

or,

$$V = \frac{nRT}{P} \quad (10-2)$$

where:

V = Volume of a given weight of gas, or, volume /unit wt (m^3/g)

n = Number of moles of gas in the volume, V

R = Universal gas constant

P = Pressure exerted on the volume of gas

T = Absolute temperature of the gas in volume, V

which states that the volume that a given weight of gas occupies decreases as temperature decreases and pressure increases. At some point, the gas changes from the gaseous state to the liquid state, after which it no longer obeys the gas laws.

The most commonly used equipment that employs condensation technology uses temperature decrease as the mechanism. Often, water-cooled condensers are used as pretreatment devices to remove easily condensed substances (such as vapors of sulfuric acid) to protect or prolong the operating cycle times of downstream equipment. Figure 10-12 presents schematic drawings of three types of condensers used to remove gaseous pollutants from gas streams.

Incineration

The fundamental mechanism on which incineration technology for air pollution control is

based is combustion. Combustion of organic pollutants entails conversion to carbon dioxide, water, and ash. Some inorganic materials, such as sulfur and nitrogen, are often oxidized to problematic substances during the combustion process. Other inorganic materials—for instance, heavy metals—become incorporated in the ash and can add to ultimate disposal problems.

As an air pollution abatement technology, incineration is used for many purposes, including odor control, reduction of releases of hydrocarbons to the air (flares at petroleum refineries, for example), and destruction of volatile organic compounds (VOCs).

In the context of air pollution control, incinerators are of two types: thermal oxidizers and catalytic oxidizers. The difference between the two is that thermal oxidizers accomplish combustion by use of heat alone. Catalytic oxidizers, on the other hand, use a catalyst to decrease the activation energy of the combustion process, or to otherwise effect acceleration of the combustion process, and are thus able to accomplish reasonably complete combustion at significantly lower temperatures.

Thermal Oxidizers

The basic components of a thermal oxidizer for air pollution control are illustrated in Figure 10-13.

A typical thermal oxidizer consists of a combustion chamber in which the combustion process takes place; a burner, for combusting a support fuel, needed to elevate the temperature in the combustion chamber as necessary; an injection device, used to inject what is to be treated into the combustion chamber; and a flue, used to transport the treated gas stream to the discharge location.

Additional components that can be added to a thermal oxidizer include heat recovery equipment and a system to “preheat” the gas stream containing pollutants.

Catalytic Oxidizers

As explained previously, the process of catalytic oxidation is essentially the same as thermal oxidation except that a catalyst enables the combustion process to take place at lower temperatures. The advantages include less expensive construction costs for the equipment and reduced use of auxiliary fuel.




Figure 10-12 Three types of condensers for air pollution control.

A schematic drawing of a typical catalytic oxidizer is shown in Figure 10-14; a photograph of a catalytic oxidizer in operation is presented in Figure 10-15.

Biofiltration

General

The removal of air contaminants from air streams by means of dissolution of those contaminants into water, followed by biodegradation of the contaminants, has been a useful concept for control of air pollutants for many years. When a solid phase filter is used as the medium to contain both the liquid into which the contaminants dissolve and the

microorganisms to effect the biodegradation, the process is known as "biofiltration." Biofiltration has been used since the mid-1970s for treatment of malodorous compounds as well as volatile organic compounds (VOCs). This technology is applicable to the treatment of contaminated air that contains the normal concentration of oxygen and dilute concentrations of biodegradable organic gasses.

The solid phase filter is normally compost, sphagnum peat, or soil. The solid media are surrounded by a film of aqueous liquor, which is teeming with microorganisms. As the stream of contaminated air flows through the filter, the contaminants dissolve into the aqueous liquor (driven by entropy). These dissolved contaminants are then consumed as food by




Figure 10-13 Basic components of a thermal oxidizer for air pollution control. (From Freeman, © 1989. Reprinted by permission of McGraw-Hill, Inc.)




Figure 10-14 Schematic drawing of a typical catalytic oxidizer. (From Buonicore and Davis, © 1992. Reprinted by permission of John Wiley and Sons, Inc.)

the microorganisms. Carbon dioxide, water, oxidized organic compounds, and more microorganisms are the end products. When reduced sulfur compounds such as hydrogen sulfide, dimethyldisulfide, and mercaptans are present as contaminants to be removed from the stream of contaminated air, mineral acids are among the end products.

Oxygen contained in the stream of contaminated air is necessary in order to maintain aerobic conditions within the biofilter. Also, nitrogen, phosphorus, and other nutrients are required to maintain a robust microbial population. Typically, a solution of water containing sufficient nutrients is sprayed onto the biofilter to supply sufficient moisture as well as nutrients. In addition, the stream of contaminated air is humidified before it is applied to the biofilter. The drying action (by means of evaporation) of the stream of air flowing through the biofilter must be counterbalanced by the humidifier and the applied liquid spray.

Figure 10-16 presents a schematic of a typical biofilter system, which consists of a bed of filter material, an air distribution system, a system to supply nutrients, a humidifier, a blower, and ductwork. The filter material can be composed of compost material, sphagnum peat, or highly porous soil. The filter bed is typically about one meter (3 feet, or so) in depth.



Figure 10-15 Photograph of an operating catalytic oxidizer. (Courtesy of Stealth Industries, Inc.)

Design

A primary design parameter of a biofilter system is residence time (i.e., the stream of contaminated air must remain within the filter bed for sufficient time for the contaminants to dissolve into the liquid that surrounds the filter media). A second design parameter relates to the quantity of liquid to be maintained within the filter bed. If too much liquid is supplied to the bed, then the pores, or passageways, for air will be blocked, with the consequence that anoxic or anaerobic conditions will develop. If insufficient liquid is present within the filter bed, the target contaminants will not dissolve out of the air stream, with the consequence that treatment will not take place. Other design parameters include quantity and type of nutrients to be supplied, temperature control, pH control, and removal of excess liquid.

The residence time for the biofilter is a function of rate of flow of contaminated air as well as volume of filter media. Because it has been determined through operating experience that a filter bed depth of about 1 meter is optimum, the parameter of filter volume reduces to one of filter area; that is, the horizontal dimensions of the filter bed. Successful biofilter systems have filter areas that range from 100 to 22,000 ft² (10 to 2,000 m²). Flow rates of contaminated gases have ranged from 600 to 90,000 cfm (1000 to 150,000 m³/hr). These parameters are compatible with air pollutant treatment rates of 10 to 100 g/m³/hr., and surface loads of up to 16 scfm/ft² (300 m³/hr./m²). The optimal values for these parameters for any given application depend on the filter media, the concentration of pollutants, and the nature of the pollutants, as well as the temperature, pH, and alkalinity.

The nature of the filter media has a major influence on the economics of construction and operation of a biofilter system, in that the cost of operation is highly dependent on the amount of electrical energy used to blow contaminated air through the filter. The amount of electrical energy, in turn, is a function of the back pressure created by the filter. The back pressure increases with rate of flow, decrease in filter media porosity, increase in filter moisture content, and is




Figure 10-16 Schematic of a typical biofilter system.

affected by temperature. Also, increased biological growth on the filter media increases the back pressure.

Sphagnum peat is an excellent medium for biofilters. This material, when handled and installed properly, provides for extremely large surface area, allows relatively free flow of air, holds moisture well, and provides an excellent medium for the growth and maintenance of a robust microbial population. In particular, sphagnum peat harbors microbial populations that have a high percentage of fungi species, which are very effective in breaking down certain air pollutants. Sphagnum peat can be obtained in large quantities through agricultural supply outlets.

Compost material has also proved to be an effective medium for biofilters. Use of compost derived from municipal solid waste, bark, tree trimmings, and leaves has the additional benefit of avoiding the creation of more solid waste.

Eitner has developed values for parameters for filter material as follows:

- Pore volume $\geq 80\%$
- pH - between 7 and 8
- $d_{60} \geq 4$ mm
- Total organic matter content $\geq 55\%$

Operation and Maintenance

Over time, biofilter beds have undergone settling and consolidation to such an extent that

“fluffing” is required in order to avoid excess back pressure and channeling of air flow. Typically, beds have required reworking at 2-year intervals, with complete replacement every 5 to 6 years.

Routine and periodic maintenance of biofilters includes:

Daily check of major operating parameters:

- Off-gas temperature
- Off-gas humidity
- Filter temperature
- Back pressure
- Periodic check of filter moisture content and pH

When designed, operated, and maintained properly, biofilter technology offers an effective, low-cost solution to control air pollution caused by dilute concentrations of malodorous reduced sulfur compounds, certain VOCs, and many other biodegradable organics. Industries that have successfully used biofilters, worldwide, include:

- Fish rendering
- Print shops
- Pet food manufacturing
- Flavors and fragrances
- Residential wastewater treatment plants
- Landfill gas extraction
- Tobacco processing

- Chemical manufacturing
- Chemical storage
- Industrial wastewater treatment plants

Bibliography

- Alley, R.E., and Associates, Inc., *Air Quality Control Handbook*, McGraw-Hill, New York, 1998.
- Avallone, E.A., and T. Baumeister, III (eds.), *Marks' Standard Handbook for Mechanical Engineers*, 9th ed., McGraw-Hill, New York, 1987.
- Billings, C.E., and J. Wilder, *Handbook of Fabric Filter Technology, Vol. 1: Fabric Filter Systems Study*, GCA Corp., Bedford, Massachusetts; PB-200-648, NTIS, Springfield, Virginia, December 1970.
- Bilotti, J.P., and T.K. Sutherland, in *Air Pollution Control Equipment: Selection, Design, Operation and Maintenance*, L. Theodore and A.J. Buonicore (eds.), Prentice-Hall, Englewood Cliffs, New Jersey, 1982.
- Borgwardt, R.H., "Limestone Scrubbing of SO₂ at EPA Pilot Plant," Monsanto Research Company, Progress Report 12, St. Louis, Missouri, 1973.
- Buonicore, A.J., and W.T. Davis, *Air Pollution Engineering Manual*, Van Nostrand Reinhold, New York, 1992.
- Cheremisnoff, P.N., and R.A. Young (eds.), *Pollution Engineering Practice Handbook*, Ann Arbor Science, Ann Arbor, Michigan, 1975.
- Control Techniques for Sulfur Oxide Emissions from Stationary Sources*, 2nd ed., Emission Standards and Engineering Division, EPA 450/13-811064, Research Triangle Park, North Carolina, 1981.
- Control Technologies for Hazardous Air Pollutants*, U.S. Environmental Protection Agency, Office of Research and Development, EPA 625/6-91/014, Washington, D.C., 1991.
- Cooper, C.D., and F.C. Alley, *Air Pollution Control: A Design Approach*, Waveland Press, Inc., Prospect Height, Illinois, 1986.
- Crawford, M., *Air Pollution Control Theory*, McGraw-Hill, New York, 1976.
- Davis, W.T., and R.F. Kurzynske, "The Effect of Cyclonic Precleaners on the Pressure Drop of Fabric Filters," *Filtration Separation*, 16(5).
- Davis, W.T., and W.F. Frazier, "A laboratory Comparison of the Filtration Performance of Eleven Different Fabric Filter Materials Filtering Resuspended Flyash," Proceedings of the 75th Annual Meeting of the Air Pollution Control Association, 1982.
- Dennis, R., and H.A. Klemm, *Fabric Filter Model Format Change, Vol. 1: Detailed Technical Report*, EPA 600/7-79-0432, U.S. Environmental Protection Agency.
- Dennis, R., R.W. Cass, D.W. Cooper, et al., *Filtration Model for Coal Flyash with Glass Fabrics*, EPA 600-7-77-084, August 1977.
- Donovan, R.P., B.E. Daniel, and J.H. Turner, *EPA Fabric Filtration Studies, 3. Performance of Filter-Bags Made From Expanded PTFE Laminate*, EPA 600/2-76-168c, U.S. Environmental Protection Agency, Research Triangle Park, North Carolina, December 1976, NTIS PB-263-132.
- Durham, J.F., and R.E. Harrington, "Influence of Relative Humidity on Filtration Resistance and Efficiency of Fabric Dust filters," *Filtration Separation*, 8:389-393, July/August 1971.
- Eitner, D., and H.G. Gethke, "Design Construction and Operation of Bio-filters for Odor Control in Sewage Treatment Plants," 80th Annual meeting of the Air Pollution Control Association, New York, 1987.
- Ellenbecker, M.J., and D. Leith, "Dust Removal from Nonwoven Fabrics," *Annual Meeting of the Air Pollution Control Association*, Montreal, Quebec, June 22-27, 1980.
- Evaluation of the Efficiency of Industrial Flares: Test Results*, U.S. Environmental Protection Agency, EPA 600/2784/095, Washington, D.C., 1984.
- Fernandes, I.H., "Incinerator Air Pollution Control," Proceedings of National Incinerator Conference, ASME, New York, 1970.
- Frazier, W.F., and W.T. Davis, "Effects of Flyash Size Distribution on the Performance of a Fiberglass Filter," *Symposium on the*

- Transfer and Utilization of Particulate Control Technology*. Vol. II: Particulate Control Devices, EPA-600/9-82-0050c, July 1982, pp. 171-180.
- Frederick, E.R., *Electrostatic Effects in Fabric Filtration: Volume 11, Turboelectric Measurements and Bag Performance* (annotated data), EPA-600/7-78-142b, NTIS PB-287-207, July 1978.
- Freeman, H.M. (ed.), *Standard Handbook of Hazardous Waste Treatment and Disposal*, McGraw-Hill, New York, 1989.
- Greiner, G.P., J.C. Mycock, and D.S. Beachler, "The IBFM, a Unique Tool for Troubleshooting and Monitoring Baghouses," Paper 85-54.2, *Annual Meeting of the Air Pollution Control Association*, Detroit, Michigan, June 1985.
- Hotchkiss, C.B., and L.F. Cox, "Fabric and Finish Selection, Manufacturing Techniques and other Factors Affecting Bag Life in the Coal-fired Boiler Applications," Proceedings Second EPRI Conference on Fabric Filter Technology for Coal-Fired Power Plants, Electric Power Research Institute, Palo Alto, California, EPRI CS-3257, November 1983.
- Katz, J., "The Art of Electrostatic Precipitation," Precipitator Technology, Inc., Munhall, Pennsylvania, 1979.
- Ketchuk, M.M., A. Walsh, O.F. Fortune, et al., "Fundamental Strategies for Cleaning Reverse-air Baghouses," Proceedings Fourth Symposium on the Transfer and Utilization of Particulate Control Technology, Vol. 1: Fabric Filtration, EPA-600/9-84-025a, U.S. Environmental Protection Agency, Research Triangle Park, North Carolina, November 1984.
- Larson, R.I., "The Adhesion and Removal of Particles Attached to Air Filter Surface," *AIHA Journal*, 19 (1958).
- Licht, W., *Air Pollution Control Engineering*, Marcel Dekker, New York, 1980.
- Liptak, B.G. (ed.), *Environmental Engineers' Handbook, Volume II, Air Pollution*, Chilton Book Company, Radnor, Pennsylvania, 1974.
- Lund, H.F. (ed.), *Industrial Pollution Control Handbook*, McGraw-Hill, New York, 1971.
- Magill, P.L., F.R. Holden, and C. Ackley (eds.), *Air Pollution Handbook*, McGraw-Hill, New York, 1956.
- "Menard Cleaning of a Fabric Filter Dust Collector," Proceedings Fourth Symposium on the Transfer and Utilization of Particulate Control Technology, Vol. 1: Fabric Filtration, EPA 600/9-84-025a, U.S. Environmental Protection Agency, Research Triangle Park, North Carolina, November 1984.
- National Research Council, *Odors from Stationary and Mobile Sources*, Contract 68-01-4655, U.S. Environmental Protection Agency, Washington, D.C., 1979.
- Ottmers, D.M., et al., "Evaluations of Regenerable Flue Gas Desulfurization Processes," Vol. 11, Electric Power Research Institute, EPRI RP-535-1, Palo Alto, California, 1976.
- Perry, R., et al. (eds.), *Perry's Chemical Engineers' Handbook*, McGraw-Hill, New York, 1973.
- Rafson, H.J. (ed.), *Handbook of Odor and VOC Control*, McGraw-Hill, New York, 1998.
- Reisinger, A.A., and W.T. Grubb, "Fabric Evaluation Program at Coyote Unit #1, Operating Results Update," Proceedings Second EPRI Conference on Fabric Filter Technology for Coal-Fired Power Plants, Electric Power Research Institute, Palo Alto, California, EPRI CS03257, November 1983.
- Robinson, J.W., R.E. Harrington, and P.W. Spaite, "A New Method for Analysis of Multicompartmented Fabric Filtration," *Atmospheric Environment*, 1(4):499, 1967.
- Siebert, P.C., *Handbook on Fabric Filtration*, ITT Research Institute, Chicago, 1977.
- Stern, A.C. (ed.), *Air Pollution*, 3rd ed., Academic Press, New York, 1977.
- Strauss, W., *Industrial Gas Cleaning*, 2nd ed., Pergamon Press, Oxford, England, 1975.
- The Fabric Filter Manual*, C. E. Billings (ed.), McIlvaine Co., Northbrook, Illinois.
- Theodore, L., and A. Buonicore, *Industrial Air Pollution Control Equipment*, CRC Press, Cleveland, Ohio, 1976.
- U.S. Department of Health, Education and Welfare, *Recommended Industrial Ventilation Guidelines*, Publication No. (NIOSH) 76-162, Washington, D.C., 1976.

- U.S. Department of the Interior, *Methods and Costs for Stabilizing Fine-Sized Mineral Wastes*, Bureau of Mines, RI 7896, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Flue Gas Desulfurization System Capabilities for Coal-Fired Steam Generators*, Volume 11, EPA 600/7-78/032b, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Flue Gas Desulfurization: Lime/Limestone Processes*, Technology Transfer, EPA 625/8-81/006, Research Triangle Park, North Carolina, 1981.
- U.S. Environmental Protection Agency, *Fugitive Emissions from Integrated Iron and Steel Plants*, EPA 600/2-78/050, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Manual of Electrostatic Precipitator Technology*, APTD 0610, Washington, D.C., 1970.
- U.S. Environmental Protection Agency, "Standards of Performance for New Stationary Sources," Code of Federal Regulations, Title 40, Part 60, U.S. Government Printing Office, Washington, D.C., 1971–1997.
- U.S. Environmental Protection Agency, "Standards of Performance for New Stationary Sources," Code of Federal Regulations, Title 40, Part 60, U.S. Government Printing Office, Washington, D.C., 1971–1988.
- U.S. Environmental Protection Agency, *Air Pollution Engineering Manual*, 2nd ed, AP-40, Research Triangle Park, North Carolina, 1973.
- U.S. Environmental Protection Agency, *An Update of the Wellman-Lord Flue Gas Desulfurization Process*, EPA 600/2-76/136a, Washington, D.C., 1976.
- U.S. Environmental Protection Agency, *Assessment of the Use of Fugitive Emission Control Devices*, EPA 600/7-79/045, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, *Capital and Operating Costs of Selected Air Pollution Control Systems*, EPA 450/5-80/002, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Handbook Control Technology for Hazardous Air Pollutants*, Center for Environmental Research Information, EPA 625/6-86/014, Cincinnati, Ohio, 1986.
- U.S. Environmental Protection Agency, *Compilation of Air Pollutant Emission Factors*, EPA AP-42, Research Triangle Park, North Carolina, 1973.
- U.S. Environmental Protection Agency, *Continuous Emission Monitoring Systems for Noncriteria Pollutants Handbook*, Office of Research and Development, EPA 1625/R97/001, Cincinnati, Ohio, 1997.
- U.S. Environmental Protection Agency, *Control of Volatile Organic Compound Emissions from Manufacture of High-Density Polyethylene, Polypropylene, and Polystyrene Resins*, EPA 450/3-83/008, Research Triangle Park, North Carolina.
- U.S. Environmental Protection Agency, *Control of Volatile Organic Compound Leaks from Synthetic Organic Chemical and Polymer Manufacturing Equipment*, EPA 450/3-83/006, Research Triangle Park, North Carolina, 1983.
- U.S. Environmental Protection Agency, *Control of Volatile Organic Emissions from Existing Stationary Sources—Volume 1: Control Methods for Surface Coating Operations*, EPA 450/2-76/028, Research Triangle Park, North Carolina, 1976.
- U.S. Environmental Protection Agency, *Control Techniques for Nitrogen Oxides Emissions from Stationary Sources*, rev. 2nd ed., Emission Standards and Engineering Division, EPA 450/3-83/002, Research Triangle Park, North Carolina, 1983.
- U.S. Environmental Protection Agency, *Control Techniques for Particulate Emissions from Stationary Sources*, Volume 1, EPA 450/3-8 IA05a, Research Triangle Park, North Carolina, 1982.
- U.S. Environmental Protection Agency, *Enhanced Monitoring Reference Document*, Office of Air Quality and Standards, Emission Measurement Branch, Washington, D.C., 1993.
- U.S. Environmental Protection Agency, *Evaluation of Control Technologies for Hazardous Air Pollutants—Appendices*, EPA 600/7-86/0096, Washington, D.C., 1985.

- U.S. Environmental Protection Agency, *Evaluation of the Efficiency of Industrial Flares: Test Results*, EPA 600/2-84/095, Washington, D.C., 1984.
- U.S. Environmental Protection Agency, *Adipic Acid-Enhanced Lime/Limestone Test Results at the EPA Alkali Scrubbing Test Facility*, Technology Transfer, EPA 625/2-82/029, Research Triangle Park, North Carolina, 1982.
- U.S. Environmental Protection Agency, *Flue Gas Desulfurization and Sulfuric Acid Production Via Magnesia Scrubbing*, Technology Transfer, EPA 625/2-75/077, Washington, D.C., 1975.
- U.S. Environmental Protection Agency, *Flue Gas Desulfurization: Dual Alkali Process*, Technology Transfer, EPA 625/8-80/004, Research Triangle Park, North Carolina, 1980.
- U.S. Environmental Protection Agency, *Fuel Gas and Desulfurization Injections and Performance Evaluation Manual*, Energy Engineering Research Laboratory, EPA 625/1-85/019, Research Triangle Park, North Carolina, 1985.
- U.S. Environmental Protection Agency, *Fugitive and Fine Particle Control Using Electrostatically Charged Fog*, EPA 600/7-79/078, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, *Fugitive Emissions from Iron Foundries*, EPA 00/7-79/195, Washington, D.C., 1979.
- U.S. Environmental Protection Agency, *Fugitive Emissions Sources of Organic Compounds*, EPA 450/3-82/010, Research Triangle Park, North Carolina, 1982.
- U.S. Environmental Protection Agency, *Fugitive VOC Emissions in the Synthetic Organic Chemicals Manufacturing Industry*, Office of Air Quality Planning and Standards, EPA 625/10-84/004, Research Triangle Park, North Carolina, 1984.
- U.S. Environmental Protection Agency, *Guidelines for Development of Control Strategies in Areas with Fugitive Dust Problems*, EPA 450/12-77/029, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Handbook of Fabric Filter Technology*, APTD-0690, Research Triangle Park, North Carolina, 1970.
- U.S. Environmental Protection Agency, *Handbook—Control Technologies for Hazardous Air Pollutants*, Office of Research and Development, EPA 625/6-86/014, Cincinnati, Ohio, 1986.
- U.S. Environmental Protection Agency, *Handbook—Control Technologies for Hazardous Air Pollutants*, EPA 625/6-86/014, Cincinnati, Ohio, 1986.
- U.S. Environmental Protection Agency, *Handbook—Permit Writer's Guide to Test Burn Data—Hazardous Waste Incineration*, EPA 625/6-86/012, Cincinnati, Ohio, 1986.
- U.S. Environmental Protection Agency, *Industrial Guide for Air Pollution Control*, Technology Transfer, EPA 625/6-78/004, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Inspection Manual for Evaluation of Electrostatic Precipitator Performance*, EPA 340/1-79/007, Washington, D.C., 1981.
- U.S. Environmental Protection Agency, *Investigation of Fugitive Dust—Volume I: Sources, Emissions and Control*, EPA 450/3-74/036a, Washington, D.C., 1974.
- U.S. Environmental Protection Agency, *Operation and Maintenance Manual for Electrostatic Precipitators*, Air and Energy Engineering Research Laboratory, EPA 625/1-85/017, Research Triangle Park, North Carolina, 1985.
- U.S. Environmental Protection Agency, *Operation and Maintenance Manual for Fabric Filters*, Air and Energy Engineering Research Laboratory, EPA 625/1-86/020, Research Triangle Park, North Carolina, 1986.
- U.S. Environmental Protection Agency, *Organic Air Emissions from Waste Management Facilities*, Center for Environmental Research Information, EPA/625/R-92/003, Cincinnati, Ohio, 1992.
- U.S. Environmental Protection Agency, *Organic Chemical Manufacturing, Volume 4: Combustion Control Devices*, EPA 450/3-80/026, Washington, D.C., 1980.
- U.S. Environmental Protection Agency, *Particulate Control by Fabric Filtration on*

- Coal-Fired Industrial Boilers*, Industrial Environmental Research Laboratory, EPA 625/2-79/021, Research Triangle Park, North Carolina, 1979.
- U.S. Environmental Protection Agency, *Physical Coal Cleaning for Utility Boiler SO₂ Emission Control*, EPA 600/7-78/034, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Procedures Manual for Fabric Filter Evaluation*, EPA 600/7-78/113, Washington, D.C., 1978.
- U.S. Environmental Protection Agency, *Regulatory Options for the Control of Odors*, EPA 450/5-85/003, Research Triangle Park, North Carolina, 1980.
- U.S. Environmental Protection Agency, *Standards Support and Environmental Impact Statement Volume I: Proposed Standards of Performance for Grain Elevator Industry*, EPA 450/2-77/001a, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Technical Guidance for Development of Control Strategies in Areas with Fugitive Dust Problems*, EPA 450/3-77/010, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Technical Guide for Review and Evaluation of Compliance Schedules*, EPA 3401I-73/00 1a, Washington, D.C., 1973.
- U.S. Environmental Protection Agency, *Wet Scrubber Handbook*, EPA R/72/118a, Research Triangle Park, North Carolina, 1972.
- U.S. Environmental Protection Agency, *Wet Scrubber Performance Model*, EPA 600/2-77/127, Washington, D.C., 1977.
- U.S. Environmental Protection Agency, *Wet Scrubber System Study*, EPA R2/72/118a, Research Triangle Park, North Carolina, 1972.
- Vesilind, P.A., and J.J. Pierce, *Environmental Engineering*, Ann Arbor Science, Ann Arbor, Michigan, 1982.
- Zimon, A.D., *Adhesion of Dust and Powder*, Plenum Press, New York, 1969, p. 112.

Index

A

- A/S (air-to-solids) ratio, 375
- Above-ground storage tanks (ASTs), 164
- Absorbent, 376
- Absorption, 449–551
- Accounting system, accurate cost, 211
- Acid Dip, 67
- Acidity, 185
- Activated alumina, 448–49
- Activated carbon, 376–81
- Activated carbon, adsorbents other than, 448–49
- Activated sludge, 265
 - aeration systems for, 283–97
 - contact stabilization modification of, 276
 - extended aeration, 276
 - high-rate modification of, 276
 - PACT modification of, 274
- Activated sludge process, variations of, 270
- Activated sludge systems, characteristics of, 283
- Adsorbents other than activated carbon, 448–49
- Adsorption, 376–81, 446–47
- Adsorption equilibria, 376–81
- Aerated lagoons, 297–98
- Aeration activated sludge, extended, 276
- Aeration, deep shaft, 280–82
- Aeration systems for activated sludge, 283–97
- Aerobic technologies, 265–310
- AFFI (American Frozen Food Institute), 77, 79, 81–83
- Agents
 - inorganic binding, 430–32
 - inorganic chelating, 248
 - mixtures made stable by chelating, 44
 - organic binding, 429–30
 - organic chelating, 248
 - reaction to destroying or deactivating chelating, 247–48
- Air
 - characteristics of discharges to, 192–97
 - sample collection, 193–97
 - stack sampling, 193
 - management of discharges to, 20–28
 - analysis of manufacturing processes, 20–25
 - bench scale investigations, 26
 - economic comparisons, 28
 - pilot scale investigations, 26–27
 - preliminary designs, 27–28
 - selection of candidate technologies, 26
 - treatment objectives, 26
 - wastes minimization and characterization study, 25–26
 - quantity of, 375
- Air discharges from industry, treating, 437–60
 - containment, 437–38
 - fans and ductwork, 438
 - hoods and isolation chambers, 438
 - reduction at source, 437
 - treatment, 438
- Air-dissolving system, optimum pressure for, 375–76
- Air in water, dissolution of, 369–73
- Air pollutants, 198–200
- Air pollution control (APC), 106, 155
 - law as of Year 2000, 56
 - laws, 55–60
- Air Pollution Management Plan (APMP), 437
- Air sampling, ambient, 198–201
 - air pollutants, 198–200
 - malodorous substances, 200–201
 - sampling methods for air toxics, 201
- Air-to-solids (A/S), ratio, 375
- Air toxics, 198
 - sampling methods for, 201
- Alkaline chlorination of cyanide, 239
- Alkalinity, 185
- Alodizing, anodizing and, 99–100
 - waste treatment and disposal, 103
 - wastes generation, 100–101
 - wastes minimization, 101–3
- Alternative landfills, 408–9
- Aluminum die casting, 93–95
- Ambient air sampling, 198–201
- American Frozen Food Institute (AFFI), 77, 79, 81–83

American Society for Testing Materials (ASTM), 62
 American Society of Civil Engineers (ASCE), 293
 Anaerobic contact reactors, 318
 Anaerobic digesters, mixed, heated, 317–18
 Anaerobic lagoons, 322
 Anaerobic metabolism, mechanisms of, 312–16
 Anaerobic suspended growth systems, 316–18
 Anaerobic technologies
 development of, 312
 using, 310–22
 Anaerobic treatment systems, variations of, 316
 Analysis, sample, 198
 Annualized costs, 15–16
 Anodizing and alodizing, 99–100
 waste treatment and disposal, 103
 wastes generation, 100–101
 wastes minimization, 101–3
 APC (air pollution control), 106, 155
 law as of Year 2000, 56
 laws, 55–60
 APMP (Air Pollution Management Plan), 437
 ASCE (American Society of Civil Engineers), 293
 Asphalt, 429
 ASTM (American Society for Testing Materials), 62
 ASTs (above-ground storage tanks), 164
 Attached growth systems, 301–2
 Audit
 waste, 215–16
 wastes, 166
 Audit, Environmental, 166, 172–79

B

Bags, Tedlar, 193
 Bar racks, 323
 Barriers, separation using physical, 322–33
 Batteries, manufacture of lead acid, 138–44
 wastes generation, 141–42
 wastes minimization, 142–43
 wastewater treatment, 143–44
 Battery manufacture, lead, 138–41
 Bayer Reaction, 102
 Bed, fluidized, 310
 Bed reactors
 expanded, 319–20
 fluidized, 320–21

 packed, 321
 Bed technology, fluidized, 409–12
 Beef, production and process of, 124–25
 production processes, 126
 treatment and disposal, 128–30
 wastes generation, 126–27
 wastes minimization, 127–28
 Bench scale investigations, 4–6, 26
 Best management practices (BMPs), 150–51
 BET isotherms, 378
 Bids for construction, competitive, 17–18
 Binders used for S/S technologies, 429–32
 Binding agents
 inorganic, 430–32
 organic, 429–30
 Biofiltration, 453–56
 Biological degradable substances, 247
 Biological oxygen demand (BOD), 154–55,
 159, 164, 179–83, 262, 279, 301
 Biological treatment, 255
 of industrial wastes, 256–62
 kinetics in laboratory, 258–61
 technologies, 262–322
 BMPs (best management practices), 150–51
 BOD (biological oxygen demand), 154–55,
 159, 164, 179–83, 262, 279, 301
 BOD test considerations, 300–301
 BOD₅ (biological oxygen demand), 79, 81–83,
 127
 Body feed, 339–41
 Bonding, hydrogen, 37–38
 Breakpoint chlorination, 238
 Bulking sludge, 268–70

C

CAA (Clean Air Act), 61, 198
 Candidate technologies, selection of, 4
 Carbamates, 235
 uses in metals removal, 235
 Car bottom gasification furnaces, 420–21
 Carbon, adsorbents other than activated, 448–49
 Carbon monoxide (CO), 199
 Carbon products, effectiveness among different,
 381
 Catalytic oxidation, 254
 Catalytic oxidizers, 452–53
 Caustic, 62
 CBOD (carbonaceous BOD), 300–301

- Cellulose manufacturing plant, pretreatment for microcrystalline, 8–10
 - Cement, Portland, 430
 - Centrifugal force, 194
 - Centrifugation, 365–67
 - Chambers, hoods and isolation, 438
 - Chelating agents
 - inorganic, 248
 - mixtures made stable by, 44
 - organic, 248
 - reaction to destroying or deactivating, 247–48
 - Chemical descaling, 61–62
 - Chemical methods of wastewater treatment, 230–55
 - reaction to produce insoluble solids, 230–38
 - Chemical oxygen demand (COD), 183
 - Chemical structure and polarity of water, 36–37
 - Chlorides, 192
 - Chlorination of hydrogen sulfide, 253
 - Chlorine demand, 191–92
 - Chlorine residual, 191–92
 - Clarifier-thickeners
 - design calculations, 354–61
 - design criteria for, 349–54
 - Clean Air Act (CAA), 61, 198
 - Clean Water Act (CWA), 61, 172, 179, 186
 - CMR (completely mixed mode), 318
 - CO (carbon monoxide), 199
 - Coacervation, 245
 - Co-precipitation, 253
 - CO₂ (carbon dioxide), 199, 256
 - COD (chemical oxygen demand), 183
 - Coke, production and processing of, 103–7
 - air pollution control, 106
 - coking process, 103–5
 - sources of wastes, 105–6
 - wastes minimization, 106
 - wastewater treatment, 106–7
 - Coking process, 103–5
 - Colloidal suspensions, 43–44
 - producing coagulation of, 239–47
 - Colloidal waste systems, coagulation of, 244–47
 - Colloids, lyophobic, 244–45, 245–47
 - Color, 186
 - Companywide philosophy of waste minimization, 211–12
 - Competitive bids for construction, 17–18
 - Completely mixed mode (CMR), 318
 - Composting industrial wastes, process of, 421–27
 - mechanical composting technology, 425–26
 - windrow composting technology, 423–25
 - Composting, suitability of waste for, 400
 - Composting technology
 - mechanical, 425–26
 - windrow, 423–25
 - Compounds, disadvantages of treatment by
 - production of insoluble, 236
 - Condensation, 194, 451
 - Constituent equalization, 226
 - Construction, competitive bids for, 17–18
 - Contact reactors, anaerobic, 318
 - Containers, evacuated collection, 193
 - Contamination, prevention of groundwater, 151–52
 - Control laws
 - air pollution, 55–60
 - groundwater pollution, 52–55
 - Control subsystems, two, 230
 - Conventional complete mix, 273–74
 - Conventional landfill, 400
 - Conventional plug flow, 270–72
 - Copper-forming industry, 74–77
 - copper forming process, 74–76
 - wastes generation, 76–77
 - Copper forming process, 74–76
 - Cost accounting system, accurate, 211
 - Costs, annualized, 15–16
 - Covalent bond, 35–7
 - Crabmeat, use of, 235–36
 - CWA (Clean Water Act), 61, 172, 179, 186
 - Cyanide, alkaline chlorination of, 239
- ## D
- DAF (dissolved air flotation), 128, 137, 154, 369, 373–74
 - De-inking, wastes from, 86–93
 - De-inking process - wastes generation, 88–89
 - wastes generation and wastes minimization, 89
 - wastes minimization, 92
 - wastewater characteristics, 89–92
 - wastewater treatment, 92–93
 - Deep bed granular filters, 333
 - Deep shaft aeration, 280–82
 - Degreasing, 62–64
 - Department of Transportation (DOT), 201
 - Descaling, chemical, 61–62
 - Desmutting, 67

Die casting, 93–99

- additional waste management considerations, 98–99
- aluminum, 93–95
- magnesium, 93, 95
- waste management, 95–98
- waste streams, 95–98
- zinc, 93, 95

Digesters, mixed, heated anaerobic, 317–18

Discharges to air, characteristics of, 192–97

- sample collection, 193–97
- stack sampling, 193

Discharges to air, management of, 20–28

- analysis of manufacturing processes, 20–25
- bench scale investigations, 26
- economic comparisons, 28
- pilot scale investigations, 26–27
- preliminary designs, 27–28
- selection of candidate technologies, 26
- treatment objectives, 26
- wastes minimization and characterization study, 25–26

Discrete settling, 345–46

Disposal of solid wastes from industry, treatment and, 397–436

Disposal of wastes, treatment and, 84–86

Dissolution of air in water, 369–73

Dissolved air flotation (DAF), 128, 137, 154, 369

- equipment, 373–74

Dissolved solids (TDS), 154, 159

DO (dissolved oxygen), 185–86, 293

DOT (Department of Transportation), 201

Downflow granular filters, 335–37

Drinks, production of bottled soft, 119–22

Dry impingement, 194–96

Ductwork, fans and, 438

E

Eckenfelder's equations, 307

Electrical stability, 33–35

Electrodialysis, 332–33

Electroplating of tin, 65–74

- production processes, 65–70
- sources and characteristics of wastes, 70–72
- wastes minimization, 72–73
- wastewater treatment, 73–74

Electrostatic impingement, 194

Electrostatic precipitators (ESPs), 439–42

Emulsification, 40–43

Emulsions, forming by vigorous mixing, 42–43

Emulsions, forming with emulsifying agents, 40–43

Environmental Audit, 166, 172–79

EPA (Environmental Protection Agency), 111, 301

Epoxys, 429

Equalization

- constituent, 226
- flow, 224–26
- waste, 223–26

Equations

- Eckenfelder's, 307
- for treatment of industrial wastes, 256–62

Equipment, DAF (dissolved air flotation), 373–74

ESPs (electrostatic precipitators), 439–42

Evacuated collection containers, 193

Expanded bed reactors, 319–20

Extraction, solvent, 253–54

F

F/M (food-to-microorganism), 268

F/M (food-to-microorganism) ratio, 258

Fabric filters, 442

Fans and ductwork, 438

Fats, oils and greases (FOG), 79, 154, 157, 191

Federal stormwater regulations, 149–51

Fenton's reagent, 251

Ferric ions, insoluble, 249

Ferrous ions

- hydrogen peroxide plus, 251
- soluble, 249

Film systems, fixed, 319–22

Filters

- deep bed granular, 333
- downflow granular, 335–37
- fabric, 442
- plate and frame, 326
- roughing, 307–8
- swimming pool, 341
- trickling, 302–6
 - design, 304–6
 - recirculation, 304
- upflow granular, 334–35

Filtration, 194

- pressure and vacuum, 337–41
- using granular media, 333–44

Fish, rendering of by-products from processing
 of, 130–38
 rendering process, 130–32
 treatment and disposal, 135–38
 wastes generation, 132–34
 wastes minimization, 134–35

Fixed film systems, 319–22

Flat-plate precipitators, 441

Flocculent settling, 346

Flotation, 367–69
 gravity, 367–68

Flow equalization, 224–26

Fluidized bed technology, 409–12

Fluidized bed, 310

Fluidized bed reactors, 320–21

FOG (fats, oils and greases), 79, 154, 157, 191

Food-to-microorganism (F/M), 268
 ratio, 258

Foods, prepared frozen, 77–86
 treatment and disposal of wastes, 84–86
 wastes generation, 78–83
 wastes minimization, 84

Formaldehyde, urea, 429–30

Frame filters, plate and, 326

Free radicals, oxidative destruction of organics
 by, 250

Freundlich, model for adsorption, 378

Frozen foods, prepared, 77–86
 treatment and disposal of wastes, 84–86
 wastes generation, 78–83
 wastes minimization, 84

Fundamentals, 29–48
 characteristics of industrial wastewater,
 29–30
 chemical structure and polarity of water,
 36–37
 colloidal suspensions, 43–44
 electrical stability, 33–35
 emulsification, 40–43
 examples, 45–47
 forming emulsions with emulsifying agents,
 40–43
 hydrogen bonding, 37–38
 mixtures made stable by chelating agents, 44
 polar properties of water, 30–33
 polar solvents versus nonpolar solvents,
 38–40
 thermodynamic stability, 33–35

Furnaces, car bottom gasification, 420–21

G

Galvanizing, wastewater from metal, 47

Gaseous pollutants, treatment systems for
 control of, 444–56
 absorption, 449–551
 adsorbents other than activated carbon,
 448–49
 adsorption, 446–47
 biofiltration, 453–56
 condensation, 451
 incineration, 451–53

Gases, 1–28
 landfill, 408
 reaction to produce insoluble, 238–39

Gasification furnaces, car bottom, 420–21

Gasification systems, roller hearth, 420

GCL (geosynthetic clay liner), 402

Gel, silica, 449

Geosynthetic clay liner (GCL), 402

Granular filters
 deep bed, 333
 downflow, 335–37
 upflow, 334–35

Granular media, filtration using, 333–44

Gravity flotation, 367–68

Gravity separators, 438

Grease, 190

Groundwater contamination, prevention of,
 151–52

Groundwater pollution control laws, 52–55

Growth, lag phase of, 266

Growth systems, attached, 301–2

Gypsum, 431

H

H₂O (water), 256–322
 chemical structure and polarity of, 36–37
 dissolution of air in, 369–73
 polar properties of, 30–33

H₂S (hydrogen sulfide), 200

Hardness, 192

Hazardous substance, determining source of
 each, 171

Hazardous substances, identifying that are
 purchased, 169–70

Hazardous substances, identifying that leave
 facility, 170–71

Hazardous waste, 18–20

HDPE (high-density polyethylene), 401–2, 433

Hearth incinerator technologies, 416–17
 Heavy metals, removal of, 47
 High-density polyethylene (HDPE), 401–2, 433
 Hoods and isolation chambers, 438
 Housekeeping, immaculate, 212
 HRTs (hydraulic retention times), 280, 320, 365
 Hydrocarbons, 200
 Hydrogen bonding, 37–38
 Hydrogen peroxide
 oxidation with, 250–51
 ozone plus, 252–53
 plus ferrous ions, 251
 Hydrogen peroxide plus UV light, 251–52
 Hydrogen sulfide, chlorination of, 253

I

Immaculate housekeeping, 212
 Impaction, 196–97
 Impingement
 dry, 194–96
 electrostatic, 194
 wet, 196
 Incineration, 451–53
 suitability of waste for, 400
 Incineration, solid waste, 409–21
 fluidized bed technology, 409–12
 hearth incinerator technologies, 416–17
 modular systems, 417
 rotary kiln technology, 412–16
 starved air technologies, 417–21
 Incinerator technologies, hearth, 416–17
 Industrial solid wastes, S/S of, 427–33
 binders used for S/S technologies, 429–32
 mechanisms involved in S/S treatment procedures, 432–33
 S/S process systems, 428–29
 Industrial stormwater
 management, 149–65
 design storm, 152–53
 Federal stormwater regulations, 149–51
 general, 149
 prevention of groundwater contamination, 151–52
 stormwater retention, 153
 stormwater segregation, collection, retention, and treatment, 152
 stormwater treatment, 153–54

 system failure protection, 153
 as source of process water makeup, 154–64
 Industrial waste system, 222
 Industrial wastes, 18
 characteristics of, 179, 179–91
 equations for biological treatment of, 256–62
 management of, 1–28
 analysis of manufacturing processes, 2–3
 annualized costs, 15–16
 bench scale investigations, 4–6
 competitive bids for construction, 17–18
 economic comparisons, 8–10
 final design, 17–18
 gases, 1–28
 liquids, 1–28
 O&M (operational and maintenance) costs, 10–15
 pilot scale investigations, 7–8
 preliminary designs, 8
 selection of candidate technologies, 4
 solids, 1–28
 treatment objectives, 4
 wastes characterization study, 3–4
 wastes minimization, 3–4
 process of composting, 421–27
 mechanical composting technology, 425–26
 windrow composting technology, 423–25
 Industrial wastewater
 characteristics of, 29–30
 miscellaneous characteristics, 191–92
 priority pollutants, 179
 containing dissolved iron, 47
 management of, 1–18
 treated by insoluble substances, 236–38
 treatment, 265–310, 310–22, 385–88
 Industries
 characteristics of solid waste streams from, 201
 hazardous wastes, 201–3
 nonhazardous solid wastes from industries, 203–5
 management of solid wastes from, 18–20
 methods for treating wastewaters from, 219–396
 nonhazardous solid wastes from, 203–5
 treating air discharges from, 437–60
 containment, 437–38

- fans and ductwork, 438
 - hoods and isolation chambers, 438
 - reduction at source, 437
 - treatment, 438
- treatment and disposal of solid wastes from, 397–436
- wastes from, 61–148
 - chemical descaling, 61–62
 - degreasing, 62–64
 - electroplating of tin, 65–74
 - rinsing, 64–65
- Inertial separators, 438
- Inorganic binding agents, 430–32
- Inorganic chelating agents, 248
- Insoluble compounds, disadvantages of treatment by production of, 236
- Insoluble ferric ions, 249
- Insoluble gases, reactions to produce, 238–39
- Insoluble solids, reaction to produce, 230–38
- Insoluble substances
 - industrial wastewater treated by, 236–38
 - removal by forming, 238
- Investigations
 - bench scale, 4–6, 26
 - pilot scale, 7–8, 26–27
- Ion exchanges, 381–88
 - applications to industrial wastewater treatment, 385–88
 - breakthrough curve, 388
 - design criteria, 389
 - kinetics of, 384–85
 - mechanisms of, 384
 - removal of specific organic substances, 389
 - scrubbing, 390–91
 - stripping, 389–90
- Ion selectivity, 385
- Ions
 - hydrogen peroxide plus ferrous, 251
 - insoluble ferric, 249
 - soluble ferrous, 249
- Iron, 192
 - industrial wastewater containing dissolved, 47
- Irrigation, spray, 392
- Isolation chambers, hoods and, 438
- K**
- Kiln, rotary, 412–16, 419
- Kinetics in laboratory, biological treatment, 258–61
- $K_L a$, 287, 294
- L**
- Lag phase of growth, 266
- Lagoon systems, design of, 299–300
- Lagoons
 - aerated, 297–98
 - anaerobic, 322
 - facultative, 298
 - nonaerated facultative, 298–99
- Lamella settlers, 361–65
- Land application, 392
- Landfill cover and cap systems, 402–6
- Landfill gas (LFG), 407–8
- Landfill liner system, 400–402
- Landfilling, suitability of waste for, 399–400
- Landfills
 - alternative, 408–9
 - conventional, 400
 - discharges from, 407–8
 - solid waste, 400–409
 - alternative landfills, 408–9
 - conventional landfill, 400
 - discharges from landfills, 407–8
 - landfill cover and cap systems, 402–6
 - landfill liner system, 400–402
 - stormwater management, 406–7
- Langmuir, model for adsorption, 377–81
- Laws
 - air pollution control, 55–60
 - groundwater pollution control, 52–55
 - and regulations, 49–60
 - air pollution control law as of Year 2000, 56
 - air pollution control laws, 55–60
 - groundwater pollution control laws, 52–55
 - history of permitting and reporting requirements, 49–50
 - introduction, 49
 - Title I, 58
 - Title III, 58
 - Title IV, 59
 - Title V, 56–58
 - Title VII, 59–60
 - water pollution control laws, 50–52
 - water pollution control, 50–52

Leachate, 248, 401–8

collection, 401

incineration, 407

treatment, 249

Lead acid batteries, manufacture of, 138–44

wastes generation, 141–42

wastes minimization, 142–43

wastewater treatment, 143–44

Lead battery manufacture, 138–41

Ledy Oxide, 140

LFG (landfill gas), 407–8

Lights

hydrogen peroxide plus UV, 251–52

ozone plus UV, 253

Lime, 431

Liquids, 1–28

Low-energy complete mix approach, 300

Lyophilic colloids, 245–47

Lyophilic sols, 242

electrokinetics of, 244

Lyophobic colloids, 244–45

Lyophobic sols, 240–42

electrokinetics of, 242–44

M

MACT (Maximum Achievable Control Technology), 198, 201

Magnesium die casting, 93, 95

Malodorous substances, 200–201

Management

of discharges to air, 20–28

analysis of manufacturing processes, 20–25

bench scale investigations, 26

economic comparisons, 28

pilot scale investigations, 26–27

preliminary designs, 27–28

selection of candidate technologies, 26

treatment objectives, 26

wastes minimization and characterization study, 25–26

of industrial wastewater, 1–18

analysis of manufacturing processes, 2–3

annualized costs, 15–16

bench scale investigations, 4–6

competitive bids for construction, 17–18

economic comparisons, 8–10

final design, 17–18

O&M (operational and maintenance)

costs, 10–15

pilot scale investigations, 7–8

preliminary designs, 8

selection of candidate technologies, 4

treatment objectives, 4

wastes characterization study, 3–4

wastes minimization, 3–4

of solid wastes from industries, 18–20

Manganese, 192

Manufacturing plant, pretreatment for microcrystalline cellulose, 8–10

Manufacturing processes

analysis of, 2–3, 20–25

changing, 213

Mass diagram, 225, 227

Materials, substitution of, 212–13

Mathematical model of PACT process, predictive, 274–76

Maximum Achievable Control Technology (MACT), 198, 201

Meat

production and processing of red, 124

production processes, 126

treatment and disposal, 128–30

wastes generation, 126–27

wastes minimization, 127–28

rendering of by-product from processing of rendering process, 130–32

treatment and disposal, 135–38

wastes generation, 132–34

wastes minimization, 134–35

rendering of by-products from processing of, 130–38

Mechanical composting technology, 425–26

Media, filtration using granular, 333–44

Membrane separation, 326–33

electrodialysis, 332–33

removal mechanisms, 330–31

reverse osmosis, 331–32

Metabolism, mechanisms of anaerobic, 312–16

Metal galvanizing, wastewater from, 47

Metals, 186

removal of heavy, 47

Methane, 200–201

Methyl-tert-butyl ether (MTBE), 191

MF (microfiltration), 326

Microcrystalline cellulose manufacturing plant, pretreatment for, 8–10

- Microfiltration (MF), 326
- Microorganisms, 255
- Microscreening, 324–30
- Minimization, companywide philosophy of waste, 211–12
- Mix approach, low-energy complete, 300
- Mix, conventional complete, 273–74
- Mixed liquor suspended solids (MLSS), 264–65, 279–80
- Mixed liquor volatile suspended solids (MLVSS), 264–66, 268, 280
- Mixing, forming emulsions by vigorous, 42–43
- Mixtures made stable by chelating agents, 44
- MLSS (mixed liquor suspended solids), 264–65, 279–80
- MLVSS (mixed liquor volatile suspended solids), 264–66, 268, 280
- Molecular weight cutoff (MWCO), 326, 328
- MSGP (Multi-Sector General Permit), 150–51
- MSWLFs (municipal solid wastes landfill facilities), 203
- MTBE (Methyl-tert-butyl ether), 191
- Multi-Sector General Permit (MSGP), 150–51
- Municipal solid wastes landfill facilities (MSWLFs), 203
- MWCO (molecular weight cutoff), 326, 328
- N**
- NAAQS (National Ambient Air Quality Standards), 193
- Nanofiltration (NF), 326
- National Ambient Air Quality Standards (NAAQS), 193
- National Pollutant Discharge Elimination System (NPDES), 4, 150, 155, 162
- NBOD (nitrogenous oxygen demand), 301
- Nephelometric Turbidity Units (NTUs), 186
- NF (nanofiltration), 326
- Nitrogen, compounds containing, 188
- Nitrogenous oxygen demand (NBOD), 301
- NOI (Notice of Intent), 150
- Non-steady state method, 293–94
- Nonaerated facultative lagoons, 298–99
- Nonbiodegradable substances, biologically degradable substance from, 247
- Nonhazardous solid wastes from industries, 203–5
- Nonobjectionable substances, producing, 248–53
- Nonpolar solvents, polar solvents versus, 38–40
- Notice of Intent (NOI), 150
- NO_x (oxides of nitrogen), 199
- NPDES (National Pollutant Discharge Elimination System), 4, 150, 155, 162
- NTUs (Nephelometric Turbidity Units), 186
- Nutrients, 426
- O**
- O&M (operational and maintenance) costs, 10–15, 265, 399
- Objectionable substances; *See* Nonobjectionable substances
- Odors, 426–27
- Off-gas method, 294–98
- Oil and grease, 190
- Oily wastewater pretreatment system (OWPS), 159
- Oily wastewater treatment plant (OWTP), 155
- OIT (operator interface terminal), 159
- Operator interface terminal (OIT), 159
- Organic binding agents, 429–30
- Organic chelating agents, 248
- Organic matter, 255
- Organic substances, removal of specific, 389
- Organics, 200
 - oxidative destruction by free radicals, 250
- ORP (oxidation-reduction potential), 433
- OTR (oxygen transfer rate), 296
- OWPS (oily wastewater pretreatment system), 159
- OWTP (oily wastewater treatment plant), 155
- Oxidation
 - catalytic, 254
 - with hydrogen peroxide, 250–51
 - with ozone, 252
 - Pasveer, 280
 - ponds, 299–301
 - thermal, 254
- Oxidation-reduction potential (ORP), 433
- Oxidative destruction of organics by free radicals, 250
- Oxides of sulfur, 199
- Oxidizers
 - catalytic, 452–53
 - thermal, 452
- Oxygen, 255
- Oxygen in wastewater treatment, 261–62

Oxygen transfer rate (OTR), 296

testing, 287

Ozone, 199

oxidation with, 252

plus hydrogen peroxide, 252–53

plus UV light, 253

P

P&M (process and maintenance), 155, 157

Packaged water treatment systems, 341–44

Packed bed reactors, 321

PACT modification of activated sludge, 274

PACT (powdered activated carbon technology), 274

PACT process, predictive mathematical model of, 274–76

Particulates, 200

treatment systems for control of, 438–44

Partition-gravimetric method, 190–91

Partition-infrared method, 191

Parts cleaning process, wastewater from, 47

Pasveer oxidation ditch and variations, 280

PCBs (polychlorinated biphenyls), 93, 152, 397

Permitting requirements, history of, 49–50

Peroxide, oxidation with hydrogen, 250–51

PH, 185

PH control, 227–30

Phase I, 215

Phase II, 215–16

Phosphorus, compounds containing, 186–88

Physical barriers, separation using, 322–33

bar racks, 323

membrane separation, 326–33

microscreening, 324–30

plate and frame filters, 326

racks and screens, 322–26

rotating cylindrical screens, 324

tangential screens, 323–24

vibrating screens, 323

Physical methods of wastewater treatment, 322–93

Pickling, 61, 67

Pilot scale investigations, 7–8, 26–27

Pin floc, 268

Plain sedimentation, 344–65

Plate and frame filters, 326

Plate settlers, 361–65

Plate-wire precipitators, 441

PLC (programmable logic controller), 159

Plug flow, conventional, 270–72

Polar properties of water, 30–33

Polar solvents versus nonpolar solvents, 38–40

Polarity of water, chemical structure and, 36–37

Pollutants, 191–92

air, 198–200

treatment systems for control of gaseous, 444–56

absorption, 449–551

adsorbents other than activated carbon, 448–49

adsorption, 446–47

biofiltration, 453–56

condensation, 451

incineration, 451–53

Pollution

air, 55–56, 55–60

groundwater, 52–55

prevention, 208–18

benefits of, 216

benefits of pollution prevention, 216

evaluating economics of, 172

findings and policy, 208–9

waste audit, 215–16

water, 50–52

Pollution prevention

general approach, 209–12

accurate cost accounting system, 211

active technology transfer program, 212

clear objectives, 210–11

companywide philosophy of waste minimization, 211–12

explicit scope, 210–11

support from top management, 209–10

source reduction, 212–15

achieving reduction of wastes at the source, 216

changing equipment, 213

changing manufacturing processes, 212

immaculate housekeeping, 212

recycle and reuse, 213–14

segregation of waste streams, 214–15

selective mixing of waste streams, 215

substitution of materials, 212–13

waste exchanges, 215

Polychlorinated biphenyls (PCBs), 93, 152, 397

- Polyesters, 430
 - Polyolefins, 430
 - Ponds, oxidation, 299–301
 - Pork, production and processing of, 124
 - production processes, 126
 - treatment and disposal, 128–30
 - wastes generation, 126–27
 - Portland cement, 430
 - Potentially responsible party (PRP), 216
 - POTWs (publicly owned treatment works), 29, 86, 200, 407
 - Poultry
 - processing wastewater, 45–46
 - rendering of by-products from processing of, 130–38
 - rendering process, 130–32
 - treatment and disposal, 135–38
 - wastes generation, 132–34
 - wastes minimization, 134–35
 - Powdered activated carbon technology (PACT), 274
 - Pozzolan substances, 431
 - Precipitators
 - flat-plate, 441
 - plate-wire, 441
 - tubular, 441–42
 - two-stage, 441
 - wet, 442
 - Precoat, 339
 - Precipitation, 62, 231, 249
 - Preclean, 66
 - Prepared frozen foods, 77–86
 - Preplating, 66
 - Pressure and vacuum filtration, 337–41
 - Pretreatment Regulations, 51–52
 - Prevention, pollution, 208–18
 - benefits of pollution prevention, 216
 - general approach, 209–12
 - source reduction, 212–15
 - waste audit, 215–16
 - Process and maintenance (P&M), 155, 157
 - Programmable logic controller (PLC), 159
 - PRP (potentially responsible party), 216
 - Publicly owned treatment works (POTWs), 29, 86, 200, 407
 - Pumps, vacuum, 193
- R**
- Ratios
 - A/S (air-to-solids), 375
 - calculations of recycle, 375
 - F/M (food-to-microorganism), 258
 - RBCs (rotating biological contactors), 302–3, 308–9
 - RCRA (Resource, Conservation and Recovery Act), 18–19, 172, 179, 201, 203, 397
 - RDF (refuse derived fuel), 409
 - Reactors
 - anaerobic contact, 318
 - expanded bed, 319–20
 - fluidized bed, 320–21
 - packed bed, 321
 - rotary hearth, 419–20
 - rotary kiln, 419
 - Recycle and reuse, 213–14
 - Recycle ratios, calculations of, 375
 - Red meat, production and processing of, 124
 - production processes, 126
 - treatment and disposal, 128–30
 - wastes generation, 126–27
 - wastes minimization, 127–28
 - Refuse derived fuel (RDF), 409
 - Regulations
 - laws and, 49–60
 - air pollution control law as of Year 2000, 56
 - air pollution control laws, 55–60
 - groundwater pollution control laws, 52–55
 - history of permitting and reporting requirements, 49–50
 - introduction, 49
 - Title I, 58
 - Title III, 58
 - Title IV, 59
 - Title V, 56–58
 - Title VII, 59–60
 - water pollution control laws, 50–52
 - Regulations, Pretreatment, 51–52
 - Reporting requirements, history of, 49–50
 - Resin, 448
 - Resource, Conservation and Recovery Act (RCRA), 18–19, 172, 179, 201, 203, 397
 - Reverse osmosis, 331–32
 - Reverse osmosis (RO), 326
 - Rinsewater pretreatment plant (RPP), 155
 - Rinsing, 64–65

RMF (Runoff Management Facility), 155, 157, 159, 162
 RO (reverse osmosis), 326
 Roller hearth gasification systems, 420
 Rotary hearth reactors, 419–20
 Rotary kiln technology, 412–16, 419
 Rotating biological contactors (RBCs), 302–3, 308–9
 Rotating cylindrical screens, 324
 Roughing filters, 307–8
 RPP (rinsewater pretreatment plant), 155
 Rubber
 production of synthetic, 111–15
 synthetic
 production of synthetic rubber, 111–15
 specialty products, 115
 wastes generation, 115–18
 wastes minimization, 118
 wastewater treatment, 118–19
 Rubber industry, synthetic, 110–19
 Runoff Management Facility (RMF), 155, 157, 159, 162

S

S/S process systems, 428–29
 S/S (solidification and stabilization), 427–33
 S/S technologies, binders used for, 429–32
 S/S treatment procedures, mechanisms involved in, 432–33
 Safe Drinking Water Act (SDWA), 179
 Sample analysis, 198
 SBR systems, designing of, 279–80
 SBRs (sequencing batch reactors), 277
 Screens; *See also* Microscreening
 rotating cylindrical, 324
 tangential, 323–24
 vibrating, 323
 Scrubbers
 tray, 443–44
 venturi, 442–43
 wet, 442
 Scrubbing, 390–91
 SDWA (Safe Drinking Water Act), 179
 Sedimentation, plain, 344–65
 Selectors, 268–70
 Separation using physical barriers, 322–33
 bar racks, 323
 membrane separation, 326–33
 microscreening, 324–30

 plate and frame filters, 326
 rotating cylindrical screens, 324
 tangential screens, 323–24
 vibrating screens, 323

Separators

 gravity, 438
 inertial, 438

Settling column, 348

Sequencing batch reactors (SBRs), 277

Settable solids, 190

Settlers

 lamella, 361–65
 plate, 361–65
 tube, 361–65

Silica gel, 449

Silicates, 431–32

Sludge

 activated, 265
 aeration systems for activated, 283–97
 bulking, 268–70
 contact stabilization modification of
 activated, 276
 extended aeration activated, 276
 high-rate modification of activated, 276
 PACT modification of activated, 274
 thickening, 346–49

Sludge process

 SBR of activated, 277–79
 variations of activated, 270

Sludge systems, characteristics of activated, 283

Soft drink bottling industry, 119–23

 production of bottled soft drinks, 119–22
 wastes generation, 122–23
 wastes minimization, 123
 wastewater treatment, 123

Soft drinks, production of bottled, 119–22

Solid waste

 incineration, 409–21
 fluidized bed technology, 409–12
 hearth incinerator technologies, 416–17
 modular systems, 417
 rotary kiln technology, 412–16
 starved air technologies, 417–21
 landfills, 400–409
 alternative landfills, 408–9
 conventional landfill, 400
 discharges from landfills, 407–8
 landfill cover and cap systems, 402–6

- landfill liner system, 400–402
- stormwater management, 406–7
- Solid waste streams, characteristics of, 201
 - hazardous wastes, 201–3
 - nonhazardous solid wastes from industries, 203–5
- Solid wastes
 - characterization of, 398–400
 - opportunities for waste reduction, 398–400
 - rate of waste generation, 399
 - suitability of waste for composting, 400
 - suitability of waste for incineration, 400
 - suitability of waste for landfilling, 399–400
 - whether waste is hazardous, 399
- from industries
 - management of, 18–20
 - nonhazardous, 203–5
 - treatment and disposal of, 397–436
- S/S of industrial, 427–33
- Solidification and stabilization (S/S), 427–33
- Solids, 1–28
 - adsorption on, 194
 - reaction to produce insoluble, 230–38
 - setttable, 190
 - suspended, 188–90
 - total, 188
- Sols
 - electrokinetics of lyophilic, 244
 - electrokinetics of lyophobic, 242–44
 - lyophilic, 242
 - lyophobic, 240–42
- Soltex extraction method, 191
- Soluble ferrous ions, 249
- Solutions, true, 38–40
- Solvent extraction, 253–54
- Solvents, polar solvents versus nonpolar, 38–40
- SOTR (standard oxygen transfer rate), 295–96
- Source reduction, 212–15
- SP3 (stormwater pollution prevention plan), 150–51
- Special wastes, 18
- Spray irrigation, 392
- SRBs (styrene butadiene rubbers), 111, 113
- Stability
 - electrical, 33–35
 - thermodynamic, 33–35
- Stack sampling, 193
- Standard oxygen transfer rate (SOTR), 295–96
- Starved air technologies, 417–21
- Static pile technology, 425
- Stormwater
 - retention, 153
 - as source of process
 - BOD (biological oxygen demand), 154–55
 - case history, 155–64
 - heat, 155
 - TDS (dissolved solids), 154
 - as source of process water makeup, 154–64
 - treated, 154
- Stormwater management, 406–7
- Stormwater management, industrial, 149–65
 - design storm, 152–53
 - Federal stormwater regulations, 149–51
 - general, 149
 - prevention of groundwater contamination, 151–52
 - stormwater, 153–54
 - stormwater retention, 153
 - stormwater segregation, collection, retention, and treatment, 152
 - system failure protection, 153
- Stormwater pollution prevention plan (SP3), 150–51
- Stormwater regulations, Federal, 149–51
 - background, 149–50
 - construction general permit, 151
 - individual permit, 150–51
 - MSGP (Multi-Sector General Permit), 150
 - SP3 (stormwater pollution prevention plan), 151
- Stormwater segregation, collection, retention, and treatment, 152
- Streams
 - characteristics of solid waste, 201
 - segregation of waste, 214–15
 - selective mixing of waste, 215
 - waste, 95–98, 171
- Stripping, 389–90
- Styrene butadiene rubbers (SRBs), 111, 113
- Substances
 - malodorous, 200–201
 - producing nonobjectionable, 248–53
 - removal by forming insoluble, 238
 - volatile, 169

Subsystems, two control, 230

Sulfur

oxides of, 199

producing elemental, 253

Sulfur compounds, miscellaneous reduced, 200

Sulfuric Acid, 62

Suspended growth systems, 265

anaerobic, 316–18

Suspended solids, 188–90

Suspensions, colloidal, 43–44

Swimming pool filters, 341

Synthetic rubber industry, 110–19

production of synthetic rubber, 111–15

specialty products, 115

wastes generation, 115–18

wastes minimization, 118

wastewater treatment, 118–19

Synthetic rubber, production of, 111–15

T

Tangential screens, 323–24

TCE (trichloroethylene), 169

TCLP (Toxic Characteristics Leaching Procedure), 202, 399

TDS (dissolved solids), 154, 159

Technologies

aerobic, 265–310

binders used for S/S, 429–32

biological treatment, 262–322

candidate treatment, 221

development of anaerobic, 312

fluidized bed, 409–12

hearth incinerator, 416–17

mechanical composting, 425–26

rotary kiln, 412–16

selection of candidate, 4

starved air, 417–21

static pile, 425

using anaerobic, 310–22

windrow composting, 423–25

Technology transfer program, active, 212

Tedlar bags, 193

Tests, TCLP (Toxic Characteristic Leaching Procedure), 202

Thermal oxidation, 254

Thermal oxidizers, 452

Thermodynamic stability, 33–35

Tin, electroplating of, 65–74

production processes, 65–70

sources and characteristics of wastes, 70–72

wastes minimization, 72–73

wastewater treatment, 73–74

Total reduced sulfur (TRS), 200

Total solids, 188

Total suspended solids (TSS), 127, 154, 157, 159, 188, 300

Total Volatile Suspended Solids (TVSS), 190

Toxicity, 56, 62, 72, 171, 208, 212, 249, 399, *see* Hazardous

Toxic Characteristics Leaching Procedure (TCLP), 202, 399

Toxic loads, analyzing feasibility of reducing, 171–72

Toxics, sampling methods for air, 201

Tray scrubbers, 443–44

Treated stormwater, 154

Treatment

application of ion exchanges to industrial wastewater, 385–88

biological, 255

chemical methods of wastewater, 230–55

oxygen in wastewater, 261–62

physical methods of wastewater, 322–93

systems

for control of gaseous pollutants, 444–56

packaged water, 341–44

variations of anaerobic, 316

technologies

biological, 262–322

candidate, 221

wastewater

manufacture of lead acid batteries, 143–44

soft drink bottling industry, 123

synthetic rubber industry, 118–19

wetlands, 393

Treatment and disposal, 128–30

production and processing of beef, 128–30

production and processing of pork, 128–30

production and processing of red meat, 128–30

rendering of by-products from processing of fish, 135–38

rendering of by-products from processing of meat, 135–38

rendering of by-products from processing of poultry, 135–38

of solid wastes from industry, 397–436

- of wastes, 84–86
- Treatment methods, miscellaneous wastewater, 392–93
 - land application, 392
 - spray irrigation, 392
 - wastewater application rate, 392–93
 - wetlands treatment, 393
- Treatment of industrial wastewater, 310–22
- Treatment of winery wastes, 110
- Trichloroethylene (TCE), 169
- Trickling filters, 302–6
 - design, 304–6
 - recirculation, 304
 - media, 305
- TRS (total reduced sulfur), 200
- True solutions, 38–40
- TSS (total suspended solids), 127, 154, 157, 159, 188, 300
- Tube settlers, 361–65
- Tubular precipitators, 441–42
- Turbidity, 186
- TVSS (Total Volatile Suspended Solids), 190
- Two-stage precipitators, 441

U

- UASB (upflow anaerobic sludge blanket), 316–17
- UF (ultrafiltration), 326
- Upflow anaerobic sludge blanket (UASB), 316–17
- Upflow granular filters, 334–35
- Urea-formaldehyde, 429–30
- UV light
 - hydrogen peroxide plus, 251–52
 - ozone plus, 253

V

- Vacuum filtration, and pressure, 337–41
- Vacuum pumps, 193
- Venturi scrubbers, 442–43
- Vibrating screens, 323
- Vitis Vinifera*, 107
- VOCs (volatile organic compounds), 200, 403, 446, 453
- Volatile substances, 169

W

- Waste audit, 215–16

- Phase I, 215
- Phase II, 215–16
- Waste equalization, 223–26
- Waste exchanges, 215
- Waste generation, rate of, 399
- Waste management, 95–98
 - considerations, 98–99
- Waste minimization, companywide philosophy of, 211–12
- Waste reduction, opportunities for, 398–400
- Waste streams, 95–98
 - characteristics of solid, 201
 - prioritizing to be reduced, 171
 - segregation of, 214–15
 - selective mixing of, 215
- Waste systems, coagulation of colloidal, 244–47
- Waste-to-energy (WTE), 409, 412, 415
- Waste treatment and disposal, anodizing and alodizing, 103
- Wastes
 - audits, 166
 - analyzing feasibility of reducing toxic loads, 171–72
 - determining source of each hazardous substance, 171
 - evaluating economics of pollution prevention, 172
 - identifying hazardous substances that are purchased, 169–70
 - identifying hazardous substances that leave facility, 170–71
 - prioritizing waste streams to be reduced, 171
 - characteristics of industrial, 179
 - characterization, 166–207
 - ambient air sampling, 198–201
 - characteristics of discharges to air, 192–97
 - characteristics of industrial wastes, 179
 - characteristics of industrial wastewater, 179–91
 - characteristics of solid waste streams from industries, 201
 - Environmental Audit, 172–79
 - sample analysis, 198
 - wastes audit, 169–72
 - characterization of solid, 398–400

- opportunities for waste reduction, 398–400
- rate of waste generation, 399
- suitability of waste for composting, 400
- suitability of waste for incineration, 400
- suitability of waste for landfilling, 399–400
- whether waste is hazardous, 399
- characterization study, 166–69
 - choice of sampling location, 166–68
 - sample preservation, 169
 - sampling equipment, 168
 - sampling for oil and grease, 169
 - volatile substances, 169
- and wastes minimization, 3–4
- from De-inking, 86–93
 - De-inking process - wastes generation, 88–89
 - wastes generation and wastes minimization, 89
 - wastes minimization, 92
 - wastewater characteristics, 89–92
 - wastewater treatment, 92–93
- equations for biological treatment of industrial, 256–62
- generation, 76–78,
 - anodizing and alodizing, 100–101
 - manufacture of lead acid batteries, 141–42
 - production and processing of beef, 126–27
 - production and processing of pork, 126–27
 - production and processing of red meat, 126–27
 - rendering of by-products from processing of fish, 132–34
 - rendering of by-products from processing of meat, 132–34
 - rendering of by-products from processing of poultry, 132–34
 - soft drink bottling industry, 122–23
 - synthetic rubber industry, 115–18
 - wastes from De-inking, 88–89
- hazardous, 18–20
- industrial, 18
- from industries, 61–148
 - chemical descaling, 61–62
 - degreasing, 62–64
 - electroplating of tin, 65–74
 - nonhazardous solid, 203–5
 - rinsing, 64–65
 - treatment and disposal of solid, 397–436
- management of industrial, 1–28
 - analysis of manufacturing processes, 2–3
 - annualized costs, 15–16
 - bench scale investigations, 4–6
 - competitive bids for construction, 17–18
 - economic comparisons, 8–10
 - final design, 17–18
 - gases, 1–28
 - liquids, 1–28
 - O&M (operational and maintenance) costs, 10–15
 - pilot scale investigations, 7–8
 - preliminary designs, 8
 - selection of candidate technologies, 4
 - solids, 1–28
 - treatment objectives, 4
 - wastes characterization study, 3–4
 - wastes minimization, 3–4
- minimization, 72–73
 - anodizing and alodizing, 101–3
 - and characterization study, 25–26
 - manufacture of lead acid batteries, 142–43
 - prepared frozen foods, 84
 - production and processing of beef, 127–28
 - production and processing of Coke, 106
 - production and processing of pork, 127–28
 - production and processing of red meat, 127–28
 - rendering of by-products from processing of fish, 134–35
 - rendering of by-products from processing of meat, 134–35
 - rendering of by-products from processing of poultry, 134–35
 - soft drink bottling industry, 123
 - synthetic rubber industry, 118
 - wastes characterization study, 3–4
 - wastes from De-inking, 89, 92
 - wine-making industry, 110
- process of composting industrial, 421–27
 - mechanical composting technology, 425–26

- windrow composting technology, 423–25
 - S/S of industrial solid, 427–33
 - binders used for S/S technologies, 429–32
 - mechanisms involved in S/S treatment procedures, 432–33
 - S/S process systems, 428–29
 - solid, 18–20, 400–409
 - sources and characteristics of, 70–72
 - sources of, 105–6
 - special, 18
 - suitability
 - for incineration, 400
 - for landfilling, 399–400
 - treatment and disposal of, 84–86
 - treatment of winery, 110
 - wine-making, 108–10
 - Wastes at source, achieving reduction of, 216
 - Wastewater
 - application rate, 392–93
 - characteristics, 89–92
 - characteristics of industrial, 29–30, 179–91
 - pollutants, 191–92
 - priority pollutants, 179
 - containing dissolved iron, 47
 - management of industrial, 1–18
 - from metal galvanizing, 47
 - from parts cleaning process, 47
 - poultry processing, 45–46
 - Wastewater treated by insoluble substances, industrial, 236–38
 - Wastewater treatment
 - application of ion exchanges to, 385–88
 - chemical methods of, 230–55
 - reaction to produce insoluble solids, 230–38
 - electroplating of tin, 73–74
 - manufacture of lead acid batteries, 143–44
 - oxygen in, 261–62
 - physical methods of, 322–93
 - adsorption, 376–81
 - centrifugation, 365–67
 - filtration using granular media, 333–44
 - flotation, 367–69
 - ion exchange, 381–88
 - plain sedimentation, 344–65
 - production and processing of Coke, 106–7
 - soft drink bottling industry, 123
 - synthetic rubber industry, 118–19
 - wastes from De-inking, 92–93
 - Wastewater treatment methods, miscellaneous, 392–93
 - land application, 392
 - spray irrigation, 392
 - wastewater application rate, 392–93
 - wetlands treatment, 393
 - Wastewaters from industry, methods for treating, 219–396
 - chemical methods of wastewater treatment, 230–55
 - general, 219–20
 - pH control, 227–30
 - principle and nonprinciple treatment mechanisms, 220–22
 - waste equalization, 223–26
 - constituent equalization, 226
 - flow equalization, 224–26
 - Wastewaters, treatment of industrial, 265–310, 310–22
 - Water (H₂O)
 - chemical structure and polarity of, 36–37
 - dissolution of air in, 369–73
 - polar properties of, 30–33
 - Water makeup, stormwater as source of process, 154–64
 - Water pollution control laws, 50–52
 - Water treatment systems, packaged, 341–44
 - Wet impingement, 196
 - Wet precipitators, 442
 - Wet scrubbers, 442
 - Wetlands treatment, 393
 - Windrow composting technology, 423–25
 - Wine-making industry, 107–10
 - treatment of winery wastes, 110
 - wastes minimization, 110
 - wine-making wastes, 108–10
 - wine production process, 107–8
 - Wine-making wastes, 108–10
 - Wine production process, 107–8
 - Winery wastes, treatment of, 110
 - WTE (waste-to-energy), 409, 412, 415
- Z**
- Zeta potential, 243
 - Zinc die casting, 93, 95